

**Ohio**  
**Manual of**  
**Uniform**  
**Traffic**  
**Control**  
**Devices**



**2005 Edition**

**Revision 1**

**December 23, 2009**

**Effective January 15, 2010**

**Ohio Department of Transportation**  
**Office of Traffic Engineering**



# Ohio Manual of Uniform Traffic Control Devices for Streets and Highways



**2005  
Edition  
Revision 1**





**2005 Edition of the OMUTCD, Revision 1**  
**December 23, 2009**  
**(Effective January 15, 2010)**

**As of December 23, 2009 the Ohio Manual of Uniform Traffic Control Devices (OMUTCD) has been revised.**

Primarily, this revision incorporates into the OMUTCD Revision 2 of the national 2003 Manual on Traffic Control Devices (published in December 2007 by the Federal Highway Administration), which involved retroreflectivity guidelines for highway signs. A couple of corrections have also been incorporated into the text with this revision. This revision of the 2005 OMUTCD involves the Title Sheet, Preface and Introduction, pages in Parts 1, 2 and 6, and Appendix C.

The revised OMUTCD is available on-line from the ODOT Office of Traffic Engineering at <http://www.dot.state.oh.us/Divisions/HighwayOps/Traffic/publications2/OhioMUTCD/Pages/default.aspx>.

A revision set which can be used to update paper copies of the existing Manual is also available on-line at the same web address. A CD with the revised Manual should be available within a few weeks. Please contact the Office of Traffic Engineering to request copies (Gerri Parker at 614-466-4700; or Lisa McConnell at 614-728-9361).

The following list details the specific revisions that have been made to the OMUTCD:

Part	Old Page	New Page	Section or Table Revised	Description
00	i – ii	i – ii	Title Sheet	Added “Revision 1” to the title page, with the related dates; and updated the website addresses shown on the back of the sheet.
00	iii	iii	Preface	Revised the second paragraph to incorporate a reference to Revision 2 of the national MUTCD. Also updated the web address in the sixth paragraph. [Reprinted page iv as part of the double-sided Revision package.]
00	v	v	Addresses for Publications Referenced in the OMUTCD	Updated the web address for the FHWA Office of Transportation Operations. [Reprinted page vi as part of the double-sided Revision package.]
I	I-1 – I-2	I-1 – I-2	Introduction	Reprinted these two pages as part of the Revision Set.
I	I-3 – I-6	I-3 – I-6	Introduction	On page I-3 added a new item related to the change in Section 2A.09. Text shifted on pages I-4 through I-6.
I	I-7	I-7	Table I-1	Added information about Revision 1.
I	I-8	I-8	Table I-2	Added information about Revision 1.
1	1A-8	1A-8	Section 1A.11	After the fifth paragraph, added a new paragraph that discusses the availability of the publication entitled “Maintaining Traffic Sign Retroreflectivity.” [Reprinted page 1A-7 as part of the double-sided Revision package.]
2	2TC-1 – 2TC-10	2TC-1 – 2TC-10	Part 2 TOC	Updated the Table of Contents for Part 2, and reprinted it in total as part of the Revision package.
2	2A-5	2A-5 – 2A-6	Section 2A.09	Revised the title of the section to “Maintaining Minimum Retroreflectivity,” and replaced the text of the Section.
2	-	2A-7	Table 2A-3	Added a new Table 2A-3 entitled “Minimum Maintained Retroreflectivity Levels.”
2	2A-6	2A-8	Section 2A.10	Revised the reference to “Table 2A-3” to “Table 2A-4.”

Part	Old Page	New Page	Section or Table Revised	Description
2	2A-6	2A-8	Section 2A.11	Revised the reference to "Table 2A-4" in the second paragraph to "Table 2A-5."
2	2A-6	2A-8	Section 2A.12	In the first line of the second paragraph, revised "for up to five different sizes" to "for various sizes."
2	2A-7	2A-9	Table 2A-3	Revised the Table number to "Table 2A-4."
2	2A-8	2A-10	Table 2A-4	Revised the Table number to "Table 2A-5."
2	2A-9 – 2A-15	2A-11 – 2A-17	-	With the addition of new Table 2A-3, the page numbers changed. Reprinted pages 2A-11 through 2A-17 as part of the Revision package.
2	2A-16	2A-18	Section 2A.22	In the first paragraph, revised the first sentence and added a cross-reference to Section 2A.09.
2	2B-1	2B-1	Section 2B.02	In the first paragraph, revised "Tables 2A-3 and 2A-4" to "Tables 2A-4 and 2A-5." [Reprinted page B-2 as part of the double-sided Revision package.]
2	2E-20	2E-20	Section 2E.28	In the fourth paragraph, corrected "40 m" to "40 km." [Reprinted page 2E-19 as part of the double-sided Revision package.]
2	2E-30 – 2E-31	2E-30 – 2E-31	Section 2E.34	In the Section title and the first and last paragraphs of the Section, revised the sign code numbers "E5-H2" and "E5-H2a" to "E5-H1b" and "E5-H1c," respectively. [Reprinted pages 2E-29 and 2E-32 as part of the double-sided Revision package.]
2	2F-1	2F-1	Section 2F.01	Revised the sixth paragraph to "Eligible gas, food, lodging, camping and attraction services shall be located in accordance with the distance criteria established by ODOT." Revised to address anticipated rules changes for the Ohio Logo Program. [Reprinted page 2F-2 as part of the double-sided Revision package.]
6	6F-2	6F-2	Section 6F.02	In the first paragraph on page 6F-2, revised "Table 2A-4" to "Table 2A-5" in two places. [Reprinted page 6F-1 as part of the double-sided Revision package.]
6	6H-2	6H-2	Table 6H-1	In the description for TA-27, in the third row from the bottom on page 6H-2, corrected the spelling of "Intersection." [Reprinted page 6H-1 as part of the double-sided Revision package.]
6	6H-18	6H-18	Notes for Figure 6H-7	In the first line of item 5, corrected "less than" to "more than." [Reprinted page 6H-17 as part of the double-sided Revision package.]
	C-23 – C-26	C-23 – C-26	Appendix C – Guide Signs-Freeways...	On page C-23, revised the sign code numbers for "E5-H2" and "E5-H2a" to "E5-H1b" and "E5-H1c," respectively. On page C-26, corrected the title by changing the font color from blue to black. [Reprinted pages C-24 and C-25 as part of the double-sided Revision package.]

**Ohio**  
**Manual of**  
**Uniform**  
**Traffic**  
**Control**  
**Devices**



**2005 Edition**  
**Revision 1**  
**December 23, 2009**  
**Effective January 15, 2010**

**Ohio Department of Transportation**  
**Office of Traffic Engineering**

Ohio Department of Transportation  
Office of Traffic Engineering  
1980 W. Broad St., P.O. Box 899  
Columbus, OH 43216-0899

Web addresses:

ODOT: <http://www.dot.state.oh.us/pages/home.aspx>

Office of Traffic Engineering:

<http://www.dot.state.oh.us/Divisions/HighwayOps/Traffic/Pages/OTEHomePage.aspx>

ODOT Publications (Design Reference Resource Center):

<http://www.dot.state.oh.us/drrc/Pages/default.aspx>

To purchase a copy of this manual, contact the ODOT Office of Contracts at the above address, or by phone at 1-800-459-3778. This Manual is currently provided free to State and local government agencies, and public libraries; however, this may change without notice.

An Equal Opportunity Employer

## PREFACE

The “Ohio Manual of Uniform Traffic Control Devices for Streets and Highways” (OMUTCD) has been established to provide a safe, uniform and efficient system of traffic control devices on all public streets and highways within the State of Ohio. This Manual was prepared pursuant to Section 4511.09 of the Ohio Revised Code (see Appendix B2). Standards described within this Manual may also be used by private agencies on facilities they control. In fact, it is recommended that such be done to encourage uniformity in the meaning of traffic control devices throughout the State.

This Manual is in substantial conformance with the 2003 Edition of the “Manual on Uniform Traffic Control Devices for Streets and Highways” (MUTCD) as published by the U.S. Department of Transportation, Federal Highway Administration (FHWA) and updated with Revision Numbers 1 and 2 incorporated, dated December 2007. Most of the text of the OMUTCD is identical to that of the national MUTCD, while some has been modified to meet State laws or to more closely reflect conditions and policies in Ohio. References in this Manual to State Statutes should be understood to refer to the Ohio Revised Code (O.R.C.).

Text in this Manual that is different from that in the MUTCD is shown using Arial font. For example, the text on this page is in Arial font. Text based on the MUTCD (except for Figures and Tables) is shown using Times font. See the address for AASHTO on the next page for an example of Times font. When text in the OMUTCD is a quote from the O.R.C. it is shown in italic Arial font.

The OMUTCD uses a dual system of units, showing both Metric and English units. **In Ohio, English units are the preferred system. Metric units are not used on traffic control signs.** A reminder note has been included in the footer for each chapter.

Detail drawings for traffic control signs, along with supplemental details pertaining to standard signs and designable guide signs, can be found in the “Sign Design Manual” published by the Ohio Department of Transportation (ODOT). The pavement marking alphabet and symbols are also shown in the “Sign Design Manual.”

Contact information for ordering the OMUTCD is provided on page ii. The OMUTCD, the ODOT “Traffic Engineering Manual” (TEM), and other ODOT publications are also available from the ODOT website at [www.dot.state.oh.us/drrc/Pages/default.aspx](http://www.dot.state.oh.us/drrc/Pages/default.aspx).

Improved designs and devices, signs for special applications and variations from standard sign designs and sizes which may be developed after the publication date of this Manual may be used in research or on an experimental basis. However, all such research and/or experimentation with new designs should be coordinated through ODOT (see Section 1A.10).

**Addresses for Publications Referenced in the OMUTCD**

American Association of State Highway and Transportation Officials (AASHTO)  
444 North Capitol Street, NW, Suite 225  
Washington, DC 20001  
[www.transportation.org](http://www.transportation.org)

American Railway Engineering and Maintenance-of-Way Association (AREMA)  
8201 Corporate Drive, Suite 1125  
Landover, MD 20785-2230  
[www.arena.org](http://www.arena.org)

Federal Highway Administration (FHWA)  
400 Seventh Street, SW, HOTO  
Washington, DC 20590  
[www.fhwa.dot.gov](http://www.fhwa.dot.gov)  
for the MUTCD: <http://mutcd.fhwa.dot.gov/>

Federal Highway Administration Report Center  
9701 Philadelphia Court, Unit Q  
Lanham, MD 20706  
Facsimile number: 301.577.1421  
E-mail: [report.center@fhwa.dot.gov](mailto:report.center@fhwa.dot.gov)

Illuminating Engineering Society (IES)  
120 Wall Street, Floor 17  
New York, NY 10005  
[www.iesna.org](http://www.iesna.org)

Institute of Makers of Explosives  
1120 19th Street, NW, Suite 310  
Washington, DC 20036-3605  
[www.ime.org](http://www.ime.org)

Institute of Transportation Engineers (ITE)  
1099 14th Street, NW, Suite 300 West  
Washington, DC 20005-3438  
[www.ite.org](http://www.ite.org)

International Organization for Standardization  
c/o Mr. Gerard Kuso  
Austrian Standards Institute  
Heinestrasse 38  
Postfach 130  
A-1021  
Wien, Austria  
[www.iso.ch](http://www.iso.ch)

ISEA - The International Safety Equipment Association  
1901 North Moore Street, Suite 808  
Arlington, VA 22209  
[www.safetyequipment.org](http://www.safetyequipment.org)

National Committee on Uniform Traffic Laws and Ordinances (NCUTLO)  
107 SouthWest Street, Suite 110  
Alexandria, VA 22314  
[www.ncutlo.org](http://www.ncutlo.org)

Occupational Safety and Health Administration (OSHA)  
U.S. Department of Labor  
200 Constitution Avenue, NW  
Washington, DC 20210  
[www.osha.gov](http://www.osha.gov)

Office of Transportation Operations  
Federal Highway Administration  
400 Seventh Street, SW  
Washington, DC 20590  
[www.ops.fhwa.dot.gov/siteindex.htm](http://www.ops.fhwa.dot.gov/siteindex.htm)

Transportation Research Board (TRB)  
The National Academies  
2101 Constitution Avenue, NW  
Washington, DC 20418  
[www.nas.edu/trb](http://www.nas.edu/trb)

U.S. Architectural and Transportation Barriers Compliance Board (The U.S. Access Board)  
1331 F Street, NW, Suite 1000  
Washington, DC 20004-1111  
[www.access-board.gov](http://www.access-board.gov)

### **Acknowledgments**

The Ohio Department of Transportation (ODOT) gratefully acknowledges the valuable assistance provided by the Federal Highway Administration (FHWA), the Ohio Section of the Institute of Transportation Engineers (Ohio ITE), the County Engineers Association of Ohio (CEAO), the Ohio Contractor's Association (OCA) and other transportation professionals in the development of this Manual.

Intentionally blank.

## OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES

### INTRODUCTION

**Standard:**

**As noted in Section 4511.01(QQ) of the Ohio Revised Code (O.R.C.), traffic control devices shall mean:**

***all flaggers, signs, signals, markings, and devices placed or erected by authority of a public body or official having jurisdiction, for the purpose of regulating, warning, or guiding traffic, including signs denoting names of streets and highways.***

**Support:**

The "Ohio Manual of Uniform Traffic Control Devices" (OMUTCD) has been developed pursuant to Section 4511.09 of the O.R.C. to establish standards for the use of traffic control devices in the State of Ohio. Sections 4511.10 and 4511.11 of the O.R.C. address the responsibilities that ODOT and local highway authorities have to place and maintain traffic control devices on all highways within their respective jurisdictions in conformance with the OMUTCD (see Appendix B2).

**Standard:**

**Any traffic control device design or application provision contained in this Manual shall be considered to be in the public domain. Traffic control devices contained in this Manual shall not be protected by a patent, trademark, or copyright, except for the Interstate Shield and any other items owned by FHWA.**

**Support:**

The need for uniform standards was recognized long ago. Ohio published its first recorded uniform traffic control standards manual in 1924, and subsequent editions and revisions of the Ohio Manual have in large part been updates to conform to changes in the national standards (see Table I-1). To encourage national uniformity, the American Association of State Highway Officials (AASHO), now known as the American Association of State Highway and Transportation Officials (AASHTO), published a manual for rural highways in 1927, and the National Conference on Street and Highway Safety (NCSHS) published a manual for urban streets in 1930. To meet the need for unification of the standards applicable to the different classes of road and street systems, a joint committee of AASHO and NCSHS developed and published the original edition of the national Manual on Uniform Traffic Control Devices (MUTCD) in 1935. That committee, now called the National Committee on Uniform Traffic Control Devices (NCUTCD), though changed from time to time in name, organization, and personnel, has been in continuous existence and has contributed to periodic revisions of the national Manual. However, since 1971 the FHWA has administered the national MUTCD.

**Standard:**

**The U.S. Secretary of Transportation, under authority granted by the Highway Safety Act of 1966, decreed that traffic control devices on all streets and highways open to public travel in accordance with 23 U.S.C. 109(d) and 402(a) in each State shall be in substantial conformance with the Standards issued or endorsed by the Federal Highway Administration (FHWA).**

**Support:**

23 CFR (Code of Federal Regulations) 655.603 adopts FHWA's "Manual on Uniform Traffic Control Devices" (MUTCD) as the national standard for any street, highway, or bicycle trail open to public travel in accordance with 23 U.S.C. 109(d) and 402(a).

Section 4511.09 of the Ohio Revised Code (see Appendix B2) requires the "Ohio Manual of Uniform Traffic Control Devices" to "correlate with, and so far as possible conform to" FHWA's national MUTCD.

The Standard, Guidance, Option, and Support material described in the OMUTCD provide the transportation professional with the information needed to make appropriate decisions regarding the use of traffic control devices on streets and highways. The material in this Manual is organized to differentiate between Standards that must be satisfied for the particular circumstances of a situation, Guidances that

should be followed for the particular circumstances of a situation, and Options that may be applicable for the particular circumstances of a situation.

Throughout this Manual the headings Standard, Guidance, Option, and Support are used to classify the nature of the text that follows. Figures, tables, and illustrations supplement the text and might constitute a Standard, Guidance, Option, or Support. The user needs to refer to the appropriate text to classify the nature of the figure, table, or illustration.

**Standard:**

**When used in this Manual, the text headings shall be defined as follows:**

- 1. Standard—a statement of required, mandatory, or specifically prohibitive practice regarding a traffic control device. All standards are labeled, and the text appears in bold type. The verb “shall” is typically used. Standards are sometimes modified by Options.**
- 2. Guidance—a statement of recommended, but not mandatory, practice in typical situations, with deviations allowed if engineering judgment or engineering study indicates the deviation to be appropriate. All Guidance statements are labeled, and the text appears in unbold type. The verb “should” is typically used. Guidance statements are sometimes modified by Options.**
- 3. Option—a statement of practice that is a permissive condition and carries no requirement or recommendation. Options may contain allowable modifications to a Standard or Guidance. All Option statements are labeled, and the text appears in unbold type. The verb “may” is typically used.**
- 4. Support—an informational statement that does not convey any degree of mandate, recommendation, authorization, prohibition, or enforceable condition. Support statements are labeled, and the text appears in unbold type. The verbs “shall,” “should,” and “may” are not used in Support statements.**

**Support:**

Throughout this Manual dimensions, distances, etc. are provided in both the International System of Units, a modernized version of the Metric system, and the English equivalent units (shown in parentheses).

**Standard:**

**The preferred system of measurement shall be English units. Metric legends shall not be used on traffic control signs.**

**Guidance:**

If the public agency should decide to use the International System of Units (Metric) the chosen units should be specified on plan drawings. The chosen unit of measurement should be made known to those responsible for designing, installing, or maintaining traffic control devices.

Except when a specific numeral is required by the text of a Section of this Manual, numerals shown on the sign images in the figures that specify quantities such as times, distances, speed limits, and weights should be regarded as examples only. When installing any of these signs, the numerals should be appropriately altered to fit the specific signing situation.

**Support:**

The following information will be useful when reference is being made to a specific portion of text in this Manual.

There are ten Parts in this Manual and each Part is comprised of one or more Chapters. Each Chapter is comprised of one or more Sections. Parts are given a numerical identification, such as Part 2-Signs. Chapters are identified by the Part number and a letter, such as Chapter 2B-Regulatory Signs. Sections are identified by the Chapter number and letter followed by a decimal point and a number, such as Section 2B.03-Size of Regulatory Signs.

Each Section is comprised of one or more paragraphs. The paragraphs are indented but are not identified by a number or letter. Paragraphs are counted from the beginning of each Section without regard to the

intervening text headings (Standard, Guidance, Option, or Support). Some paragraphs have lettered or numbered items. As an example of how to cite this Manual, the phrase “Not less than 12 m (40 ft) beyond the stop line” that appears on Page 4D-15 of this Manual would be referenced in writing as “Section 4D.15, P7, D1(a),” and would be verbally referenced as “Item D1(a) of Paragraph 7 of Section 4D.15.”

The MUTCD published by FHWA states that: “In accordance with 23 CFR 655.603(b)(1), States or other Federal agencies that have their own MUTCDs or Supplements shall revise these MUTCDs or Supplements to be in substantial conformance with changes to the National MUTCD within 2 years of issuance of the changes. Unless a particular device is no longer serviceable, non-compliant devices on existing highways and bikeways shall be brought into compliance with the current edition of the National MUTCD as part of the systematic upgrading of substandard traffic control devices (and installation of new required traffic control devices) required pursuant to the Highway Safety Program, 23 U.S.C. § 402(a). In cases involving Federal-aid projects for new highway or bikeway construction or reconstruction, the traffic control devices installed (temporary or permanent) shall be in conformance with the most recent edition of the National MUTCD before that highway is opened or re-opened to the public for unrestricted travel [23 CFR 655.603(d)(2)]. The FHWA has the authority to establish other target compliance dates for implementation of particular changes to the MUTCD [23 CFR 655.603(d)(4)].”

The target compliance dates established by the FHWA are as follows (the Part, Chapter and Section references noted correspond directly to Parts, Chapters and Sections in the OMUTCD):

Section 2A.09 Maintaining Minimum Retroreflectivity – new section effective January 22, 2008:

- 4 years for implementation and continued use of an assessment or management method that is designed to maintain traffic sign retroreflectivity at or above the established minimum levels;
- 7 years for replacement of regulatory, warning, and ground-mounted guide (except street name) signs that are identified using the assessment or management method as failing to meet the established minimum levels; and
- 10 years for replacement of street name signs and overhead guide signs that are identified using the assessment or management method as failing to meet the established minimum levels.

Section 2A.19 Lateral Offset—crashworthiness of sign supports—January 17, 2013 for roads with posted speed limit of 80 km/h (50 mph) or higher.

Section 2B.03 Size of Regulatory Signs—increased sign sizes and other changes to Table 2B-1—December 22, 2013.

Section 2B.04 STOP Sign (R1-1)—4-WAY plaque requirement—January 17, 2004.

Section 2B.06 STOP Sign Placement—signs mounted on back of STOP sign—December 22, 2013.

Section 2B.09 YIELD Sign Applications—changes in YIELD sign application criteria from the 1988 MUTCD—January 17, 2011.

Section 2B.10 YIELD Sign Placement—signs mounted on back of YIELD sign—December 22, 2013.

Section 2B.11 Yield Here to Pedestrians Signs (R1-5, R1-5a)—new section—December 22, 2013.

Section 2B.13 Speed Limit Sign (R2-1)—color of changeable message legend of YOUR SPEED legend—December 22, 2013.

Section 2B.25 Reversible Lane Control Signs (R3-9d, R3-9f through R3-9i)—removal of R3-9c and R3-9e signs—December 22, 2013.

Section 2B.26 Preferential Only Lane Signs (R3-10 through R3-15)—December 22, 2013.

Section 2B.27 Preferential Only Lanes for High-Occupancy Vehicles (HOVs)—new section in Millennium Edition—January 17, 2007.

Section 2B.28 Preferential Only Lane Sign Applications and Placement—December 22, 2013.

Section 2B.37 ONE WAY Signs (R6-1, R6-2)—placement requirement at intersecting alleys—January 17, 2008.

Section 2B.46 Photo Enforced Signs (R10-18, R10-19)—new section—December 22, 2013.

Section 2B.52 Hazardous Material Signs (R14-2, R14-3)—change in sign legend—December 22, 2013.

- Section 2C.04 Size of Warning Signs—increased sizes of W4-1, W5-2, W6-3, and W12-1 signs—January 17, 2008.
- Section 2C.04 Size of Warning Signs—sizes of W1 Series Arrows signs, W7 Series truck runaway signs, W12-2p low clearance signs, and W10-1 advance grade crossing sign—December 22, 2013.
- Section 2C.11 Truck Rollover Warning Signs (W1-13, W1-13a)—new section—December 22, 2013.
- Section 2C.16 NARROW BRIDGE Sign (W5-2)—elimination of symbol sign—December 22, 2013.
- Section 2C.25 PAVEMENT ENDS Sign (W8-3)—removal of symbol sign—January 17, 2011.
- Section 2C.26 Shoulder Signs (W8-4, W8-9, and W8-9a)—removal of symbol signs—January 17, 2011.
- Section 2C.30 Speed Reduction Signs (W3-5, W3-5a)—removal of R2-5 Series Reduced Speed Ahead signs and use of W3-5 or W3-5a warning signs instead—December 22, 2018.
- Section 2C.31 Merge Signs (W4-1, W4-5)—Entering Roadway Merge sign (W4-1a)—December 22, 2013.
- Section 2C.32 Added Lane Signs (W4-3, W4-6)—Entering Roadway Added Lane sign (W4-3a)—December 22, 2013.
- Section 2C.33 Lane Ends Signs (W4-2, W9-1, W9-2)—new design of W4-2 sign—December 22, 2013.
- Section 2C.34 Two-Way Traffic Sign (W6-3)—transition from one-way street—December 22, 2008.
- Section 2C.37 Intersection Warning Signs (W2-1 through W2-6)—new design of Circular Intersection (W2-6) sign—December 22, 2013.
- Section 2C.40 Vehicular Traffic Signs (W8-6, W11-1, W11-5, W11-5a, W11-6, W11-8, W11-10, W11-11, W11-12, W11-14)—new symbol signs W11-1, W11-5, W11-5a, W11-6, W11-11, and W11-14—December 22, 2013.
- Section 2C.41 Nonvehicular Signs (W11-2, W11-3, W11-4, W11-7, W11-9)—elimination of crosswalk lines from crossing signs and use of diagonal downward pointing arrow supplemental plaque (W16-7) if at the crossing—January 17, 2011.
- Section 2C.53 PHOTO ENFORCED Plaque (W16-10)—new section—December 22, 2013.
- Section 2D.38 Street Name Sign (D3-1)—symbol sizes, 150 mm (6 in) letter sizes for lettering on ground-mounted Street Name signs on roads that are not multi-lane streets with speed limits greater than 60 km/h (40 mph), other new provisions of Millennium Edition—January 9, 2012.
- Section 2D.38 Street Name Sign (D3-1)—letter sizes on ground-mounted signs on multi-lane streets with speed limits greater than 60 km/h (40 mph) and letter sizes on overhead-mounted signs—December 22, 2018.
- Section 2D.39 Advance Street Name Signs (D3-2)—new section in 2000 MUTCD and revisions in 2003 MUTCD—December 22, 2018.
- Section 2D.45 General Service Signs (D9 Series)—Traveler Info Call 511 (D12-5) sign, Channel 9 Monitored (D12-3) sign—December 22, 2013.
- Section 2D.46 Reference Location Signs (D10-1 through D10-3) and Intermediate Reference Location Signs (D10-1a through D10-3a)—location and spacing of Reference Location signs and design of Intermediate Reference Location signs—December 22, 2013.
- Section 2E.28 Interchange Exit Numbering—size of exit number plaque—January 17, 2008.
- Section 2E.28 Interchange Exit Numbering—LEFT on exit number plaques for left exits—December 22, 2018.
- Section 2E.30 Advance Guide Signs—advance placement distance—January 17, 2008.
- Section 2E.54 Reference Location Signs and Enhanced Reference Location Signs (D10-4, D10-5)—design of Enhanced Reference Location signs and Intermediate Enhanced Reference Location signs—December 22, 2013.
- Section 2E.59 Preferential Only Lane Signs—new section in 2003 Edition—December 22, 2013.
- Section 2F.05 Size of Lettering—minimum height of letters and numerals on specific service signs—January 17, 2011.

- Section 2I.03 EVACUATION ROUTE Sign (EM-1)—new design and size of EM-1 sign—December 22, 2018.
- Section 3B.01 Yellow Centerline Pavement Markings and Warrants—new section in Millennium Edition—January 3, 2003.
- Section 3B.03 Other Yellow Longitudinal Pavement Markings—spacing requirements for pavement marking arrows in two-way left-turn lanes—December 22, 2008.
- Section 3B.07 Warrants for Use of Edge Lines—new section in Millennium Edition—January 3, 2003.
- Section 3B.17 Crosswalk Markings—gap between transverse lines of a crosswalk—December 22, 2013.
- Section 3B.19 Pavement Word and Symbol Markings—typical spacing of lane-use arrows in two-way left-turn lanes shown in Figure 3B-7—December 22, 2008.
- Section 3C.01 Object Marker Design and Placement Height—width of stripes on Type 3 striped marker—December 22, 2013.
- Section 4D.01 General—location of signalized midblock crosswalks—December 22, 2013.
- Section 4D.05 Application of Steady Signal Indications—Item B.4 in STANDARD—December 22, 2008.
- Section 4D.12 Flashing Operation of Traffic Control Signals—duration of steady red clearance interval in change from red-red flashing mode to steady (stop-and-go) mode—December 22, 2013.
- Section 4E.06 Accessible Pedestrian Signals—new section in Millennium Edition—January 17, 2005.
- Section 4E.07 Countdown Pedestrian Signals—new section—December 22, 2013 for countdown pedestrian signal hardware; December 22, 2006 for operational requirements of countdown pedestrian signals.
- Section 4E.09 Accessible Pedestrian Signal Detectors—new section in Millennium Edition—January 17, 2005.
- Section 4E.10 Pedestrian Intervals and Signal Phases—pedestrian clearance time sufficient to travel to far side of the traveled way—December 22, 2008.
- Section 5C.05 NARROW BRIDGE Sign (W5-2)—elimination of symbol sign—December 22, 2013.
- Section 6D.01 Pedestrian Considerations—all new provisions for pedestrian accessibility—December 22, 2008.
- Section 6D.02 Accessibility Considerations—December 22, 2008.
- Section 6D.03 Worker Safety Considerations—high-visibility apparel requirements—December 22, 2006.
- Section 6E.02 High-Visibility Safety Apparel—high-visibility apparel requirements for flaggers—December 22, 2006.
- Section 6F.03 Sign Placement—crashworthiness of sign supports—January 17, 2005.
- Section 6F.58 Channelizing Devices—crashworthiness—January 17, 2005.
- Section 6F.59 Cones—width of retroreflective stripes—December 22, 2008.
- Section 6F.63 Type I, II, or III Barricades—crashworthiness—January 17, 2005.
- Section 6F.66 Longitudinal Channelizing Barricades—crashworthiness—January 17, 2005.
- Section 6F.82 Crash Cushions—crashworthiness—January 17, 2005.
- Section 7B.08 School Advance Warning Assembly (S1-1 with Supplemental Plaque)—use of AHEAD plaque (W16-9p) or distance plaque (W16-2 or W16-2a)—January 17, 2011.
- Section 7B.09 School Crosswalk Warning Assembly (S1-1 with Diagonal Arrow)—elimination of crosswalk lines from crossing signs and use of diagonal downward pointing arrow supplemental plaque (W16-7)—January 17, 2011.
- Section 7B.12 Reduced Speed School Zone Ahead Sign (S4-5, S4-5a)—December 22, 2018.
- Section 7E.04 Uniform of Adult Crossing Guards and Student Patrols—requirement for high-visibility apparel for adult crossing guards—December 22, 2008.
- Section 8B.03 Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1) and Number of Tracks Sign (R15-2)—retroreflective strip on crossbuck support—January 17, 2011.

Section 8B.04 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series)—removal of existing W10-6 series signs—January 17, 2006.

Section 8D.07 Traffic Control Signals at or Near Highway-Rail Grade Crossings—pre-signals—December 22, 2013.

Section 9B.04 Bicycle Lane Signs (R3-17, R3-17a, R3-17b)—deletion of preferential lane symbol (diamond) for bicycle lane signs—January 17, 2006.

Section 9B.17 Bicycle Warning Sign (W11-1)—elimination of crosswalk lines from crossing signs and use of diagonal downward pointing arrow supplemental plaque (W16-7) if at the crossing—January 17, 2011.

Chapter 9C Markings—deletion of preferential lane symbol (diamond) for bicycle pavement markings—January 17, 2007.

Part 10 Traffic Controls for Highway-Light Rail Transit Grade Crossings—automatic gates, flashing-light signals, and blank-out signs—January 17, 2011.

Section 10C.15 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series)—removal of existing W10-6 series signs—January 17, 2006.

**Option:**

In order for maintenance personnel to understand what to do when replacing a damaged non-compliant traffic control device, agencies may establish a policy regarding whether to replace the device in kind or to replace it with a compliant device.

**Support:**

Often it is desirable to upgrade to a compliant device at the time of this maintenance of a damaged device. However, it might be appropriate to replace the damaged non-compliant device in kind at the time of this maintenance activity if engineering judgment indicates that:

- A. One compliant device in the midst of a series of adjacent non-compliant devices could potentially be confusing to road users; and/or
- B. The anticipated schedule for replacement of the whole series of non-compliant devices will result in achieving timely compliance with the MUTCD.

**Table I-1. Evolution of the OMUTCD**

<b>Edition</b>	<b>Name</b>	<b>Approval</b>	<b>Effective Date</b>
1924	Manual of Standard Signs and Marker		5/24
1934	Manual of Standard Signs, Markers, and Pavement Marking		7/34
1943	Ohio Manual of Uniform Traffic Control Devices		1943
1952	Ohio Manual of Uniform Traffic Control Devices		3/52
1956	Ohio Manual of Uniform Traffic Control Devices		4/56
1962	Ohio Manual of Uniform Traffic Control Devices, Supplement (Part 7 reprint) (Using Journal Entry system to record Director's "approval.")	Vol. 47: pg 885; dated 8/27/62	8/27/62
1963	Ohio Manual of Uniform Traffic Control Devices	Vol. 48: pg 770; dated 9/19/63 Vol. 52: pg 151; dated 3/3/67 Vol. 53: pg 108; dated 2/5/68 Vol. 54: pg 873; dated 9/15/69 Vol. 56: pg 174; dated 2/19/71	9/19/63 3/25/67 3/29/68 10/31/69 3/15/71
1972	Ohio Manual of Uniform Traffic Control Devices for Streets and Highways — transition period from 1963 Edition to 1972 Edition; there was an overlap during this period between the two manual editions.  The 1975 revisions were distributed together on 7/1/1975.	Vol. 56: pg 997; dated 11/17/71 Vol. 57: pg 379; dated 4/13/72 Vol. 58: pg 179; dated 3/5/73 Vol. 58: pg 788; dated 8/3/73 Vol. 59: pg 1078; dated 11/1/74 Vol. 60: pg 311; dated 3/31/75 Vol. 60: pg 263; dated 3/13/75	1/3/72 5/31/72 4/25/73 9/10/73 11/1/74 3/31/75 7/1/75
1972	Ohio Manual of Uniform Traffic Control Devices The 1976 and both 1977 revisions were distributed together.  The 1992 revisions were distributed together on 7/27/1992.  (Journal Entries no longer used. Transmittal letter constitutes the Director's "approval.")	Vol. 61: pg 817; dated 8/11/76 Vol. 62: pg 739; dated 6/27/77 Vol. 62: pg 1081; dated 9/19/77 Vol. 64: pg 642; dated 6/27/79 Vol. 67: pg 752; dated 7/16/82 Vol. 71: pg 1085; dated 11/14/86 Vol. 75: pg 7; dated 5/22/90 Vol. 76: pg 3; dated 10/1/91 Vol. 77: pg 1; dated 7/7/92 Vol. 77: pg 1; dated 7/21/92 Vol. 79: pg 1; dated 6/6/94 Vol. 80: pg 14; dated 6/22/95 Vol. 81: pg 1; dated 9/10/96 Vol. 81: pg 1; dated 9/16/96 Adopted by Director 4/15/99	9/1/76 7/1/77 11/3/77 10/1/79 9/7/82 2/1/87 7/9/90 10/1/91 7/7/92 7/27/92 8/1/94 8/14/95 9/10/96 1/1/97 6/1/99
2003	Ohio Manual of Uniform Traffic Control Devices, 2003 Edition	8/1/03	9/1/03
2005	Ohio Manual of Uniform Traffic Control Devices, 2005 Edition	12/1/05	12/22/05
	Revision 1	December 23, 2009	1/15/10

**Table I-2. Revision Record for the 2003 and 2005 Editions of the OMUTCD**

Title	Date	Description	Effective Date
2003 Edition	August 1, 2003	New edition, updating the Manual to conform more closely to the revised and reformatted national Manual on uniform Traffic Control Devices, Millennium Edition, Revision 1 (published December 28, 2001), and to incorporate additional revisions. Part 1, General Provisions, Part 2, Signs, Part 3, Markings, and Part 9, bicycles have been revised and reformatted; Part 6, Signals and Illumination has been revised and replaced by new Part 4, Highway Traffic Signals; Part 7, Construction and Maintenance Operations has been revised and replaced by new Part 6, Temporary Traffic Control; Part 4, Islands and Part 5, Zones have been eliminated island information is now in Part 3, Markings, and zoning information is addressed in ODOT's "Traffic Engineering Manual"); and new Part 5, Low-Volume Roads, Part 7, School Areas, Part 8, Highway-Rail Grade Crossings and Part 10 Highway-Light Rail Transit Grade Crossings have been added. Also, Appendix A has been replaced with a new Appendix A, Appendix B has been revised and updated to Appendix B1 and Appendix B2, Appendix C has been temporarily eliminated, and provision for an Index has been added.	September 1, 2003
2005 Edition	December 1, 2005	New edition, updating each Part of the Manual to incorporate changes published by FHWA in the MUTCD 2003, and to incorporate additional Ohio revisions. Appendix A1, Appendix B1, and Appendix B2 have been updated. A sign index has been added in Appendix C.	December 22, 2005
2005 Edition Revision 1	December 23, 2009	Revision to incorporate changes published by FHWA in the MUTCD 2003 to address retro-reflectivity guidelines for highway signs. The Revision also included a few editorial corrections. Changes were made in the Preface, Introduction, Parts 1, 2 and 6, and Appendix C.	January 15, 2010

# OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES

## TABLE OF CONTENTS

### PREFACE

### INTRODUCTION

### TABLE OF CONTENTS

#### **PART 1. GENERAL**

Chapter 1A. General

#### **PART 2. SIGNS**

Chapter 2A. General

Chapter 2B. Regulatory Signs

Chapter 2C. Warning Signs

Chapter 2D. Guide Signs—Conventional Roads

Chapter 2E. Guide Signs—Freeways and Expressways

Chapter 2F. Specific Service Signs

Chapter 2G. Tourist-Oriented Directional Signs

Chapter 2H. Recreational and Cultural Interest Area Signs

Chapter 2I. Emergency Management Signing

#### **PART 3. MARKINGS**

Chapter 3A. General

Chapter 3B. Pavement and Curb Markings

Chapter 3C. Object Markers and End-of-Roadway Markers

Chapter 3D. Delineators

Chapter 3E. Colored Pavements

Chapter 3F. Barricades and Channelizing Devices

Chapter 3G. Islands

#### **PART 4. HIGHWAY TRAFFIC SIGNALS**

Chapter 4A. General

Chapter 4B. Traffic Control Signals—General

Chapter 4C. Traffic Control Signal Needs Studies

Chapter 4D. Traffic Control Signal Features

Chapter 4E. Pedestrian Control Features

Chapter 4F. Traffic Control Signals for Emergency Vehicle Access

Chapter 4G. Traffic Control Signals for One-Lane, Two-Way Facilities

Chapter 4H. Traffic Control Signals for Freeway Entrance Ramps

Chapter 4I. Traffic Control for Movable Bridges

Chapter 4J. Lane-Use Control Signals

Chapter 4K. Flashing Beacons

Chapter 4L. In-Roadway Lights

#### **PART 5. TRAFFIC CONTROL DEVICES FOR LOW-VOLUME ROADS**

Chapter 5A. General

Chapter 5B. Regulatory Signs

Chapter 5C. Warning Signs

Chapter 5D. Guide Signs

Chapter 5E. Markings

- Chapter 5F. Traffic Control for Highway-Rail Grade Crossings  
 Chapter 5G. Temporary Traffic Control Zones

**PART 6. TEMPORARY TRAFFIC CONTROL**

- Chapter 6A. General  
 Chapter 6B. Fundamental Principles  
 Chapter 6C. Temporary Traffic Control Elements  
 Chapter 6D. Pedestrian and Worker Safety  
 Chapter 6E. Flagger Control  
 Chapter 6F. Temporary Traffic Control Zone Devices  
 Chapter 6G. Type of Temporary Traffic Control Zone Activities  
 Chapter 6H. Typical Applications  
 Chapter 6I. Control of Traffic Through Traffic Incident Management Areas

**PART 7. TRAFFIC CONTROLS FOR SCHOOL AREAS**

- Chapter 7A. General  
 Chapter 7B. Signs  
 Chapter 7C. Markings  
 Chapter 7D. Signals  
 Chapter 7E. Crossing Supervision  
 Chapter 7F. Grade-Separated Crossings

**PART 8. TRAFFIC CONTROLS FOR HIGHWAY-RAIL GRADE CROSSINGS**

- Chapter 8A. General  
 Chapter 8B. Signs and Markings  
 Chapter 8C. Illumination  
 Chapter 8D. Flashing-Light Signals, Gates, and Traffic Control Signals

**PART 9. TRAFFIC CONTROLS FOR BICYCLE FACILITIES**

- Chapter 9A. General  
 Chapter 9B. Signs  
 Chapter 9C. Markings  
 Chapter 9D. Signals

**PART 10. TRAFFIC CONTROLS FOR HIGHWAY-LIGHT RAIL TRANSIT GRADE CROSSINGS**

- Chapter 10A. General  
 Chapter 10B. Highway-Light Rail Transit Grade Crossing Control Systems  
 Chapter 10C. Signs, Illumination, and Markings  
 Chapter 10D. Highway-Light Rail Transit Active Traffic Control Grade Crossing Systems

**APPENDIX A LEGISLATION AND RULINGS RELATED TO THE NATIONAL MUTCD**

- Appendix A1 Congressional Legislation Regarding the National MUTCD

**APPENDIX B OHIO REVISED CODE MATERIAL RELATED TO THE OMUTCD**

- Appendix B1 Cross-Reference Guide to the Ohio Revised Code  
 Appendix B2 Ohio Revised Code Sections

**APPENDIX C SIGNING INDEX**

- Regulatory Signs  
 Warning Signs  
 Guide Signs – Marker Series  
 Guide Signs – Directional Series  
 Guide Signs – Information Series  
 Guide Signs – Freeways, Expressways and Miscellaneous

Emergency Management Series  
Recreational and Cultural Interest Series  
Object Markers and End-of-Roadway Markers  
School Area Signs

**INDEX**

**(Future)**

Intentionally blank.

**PART 1. GENERAL**  
**TABLE OF CONTENTS**

		<u>Page</u>
<b>CHAPTER 1A.</b>	<b>GENERAL</b>	
Section 1A.01	Purpose of Traffic Control Devices .....	1A-1
Section 1A.02	Principles of Traffic Control Devices.....	1A-1
Section 1A.03	Design of Traffic Control Devices .....	1A-2
Section 1A.04	Placement and Operation of Traffic Control Devices .....	1A-2
Section 1A.05	Maintenance of Traffic Control Devices .....	1A-3
Section 1A.06	Uniformity of Traffic Control Devices.....	1A-3
Section 1A.07	Responsibility for Traffic Control Devices .....	1A-3
Section 1A.08	Authority for Placement of Traffic Control Devices.....	1A-3
Section 1A.09	Engineering Study and Engineering Judgment.....	1A-4
Section 1A.10	Interpretations, Experimentations, Changes, and Interim Approvals .....	1A-4
Section 1A.11	Relation to Other Publications .....	1A-8
Section 1A.12	Color Code.....	1A-11
Section 1A.13	Definitions of Words and Phrases in This Manual.....	1A-11
Section 1A.14	Abbreviations Used on Traffic Control Devices .....	1A-18
 <b><u>FIGURES</u></b>		
<b>CHAPTER 1A.</b>	<b>GENERAL</b>	
Figure 1A-1	Example of Process for Requesting and Conducting Experimentations for New Traffic Control Devices .....	1A-6
Figure 1A-2	Example of Process for Incorporating New Traffic Control Devices into the MUTCD .....	1A-9
 <b><u>TABLES</u></b>		
<b>CHAPTER 1A.</b>	<b>GENERAL</b>	
Table 1A-1	Acceptable Abbreviations.....	1A-19
Table 1A-2	Abbreviations That Are Acceptable Only with a Prompt Word.....	1A-20
Table 1A-3	Unacceptable Abbreviations.....	1A-21

Intentionally blank.

## CHAPTER 1A. GENERAL

### Section 1A.01 Purpose of Traffic Control Devices

Support:

The purpose of traffic control devices, as well as the principles for their use, is to promote highway safety and efficiency by providing for the orderly movement of all road users on streets and highways throughout the Nation.

Traffic control devices notify road users of regulations and provide warning and guidance needed for the reasonably safe, uniform, and efficient operation of all elements of the traffic stream.

**Standard:**

**Traffic control devices or their supports shall not bear any advertising message or any other message that is not related to traffic control.**

Support:

Tourist-oriented directional signs and Specific Service signs are not considered advertising; rather, they are classified as motorist service signs.

### Section 1A.02 Principles of Traffic Control Devices

Support:

This Manual contains the basic principles that govern the design and use of traffic control devices for all streets and highways open to public travel regardless of type or class or the public agency having jurisdiction. This Manual's text specifies the restriction on the use of a device if it is intended for limited application or for a specific system. It is important that these principles be given primary consideration in the selection and application of each device.

Guidance:

To be effective, a traffic control device should meet five basic requirements:

- A. Fulfill a need;
- B. Command attention;
- C. Convey a clear, simple meaning;
- D. Command respect from road users; and
- E. Give adequate time for proper response.

Design, placement, operation, maintenance, and uniformity are aspects that should be carefully considered in order to maximize the ability of a traffic control device to meet the five requirements listed in the previous paragraph. Vehicle speed should be carefully considered as an element that governs the design, operation, placement, and location of various traffic control devices.

Support:

The definition of the word "speed" varies depending on its use. The definitions of specific speed terms are contained in Section 1A.13.

Guidance:

The actions required of road users to obey regulatory devices are specified by the Ohio Revised Code (O.R.C.), or in cases not covered by State statute, by local ordinance or resolution.

The proper use of traffic control devices should provide the reasonable and prudent road user with the information necessary to reasonably safely and lawfully use the streets, highways, pedestrian facilities, and bikeways.

**Support:**

Uniformity of the meaning of traffic control devices is vital to their effectiveness. The meanings ascribed to devices in this Manual are in general accord with the publications mentioned in Section 1A.11.

Additional information regarding related sections of the Ohio Revised Code (O.R.C.) is provided in Appendices B1 and B2.

**Section 1A.03 Design of Traffic Control Devices****Guidance:**

Devices should be designed so that features such as size, shape, color, composition, lighting or retroreflection, and contrast are combined to draw attention to the devices; that size, shape, color, and simplicity of message combine to produce a clear meaning; that legibility and size combine with placement to permit adequate time for response; and that uniformity, size, legibility, and reasonableness of the message combine to command respect.

**Standard:**

**All symbols shall be unmistakably similar to or mirror images of the symbol signs adopted by FHWA and shown in the “Standard Highway Signs” book published by FHWA (see Section 1A.11). The symbols adopted for use in Ohio are shown in the “Sign Design Manual” (SDM) published by ODOT (see Section 1A.11). Symbols and colors shall not be modified unless otherwise stated herein. All symbols and colors for signs not shown in the “Standard Highway Signs” book shall follow the procedures for experimentation and change described in Section 1A.10.**

**Guidance:**

Aspects of a device’s design should be modified only if there is a demonstrated need.

**Support:**

An example of modifying a device’s design would be to modify the Side Road (W2-2) sign to show a second offset intersecting road.

**Option:**

Highway agencies may develop word message signs to notify road users of special regulations or to warn road users of a situation that might not be readily apparent. Unlike symbol signs and colors, new word message signs may be used without the need for experimentation. With the exception of symbols and colors, minor modifications in the specific design elements of a device may be made provided the essential appearance characteristics are preserved. Although the standard design of symbol signs cannot be modified, it may be appropriate to change the orientation of the symbol to better reflect the direction of travel.

**Section 1A.04 Placement and Operation of Traffic Control Devices****Guidance:**

Placement of a traffic control device should be within the road user’s view so that adequate visibility is provided. To aid in conveying the proper meaning, the traffic control device should be appropriately positioned with respect to the location, object, or situation to which it applies. The location and legibility of the traffic control device should be such that a road user has adequate time to make the proper response in both day and night conditions.

Traffic control devices should be placed and operated in a uniform and consistent manner.

Unnecessary traffic control devices should be removed. The fact that a device is in good physical condition should not be a basis for deferring needed removal or change.

### **Section 1A.05 Maintenance of Traffic Control Devices**

#### Guidance:

Functional maintenance of traffic control devices should be used to determine if certain devices need to be changed to meet current traffic conditions.

Physical maintenance of traffic control devices should be performed to retain the legibility and visibility of the device, and to retain the proper functioning of the device.

#### Support:

Clean, legible, properly mounted devices in good working condition command the respect of road users.

### **Section 1A.06 Uniformity of Traffic Control Devices**

#### Support:

Uniformity of devices simplifies the task of the road user because it aids in recognition and understanding, thereby reducing perception/reaction time. Uniformity assists road users, law enforcement officers, and traffic courts by giving everyone the same interpretation. Uniformity assists public highway officials through efficiency in manufacture, installation, maintenance, and administration. Uniformity means treating similar situations in a similar way. The use of uniform traffic control devices does not, in itself, constitute uniformity. A standard device used where it is not appropriate is as objectionable as a nonstandard device; in fact, this might be worse, because such misuse might result in disrespect at those locations where the device is needed and appropriate.

### **Section 1A.07 Responsibility for Traffic Control Devices**

#### Standard:

**The responsibility for the design, placement, operation, maintenance, and uniformity of traffic control devices shall rest with the public agency or the official having jurisdiction. In the State of Ohio, these responsibilities shall be as established in Sections 4511.09, 4511.10 and 4511.11 of the Ohio Revised Code (see Appendix B2).**

#### Support:

As provided in Section 4511.09 of the Ohio Revised Code (see Appendix B2), the "Ohio Manual of Uniform Traffic Control Devices" has been adopted by the Ohio Department of Transportation to provide for a "uniform system of traffic control devices...for use upon highways in this state."

### **Section 1A.08 Authority for Placement of Traffic Control Devices**

#### Standard:

**Traffic control devices, advertisements, announcements, and other signs or messages within the highway right-of-way shall be placed only as authorized by a public authority or the official having jurisdiction, for the purpose of regulating, warning, or guiding traffic.**

**When the public agency or the official having jurisdiction over a street or highway has granted proper authority, others such as contractors and public utility companies shall be permitted to install temporary traffic control devices in temporary traffic control zones. Such traffic control devices shall conform with the Standards of this Manual.**

#### Guidance:

Any unauthorized traffic control device or other sign or message placed on the highway right-of-way by a private organization or individual constitutes a public nuisance and should be removed. All unofficial or nonessential traffic control devices, signs, or messages should be removed.

**Support:**

Section 4511.16 of the Ohio Revised Code (O.R.C.) prohibits the display of any unauthorized sign, signal, marking or device which interferes with the effectiveness of any official traffic control device and permits its removal by the authority having jurisdiction over the street or highway (see Appendix B2).

**Standard:**

**All regulatory traffic control devices shall be supported by laws, ordinances, or regulations.**

**Support:**

Provisions of this Manual are based upon the concept that effective traffic control depends upon both appropriate application of the devices and reasonable enforcement of the regulations.

**Section 1A.09 Engineering Study and Engineering Judgment****Standard:**

**This Manual describes the application of traffic control devices, but shall not be a legal requirement for their installation.**

**Guidance:**

The decision to use a particular device at a particular location should be made on the basis of either an engineering study or the application of engineering judgment. Thus, while this Manual provides Standards, Guidance, and Options for design and application of traffic control devices, this Manual should not be considered a substitute for engineering judgment.

Engineering judgment should be exercised in the selection and application of traffic control devices, as well as in the location and design of the roads and streets that the devices complement. Jurisdictions with responsibility for traffic control that do not have engineers on their staffs should seek engineering assistance from others, such as the Ohio Department of Transportation (ODOT), their County, a nearby large City, or a traffic engineering consultant.

**Section 1A.10 Interpretations, Experimentations, Changes, and Interim Approvals****Standard:**

**Design, application, and placement of traffic control devices other than those adopted in this Manual shall be prohibited unless the provisions of this Section are followed.**

**Support:**

Continuing advances in technology will produce changes in the highway, vehicle, and road user proficiency; therefore, portions of the system of traffic control devices in this Manual will require updating. In addition, unique situations often arise for device applications that might require interpretation or clarification of this Manual. It is important to have a procedure for recognizing these developments and for introducing new ideas and modifications into the system.

**Standard:**

**Requests for any permission to experiment or interim approval shall be sent to the Federal Highway Administration (FHWA), Office of Transportation Operations, 400 Seventh Street, SW, HOTO, Washington, DC 20590. A copy of the request shall be sent to the Administrator of the Ohio Department of Transportation (ODOT), Office of Traffic Engineering at 1980 West Broad St., P.O. Box 899, Columbus, Ohio 43216-0899.**

**Requests for any interpretation or change shall be sent to the Ohio Department of Transportation (ODOT), Office of Traffic Engineering.**

**Support:**

An interpretation includes a consideration of the application and operation of standard traffic control devices, official meanings of standard traffic control devices, or the variations from standard device designs.

**Guidance:**

Requests for an interpretation of this Manual should contain the following information:

- A. A concise statement of the interpretation being sought;
- B. A description of the condition that provoked the need for an interpretation;
- C. Any illustration that would be helpful to understand the request; and
- D. Any supporting research data that is pertinent to the item to be interpreted.

**Support:**

Requests to experiment include consideration of field deployment for the purpose of testing or evaluating a new traffic control device, its application or manner of use, or a provision not specifically described in this Manual.

A request for permission to experiment will be considered only when submitted by the public agency or private toll facility responsible for the operation of the road or street on which the experiment is to take place.


A diagram indicating the process for experimenting with traffic control devices is shown in Figure 1A-1.

**Guidance:**

The request for permission to experiment should contain the following:

- A. A statement indicating the nature of the problem.
- B. A description of the proposed change to the traffic control device or application of the traffic control device, how it was developed, the manner in which it deviates from the standard, and how it is expected to be an improvement over existing standards.
- C. Any illustration that would be helpful to understand the traffic control device or use of the traffic control device.
- D. Any supporting data explaining how the traffic control device was developed, if it has been tried, in what ways it was found to be adequate or inadequate, and how this choice of device or application was derived.
- E. A legally binding statement certifying that the concept of the traffic control device is not protected by a patent or copyright. (An example of a traffic control device concept would be countdown pedestrian signals in general. Ordinarily an entire general concept would not be patented or copyrighted, but if it were it would not be acceptable for experimentation unless the patent or copyright owner signs a waiver of rights acceptable to the FHWA. An example of a patented or copyrighted specific device within the general concept of countdown pedestrian signals would be a manufacturer's design for its specific brand of countdown signal, including the design details of the housing or electronics that are unique to that manufacturer's product. As long as the general concept is not patented or copyrighted, it is acceptable for experimentation to incorporate the use of one or more patented devices of one or several manufacturers.)
- F. The time period and location(s) of the experiment.
- G. A detailed research or evaluation plan that must provide for close monitoring of the experimentation, especially in the early stages of its field implementation. The evaluation plan should include before and after studies as well as quantitative data describing the performance of the experimental device.
- H. An agreement to restore the site of the experiment to a condition that complies with the provisions of this Manual within 3 months following the end of the time period of the experiment. This agreement must also provide that the agency sponsoring the experimentation will terminate the experimentation at any time that it determines significant safety concerns are directly or indirectly attributable to the experimentation. The FHWA's Office of Transportation Operations has the right to terminate approval of the experimentation at any time if there is an indication of safety concerns. If, as a result of the experimentation, a request is made that this Manual be changed to include the device or application being experimented with, the device or application will be permitted to remain in place until an official rulemaking action has occurred.

**Figure 1A-1. Example of Process for Requesting and Conducting Experimentations for New Traffic Control Devices**



- I. An agreement to provide semiannual progress reports for the duration of the experimentation, and an agreement to provide a copy of the final results of the experimentation to the FHWA's Office of Transportation Operations within 3 months following completion of the experimentation. The FHWA's Office of Transportation Operations has the right to terminate approval of the experimentation if reports are not provided in accordance with this schedule.

Support:

Requests for changes to the Manual include consideration of a new device to replace a present standard device, an additional device to be added to the list of standard devices, or a revision to a traffic control device application or placement criteria.

Guidance:

Requests for a change to this Manual should contain the following information:

- A. A statement indicating what change is proposed;
- B. Any illustration that would be helpful to understand the request; and
- C. Any supporting research data that is pertinent to the item to be reviewed.

Support:

Requests for interim approval include consideration of allowing interim use, pending official rulemaking, of a new traffic control device, a revision to the application or manner of use of an existing traffic control device, or a provision not specifically described in this Manual. If granted, interim approval will result in the traffic control device or application being placed into the next scheduled rulemaking process for revisions to this Manual. The device or application will be permitted to remain in place, under any conditions established in the interim approval, until an official rulemaking action has occurred.

Interim approval is considered based on the results of successful experimentation, results of analytical or laboratory studies, and/or review of non-U.S. experience with a traffic control device or application. Interim approval considerations include an assessment of relative risks, benefits, and costs. Interim approval includes conditions that jurisdictions agree to comply with in order to use the traffic control device or application until an official rulemaking action has occurred.

Guidance:

The request for permission to place a traffic control device under interim approval should contain the following:

- A. A statement indicating the nature of the problem.
- B. A description of the proposed change to the traffic control device or application of the traffic control device, how it was developed, the manner in which it deviates from the standard, and how it is expected to be an improvement over existing standards.
- C. The location(s) where it will be used and any illustration that would be helpful to understand the traffic control device or use of the traffic control device.
- D. A legally-binding statement certifying that the concept of the traffic control device is not protected by a patent or copyright. (An example of a traffic control device concept would be countdown pedestrian signals in general. Ordinarily an entire general concept would not be patented or copyrighted, but if it were it would not be acceptable for interim approval unless the patent or copyright owner signs a waiver of rights acceptable to the FHWA. An example of a patented or copyrighted specific device within the general concept of countdown pedestrian signals would be a manufacturer's design for its specific brand of countdown signal, including the design details of the housing or electronics that are unique to that manufacturer's product. Interim approval of a specific patented or copyrighted product is not acceptable.)
- E. A detailed completed research or evaluation on this traffic control device.
- F. An agreement to restore the site(s) of the interim approval to a condition that complies with the provisions in this Manual within 3 months following the issuance of a final rule on this traffic control device. This agreement must also provide that the agency sponsoring the interim approval will terminate use of the device or application installed under the interim approval at any time that it

determines significant safety concerns are directly or indirectly attributable to the device or application. The FHWA's Office of Transportation Operations has the right to terminate the interim approval at any time if there is an indication of safety concerns.

Option:

The Ohio Department of Transportation (ODOT) may submit a request for interim approval for all jurisdictions in the State, as long as the request contains the information listed in the Guidance above.

**Standard:**

**Once an interim approval is granted to any jurisdiction for a particular traffic control device or application, subsequent jurisdictions shall be granted interim approval for that device or application by submitting a letter to the FHWA Office of Transportation Operations indicating they will abide by Item F above and the specific conditions contained in the original interim approval.**

**A local jurisdiction using a traffic control device or application under an interim approval that was granted either directly to that jurisdiction or on a statewide basis based on the State's request shall inform the State of the locations of such use.**

Support:

A diagram outlining FHWA's process for incorporating new traffic control devices into the national MUTCD is shown in Figure 1A-2.

For additional information concerning interpretations, experimentation, changes, or interim approvals, contact the ODOT, Office of Traffic Engineering at the address provided on page ii.

### **Section 1A.11 Relation to Other Publications**

**Standard:**

**To the extent that they are incorporated by specific reference, the latest editions of the following publications, or those editions specifically noted, shall be a part of this Manual: the current "Sign Design Manual" (SDM), published by ODOT; and "Color Specifications for Retroreflective Sign and Pavement Marking Materials" (appendix to subpart F of Part 655 of Title 23 of the Code of Federal Regulations).**

Support:

The SDM includes standard alphabets and symbols for highway signs and pavement markings.

For information about publications from the Federal Highway Administration, visit FHWA's MUTCD website at <http://mutcd.fhwa.dot.gov>, or write to the FHWA, 400 Seventh Street, SW, HOTO, Washington, DC 20590.

For information about publications published by the Ohio Department of Transportation (ODOT), visit the ODOT reference resource website at [www.dot.state.oh.us/drrc](http://www.dot.state.oh.us/drrc), or write to the ODOT Office of Contracts, 1980 West Broad Street, P.O. Box 899, Columbus, Ohio 43216-0899.


The publication entitled "Federal-Aid Highway Program Guidance on High Occupancy Vehicle (HOV) Lanes" is available at <http://www.fhwa.dot.gov/operations/hovguide01.htm>, or write to the FHWA, 400 Seventh Street, SW, HOTM, Washington, DC 20590.

The publication entitled "Maintaining Traffic Sign Retroreflectivity" (2007 Edition) is available at [www.fhwa.dot.gov/retro](http://www.fhwa.dot.gov/retro), or write to the FHWA, 1200 New Jersey Avenue, SE, HSA-1, Washington, DC 20590.

Other publications that are useful sources of information with respect to use of this Manual are listed below. See the Preface of this Manual for ordering information for the following publications:

1. "A Policy on Geometric Design of Highways and Streets," 2001 Edition (American Association of State Highway and Transportation Officials—AASHTO)
2. "Guide for the Development of Bicycle Facilities," 1999 Edition (AASHTO)
3. "Guide to Metric Conversion," 1993 Edition (AASHTO)

**Figure 1A-2. Example of Process for Incorporating New Traffic Control Devices into the MUTCD**



4. "Guidelines for the Selection of Supplemental Guide Signs for Traffic Generators Adjacent to Freeways," 2001 Edition (AASHTO)
5. "List of Control Cities for Use in Guide Signs on Interstate Highways," 2001 Edition (AASHTO)
6. "Roadside Design Guide," 2001 Edition (AASHTO)
7. "Standard Specifications for Movable Highway Bridges," 1988 Edition (AASHTO)
8. "Traffic Engineering Metric Conversion Folders—Addendum to the Guide to Metric Conversion," 1993 Edition (AASHTO)
9. "2000 AREMA Communications & Signals Manual," American Railway Engineering & Maintenance-of-Way Association (AREMA)
10. "Designing Sidewalks and Trails for Access—Part 2—Best Practices Design Guide," 2001 Edition (FHWA) [Publication No. FHWA-EP-01-027]
11. "Practice for Roadway Lighting," RP-8, 2001, Illuminating Engineering Society (IES)
12. "Safety Guide for the Prevention of Radio Frequency Radiation Hazards in the Use of Commercial Electric Detonators (Blasting Caps)," Safety Library Publication No. 20, Institute of Makers of Explosives
13. "American National Standard for High-Visibility Safety Apparel," (ANSI/ISEA 107-1999), 1999 Edition, ISEA - The Safety Equipment Association
14. "Manual of Traffic Signal Design," 1998 Edition (Institute of Transportation Engineers—ITE)
15. "Manual of Transportation Engineering Studies," 1994 Edition (ITE)
16. "Pedestrian Traffic Control Signal Indications," 1985 Edition (ITE)
17. "Preemption of Traffic Signals at or Near Railroad Grade Crossings with Active Warning Devices," (ITE)
18. "Purchase Specification for Flashing and Steady Burn Warning Lights," 1981 Edition (ITE)
19. "School Trip Safety Program Guidelines," 1984 Edition (ITE)
20. "Traffic Detector Handbook," 1991 Edition (ITE)
21. "Traffic Engineering Handbook," 1999 Edition (ITE)
22. "Traffic Signal Lamps," 1980 Edition (ITE)
23. "Traffic Control Devices Handbook," 2001 Edition (ITE)
24. "Vehicle Traffic Control Signal Heads," Part 1—1985 Edition; Part 2—1998 Edition (ITE)
25. "Uniform Vehicle Code (UVC) and Model Traffic Ordinance," 2000 Edition (National Committee on Uniform Traffic Laws and Ordinances)
26. "Occupational Safety and Health Administration Regulations (Standards - 29 CFR), General Safety and Health Provisions - 1926.20," amended June 30, 1993, Occupational Safety and Health Administration (OSHA)
27. "Highway Capacity Manual," 2000 Edition (Transportation Research Board—TRB)
28. "Recommended Procedures for the Safety Performance Evaluation of Highway Features," (NCHRP Report 350), 1993 Edition (Transportation Research Board - TRB)
29. "Accessible Pedestrian Signals," A-37, 1998 Edition, U.S. Architectural and Transportation Barriers Compliance Board (The U.S. Access Board)
30. "Building a True Community—Final Report—Public Rights-of-Way Access Advisory Committee (PRWAAC)," 2001 Edition (The U.S. Access Board)
31. "The Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)," July 1998 Edition (The U.S. Access Board)
32. "Highway-Rail Intersection Architecture," U.S. Department of Transportation, Federal Railroad Administration (USDOT/FRA)
33. "Ohio Revised Code" (O.R.C.)
34. "Traffic Engineering Manual" (TEM), current Edition (ODOT)
35. "Manual on Uniform Traffic Control Devices" (MUTCD), 2003 Edition (FHWA)
36. "Location & Design Manual, Volume One – Roadway Design," current Edition (ODOT)

## **Section 1A.12 Color Code**

### **Support:**

The following color code establishes general meanings for 10 colors of a total of 13 colors that have been identified as being appropriate for use in conveying traffic control information. Central values and tolerance limits for each color are available from the Federal Highway Administration, 400 Seventh Street, SW, HOTO, Washington, DC 20590, and at FHWA's MUTCD website at <http://mutcd.fhwa.dot.gov>.

The three colors for which general meanings have not yet been assigned are being reserved for future applications that will be determined only by FHWA after consultation with the States, the engineering community, and the general public. The meanings described in this Section are of a general nature. More specific assignments of colors are given in the individual Parts of this Manual relating to each class of devices.

### **Standard:**

**The general meaning of the 13 colors shall be as follows:**

- A. Black—regulation**
- B. Blue—road user services guidance, tourist information, and evacuation route**
- C. Brown—recreational and cultural interest area guidance**
- D. Coral—unassigned**
- E. Fluorescent Pink—incident management**
- F. Fluorescent Yellow-Green—pedestrian warning, bicycle warning, playground warning, school bus and school warning**
- G. Green—indicated movements permitted, direction guidance**
- H. Light Blue—unassigned**
- I. Orange—temporary traffic control**
- J. Purple—unassigned**
- K. Red—stop or prohibition**
- L. White—regulation**
- M. Yellow—warning**

## **Section 1A.13 Definitions of Words and Phrases in This Manual**

### **Standard:**

Unless otherwise defined herein, or in the other Parts of this Manual, definitions contained in the most recent edition of the "Ohio Revised Code," "AASHTO Transportation Glossary (Highway Definitions)," and other publications specified in Section 1A.11 are also incorporated and adopted by reference.

**The following words and phrases, when used in this Manual, shall have the following meanings:**

- 1. Active Grade Crossing Warning System—the flashing-light signals, with or without warning gates, together with the necessary control equipment used to inform road users of the approach or presence of trains at highway-rail or highway-light rail transit grade crossings.**
- 2. Approach—all lanes of traffic moving towards an intersection or a midblock location from one direction, including any adjacent parking lane(s).**
- 3. Arterial Highway (Street)—any *United States* or *state* numbered route, controlled access highway, or other major radial or circumferential street or highway designated by local authorities within their respective jurisdictions as part of a major arterial system of streets or highways. [4511.01(CCC), O.R.C.]**
- 4. Average Day—a day representing traffic volumes normally and repeatedly found at a location. Where volumes are primarily influenced by employment, the average day is typically a weekday. When volumes are primarily influenced by entertainment or recreation, the average day is typically a weekend day.**

5. **Beacon**—a highway traffic signal with one or more signal sections that operates in a flashing mode.
6. **Bicycle**—*every device, other than a tricycle designed solely for use as a play vehicle by a child, propelled solely by human power upon which any person may ride having either two tandem wheels, or one wheel in the front and two wheels in the rear, any of which is more than fourteen inches in diameter. [4511.01(G), O.R.C.]*
7. **Bicycle Lane**—a portion of a roadway that has been designated by signs and pavement markings for preferential or exclusive use by bicyclists.
8. **Centerline Markings**—the yellow pavement marking line(s) that delineates the separation of traffic lanes that have opposite directions of travel on a roadway. These markings need not be at the geometrical center of the pavement.
9. **Changeable Message Sign**—a sign that is capable of displaying more than one message, changeable manually, by remote control, or by automatic control. These signs are referred to as Dynamic Message Signs in the National Intelligent Transportation Systems (ITS) Architecture.
10. **Channelizing Line Marking**—a wide or double solid white line used to form islands where traffic in the same direction of travel is permitted on both sides of the island.
11. **Circular Intersection**—an intersection that has an island, generally circular in design, located in the center of the intersection where traffic passes to the right of the island. Circular intersections include roundabouts, rotaries, and traffic circles.
12. **Clear Zone**—the total roadside border area, starting at the edge of the traveled way, that is available for an errant driver to stop or regain control of a vehicle. This area might consist of a shoulder, a recoverable slope, and/or a nonrecoverable, traversable slope with a clear run-out area at its toe.
13. **Collector Highway**—a term denoting a highway that in rural areas connects small towns and local highways to arterial highways, and in urban areas provides land access and traffic circulation within residential, commercial, and business areas and connects local highways to the arterial highways.
14. **Concurrent Flow HOV Lane**—an HOV lane that is operated in the same direction as the adjacent mixed flow lanes, separated from the adjacent general purpose freeway lanes by a standard lane stripe, painted buffer, or barrier.
15. **Contraflow Lane**—a lane operating in a direction opposite to the normal flow of traffic designated for peak direction of travel during at least a portion of the day. Contraflow lanes are usually separated from the off-peak direction lanes by plastic pylons, or by moveable or permanent barrier.
16. **Conventional Road**—a street or highway other than a low-volume road (as defined in Section 5A.01), expressway, or freeway.
17. **Crashworthy**—a characteristic of a roadside appurtenance that has been successfully crash tested in accordance with a national standard such as the National Cooperative Highway Research Program Report 350, “Recommended Procedures for the Safety Performance Evaluation of Highway Features.”
18. **Crosswalk**—*means:*
  - (1) *That part of a roadway at intersections ordinarily included within the real or projected prolongation of property lines and curb lines or, in the absence of curbs, the edges of the traversable roadway,*
  - (2) *Any portion of a roadway at an intersection or elsewhere, distinctly indicated for pedestrian crossing by lines or other markings on the surface,*
  - (3) *Notwithstanding divisions (1) and (2) of this section, there shall not be a crosswalk where local authorities have placed signs indicating no crossing. [4511.01(LL), O.R.C.]*
19. **Crosswalk Lines**—white pavement marking lines that identify a crosswalk.
20. **Delineator**—a retroreflective device mounted on the roadway surface or at the side of the roadway in a series to indicate the alignment of the roadway, especially at night or in adverse weather.

21. **Detectable**—having a continuous edge within 150 mm (6 in) of the surface so that pedestrians who have visual disabilities can sense its presence and receive usable guidance information.
22. **Driver (or Operator)**—*every person who drives or is in actual physical control of a vehicle, trackless trolley, or streetcar.* [4511.01 (Y), O.R.C.]
23. **Dynamic Envelope**—the clearance required for the train and its cargo overhang due to any combination of loading, lateral motion, or suspension failure.
24. **Edge Line Markings**—white or yellow pavement marking lines that delineate the right or left edge(s) of a traveled way.
25. **End-of-Roadway Marker**—a device used to warn and alert road users of the end of a roadway in other than temporary traffic control zones.
26. **Engineering Judgment**—the evaluation of available pertinent information, and the application of appropriate principles, Standards, Guidance, and practices as contained in this Manual and other sources, for the purpose of deciding upon the applicability, design, operation, or installation of a traffic control device. Engineering judgment shall be exercised by an engineer, or by an individual working under the supervision of an engineer, through the application of procedures and criteria established by the engineer. Documentation of engineering judgment is not required.
27. **Engineering Study**—the comprehensive analysis and evaluation of available pertinent information, and the application of appropriate principles, Standards, Guidance, and practices as contained in this Manual and other sources, for the purpose of deciding upon the applicability, design, operation, or installation of a traffic control device. An engineering study shall be performed by an engineer, or by an individual working under the supervision of an engineer, through the application of procedures and criteria established by the engineer. An engineering study shall be documented.
28. **Expressway**—*a divided arterial highway for through traffic with full or partial control of access with an excess of fifty percent of all crossroads separated in grade.* [4511.01(ZZ), O.R.C.]
29. **Flashing**—an operation in which a signal indication is turned on and off repetitively.
30. **Freeway**—*a divided multi-lane highway for through traffic with all crossroads separated in grade and with full control of access.* [4511.01(YY), O.R.C.]
31. **Guide Sign**—a sign that shows route designations, destinations, directions, distances, services, points of interest, or other geographical, recreational, or cultural information.
32. **High Occupancy Vehicle (HOV)**—a motor vehicle carrying at least two or more persons, including carpools, vanpools, and buses.
33. **Highway (or Street)**—*the entire width between the boundary lines of every way open to the use of the public as a thoroughfare for purposes of vehicular travel.* [4511.01(BB), O.R.C.]
34. **Highway, Controlled-Access**—*Every street or highway in respect to which owners or occupants of abutting lands and other persons have no legal right of access to or from the same except at such points only and in such manner as may be determined by the public authority having jurisdiction over such street or highway.* [4511.01 (CC), O.R.C.]
35. **Highway, Through**—*Every street or highway as provided in section 4511.65 of the Revised Code.* [4511.01(HH), O.R.C.]
36. **Highway-Rail Grade Crossing**—the general area where a highway and a railroad's right-of-way cross at the same level, within which are included the railroad tracks, highway, and traffic control devices for highway traffic traversing that area.
37. **Highway Traffic Signal**—a power-operated traffic control device by which traffic is warned or directed to take some specific action. These devices do not include signals at toll plazas, power-operated signs, illuminated pavement markers, warning lights (see Section 6F.78), or steady burning electric lamps.
38. **HOV Lane**—any preferential lane designated for exclusive use by high-occupancy vehicles for all or part of a day—including a designated lane on a freeway, other highway, street, or independent roadway on a separate right-of-way.

- 39. Inherently Low Emission Vehicle (ILEV)**—any kind of vehicle that, because of inherent properties of the fuel system design, will not have significant evaporative emissions, even if its evaporative emission control system has failed.
- 40. Interchange**—a system of interconnecting roadways providing for traffic movement between two or more highways that do not intersect at grade.
- 41. Intermediate Interchange**—an interchange with an urban or rural route that is not a major or minor interchange as defined herein.
- 42. Intersection**—*means:*
- (1) The area embraced within the prolongation or connection of the lateral curb lines, or, if none, then the lateral boundary lines of the roadways of two highways which join one another at, or approximately at, right angles, or the area within which vehicles traveling upon different highways joining at any other angle may come in conflict.*
  - (2) Where a highway includes two roadways thirty feet or more apart, then every crossing of each roadway of such divided highway by an intersecting highway shall be regarded as a separate intersection. If an intersecting highway also includes two roadways thirty feet or more apart, then every crossing of two roadways of such highways shall be regarded as a separate intersection.*
  - (3) The junction of an alley with a street or highway, or with another alley, shall not constitute an intersection. [4511.01(KK), O.R.C.]*
- 42. Island**—a defined area between traffic lanes for control of vehicular movements or for pedestrian refuge. It includes all end protection and approach treatments. Within an intersection area, a median or an outer separation is considered to be an island.
- 43. Lane Line Markings**—white pavement marking lines that delineate the separation of traffic lanes that have the same direction of travel on a roadway.
- 44. Lane-Use Control Signal**—a signal face displaying indications to permit or prohibit the use of specific lanes of a roadway or to indicate the impending prohibition of such use.
- 45. Legend**—see Sign Legend.
- 46. Logo**—a distinctive emblem, symbol, or trademark that identifies a product or service.
- 47. Longitudinal Markings**—pavement markings that are generally placed parallel and adjacent to the flow of traffic such as lane lines, centerlines, edge lines, channelizing lines, and others.
- 48. Major Conventional Road**—a divided or undivided highway with four or more lanes where the primary access is by grade-separated interchanges and at-grade intersections with public roads, with numerous secondary access points with commercial and/or private driveways. Major conventional roads may or may not have partial control of access.
- 49. Major Interchange**—an interchange with another freeway or expressway, or an interchange with a high-volume multi-lane highway, principal urban arterial, or major rural route where the interchanging traffic is heavy or includes many road users unfamiliar with the area.
- 50. Major Street**—the street normally carrying the higher volume of vehicular traffic.
- 51. Median**—the area between two roadways of a divided highway measured from edge of traveled way to edge of traveled way. The median excludes turn lanes. The median width might be different between intersections, interchanges, and at opposite approaches of the same intersection.
- 52. Minor Interchange**—an interchange where traffic is local and very light, such as interchanges with land service access roads. Where the sum of the exit volumes is estimated to be lower than 100 vehicles per day in the design year, the interchange is classified as local.
- 53. Minor Street**—the street normally carrying the lower volume of vehicular traffic.
- 54. Object Marker**—a device used to mark obstructions within or adjacent to the roadway.
- 55. Occupancy Requirement**—any restriction that regulates the use of a facility for any period of the day based on a specified number of persons in a vehicle.
- 56. Occupant**—a person driving or riding in a car, truck, bus, or other vehicle.
- 57. Paved**—a bituminous surface treatment, mixed bituminous concrete, or Portland cement concrete roadway surface that has both a structural (weight bearing) and a sealing purpose for the roadway.
- 58. Pedestrian**—*any natural person afoot. [4511.01(X), O.R.C.]*

59. **Pedestrian Facilities**—a general term denoting improvements and provisions made to accommodate or encourage walking.
60. **Platoon**—a group of vehicles or pedestrians traveling together as a group, either voluntarily or involuntarily, because of traffic signal controls, geometrics, or other factors.
61. **Principal Legend**—place names, street names, and route numbers placed on guide signs.
62. **Public Road**—any road or street under the jurisdiction of and maintained by a public agency and open to public travel.
63. **Railroad**—*a carrier of persons or property operating upon rails placed principally on a private right-of-way.* [4511.01(P), O.R.C.]
64. **Raised Pavement Marker**—a device with a height of at least 10 mm (0.4 in) mounted on or in a road surface that is intended to be used as a positioning guide or to supplement or substitute for pavement markings or to mark the position of a fire hydrant.
65. **Regulatory Sign**—a sign that gives notice to road users of traffic laws or regulations.
66. **Retroreflectivity**—a property of a surface that allows a large portion of the light coming from a point source to be returned directly back to a point near its origin.
67. **Right-of-Way**—*means either of the following, as the context requires:*
  - (1) *The right of a vehicle, streetcar, trackless trolley, or pedestrian to proceed uninterruptedly in a lawful manner in the direction in which it or the individual is moving in preference to another vehicle, streetcar, trackless trolley, or pedestrian approaching from a different direction into its or the individual's path;*
  - (2) *A general term denoting land, property, or the interest therein, usually in the configuration of a strip, acquired for or devoted to transportation purposes. When used in this context, right-of-way includes the roadway, shoulders or berm, ditch, and slopes extending to the right-of-way limits under the control of the state or local authority.* [4511.01 (UU), O.R.C.]
68. **Road**—see Roadway.
69. **Roadway**—*that portion of a highway improved, designed, or ordinarily used for vehicular travel, except the berm or shoulder. If a highway includes two or more separate roadways the term "roadway" means any such roadway separately but not all such roadways collectively.* [4511.01(EE), O.R.C.]
70. **Roadway Network**—a geographical arrangement of intersecting roadways.
71. **Road User**—a vehicle operator, bicyclist, or pedestrian within the highway, including persons with disabilities.
72. **Roundabout Intersection**—a circular intersection with yield control of all entering traffic, channelized approaches, and appropriate geometric curvature, such that travel speeds on the circulatory roadway are typically less than 50 km/h (30 mph).
73. **Rumble Strip**—a series of intermittent, narrow, transverse areas of rough-textured, slightly raised, or depressed road surface that is installed to alert road users to unusual traffic conditions.
74. **Rural Highway**—a type of roadway normally characterized by lower volumes, higher speeds, fewer turning conflicts, and less conflict with pedestrians.
75. **Safety Zone**—*the area or space officially set apart within a roadway for the exclusive use of pedestrians and protected or marked or indicated by adequate signs as to be plainly visible at all times.* [4511.01(MM), O.R.C.]
76. **Shared Roadway**—a roadway that is officially designated and marked as a bicycle route, but which is open to motor vehicle travel and upon which no bicycle lane is designated.
77. **Shared-Use Path**—a bikeway outside the traveled way and physically separated from motorized vehicular traffic by an open space or barrier and either within the highway right-of-way or within an independent alignment. Shared-use paths are also used by pedestrians (including skaters, users of manual and motorized wheelchairs, and joggers) and other authorized motorized and non-motorized users.
78. **Sidewalk**—*that portion of a street between the curb lines, or the lateral lines of a roadway, and the adjacent property lines, intended for the use of pedestrians.* [4511.01(FF), O.R.C.]
79. **Sign**—any traffic control device that is intended to communicate specific information to road users through a word or symbol legend. Signs do not include traffic control signals, pavement markings, delineators, or channelization devices.

- 80. Sign Assembly**—a group of signs, located on the same support(s), that supplement one another in conveying information to road users.
- 81. Sign Illumination**—either internal or external lighting that shows similar color by day or night. Street or highway lighting shall not be considered as meeting this definition.
- 82. Sign Legend**—all word messages, logos, and symbol designs that are intended to convey specific meanings.
- 83. Sign Panel**—a separate panel or piece of material containing a word or symbol legend that is affixed to the face of a sign.
- 84. Speed**—speed is defined based on the following classifications:
- (a) **Advisory Speed**—a recommended speed for all vehicles operating on a section of highway and based on the highway design, operating characteristics, and conditions.
  - (b) **Average Speed**—the summation of the instantaneous or spot-measured speeds at a specific location of vehicles divided by the number of vehicles observed.
  - (c) **Design Speed**—a selected speed used to determine the various geometric design features of a roadway.
  - (d) **85th-Percentile Speed**—The speed at or below which 85 percent of the motor vehicles travel.
  - (e) **Operating Speed**—a speed at which a typical vehicle or the overall traffic operates. Operating speed might be defined with speed values such as the average, pace, or 85th-percentile speeds.
  - (f) **Pace Speed**—the highest speed within a specific range of speeds that represents more vehicles than in any other like range of speed. The range of speeds typically used is 10 km/h or 10 mph.
  - (g) **Posted Speed**—the speed limit determined by law and shown on Speed Limit signs.
  - (h) **Statutory Speed**—a speed limit established by legislative action that typically is applicable for highways with specified design, functional, jurisdictional and/or location characteristic and is not necessarily shown on Speed Limit signs.
- 85. Speed Limit**—the maximum (or minimum) speed applicable to a section of highway as established by law.
- 86. Speed Measurement Marking**—a white transverse pavement marking placed on the roadway to assist the enforcement of speed regulations.
- 87. Speed Zone**—a section of highway with a speed limit that is established by law but which might be different from a legislatively specified statutory speed limit.
- 88. State Highway**—*a highway under the jurisdiction of the department of transportation, outside the limits of municipal corporations, provided that the authority conferred upon the director of transportation in section 5511.01 of the Revised Code to erect state highway route markers and signs directing traffic shall not be modified by sections 4511.01 to 4511.79, and 4511.99 of the Revised Code. [4511.01(II), O.R.C.]*
- 89. State Route**—*Every highway which is designated with an official state route number and so marked. [4511.01(JJ), O.R.C.]*
- 90. Stop Line**—a solid white pavement marking line extending across approach lanes to indicate the point at which a stop is intended or required to be made.
- 91. Street**—see Highway.
- 92. Temporary Traffic Control Zone**—an area of a highway where road user conditions are changed because of a work zone or incident by the use of temporary traffic control devices, flaggers, uniformed law enforcement officers, or other authorized personnel.
- 93. Traffic**—*pedestrians, ridden or herded animals, vehicles, streetcars, trackless trolleys, and other devices, either singly or together, while using any highway for purposes of travel. [4511.01(TT), O.R.C.]*
- 94. Traffic Control Devices**—*all flaggers signs, signals, markings, and devices placed or erected by authority of a public body or official having jurisdiction, for the purpose of regulating, warning, or guiding traffic, including signs denoting names of streets and highways. [4511.01(QQ), O.R.C.]*

95. **Traffic Control Signal (Traffic Signal)**—*any device, whether manually, electrically, or mechanically operated, by which traffic is alternately directed to stop, to proceed, to change direction, or not to change direction. [4511.01(RR), O.R.C.]*
96. **Train**—*one or more locomotives coupled, with or without cars, that operates on rails or tracks and to which all other traffic must yield the right-of-way by law at highway-rail grade crossings.*
97. **Transverse Markings**—*pavement markings that are generally placed perpendicular and across the flow of traffic such as shoulder markings, word and symbol markings, stop lines, crosswalk lines, speed measurement markings, parking space markings, and others.*
98. **Traveled Way**—*the portion of the roadway for the movement of vehicles, exclusive of the shoulders, berms, sidewalks, and parking lanes.*
99. **Urban Street**—*a type of street normally characterized by relatively low speeds, wide ranges of traffic volumes, narrower lanes, frequent intersections and driveways, significant pedestrian traffic, and more businesses and houses.*
100. **Vehicle**—*every device, including a motorized bicycle, in, upon, or by which any person or property may be transported or drawn upon a highway, except that “vehicle” does not include any motorized wheelchair, any electric personal assistive mobility device, any device that is moved by power collected from overhead electric trolley wires or that is used exclusively upon stationary rails or tracks, or any device, other than a bicycle, that is moved by human power. [4511.01(A), O.R.C.]*
101. **Vehicle, Emergency**—*emergency vehicles of municipal, township, or county departments or public utility corporations when identified as such as required by law, the director of public safety, or local authorities, and motor vehicles when commandeered by a police officer. [4511.01(D), O.R.C.]*
102. **Vehicle, Motor**—*every vehicle propelled or drawn by power other than muscular power or power collected from overhead electric trolley wires, except motorized bicycles, road rollers, traction engines, power shovels, power cranes, and other equipment used in construction work and not designed for or employed in general highway transportation, hole-digging machinery, well-drilling machinery, ditch-digging machinery, farm machinery, trailers used to transport agricultural produce or agricultural production materials between a local place of storage or supply and the farm when drawn or towed on a street or highway at a speed of twenty-five miles per hour or less, threshing machinery, hay-baling machinery, agricultural tractors and machinery used in the production of horticultural, floricultural, agricultural and vegetable products, and trailers designed and used exclusively to transport a boat between a place of storage and a marina, or in and around a marina, when drawn or towed on a street or highway for a distance of no more than ten miles and at a top speed of twenty-five miles per hour or less. [4511.01(B), O.R.C.]*
103. **Vehicle, Public Safety**—*means any of the, following:*
- (1) *Ambulances, including private ambulance companies under contract to a municipal corporation, township, or county, and private ambulances and nontransport vehicles bearing license plates issued under section 4503.49 of the Revised Code,*
  - (2) *Motor vehicles used by public law enforcement officers or other persons sworn to enforce the criminal and traffic laws of the state;*
  - (3) *Any motor vehicle when properly identified as required by the director of public safety, when used in response to fire emergency calls or to provide emergency medical service to ill or injured persons, and when operated by a duly qualified person who is a member of a volunteer rescue service or a volunteer fire department, and who is on duty pursuant to the rules or directives of that service. The state fire marshal shall be designated by the director of public safety as the certifying agency for all public safety vehicles described in division (E)(3) of this section.*
  - (4) *Vehicles used by fire departments, including motor vehicles when used by volunteer fire fighters responding to emergency calls in the fire department service when identified as required by the director of public safety.*  
*Any vehicles used to transport or provide emergency medical service to an ill or injured person, when certified as a public safety vehicle, shall be considered a public safety vehicle when transporting an ill or injured person to a hospital regardless of whether such vehicle has already passed a hospital.*

*(5) Vehicles used by the commercial motor vehicle safety enforcement unit for the enforcement orders and rules of the public utilities commission as specified in section 5503.34 of the Revised Code. [4511.01(E), O.R.C.]*

104. **Warning Sign**—a sign that gives notice to road users of a situation that might not be readily apparent.
105. **Warrant**—a warrant describes threshold conditions to the engineer in evaluating the potential safety and operational benefits of traffic control devices and is based upon average or normal conditions. Warrants are not a substitute for engineering judgment. The fact that a warrant for a particular traffic control device is met is not conclusive justification for the installation of the device.
106. **Wrong-Way Arrow**—a slender, elongated, white pavement marking arrow placed upstream from the ramp terminus to indicate the correct direction of traffic flow. Wrong-way arrows are intended primarily to warn wrong-way road users that they are going in the wrong direction.

#### **Section 1A.14 Abbreviations Used on Traffic Control Devices**

##### **Standard:**

When the word messages shown in Table 1A-1 need to be abbreviated in connection with traffic control devices, the abbreviations shown in Table 1A-1 shall be used.

##### **Guidance:**

The abbreviations for the words listed in Table 1A-2 should not be used in connection with traffic control devices unless the prompt word shown in Table 1A-2 either precedes or follows the abbreviation.

##### **Standard:**

The abbreviations shown in Table 1A-3 shall not be used in connection with traffic control devices because of their potential to be misinterpreted by road users.

##### **Guidance:**

Where multiple abbreviations are permitted in Tables 1A-1 or 1A-2, the same abbreviation should be used throughout a single jurisdiction.

**Table 1A-1. Acceptable Abbreviations**

<b>Word Message</b>	<b>Standard Abbreviation</b>	<b>Word Message</b>	<b>Standard Abbreviation</b>
Afternoon / Evening	PM	Maintenance	MAINT
Alternate	ALT	Meter(s)	m
Avenue	AVE, AV	Metric Ton	t
Bicycle	BIKE	Mile(s)	MI
Boulevard	BLVD	Miles per Hour	MPH
Cannot	CANT	Minute(s)	MIN
CB Radio	CB	Monday	MON
Center	CNTR	Morning / Late Night	AM
Circle	CIR	Normal	NORM
Civil Defense	CD	North	N
Compressed Natural Gas	CNG	Northbound	N-BND
Court	CT	Parking	PKING
Crossing (other than highway-rail)	XING	Parkway	PKWY
Diesel Fuel	D	Pedestrian	PED
Do Not	DONT	Place	PL
Drive	DR	Pounds	LBS
East	E	Right	RHT
Eastbound	E-BND	Road	RD
Electric Vehicle	EV	Saturday	SAT
Emergency	EMER	Service	SERV
Entrance, Enter	ENT	Shoulder	SHLDR
Expressway	EXPWY	Slippery	SLIP
Feet	FT	South	S
FM Radio	FM	Southbound	S-BND
Freeway	FRWY, FWY	Speed	SPD
Friday	FRI	Street	ST
Hazardous Material	HAZMAT	Sunday	SUN
High Occupancy Vehicle	HOV	Telephone	PHONE
Highway	HWY	Temporary	TEMP
Highway-Rail Grade Crossing Pavement Marking	RXR	Terrace	TER
Hospital	H	Thursday	THURS
Hour(s)	HR	Ties With Lugs	LUGS
Information	INFO	Tones of Weight	T
Inherently Low Emission Vehicle	ILEV	Traffic	TRAF
It Is	ITS	Trail	TR
Junction / Intersection	JCT	Travelers	TRAVLRS
Kilogram	kg	Tuesday	TUES
Kilometer(s)	km	Two-Way Intersection	2-WAY
Kilometers per hour	km/h	Two-Wheeled Vehicles	CYCLES
Lane	LN	US Numbered Route	US
Left	LFT	Vehicles(s)	VEH
Liquid Propane Gas	LP-GAS	Warning	WARN
		Wednesday	WED
		West	W
		Westbound	W-BND
		Will Not	WONT

**Table 1A-2. Abbreviations That Are Acceptable Only with a Prompt Word**

Word	Abbreviation	Prompt Word
Access	ACCS	Road
Ahead	AHD	Fog*
Blocked	BLKD	Lane*
Bridge	BRDG	[Name]*
Chemical	CHEM	Spill
Condition	COND	Traffic*
Congested	CONG	Traffic*
Construction	CONST	Ahead
Downtown	DWNTN	Traffic*
Exit	EX, EXT	Next*
Express	EXP	Lane
Frontage	FRNTG	Road
Hazardous	HAZ	Driving
Interstate	I	[Number]
Local	LOC	Traffic
Lower	LWR	Level
Major	MAJ	Accident
Minor	MNR	Accident
Oversized	OVRSZ	Load
Prepare	PREP	To Stop
Pavement	PVMT	Wet*
Quality	QLTY	Air*
Roadwork	RDWK	Ahead [Distance]
Route	RT, RTE	Best*
Township	TWNSHP	Limits
Turnpike	TRNPK	[Name]*
Upper	UPR	Level

\* These prompt words should precede the abbreviation.

**Table 1A-3. Unacceptable Abbreviations**

<b>Abbreviation</b>	<b>Intended Word</b>	<b>Common Misinterpretation</b>
ACC	Accident	Access (Road)
CLRS	Clears	Colors
DLY	Delay	Daily
FDR	Feeder	Federal
L	Left	Lane
LT	Light (Traffic)	Left
PARK	Parking	Park
POLL	Pollution (Index)	Poll
RED	Reduce	Red
STAD	Stadium	Standard
WRNG	Warning	Wrong

Intentionally blank.

**PART 2. SIGNS****TABLE OF CONTENTS**

	<u>Page</u>
<b>CHAPTER 2A.</b>	<b>GENERAL</b>
Section 2A.01	Function and Purpose of Signs ..... 2A-1
Section 2A.02	Definitions ..... 2A-1
Section 2A.03	Standardization of Application ..... 2A-1
Section 2A.04	Excessive Use of Signs ..... 2A-2
Section 2A.05	Classification of Signs ..... 2A-2
Section 2A.06	Design of Signs ..... 2A-2
Section 2A.07	Changeable Message Signs ..... 2A-3
Section 2A.08	Retroreflectivity and Illumination ..... 2A-4
Section 2A.09	Maintaining Minimum Retroreflectivity ..... 2A-5
Section 2A.10	Shapes ..... 2A-8
Section 2A.11	Sign Colors ..... 2A-8
Section 2A.12	Dimensions ..... 2A-8
Section 2A.13	Symbols ..... 2A-9
Section 2A.14	Word Messages ..... 2A-11
Section 2A.15	Sign Borders ..... 2A-11
Section 2A.16	Standardization of Location ..... 2A-12
Section 2A.17	Overhead Sign Installations ..... 2A-15
Section 2A.18	Mounting Height ..... 2A-15
Section 2A.19	Lateral Offset ..... 2A-16
Section 2A.20	Orientation ..... 2A-17
Section 2A.21	Posts and Mountings ..... 2A-17
Section 2A.22	Maintenance ..... 2A-18
Section 2A.23	Median Opening Treatments for Divided Highways with Wide Medians ..... 2A-18
<b>CHAPTER 2B.</b>	<b>REGULATORY SIGNS</b>
Section 2B.01	Application of Regulatory Signs ..... 2B-1
Section 2B.02	Design of Regulatory Signs ..... 2B-1
Section 2B.03	Size of Regulatory Signs ..... 2B-1
Section 2B.04	STOP Sign (R1-1) ..... 2B-7
Section 2B.05	STOP Sign Applications ..... 2B-8
Section 2B.06	STOP Sign Placement ..... 2B-9
Section 2B.07	Multiway Stop Applications ..... 2B-10
Section 2B.08	YIELD Sign (R1-2) ..... 2B-11
Section 2B.09	YIELD Sign Applications ..... 2B-11
Section 2B.10	YIELD Sign Placement ..... 2B-11
Section 2B.11	Yield Here To Pedestrians Signs (R1-5, R1-5a) ..... 2B-12
Section 2B.12	In-Street Pedestrian Crossing Sign (R1-6) ..... 2B-12
Section 2B.13	Speed Limit Signs (R2-1, R2-H2b, R2-H2c) ..... 2B-13
Section 2B.14	Truck Speed Limit Signs (R2-2, R2-H2a) ..... 2B-14
Section 2B.15	Night Speed Limit Sign (R2-3) ..... 2B-14
Section 2B.16	Minimum Speed Limit Sign (R2-4) ..... 2B-15
Section 2B.17	FINES HIGHER Plaque (R2-6) ..... 2B-15
Section 2B.18	Location of Speed Limit Signs ..... 2B-16
Section 2B.19	Turn Prohibition Signs (R3-1 through R3-4, and R3-18) ..... 2B-16
Section 2B.20	Intersection Lane Control Signs (R3-5 through R3-8) ..... 2B-17
Section 2B.21	Mandatory Movement Lane Control Signs (R3-5, R3-5a, R3-7) ..... 2B-18

Section 2B.22	Optional Movement Lane Control Sign (R3-6).....	2B-19
Section 2B.23	Advance Intersection Lane Control Signs (R3-8 Series).....	2B-20
Section 2B.24	Two-Way Left Turn Only Signs (R3-9a, R3-9b).....	2B-20
Section 2B.25	Reversible Lane Control Signs (R3-9d, R3-9f through R3-9i).....	2B-21
Section 2B.26	Preferential Only Lane Signs (R3-10 through R3-15).....	2B-24
Section 2B.27	Preferential Only Lanes for High-Occupancy Vehicles (HOVs) .....	2B-27
Section 2B.28	Preferential Only Lane Sign Applications and Placement .....	2B-29
Section 2B.29	DO NOT PASS Sign (R4-1).....	2B-31
Section 2B.30	PASS WITH CARE Sign (R4-2).....	2B-32
Section 2B.31	SLOWER TRAFFIC KEEP RIGHT Sign (R4-3).....	2B-32
Section 2B.32	Slow Moving Traffic Lane Signs (R4-5, R4-6).....	2B-32
Section 2B.33	Keep Right and Keep Left Signs (R4-7, R4-8).....	2B-32
Section 2B.33.1	THROUGH TRAFFIC KEEP RIGHT (LEFT) Signs (R4-H11, R4-H12) .....	2B-34
Section 2B.34	DO NOT ENTER Sign (R5-1).....	2B-34
Section 2B.35	WRONG WAY Sign (R5-1a).....	2B-34
Section 2B.36	Selective Exclusion Signs.....	2B-35
Section 2B.37	ONE WAY Signs (R6-1, R6-2) .....	2B-37
Section 2B.38	Divided Highway Crossing Signs (R6-3, R6-3a).....	2B-37
Section 2B.39	Parking, Standing, and Stopping Signs (R7 and R8 Series) .....	2B-43
Section 2B.40	Design of Parking, Standing, and Stopping Signs .....	2B-43
Section 2B.41	Placement of Parking, Stopping, and Standing Signs.....	2B-46
Section 2B.42	Emergency Restriction Signs (R8-4, R8-7, R8-8) .....	2B-47
Section 2B.43	WALK ON LEFT FACING TRAFFIC and No Hitchhiking Signs (R9-1, R9-4, R9-4a) .....	2B-47
Section 2B.44	Pedestrian Crossing Signs (R9-2, R9-3).....	2B-47
Section 2B.45	Traffic Signal Signs (R10-1 through R10-21).....	2B-49
Section 2B.46	Photo Enforced Signs (R10-18, R10-19).....	2B-51
Section 2B.47	KEEP OFF MEDIAN Sign (R11-1) .....	2B-52
Section 2B.48	ROAD CLOSED Sign (R11-2) and LOCAL TRAFFIC ONLY Signs (R11-3 Series, R11-4) .....	2B-52
Section 2B.49	Weight Limit Signs (R12-1 through R12-5).....	2B-52
Section 2B.50	Weigh Station Signs (R13 Series) .....	2B-53
Section 2B.51	TRUCK ROUTE Sign (R14-1).....	2B-54
Section 2B.52	Hazardous Material Signs (R14-2, R14-3) .....	2B-54
Section 2B.53	National Network Signs (R14-4, R14-5) .....	2B-54
Section 2B.54	Other Regulatory Signs.....	2B-55

**CHAPTER 2C.****WARNING SIGNS**

Section 2C.01	Function of Warning Signs.....	2C-1
Section 2C.02	Application of Warning Signs .....	2C-1
Section 2C.03	Design of Warning Signs.....	2C-1
Section 2C.04	Size of Warning Signs .....	2C-1
Section 2C.05	Placement of Warning Signs .....	2C-4
Section 2C.06	Horizontal Alignment Signs (W1-1 through W1-5, W1-11, W1-15).....	2C-6
Section 2C.07	Combination Horizontal Alignment/Advisory Speed Signs (W1-1a, W1-2a) .....	2C-7
Section 2C.08	Combination Horizontal Alignment/Intersection Sign (W1-10) .....	2C-8
Section 2C.09	One-Direction Large Arrow Sign (W1-6) .....	2C-8
Section 2C.10	Chevron Alignment Sign (W1-8).....	2C-8
Section 2C.11	Truck Rollover Warning Sign (W1-13).....	2C-9
Section 2C.12	Hill Signs (W7-1, W7-1a, W7-1b).....	2C-9
Section 2C.13	Truck Escape Ramp Signs (W7-4 Series).....	2C-10
Section 2C.14	HILL BLOCKS VIEW Sign (W7-6) .....	2C-10
Section 2C.15	ROAD NARROWS Sign (W5-1) .....	2C-11
Section 2C.16	NARROW BRIDGE Sign (W5-2).....	2C-12

Section 2C.17	ONE LANE BRIDGE Sign (W5-3).....	2C-12
Section 2C.18	Divided Highway (Road) Sign (W6-1).....	2C-12
Section 2C.19	Divided Highway (Road) Ends Sign (W6-2).....	2C-12
Section 2C.20	Double Arrow Sign (W12-1).....	2C-13
Section 2C.21	DEAD END/NO OUTLET Signs (W14-1, W14-1a, W14-2, W14-2a).....	2C-13
Section 2C.22	Low Clearance Signs (W12-2 and W12-2p).....	2C-13
Section 2C.23	BUMP and DIP Signs (W8-1, W8-2).....	2C-14
Section 2C.24	SPEED HUMP Sign (W17-1).....	2C-14
Section 2C.25	PAVEMENT ENDS Sign (W8-3).....	2C-14
Section 2C.26	Shoulder Signs (W8-4, W8-9, W8-9a).....	2C-15
Section 2C.27	Slippery When Wet Sign (W8-5).....	2C-16
Section 2C.28	BRIDGE ICES BEFORE ROAD Sign (W8-13).....	2C-16
Section 2C.29	Advance Traffic Control Signs (W3-1, W3-2, W3-3, W3-4).....	2C-16
Section 2C.30	Speed Reduction Signs (W3-5, W3-5a).....	2C-17
Section 2C.31	Merge Signs (W4-1, W4-5).....	2C-17
Section 2C.32	Added Lane Signs (W4-3, W4-6).....	2C-18
Section 2C.33	Lane Ends Signs (W4-2, W9-1, W9-2).....	2C-19
Section 2C.34	Two-Way Traffic Sign (W6-3).....	2C-19
Section 2C.35	NO PASSING ZONE Sign (W14-3).....	2C-19
Section 2C.36	Advisory Exit, Ramp, and Curve Speed Signs (W13-2, W13-3, W13-5).....	2C-19
Section 2C.37	Intersection Warning Signs (W2-1 through W2-6).....	2C-20
Section 2C.38	Two-Direction Large Arrow Sign (W1-7).....	2C-22
Section 2C.39	Traffic Signal Signs (W25-1, W25-2).....	2C-22
Section 2C.40	Vehicular Traffic Signs (W8-6, W11-1, W11-5, W11-5a, W11-8, W11-10, W11-11, W11-12p, W11-14).....	2C-23
Section 2C.41	Nonvehicular Traffic Signs (W11-2, W11-3, W11-4, W11-6, W11-7, W11-9).....	2C-23
Section 2C.42	Playground Sign (W15-1).....	2C-25
Section 2C.43	Use of Supplemental Plaques.....	2C-26
Section 2C.44	Design of Supplemental Plaques.....	2C-26
Section 2C.45	Distance Plaques (W16-2 Series, W16-3 Series, W16-4, W7-3a).....	2C-26
Section 2C.46	Advisory Speed Plaque (W13-1).....	2C-26
Section 2C.47	Supplemental Arrow Plaques (W16-5p, W16-6p, W16-7p).....	2C-27
Section 2C.48	Hill-Related Plaques (W7- 2 Series, W7-3 Series).....	2C-27
Section 2C.49	Advance Street Name Plaques (W16-8, W16-8a).....	2C-27
Section 2C.50	CROSS TRAFFIC DOES NOT STOP Plaque (W4-4p).....	2C-27
Section 2C.51	SHARE THE ROAD Plaque (W16-1).....	2C-27
Section 2C.52	High-Occupancy Vehicle (HOV) Plaque (W16-11).....	2C-28
Section 2C.53	PHOTO ENFORCED Plaque (W16-10).....	2C-28

## CHAPTER 2D. GUIDE SIGNS—CONVENTIONAL ROADS

Section 2D.01	Scope of Conventional Road Guide Sign Standards.....	2D-1
Section 2D.02	Application.....	2D-1
Section 2D.03	Color, Retroreflection, and Illumination.....	2D-1
Section 2D.04	Size of Signs.....	2D-1
Section 2D.05	Lettering Style.....	2D-2
Section 2D.06	Size of Lettering.....	2D-3
Section 2D.07	Amount of Legend.....	2D-3
Section 2D.08	Arrows.....	2D-3
Section 2D.09	Numbered Highway Systems.....	2D-4
Section 2D.10	Route Signs and Auxiliary Signs.....	2D-5
Section 2D.11	Design of Route Signs.....	2D-5
Section 2D.12	Design of Route Sign Auxiliaries.....	2D-7
Section 2D.13	Junction Auxiliary Sign (M2-1).....	2D-7
Section 2D.14	Combination Junction Sign (M2-2).....	2D-8

Section 2D.15	Cardinal Direction Auxiliary Signs (M3-1 through M3-4) .....	2D-8
Section 2D.16	Auxiliary Signs for Alternative Routes (M4 Series) .....	2D-8
Section 2D.17	ALTERNATE Auxiliary Signs (M4-1, M4-1a) .....	2D-8
Section 2D.18	BY-PASS Auxiliary Sign (M4-2) .....	2D-9
Section 2D.19	BUSINESS Auxiliary Sign (M4-3) .....	2D-9
Section 2D.20	TRUCK Auxiliary Sign (M4-4).....	2D-9
Section 2D.21	TO Auxiliary Sign (M4-5).....	2D-10
Section 2D.22	END Auxiliary Sign (M4-6) .....	2D-10
Section 2D.23	TEMPORARY Auxiliary Signs (M4-7, M4-7a) .....	2D-10
Section 2D.24	Temporary Detour and Auxiliary Signs .....	2D-10
Section 2D.25	Advance Turn Arrow Auxiliary Signs (M5-1, M5-2) .....	2D-10
Section 2D.26	Directional Arrow Auxiliary Signs (M6 Series).....	2D-10
Section 2D.27	Route Sign Assemblies .....	2D-11
Section 2D.28	Junction Assembly.....	2D-12
Section 2D.29	Advance Route Turn Assembly .....	2D-12
Section 2D.30	Directional Assembly .....	2D-13
Section 2D.31	Confirming or Reassurance Assemblies .....	2D-13
Section 2D.32	Trailblazer Assembly.....	2D-17
Section 2D.33	Destination and Distance Signs .....	2D-17
Section 2D.34	Destination Signs (D1 Series).....	2D-17
Section 2D.35	Location of Destination Signs .....	2D-19
Section 2D.36	Distance Signs (D2 Series).....	2D-19
Section 2D.37	Location of Distance Signs.....	2D-20
Section 2D.38	Street Name Sign (D3-1) .....	2D-20
Section 2D.39	Advance Street Name Signs (D3-2).....	2D-22
Section 2D.40	Parking Area Sign (D4-1) .....	2D-23
Section 2D.41	PARK & RIDE Sign (D4-2) .....	2D-24
Section 2D.42	Rest Area Signs (D5 Series) .....	2D-24
Section 2D.43	Scenic Area Signs (D6 Series).....	2D-25
Section 2D.44	Weigh Station Signing (D8 Series).....	2D-25
Section 2D.45	General Service Signs (D9 Series) .....	2D-27
Section 2D.46	Reference Location Signs (D10-1 through D10-3) and Intermediate Reference Location Signs (D10-1a through D10-3a) .....	2D-30
Section 2D.47	Traffic Signal Speed Sign (I1-1).....	2D-32
Section 2D.48	General Information Signs (I Series).....	2D-33
Section 2D.49	Signing of Named Highways .....	2D-35
Section 2D.50	Trail Signs.....	2D-36
Section 2D.51	Crossover Signs (D13 Series).....	2D-36
Section 2D.52	National Scenic Byways Signs (D6-4, D6-4a) .....	2D-36
Section 2D.53	Ohio Byway Signs (M8-H3, M8-H3p) .....	2D-37

**CHAPTER 2E.****GUIDE SIGNS—FREEWAYS AND EXPRESSWAYS**

Section 2E.01	Scope of Freeway and Expressway Guide Sign Standards .....	2E-1
Section 2E.02	Freeway and Expressway Signing Principles .....	2E-1
Section 2E.03	General.....	2E-2
Section 2E.04	Color of Guide Signs .....	2E-2
Section 2E.05	Retroreflection or Illumination.....	2E-2
Section 2E.06	Characteristics of Urban Signing.....	2E-2
Section 2E.07	Characteristics of Rural Signing.....	2E-3
Section 2E.08	Memorial Highway Signing (E8-H5, M1-10).....	2E-3
Section 2E.09	Amount of Legend on Guide Signs .....	2E-4
Section 2E.10	Number of Signs at an Overhead Installation and Sign Spreading.....	2E-5
Section 2E.11	Pull-Through Signs (E6-H2) .....	2E-5
Section 2E.12	Designation of Destinations.....	2E-6

Section 2E.13	Size and Style of Letters and Signs .....	2E-6
Section 2E.14	Interline and Edge Spacing .....	2E-7
Section 2E.15	Sign Borders .....	2E-7
Section 2E.16	Abbreviations.....	2E-7
Section 2E.17	Symbols.....	2E-7
Section 2E.18	Arrows for Interchange Guide Signs .....	2E-7
Section 2E.19	Diagrammatic Signs (E4-H1) .....	2E-8
Section 2E.20	Signing for Interchange Lane Drops.....	2E-9
Section 2E.21	Changeable Message Signs.....	2E-15
Section 2E.22	Overhead Sign Installations .....	2E-17
Section 2E.23	Lateral Offset.....	2E-17
Section 2E.24	Guide Sign Classification .....	2E-18
Section 2E.25	Route Signs and Trailblazer Assemblies .....	2E-19
Section 2E.26	Signs for Intersections at Grade.....	2E-19
Section 2E.27	Interchange Guide Signs.....	2E-20
Section 2E.28	Interchange Exit Numbering (E1-H5) .....	2E-20
Section 2E.29	Interchange Classification.....	2E-24
Section 2E.30	Advance Guide Signs (E1-H1) .....	2E-24
Section 2E.31	Next Exit Supplemental Signs (E2-H1, E2-H1a) .....	2E-26
Section 2E.32	Other Supplemental Guide Signs (E3-H1) .....	2E-27
Section 2E.33	Exit Direction Signs (E1-H3) .....	2E-27
Section 2E.34	Exit Gore Signs (E5-H1, E5-H1a, E5-H2, E5-H2a).....	2E-30
Section 2E.35	Post-Interchange Signs.....	2E-31
Section 2E.36	Distance Signs (E7-H1).....	2E-32
Section 2E.37	Interchange Sequence Signs .....	2E-33
Section 2E.38	Community Interchanges Identification Signs (E7-H3) .....	2E-33
Section 2E.39	NEXT X EXITS Sign (E7-H4).....	2E-36
Section 2E.40	Signing by Type of Interchange.....	2E-36
Section 2E.41	Freeway-to-Freeway Interchange.....	2E-36
Section 2E.42	Cloverleaf Interchange.....	2E-43
Section 2E.43	Cloverleaf Interchange with Collector-Distributor Roadways .....	2E-43
Section 2E.44	Partial Cloverleaf Interchange .....	2E-44
Section 2E.45	Diamond Interchange.....	2E-44
Section 2E.46	Diamond Interchange in Urban Area.....	2E-45
Section 2E.47	Closely Spaced Interchanges .....	2E-45
Section 2E.48	Minor Interchange.....	2E-45
Section 2E.49	Signing of Approaches and Connecting Roadways.....	2E-45
Section 2E.50	Wrong-Way Traffic Control at Interchange Ramps .....	2E-52
Section 2E.51	General Service Signs.....	2E-54
Section 2E.52	Rest and Scenic Area Signs (D5 Series, D6 Series) .....	2E-56
Section 2E.53	Tourist Information and Welcome Center Signs .....	2E-59
Section 2E.54	Reference Location Signs and Enhanced Reference Location Signs (D10-4, D10-5, D10-H5a) .....	2E-60
Section 2E.55	Miscellaneous Guide Signs.....	2E-62
Section 2E.56	Radio Information Signing .....	2E-62
Section 2E.57	Carpool and Ridesharing Signing .....	2E-63
Section 2E.58	Weigh Station Signing .....	2E-64
Section 2E.59	Preferential Only Lane Signs.....	2E-64
<b>CHAPTER 2F.</b>	<b>SPECIFIC SERVICE SIGNS</b>	
Section 2F.01	Eligibility .....	2F-1
Section 2F.02	Application.....	2F-1
Section 2F.03	Logos and Logo Panels.....	2F-2
Section 2F.04	Number and Size of Logos and Signs.....	2F-2

Section 2F.05	Size of Lettering .....	2F-5
Section 2F.06	Signs at Interchanges .....	2F-5
Section 2F.07	Single-Exit Interchanges.....	2F-5
Section 2F.08	Double-Exit Interchanges .....	2F-6
Section 2F.09	Signs at Intersections .....	2F-6
Section 2F.10	Signing Policy.....	2F-6

## **CHAPTER 2G. TOURIST-ORIENTED DIRECTIONAL SIGNS**

Section 2G.01	Purpose and Application.....	2G-1
Section 2G.02	Design .....	2G-1
Section 2G.03	Style and Size of Lettering .....	2G-2
Section 2G.04	Arrangement and Size of Signs .....	2G-2
Section 2G.05	Advance Signs .....	2G-5
Section 2G.06	Sign Locations .....	2G-5
Section 2G.07	State Policy .....	2G-6

## **CHAPTER 2H. RECREATIONAL AND CULTURAL INTEREST AREA SIGNS**

Section 2H.01	Scope.....	2H-1
Section 2H.02	Application of Recreational and Cultural Interest Area Signs .....	2H-1
Section 2H.03	Regulatory and Warning Signs .....	2H-1
Section 2H.04	General Design Requirements for Recreational and Cultural Interest Area Symbol Signs .....	2H-1
Section 2H.05	Symbol Sign Sizes .....	2H-2
Section 2H.06	Use of Educational Plaques .....	2H-2
Section 2H.07	Use of Prohibitive Slash .....	2H-2
Section 2H.08	Placement of Recreational and Cultural Interest Area Symbol Signs .....	2H-12
Section 2H.09	Destination Guide Signs .....	2H-12

## **CHAPTER 2I. EMERGENCY MANAGEMENT SIGNING**

Section 2I.01	Emergency Management .....	2I-1
Section 2I.02	Design of Emergency Management Signs.....	2I-1
Section 2I.03	EVACUATION ROUTE Sign (EM-1).....	2I-1
Section 2I.04	AREA CLOSED Sign (EM-2).....	2I-3
Section 2I.05	TRAFFIC CONTROL POINT Sign (EM-3) .....	2I-3
Section 2I.06	MAINTAIN TOP SAFE SPEED Sign (EM-4).....	2I-3
Section 2I.07	ROAD (AREA) USE PERMIT REQUIRED FOR THRU TRAFFIC Sign (EM-5) .....	2I-4
Section 2I.08	Emergency Aid Center Signs (EM-6 Series).....	2I-5
Section 2I.09	Shelter Directional Signs (EM-7 Series) .....	2I-5

## **FIGURES**

### **CHAPTER 2A. GENERAL**

Figure 2A-1	Examples of Heights and Lateral Locations of Signs for Typical Installations ..	2A-13
Figure 2A-2	Examples of Locations for Some Typical Signs at Intersections .....	2A-14

### **CHAPTER 2B. REGULATORY SIGNS**

Figure 2B-1	STOP, YIELD, Speed Limit, FINES HIGHER, and Photo Enforcement Signs ..	2B-9
Figure 2B-2	Unsignalized Pedestrian Crosswalk Signs.....	2B-13
Figure 2B-3	Speed Limit and Turn Prohibition Signs .....	2B-15
Figure 2B-4	Intersection Lane Control Signs .....	2B-19
Figure 2B-5	Center and Reversible Lane Control Signs.....	2B-20
Figure 2B-6	Location of Reversible Two-Way Left-Turn Signs.....	2B-22

Figure 2B-7	Examples of Preferential Only Lane Signs.....	2B-26
Figure 2B-8	Passing, Keep Right, and Truck Lane Signs.....	2B-33
Figure 2B-9	Traffic Prohibition Signs .....	2B-35
Figure 2B-10	Example of Wrong-Way Signing for a Divided Highway with a Median Width of 9 m (30 ft) or Greater .....	2B-36
Figure 2B-11	ONE WAY and Divided Highway Crossing Signs .....	2B-37
Figure 2B-12	Examples of Locations of ONE WAY Signs.....	2B-38
Figure 2B-13	Examples of ONE WAY Signing for Divided Highways with Medians of 9 m (30 ft) or Greater.....	2B-40
Figure 2B-14	Examples of ONE WAY Signing for Divided Highways with Medians Less Than 9 m (30 ft).....	2B-41
Figure 2B-15	Examples of ONE WAY Signing for Divided Highways with Medians Less Than 9 m (30 ft) and Separated Left-Turn Lanes.....	2B-42
Figure 2B-16	No Parking Signs (R7 Series) .....	2B-44
Figure 2B-17	No Parking Signs (R8 Series) .....	2B-45
Figure 2B-18	Pedestrian Signs.....	2B-48
Figure 2B-19	Traffic Signal Signs .....	2B-50
Figure 2B-20	Road Closed and Weight Limit Signs.....	2B-53
Figure 2B-21	Truck Signs .....	2B-54
Figure 2B-22	Seat Belt Symbol.....	2B-55

**CHAPTER 2C.****WARNING SIGNS**

Figure 2C-1	Horizontal Alignment Signs .....	2C-6
Figure 2C-2	Vertical Grade Signs.....	2C-10
Figure 2C-3	Miscellaneous Warning Signs .....	2C-11
Figure 2C-4	Roadway Condition and Advance Traffic Control Signs .....	2C-15
Figure 2C-5	Advisory Speed and Speed Reduction Signs .....	2C-17
Figure 2C-6	Merging and Passing Signs.....	2C-18
Figure 2C-7	Example of Advisory Speed Signing for an Exit Ramp .....	2C-21
Figure 2C-8	Intersection Warning Signs.....	2C-22
Figure 2C-9	Vehicular Traffic Signs.....	2C-24
Figure 2C-10	Nonvehicular Traffic Signs .....	2C-24
Figure 2C-11	Supplemental Warning Plaques .....	2C-25

**CHAPTER 2D.****GUIDE SIGNS—CONVENTIONAL ROADS**

Figure 2D-1	Examples of Color-Coded Destination Guide Signs .....	2D-2
Figure 2D-2	Arrows for Use on Guide Signs.....	2D-4
Figure 2D-3	Route Signs .....	2D-7
Figure 2D-4	Route Sign Auxiliaries.....	2D-9
Figure 2D-5	Directional Arrow Auxiliary Signs.....	2D-11
Figure 2D-6	Illustration of Directional Assemblies and Other Route Signs (For One Direction of Travel Only).....	2D-14
Figure 2D-7	Examples of Destination and Distance Signs .....	2D-18
Figure 2D-8	Examples of Street Name and Parking Signs .....	2D-22
Figure 2D-9	Examples of Rest Area and Scenic Overlook Signs .....	2D-25
Figure 2D-10	Example of Weigh Station Signing.....	2D-26
Figure 2D-11	General Service Signs .....	2D-28
Figure 2D-12	General Information Signs .....	2D-31
Figure 2D-13	Reference Location Signs .....	2D-32
Figure 2D-14	Examples of Use of the National Scenic Byways Sign .....	2D-38

**CHAPTER 2E.****GUIDE SIGNS—FREEWAYS AND EXPRESSWAYS**

Figure 2E-1	Example of Guide Sign Spreading.....	2E-4
Figure 2E-2	Pull-Through Signs.....	2E-4
Figure 2E-3	Diagrammatic Sign for a Single-Lane Left Exit.....	2E-9
Figure 2E-4	Diagrammatic Signs for Split with Dedicated Lanes.....	2E-10
Figure 2E-5	Diagrammatic Signs for Split with Optional Lane.....	2E-11
Figure 2E-6	Diagrammatic Signs for Two-Lane Exit with Optional Lane.....	2E-12
Figure 2E-7	Diagrammatic Signs for Two-Lane Exit with Optional Lane.....	2E-13
Figure 2E-8	EXIT ONLY on Left with Diagrammatic Sign for Left Lane Dropped at an Interchange.....	2E-14
Figure 2E-9	EXIT ONLY Panels.....	2E-15
Figure 2E-10	EXIT ONLY Panels for Right Lane Dropped at an Interchange.....	2E-16
Figure 2E-11	Interstate and U.S. Route Signs.....	2E-18
Figure 2E-12	Example of Interchange Numbering for Mainline and Circumferential Routes.....	2E-21
Figure 2E-13	Example of Interchange Numbering for Mainline, Loop, and Spur Routes.....	2E-22
Figure 2E-14	Example of Interchange Numbering If Routes Overlap.....	2E-23
Figure 2E-15	Examples of Interchange Advance Guide Signs.....	2E-25
Figure 2E-16	Next Exit Supplemental Advance Guide Signs.....	2E-26
Figure 2E-17	Supplemental Guide Signs for Multi-exit Interchanges.....	2E-28
Figure 2E-18	Supplemental Guide Sign for a Park and Ride Facility (Route without Exit Numbering).....	2E-28
Figure 2E-19	Supplemental Guide Sign for a Park and Ride Facility (Route with Exit Numbering).....	2E-29
Figure 2E-20	Interchange Exit Direction Sign.....	2E-29
Figure 2E-21	Exit Gore Signs.....	2E-31
Figure 2E-22	Post-Interchange Distance Sign.....	2E-32
Figure 2E-23	Signing of Closely Spaced Interchanges Using Interchange Sequence Signs....	2E-34
Figure 2E-24	Interchange Sequence Sign.....	2E-35
Figure 2E-25	Community Interchanges Identification Sign.....	2E-35
Figure 2E-26	NEXT EXITS Sign.....	2E-35
Figure 2E-27	Examples of Freeway-to-Freeway Interchange Guide Signs.....	2E-37
Figure 2E-28	Examples of Guide Signs for Full Cloverleaf Interchange.....	2E-38
Figure 2E-29	Examples of Guide Signs for Full Cloverleaf Interchange with Collector-Distributor Roadways.....	2E-39
Figure 2E-30	Examples of Partial Cloverleaf Interchange Guide Signs.....	2E-40
Figure 2E-31	Examples of Diamond Interchange Guide Signs.....	2E-41
Figure 2E-32	Examples of Diamond Interchange Guide Signs in an Urban Area.....	2E-42
Figure 2E-33	Examples of Minor Interchange Guide Signs.....	2E-46
Figure 2E-34	Example of Crossroad Signing for One-Lane Approach.....	2E-47
Figure 2E-35	Example of Minor Interchange Crossroad Signing.....	2E-48
Figure 2E-36	Examples of Multi-lane Crossroad Signing for Diamond Interchange.....	2E-49
Figure 2E-37	Examples of Multi-lane Crossroad Signing for Partial Cloverleaf Interchange.....	2E-50
Figure 2E-38	Examples of Multi-lane Crossroad Signing for Cloverleaf Interchange.....	2E-51
Figure 2E-39	Examples of Regulatory Signing and Pavement Markings at Exit Ramp Termination to Deter Wrong-Way Entry.....	2E-53
Figure 2E-40	Examples of Regulatory Signing and Pavement Markings at Entrance Ramp Termination Where Design Does Not Clearly Indicate the Direction of Flow.....	2E-53
Figure 2E-41	Examples of General Service Signs (without Exit Numbering).....	2E-57
Figure 2E-42	Examples of General Service Signs (with Exit Numbering).....	2E-57
Figure 2E-43	Examples of Next Services Sign.....	2E-57
Figure 2E-44	Examples of Rest Area, Scenic Overlook, and Welcome Center Signs.....	2E-58
Figure 2E-45	Enhanced Reference Location Signs.....	2E-60
Figure 2E-46	Example of Signing for the Entrance to Barrier-Separated HOV Lanes.....	2E-68

Figure 2E-47	Example of Signing for the Intermediate Entry to and Exit from Barrier- or Buffer-Separated HOV Lanes.....	2E-69
Figure 2E-48	Example of Signing for the Entrance to and Exit from an Added HOV Lane ...	2E-70
Figure 2E-49	Example of Signing for the Entrance to and Exit from a General Purpose Lane that Becomes an HOV Lane .....	2E-71
Figure 2E-50	Example of Signing for a Direct Access Ramp to an HOV Lane from a Park & Ride Facility .....	2E-72
Figure 2E-51	Example of Signing for a Direct Access Ramp to an HOV Lane from a Local Street .....	2E-73
Figure 2E-52	Example of Signing for a Direct Access Ramp between HOV Lanes on Separate Freeways .....	2E-74

**CHAPTER 2F. SPECIFIC SERVICE SIGNS**

Figure 2F-1	Examples of Specific Service Signs .....	2F-3
Figure 2F-2	Examples of Specific Service Sign Locations .....	2F-4

**CHAPTER 2G. TOURIST-ORIENTED DIRECTIONAL SIGNS**

Figure 2G-1	Examples of Tourist-Oriented Directional Signs .....	2G-3
Figure 2G-2	Examples of Intersection Approach Signs and Advance Signs for Tourist-Oriented Directional Signs.....	2G-4

**CHAPTER 2H. RECREATIONAL AND CULTURAL INTEREST AREA SIGNS**

Figure 2H-1	Examples of Use of Educational Plaques, Prohibitory Slashes, and Arrows .....	2H-4
Figure 2H-2	Examples of General Directional Guide Signs for Conventional Roads.....	2H-5
Figure 2H-3	Height and Lateral Position of Signs Located Within Recreational and Cultural Interest Areas .....	2H-6
Figure 2H-4	Examples of Symbol Signing Layout .....	2H-7
Figure 2H-5	Recreational and Cultural Interest Area Symbol Signs .....	2H-8

**CHAPTER 2I. EMERGENCY MANAGEMENT SIGNING**

Figure 2I-1	Emergency Management Signs.....	2I-4
-------------	---------------------------------	------

**TABLES**

**CHAPTER 2A. GENERAL**

Table 2A-1	Illumination of Sign Elements .....	2A-5
Table 2A-2	Retroreflection of Sign Elements.....	2A-5
Table 2A-3	Minimum Maintained Retroreflectivity Levels .....	2A-7
Table 2A-4	Use of Sign Shapes .....	2A-9
Table 2A-5	Common Uses of Sign Colors.....	2A-10

**CHAPTER 2B. REGULATORY SIGNS**

Table 2B-1	Regulatory Sign Sizes .....	2B-2
Table 2B-2	Meanings of Symbols and Legends on Reversible Lane Control Signs.....	2B-23

**CHAPTER 2C. WARNING SIGNS**

Table 2C-1	Categories of Warning Signs .....	2C-2
Table 2C-2	Warning Sign Sizes.....	2C-3
Table 2C-3	Minimum Size of Supplemental Warning Plaques .....	2C-4
Table 2C-4	Guidelines for Advance Placement of Warning Signs .....	2C-5
Table 2C-5	Horizontal Alignment Sign Usage .....	2C-7

<b>CHAPTER 2H.</b>	<b>RECREATIONAL AND CULTURAL INTEREST AREA SIGNS</b>	
Table 2H-1	Category Chart for Symbols .....	2H-3
<b>CHAPTER 2I.</b>	<b>EMERGENCY MANAGEMENT SIGNING</b>	
Table 2I-1	Emergency Management Sign Sizes.....	2I-2

## CHAPTER 2A. GENERAL

### Section 2A.01 Function and Purpose of Signs

Support:

This Manual contains Standards, Guidance, and Options for the signing within the right-of-way of all types of highways open to public travel. The functions of signs are to provide regulations, warnings, and guidance information for road users. Both words and symbols are used to convey the messages. Signs are not typically used to confirm rules of the road.

Detailed sign requirements are located in the following Chapters of Part 2:

Chapter 2B—Regulatory Signs

Chapter 2C—Warning Signs

Chapter 2D—Guide Signs (Conventional Roads)

Chapter 2E—Guide Signs (Freeways and Expressways)

Chapter 2F—Specific Service (Logo) Signs

Chapter 2G—Tourist-Oriented Direction Signs

Chapter 2H—Recreational and Cultural Interest Area Signs

Chapter 2I—Emergency Management Signs

**Standard:**

**Because the requirements and standards for signs depend on the particular type of highway upon which they are to be used, the following definitions shall apply:**

- A. Freeway—*a divided multi-lane highway for through traffic with all crossroads separated in grade and with full control of access* [4511.01(YY), O.R.C.];**
- B. Expressway—*a divided arterial highway for through traffic with full or partial control of access with an excess of fifty per cent of all crossroads separated in grade* [4511.01(ZZ), O.R.C.];**
- C. Conventional Road—*a street or highway other than a low-volume road (as defined in Section 5A.01), a freeway, or an expressway; and***
- D. Special Purpose Road—*a low-volume, low-speed road that serves recreational areas or resource development activities, or that provides local access.***

### Section 2A.02 Definitions

Support:

Definitions that are applicable to signs are given in Sections 1A.13 and 2A.01.

### Section 2A.03 Standardization of Application

Support:

It is recognized that urban traffic conditions differ from those in rural environments, and in many instances signs are applied and located differently. Where pertinent and practical, this Manual sets forth separate recommendations for urban and rural conditions.

Guidance:

Signs should be used only where justified by engineering judgment or studies, as noted in Section 1A.09.

Results from traffic engineering studies of physical and traffic factors should indicate the locations where signs are deemed necessary or desirable.

Roadway geometric design and sign application should be coordinated so that signing can be effectively placed to give the road user any necessary regulatory, warning, guidance, and other information.

**Standard:**

**Each standard sign shall be displayed only for the specific purpose as prescribed in this Manual. Determination of the particular signs to be applied to a specific condition shall be made in accordance with the criteria set forth in Part 2. Before any new highway, detour, or temporary route is opened to traffic, all necessary signs shall be in place. Signs required by road conditions or restrictions shall be removed when those conditions cease to exist or the restrictions are withdrawn.**

**Section 2A.04 Excessive Use of Signs**

Guidance:

Regulatory and warning signs should be used conservatively because these signs, if used to excess, tend to lose their effectiveness. If used, route signs and directional signs should be used frequently because they promote reasonably safe and efficient operations by keeping road users informed of their location.

**Section 2A.05 Classification of Signs**

**Standard:**

**Signs shall be defined by their function as follows:**

- A. Regulatory signs give notice of traffic laws or regulations.**
- B. Warning signs give notice of a situation that might not be readily apparent.**
- C. Guide signs show route designations, destinations, directions, distances, services, points of interest, and other geographical, recreational, or cultural information.**

**Section 2A.06 Design of Signs**

Support:

This Manual shows many typical standard signs approved for use on streets, highways, bikeways, and pedestrian crossings.

In the specifications for individual signs, the general appearance of the legend, color, and size are shown in the accompanying tables and illustrations, and are not always detailed in the text.

Detailed drawings of standard signs and alphabets are shown in the "Sign Design Manual" (SDM) published by ODOT. Section 1A.11 contains information regarding how to obtain this publication.

The basic requirements of a highway sign are that it be legible to those for whom it is intended and that it be understandable in time to permit a proper response. Desirable attributes include:

- A. High visibility by day and night; and
- B. High legibility (adequately sized letters or symbols, and a short legend for quick comprehension by a road user approaching a sign).

Standardized colors and shapes are specified so that the several classes of traffic signs can be promptly recognized. Simplicity and uniformity in design, position, and application are important.

**Standard:**

**The term legend shall include all word messages and symbol designs that are intended to convey specific meanings.**

**Uniformity in design shall include shape, color, dimensions, legends, borders, and illumination or retroreflectivity.**

**Where a standard word message is applicable, the wording shall be as herein provided. Standardization of these designs does not preclude further improvement by minor changes in the**

**proportion or orientation of symbols, width of borders, or layout of word messages, but all shapes and colors shall be as indicated.**

**In situations where word messages are required other than those herein provided, the signs shall be of the same shape and color as standard signs of the same functional type.**

**Except as stated in the Option below, Internet addresses shall not be shown on any sign, supplemental plaque, sign panel (including logo panels on specific service signs), or changeable message sign.**

Guidance:

Unless otherwise stated in this Manual or shown in the SDM for a specific sign, and except as stated in the Option below, phone numbers of more than four characters should not be shown on any sign, supplemental plaque, sign panel (including logo panels on specific service signs), or changeable message sign.

Option:

Internet addresses or phone numbers with more than four characters may be shown on signs, supplemental plaques, sign panels, and changeable message signs that are intended for viewing only by pedestrians, bicyclists, occupants of parked vehicles, or drivers of vehicles on low-speed roadways where engineering judgment indicates that drivers can reasonably safely stop out of the traffic flow to read the message.

Highway agencies may develop special word message signs in situations where roadway conditions make it necessary to provide road users with additional regulatory, warning, or guidance information.

## **Section 2A.07 Changeable Message Signs**

**Standard:**

**To the extent practical, changeable message signs, which are traffic control devices designed to display variable messages, shall conform to the principles established in this Manual, and with the design and applications prescribed in Sections 2E.21, 6F.02, and 6F.55.**

Guidance:

Except for safety or transportation-related messages, changeable message signs should not be used to display information other than regulatory, warning, and guidance information related to traffic control.

Support:

Changeable message signs, with more sophisticated technologies, are gaining widespread use to inform road users of variable situations, particularly along congested traffic corridors. Highway and transportation organizations are encouraged to develop and experiment (see Section 1A.10) with changeable message signs and to carefully evaluate such installations so that experience is gained toward adoption of future standards.

Information regarding the design and application of portable changeable message signs in temporary traffic control zones is contained in Section 6F.55. Section 1A.14 contains information regarding the use of abbreviations on traffic control devices, including changeable message signs.

Option:

Changeable message signs (including portable changeable message signs) that display a regulatory or warning message may use a black background with a white, yellow, orange, red, or fluorescent yellow-green legend as appropriate, except where specifically restricted in this Manual for a particular sign.

Changeable message signs, both permanent and portable, may be used by highway agencies to display safety or transportation-related messages. Highway agencies may develop and establish a policy regarding the display of safety and transportation-related messages on permanent and changeable message signs that specifies the allowable messages and applications, consistent with the provisions of this Manual.

**Support:**

Examples of safety messages include SEAT BELTS BUCKLED? and DON'T DRINK AND DRIVE. Examples of transportation-related messages include STADIUM EVENT SUNDAY, EXPECT DELAYS NOON TO 4 PM and OZONE ALERT CODE RED—USE TRANSIT.

**Guidance:**

When a changeable message sign is used to display a safety or transportation-related message, the requirements of Section 6F.55 should be followed. The message should be simple, brief, legible, and clear. A changeable message sign should not be used to display a safety or transportation-related message if doing so would adversely affect the respect for the sign. "CONGESTION AHEAD" or other overly simplistic or vague messages should not be displayed alone. These messages should be supplemented with a message on the location or distance to the congestion or incident, how much delay is expected, alternative route, or other similar messages.

**Standard:**

**When a changeable message sign is used to display a safety or transportation-related message, the display format shall not be of a type that could be considered similar to advertising displays. The display format shall not include animation, rapid flashing, or other dynamic elements that are characteristic of sports scoreboards or advertising displays.**

**Section 2A.08 Retroreflectivity and Illumination****Support:**

There are many materials currently available for retroreflection and various methods currently available for the illumination of signs. New materials and methods continue to emerge. New materials and methods can be used as long as the signs meet the standard requirements for color, both by day and by night.

**Standard:**

**Regulatory, warning, and guide signs shall be retroreflective or illuminated to show the same shape and similar color by both day and night, unless specifically stated otherwise in the text discussion in this Manual of a particular sign or group of signs.**

**The requirements for sign illumination shall not be considered to be satisfied by street or highway lighting.**

**Guidance:**

All overhead sign installations should be illuminated unless an engineering study shows that retroreflection will perform effectively without illumination.

**Option:**

Sign elements may be illuminated by the means shown in Table 2A-1.

Retroreflection of sign elements may be accomplished by the means shown in Table 2A-2.

Light Emitting Diode (LED) units may be used individually within the face of a sign and in the border of a sign, except for changeable message signs, to improve the conspicuity, increase the legibility of sign legends and borders, or provide a changeable message. Individual LED pixels may be used in the border of a sign.

**Standard:**

**If used, the LEDs shall be the same color as the sign legend, border, or background. If flashed, all LED units shall flash simultaneously at a rate of more than 50 and less than 60 times per minute. The uniformity of the sign design shall be maintained without any decrease in visibility, legibility, or driver comprehension during either daytime or nighttime conditions.**

**Table 2A-1. Illumination of Sign Elements**

Means of Illumination	Sign Element To Be Illuminated
Light behind the sign face	<ul style="list-style-type: none"> <li>• Symbol or word message</li> <li>• Background</li> <li>• Symbol, word message, and background (through a translucent material)</li> </ul>
Attached or independently mounted light source designed to direct essentially uniform illumination onto the sign face	<ul style="list-style-type: none"> <li>• Entire sign face</li> </ul>
Light emitting diodes (LEDs)	<ul style="list-style-type: none"> <li>• Symbol or word message</li> <li>• Portions of the sign border</li> </ul>
Other devices, or treatments that highlight the sign shape, color, or message: Luminous tubing Fiber optics Incandescent light bulbs Luminescent panels	<ul style="list-style-type: none"> <li>• Symbol or word message</li> <li>• Entire sign face</li> </ul>

**Table 2A-2. Retroreflection of Sign Elements**

Means of Retroreflection	Sign Element
Reflector “buttons” or similar units	Symbol Word Message Border
A material that has a smooth, sealed outer surface over a microstructure that reflects light	Symbol Word Message Border Background

**A module of multiple LED units used as a closely-spaced, single light source shall only be used within the sign face for legends or symbols.**

Support:

Information regarding the use of retroreflective material on the sign support is contained in Section 2A.21.

**Section 2A.09 Maintaining Minimum Retroreflectivity**

Support:

Retroreflectivity is one of several factors associated with maintaining nighttime sign visibility (see Section 2A.22).

**Standard:**

**Public agencies or officials having jurisdiction shall use an assessment or management method that is designed to maintain sign retroreflectivity at or above the minimum levels in Table 2A-3.**

**Support:**

Compliance with the above standard is achieved by having a method in place and using the method to maintain the minimum levels established in Table 2A-3. Provided that an assessment or management method is being used, an agency or official having jurisdiction would be in compliance with the above Standard even if there are some individual signs that do not meet the minimum retroreflectivity levels at a particular point in time.

**Guidance:**

Except for those signs specifically identified in the Option in this Section, one or more of the following assessment or management methods should be used to maintain sign retroreflectivity:

- A. Visual Nighttime Inspection – The retroreflectivity of an existing sign is assessed by a trained sign inspector conducting a visual inspection from a moving vehicle during nighttime conditions. Signs that are visually identified by the inspector to have retroreflectivity below the minimum levels should be replaced.
- B. Measured Sign Retroreflectivity – Sign retroreflectivity is measured using a retroreflectometer. Signs with retroreflectivity below the minimum levels should be replaced.
- C. Expected Sign Life – When signs are installed, the installation date is labeled or recorded so that the age of a sign is known. The age of the sign is compared to the expected sign life. The expected sign life is based on the experience of sign retroreflectivity degradation in a geographic area compared to the minimum levels. Signs older than the expected life should be replaced.
- D. Blanket Replacement – All signs in an area/corridor, or of a given type, should be replaced at specified intervals. This eliminates the need to assess retroreflectivity or track the life of individual signs. The replacement interval is based on the expected sign life, compared to the minimum levels, for the shortest-life material used on the affected signs.
- E. Control Signs – Replacement of signs in the field is based on the performance of a sample of control signs. The control signs might be a small sample located in a maintenance yard or a sample of signs in the field. The control signs are monitored to determine the end of retroreflective life for the associated signs. All field signs represented by the control sample should be replaced before the retroreflectivity levels of the control sample reach the minimum levels.
- F. Other Methods – Other methods developed based on engineering studies can be used.

**Support:**

Additional information about these methods is contained in the 2007 Edition of FHWA's "Maintaining Traffic Sign Retroreflectivity" (see Section 1A.11).

**Option:**

Highway agencies may exclude the following signs from the retroreflectivity maintenance guidelines described in this Section:

- A. Parking, Standing, and Stopping signs (R7 and R8 series)
- B. Walking/Hitchhiking/Crossing signs (R9 series, R10-1 through R10-4b)
- C. Adopt-A-Highway signs
- D. All signs with blue or brown backgrounds
- E. Bikeway signs that are intended for exclusive use by bicyclists or pedestrians

**Table 2A-3. Minimum Maintained Retroreflectivity Levels ①**

Sign Color	Sheeting Type (ASTM D4956-04)				Additional Criteria
	Beaded Sheeting			Prismatic Sheeting	
	I	II	III	III, IV, VI, VII, VIII, IX, X	
White On Green	W*; G ≥ 7	W*; G ≥ 15	W*; G ≥ 25	W ≥ 250; G ≥ 25	Overhead
	W*; G ≥ 7	W ≥ 120; G ≥ 15			Ground-mounted
Black on Yellow or Black on Orange	Y*; O*	Y ≥ 50; O ≥ 50			②
	Y*; O*	Y ≥ 75; O ≥ 75			③
White on Red	W ≥ 35; R ≥ 7				④
Black on White	W ≥ 50				-
<p>① The minimum maintained retroreflectivity levels shown in this table are in units of cd/lx/m<sup>2</sup> measured at an observation angle of 0.2° and an entrance angle of -4.0°.</p> <p>② For text and fine symbol signs measuring at least 1200 mm (48 in) and for all sizes of bold symbol signs</p> <p>③ For text and fine symbol signs measuring less than 1200 mm (48 in)</p> <p>④ Minimum Sign Contrast Ratio ≥ 3:1 (white retroreflectivity ÷ red retroreflectivity)</p> <p>* This sheeting type should not be used for this color for this application.</p>					
<b>Bold Symbol Signs</b>					
<ul style="list-style-type: none"> <li>• W1-1, -2 – Turn and Curve</li> <li>• W1-3, -4 – Reverse Turn and Curve</li> <li>• W1-5 – Winding Road</li> <li>• W1-6, -7 – Large Arrow</li> <li>• W1-8 – Chevron</li> <li>• W1-10 – Intersection in Curve</li> <li>• W1-11 – Hairpin Curve</li> <li>• W1-15 – 270 Degree Loop</li> <li>• W2-1 – Cross Road</li> <li>• W2-2, -3 – Side Road</li> <li>• W2-4, -5 – T and Y Intersection</li> <li>• W2-6 – Circular Intersection</li> <li>• W3-1 – Stop Ahead</li> </ul>		<ul style="list-style-type: none"> <li>• W3-2 – Yield Ahead</li> <li>• W3-3 – Signal Ahead</li> <li>• W4-1 – Merge</li> <li>• W4-2 – Lane Ends</li> <li>• W4-3 – Added Lane</li> <li>• W4-5 – Entering Roadway Merge</li> <li>• W4-6 – Entering Roadway Added Lane</li> <li>• W6-1, -2 – Divided Highway Begins and Ends</li> <li>• W6-3 – Two-Way Traffic</li> <li>• W10-1, -2, -3, -4, -11, -12 – Highway-Railroad Advance Warning</li> </ul>		<ul style="list-style-type: none"> <li>• W11-2 – Pedestrian Crossing</li> <li>• W11-3 – Deer Crossing</li> <li>• W11-4 – Cattle Crossing</li> <li>• W11-5 – Farm Equipment</li> <li>• W11-6 – Snowmobile Crossing</li> <li>• W11-7 – Equestrian Crossing</li> <li>• W11-8 – Fire Station</li> <li>• W11-10 – Truck Crossing</li> <li>• W12-1 – Double Arrow</li> <li>• W16-5p, -6p, -7p – Pointing Arrow Plaques</li> <li>• W20-7a – Flagger</li> <li>• W21-1a – Worker</li> </ul>	
<b>Fine Symbol Signs</b> – Symbol signs not listed as Bold Symbol Signs.					
<b>Special Cases</b>					
<ul style="list-style-type: none"> <li>• W3-1 – Stop Ahead: Red retroreflectivity ≥ 7</li> <li>• W3-2 – Yield Ahead: Red retroreflectivity ≥ 7; White retroreflectivity ≥ 35</li> <li>• W3-3 – Signal Ahead: Red retroreflectivity ≥ 7; Green retroreflectivity ≥ 7</li> <li>• W3-5 – Speed Reduction: White retroreflectivity ≥ 50</li> <li>• For non-diamond shaped signs such W14-3 (No Passing Zone), W4-4p (Cross Traffic Does Not Stop), or W13-1, -2, -3, -5 (Speed Advisory Plaques), use largest sign dimension to determine proper minimum retroreflectivity level.</li> </ul>					

## **Section 2A.10 Shapes**

### **Standard:**

Particular shapes, as shown in Table 2A-4, shall be used exclusively for specific signs or series of signs, unless specifically stated otherwise in the text discussion in this Manual for a particular sign or class of signs.

## **Section 2A.11 Sign Colors**

### **Standard:**

The colors to be used on standard signs and their specific use on these signs shall be as indicated in the applicable Sections of this Manual. The color coordinates and values shall be as described in 23 CFR, Part 655, Subpart F, Appendix.

### **Support:**

As a quick reference, common uses of sign colors are shown in Table 2A-5. Color schemes on specific signs are shown in the illustrations located in each appropriate Section.

Whenever white is specified herein as a color, it is understood to include silver-colored retroreflective coatings or elements that reflect white light.

The colors coral, purple, and light blue are being reserved for uses that will be determined in the future by the Federal Highway Administration (FHWA).

Information regarding color coding of destinations on guide signs is contained in Section 2D.03.

## **Section 2A.12 Dimensions**

### **Support:**

Sign sizes for use on the different classes of highways are shown in Sections 2B.03, 2C.04, 2D.04, 5A.03, 6F.02, 7B.01, 8B.02, and 9B.02, and in the SDM.

The SDM (see Section 1A.11) prescribes design details for various sizes depending on the type of traffic facility, including bikeways. Smaller sizes are designed to be used on bikeways and some other off-road applications. Larger sizes are designed for use on freeways and expressways, and can also be used to enhance road user safety and convenience on other facilities, especially on multi-lane divided highways and on undivided highways having five or more lanes of traffic and/or high speeds. The intermediate sizes are designed to be used on other highway types.

### **Standard:**

The sign dimensions prescribed in this Manual and in the SDM (see Section 1A.11) shall be used unless engineering judgment determines that other sizes are appropriate. Where engineering judgment determines that sizes smaller than the prescribed dimensions are appropriate for use, the sign dimensions shall not be less than the minimum dimensions specified in this Manual. Where engineering judgment determines that sizes larger than the prescribed dimensions are appropriate for use, standard shapes and colors shall be used and standard proportions shall be retained as much as practical.

### **Guidance:**

Increases above the prescribed sizes should be used where greater legibility or emphasis is needed. Wherever practical, the overall sign dimensions should be increased in 150 mm (6 in) increments.

**Table 2A-4. Use of Sign Shapes**

Shape	Signs
Octagon	* Stop
Equilateral Triangle (1 point down)	* Yield
Circle	* Highway-Rail Grade Crossing (Advance Warning)
Pennant Shape/ Isosceles Triangle (longer axis horizontal)	* No Passing
Pentagon (pointed up)	* School Advance Warning Sign * County Route Sign
Crossbuck (two rectangles in an "X" configuration)	* Highway-Rail Grade Crossing
Diamond	Warning Series
Rectangle (including square)	Regulatory Series ** Guide Series Warning Series
Trapezoid	* Recreational and Cultural Interest Area Series National Forest Route Sign

\* This sign shall be exclusively the shape shown.

\*\* Guide series includes general service, specific service, recreation, and emergency management signs.

**Section 2A.13 Symbols**

Support:

Sometimes a change from word messages to symbols requires significant time for public education and transition. Therefore, this Manual includes the practice of using educational plaques to accompany some new symbol signs.

**Standard:**

**Symbol designs shall in all cases be unmistakably similar to those shown in this Manual and in the SDM (see Section 1A.11). New symbol designs shall be adopted by the Federal Highway Administration based on research evaluations to determine road user comprehension, sign conspicuity, and sign legibility.**

**Table 2A-5. Common Uses of Sign Colors**

Type of Sign	Legend					Background									
	Black	Green	Red	White	Yellow	Black	Blue	Brown	Green	Orange	Red	White	Yellow	Fluorescent Yellow-Green	Fluorescent Pink
Regulatory	X		X	X		X					X	X			
Prohibitive			X	X							X	X			
Permissive		X										X			
Warning	X												X		
Pedestrian	X												X	X	
Bicycle	X												X	X	
Guide				X					X						
Interstate Route				X			X				X				
State Route	X											X			
US Route	X											X			
County Route					X		X								
Forest Route				X				X							
Street Name				X					X						
Destination				X					X						
Reference Location				X					X						
Information				X			X		X						
Evacuation Route				X			X								
Road User Service				X			X								
Recreational				X				X	X						
Temporary Traffic Control	X									X					
Incident Management	X									X					X
Changeable Message Sign *				X	X	X									
School	X												X	X	

\* Reverse colors or fluorescent yellow-green pixels may also be used on changeable message signs.

**Guidance:**

New warning or regulatory symbol signs not readily recognizable by the public should be accompanied by an educational plaque.

**Option:**

Highway agencies may conduct research studies to determine road user comprehension, sign conspicuity, and sign legibility.

Educational plaques may be left in place as long as they are in serviceable condition.

Although most standard symbols are oriented facing left, mirror images of these symbols may be used where the reverse orientation might better convey to road users a direction of movement.

**Section 2A.14 Word Messages****Standard:**

**Except as noted in Section 2A.06, all word messages shall use standard wording and letters as shown in this Manual and the SDM (see Section 1A.11).**

**Guidance:**

Word messages should be as brief as possible and the lettering should be large enough to provide the necessary legibility distance. A minimum specific ratio, such as 25 mm (1 in) of letter height per 12 m (40 ft) of legibility distance, should be used.

**Support:**

Some research indicates that a ratio of 25 mm (1 in) of letter height per 10 m (33 ft) of legibility distance could be beneficial.

**Guidance:**

Abbreviations (see Section 1A.14) should be kept to a minimum, and should include only those that are commonly recognized and understood, such as AVE (for Avenue), BLVD (for Boulevard), N (for North), or JCT (for Junction).

**Standard:**

**All sign lettering shall be in capital letters as provided in the SDM, except as indicated in the Option below.**

**Option:**

Word messages on street name signs and destinations on guide signs may be composed of a combination of lower-case letters with initial upper-case letters.

**Section 2A.15 Sign Borders****Standard:**

**Unless specifically stated otherwise, each sign illustrated herein shall have a border of the same color as the legend, at or just inside the edge.**

**The corners of all sign borders shall be rounded, except for STOP signs.**

**Guidance:**

A dark border on a light background should be set in from the edge, while a light border on a dark background should extend to the edge of the panel. A border for 750 mm (30 in) signs with a light background should be from 13 to 19 mm (0.5 to 0.75 in) in width, 13 mm (0.5 in) from the edge. For similar signs with a light border, a width of 25 mm (1 in) should be used. For other sizes, the border width should be of similar proportions, but should not exceed the stroke-width of the major lettering of the sign. On signs exceeding 1800 x 3000 mm (72 x 120 in) in size, the border should be 50 mm (2 in) wide, or on larger signs,

75 mm (3 in) wide. Except for STOP signs and as otherwise provided in Section 2E.15, the corners of the sign should be rounded to fit the border.

### **Section 2A.16 Standardization of Location**

Support:

Standardization of position cannot always be attained in practice. Examples of heights and lateral locations of signs for typical installations are illustrated in Figure 2A-1, and examples of locations for some typical signs at intersections are illustrated in Figure 2A-2.

**Standard:**

**Signs requiring different decisions by the road user shall be spaced sufficiently far apart for the required decisions to be made reasonably safely. One of the factors considered when determining the appropriate spacing shall be the posted or 85th-percentile speed.**

Guidance:

Signs should be located on the right side of the roadway where they are easily recognized and understood by road users. Signs in other locations should be considered only as supplementary to signs in the normal locations, except as otherwise indicated.

Signs should be individually installed on separate posts or mountings except where:

- A. One sign supplements another, or
- B. Route or directional signs are grouped to clarify information to motorists, or
- C. Regulatory signs that do not conflict with each other are grouped, such as turn prohibition signs posted with one-way signs, street name signs posted with a stop or yield sign, or a parking regulation sign posted with a speed limit sign.

Signs should be located so that they:

- A. Are outside the clear zone unless placed on a breakaway or yielding support (see Section 2A.19);
- B. Optimize nighttime visibility;
- C. Minimize the effects of mud splatter and debris;
- D. Do not obscure each other; and
- E. Are not hidden from view.

Support:

The clear zone is the total roadside border area, starting at the edge of the traveled way, available for use by errant vehicles. The width of the clear zone is dependent upon traffic volumes, speeds, and roadside geometry. Additional information can be found in the “AASHTO Roadside Design Guide” (see the Preface for AASHTO’s address) and ODOT’s “Location and Design Manual, Volume One – Roadway Design” (see Section 1A.11).

Guidance:

With the increase in traffic volumes and the desire to provide road users regulatory, warning, and guidance information, an order of priority for sign installation should be established.


Support:

An order of priority is especially critical where space is limited for sign installation and there is a demand for several different types of signs. Overloading road users with too much information is not desirable.

Guidance:


Because regulatory and warning information is more critical to the road user than guidance information, regulatory and warning signing whose location is critical should be displayed rather than guide signing in cases where conflicts occur. Information of a less critical nature should be moved to less critical locations or omitted.

**Figure 2A-1. Examples of Heights and Lateral Locations of Signs for Typical Installations**



Note:  
See Section 2A.19 for reduced lateral offset distances that may be used in areas where lateral offsets are limited, and in urban areas where sidewalk width is limited or where existing poles are close to the curb.

**Figure 2A-2. Examples of Locations for Some Typical Signs at Intersections**



Note: Lateral offset is a minimum of 1.8 m (6 ft) measured from the edge of the shoulder, or 3.7 m (12 ft) measured from the edge of the traveled way. See Section 2A.19 for lower minimums that may be used in urban areas, or where lateral offset space is limited.

**Option:**

Under some circumstances, such as on curves to the right, signs may be placed on median islands or on the left side of the road. A supplementary sign located on the left of the roadway may be used on a multi-lane road where traffic in the right lane might obstruct the view to the right.

**Guidance:**

In urban areas where crosswalks exist, signs should not be placed within 1.2 m (4 ft) in advance of the crosswalk.

**Section 2A.17 Overhead Sign Installations****Guidance:**

Overhead signs should be used on freeways and expressways, at locations where some degree of lane-use control is desirable, and at locations where space is not available at the roadside.

**Support:**

The operational requirements of the present highway system are such that overhead signs have value at many locations. The factors to be considered for the installation of overhead sign displays are not definable in specific numerical terms.

**Option:**

The following conditions (not in priority order) may be considered in an engineering study to determine if overhead signs would be beneficial:

- A. Traffic volume at or near capacity;
- B. Complex interchange design;
- C. Three or more lanes in each direction;
- D. Restricted sight distance;
- E. Closely spaced interchanges;
- F. Multi-lane exits;
- G. Large percentage of trucks;
- H. Street lighting background;
- I. High-speed traffic;
- J. Consistency of sign message location through a series of interchanges;
- K. Insufficient space for ground-mounted signs;
- L. Junction of two freeways; and
- M. Left exit ramps.

Over-crossing structures may serve for the support of overhead signs, and under some circumstances, may be the only practical solution that will provide adequate viewing distance. Use of such structures as sign supports may eliminate the need for the foundations and sign supports along the roadside.

**Section 2A.18 Mounting Height****Support:**

The provisions of this Section apply unless specifically stated otherwise for a particular sign elsewhere in this Manual.

**Standard:**

**Signs installed at the side of the road in rural districts shall be at least 1.5 m (5 ft), measured from the bottom of the sign to the near edge of the pavement.**

**Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 2.1 m (7 ft).**

**Directional signs on freeways and expressways shall be installed with a minimum height of 2.1 m (7 ft). If a secondary sign is mounted below another sign, the major sign shall be installed at least 2.4 m (8 ft) and the secondary sign at least 1.5 m (5 ft) above the level of the pavement edge. All route signs, warning signs, and regulatory signs on freeways and expressways shall be at least 2.1 m (7 ft) above the level of the pavement edge.**

Option:

The height to the bottom of a secondary sign mounted below another sign may be 0.3 m (1 ft) less than the height specified above.

Where signs are placed 9 m (30 ft) or more from the edge of the traveled way, the height to the bottom of such signs may be 1.5 m (5 ft) above the level of the pavement edge.

A route sign assembly consisting of a route sign and auxiliary signs (see Section 2D.27) may be treated as a single sign for the purposes of this Section.

The mounting height may be adjusted when supports are located near the edge of the right-of-way on a steep backslope.

Support:

Without this flexibility regarding steep backslopes, some agencies might decide to relocate the sign closer to the road, which might be less desirable.

**Standard:**

**Overhead-mounted signs shall provide a vertical clearance of not less than 5.2 m (17 ft) to the sign, light fixture, or sign bridge, over the entire width of the pavement and shoulders except where a lesser vertical clearance is used for the design of other structures.**

Option:

If the vertical clearance of other structures is less than 4.9 m (16 ft), the vertical clearance to overhead sign structures or supports may be as low as 0.3 m (1 ft) higher than the vertical clearance of the other structures.

In special cases it may be necessary to reduce the clearance to overhead signs because of substandard dimensions in tunnels and other major structures such as double-deck bridges.

Support:

Figure 2A-1 illustrates some examples of the mounting height requirements contained in this Section.

## **Section 2A.19 Lateral Offset**

**Standard:**

**For overhead sign supports, the minimum lateral offset from the edge of the shoulder (or if no shoulder exists, from the edge of the pavement) to the near edge of overhead sign supports (cantilever or sign bridges) shall be 1.8 m (6 ft). Overhead sign supports shall have a barrier or crash cushion to shield them if they are within the clear zone.**

**Ground-mounted sign supports shall be breakaway, yielding, or shielded with a longitudinal barrier or crash cushion if within the clear zone.**

Guidance:

For ground-mounted signs, the minimum lateral offset should be 3.7 m (12 ft) from the edge of the traveled way. If a shoulder wider than 1.8 m (6 ft) exists, the minimum lateral offset for ground-mounted signs should be 1.8 m (6 ft) from the edge of the shoulder.

**Support:**

The minimum lateral offset is intended to keep trucks and cars that use the shoulders from striking the signs or supports.

**Guidance:**

All supports should be located as far as practical from the edge of the shoulder. Advantage should be taken to place signs behind existing roadside barriers, on over-crossing structures, or other locations that minimize the exposure of the traffic to sign supports.

**Option:**

Where permitted, signs may be placed on existing supports used for other purposes, such as highway traffic signal supports, highway lighting supports, and utility poles.

**Standard:**

**If signs are placed on existing supports, they shall meet other placement criteria contained in this Manual.**

**Option:**

Lesser lateral offsets may be used on connecting roadways or ramps at interchanges, but not less than 1.8 m (6 ft) from the edge of the traveled way.

In areas where lateral offsets are limited, a minimum lateral offset of 0.6 m (2 ft) may be used.

A minimum offset of 0.3 m (1 ft) from the face of the curb may be used in urban areas where sidewalk width is limited or where existing poles are close to the curb.

**Support:**

Figures 2A-1 and 2A-2 illustrate some examples of the lateral offset requirements contained in this Section.

**Section 2A.20 Orientation****Guidance:**

Unless otherwise stated in this Manual, signs should be vertically mounted at right angles to the direction of, and facing, the traffic that they are intended to serve.

Where mirror reflection from the sign face is encountered to such a degree as to reduce legibility, the sign should be turned slightly away from the road. Signs that are placed 9 m (30 ft) or more from the pavement edge should be turned toward the road. On curved alignments, the angle of placement should be determined by the direction of approaching traffic rather than by the roadway edge at the point where the sign is located.

**Option:**

On grades, sign faces may be tilted forward or back from the vertical position to improve the viewing angle.

**Section 2A.21 Posts and Mountings****Standard:**

**Sign posts, foundations, and mountings shall be so constructed as to hold signs in a proper and permanent position, and to resist swaying in the wind or displacement by vandalism.**

**Support:**

The latest edition of AASHTO's "Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals" contains additional information regarding posts and mounting (see the Preface for AASHTO's address).

**Option:**

Where engineering judgment indicates a need to draw attention to the sign during nighttime conditions, a strip of retroreflective material may be used on regulatory and warning sign supports.

**Standard:**

**If a strip of retroreflective material is used on the sign support, it shall be at least 50 mm (2 in) in width, it shall be placed for the full length of the support from the sign to within 0.6 m (2 ft) above the edge of the roadway, and its color shall match the background color of the sign, except that the color of the strip for the YIELD and DO NOT ENTER signs shall be red.**

**Section 2A.22 Maintenance****Guidance:**

Maintenance activities should consider proper position, cleanliness, legibility, and daytime and nighttime visibility (see Section 2A.09). Damaged or deteriorated signs should be replaced.

To assure adequate maintenance, a schedule for inspecting (both day and night), cleaning, and replacing signs should be established. Employees of highway, law enforcement, and other public agencies whose duties require that they travel on the roadways should be encouraged to report any damaged, deteriorated, or obscured signs at the first opportunity.

Steps should be taken to see that weeds, trees, shrubbery, and construction, maintenance, and utility materials and equipment do not obscure the face of any sign.

A regular schedule of replacement of lighting elements for illuminated signs should be maintained.

**Section 2A.23 Median Opening Treatments for Divided Highways with Wide Medians****Support:**

As noted in Section 1A.13, the definition of “intersection” in O.R.C. 4511.01(KK) (see Appendix B2) includes in part the following:

*“Where a highway includes two roadways thirty feet or more apart, then every crossing of each roadway of such divided highway by an intersecting highway shall be regarded as a separate intersection. If an intersecting highway also includes two roadways thirty feet or more apart, then every crossing of two roadways of such highways shall be regarded as a separate intersection;”*

**Standard:**

**Where divided highways are separated by median widths at the median opening itself of 9 m (30 ft) or more, median openings shall be signed as two separate intersections.**

## **CHAPTER 2B. REGULATORY SIGNS**

### **Section 2B.01 Application of Regulatory Signs**

**Standard:**

Regulatory signs shall be used to inform road users of selected traffic laws or regulations and indicate the applicability of the legal requirements.

Regulatory signs shall be installed at or near where the regulations apply. The signs shall clearly indicate the requirements imposed by the regulations and shall be designed and installed to provide adequate visibility and legibility in order to obtain compliance.

Regulatory signs shall be retroreflective or illuminated to show the same shape and similar color by both day and night, unless specifically stated otherwise in the text discussion of a particular sign or group of signs (see Section 2A.08).

Regulatory sign designs contained in the “Sign Design Manual” (SDM) (see Section 1A.11) are incorporated by reference into this Manual, and shall have the same legal applicability as if they had been included in this Manual.

The requirements for sign illumination shall not be considered to be satisfied by street, highway, or strobe lighting.

### **Section 2B.02 Design of Regulatory Signs**

**Support:**

Most regulatory signs are rectangular, with the longer dimension vertical. The shapes and colors of regulatory signs are listed in Tables 2A-4 and 2A-5, respectively. Exceptions are specifically noted in the following Sections.

The use of educational plaques to supplement symbol signs is described in Section 2A.13.

**Guidance:**

Changeable message signs displaying a regulatory message incorporating a prohibitory message that includes a red circle and slash on a static sign should display a red symbol that approximates the same red circle and slash as closely as possible.

### **Section 2B.03 Size of Regulatory Signs**

**Standard:**

The sizes for regulatory signs shall be as shown in Table 2B-1 and the “Sign Design Manual” (SDM) (see Section 1A.11).

**Guidance:**

The Freeway and Expressway sizes should be used for higher-speed applications to provide larger signs for increased visibility and recognition.

**Option:**

The Minimum size may be used on low-speed roadways where the reduced legend size would be adequate for the regulation or where physical conditions preclude the use of the other sizes.

The Oversized size may be used for those special applications where speed, volume, or other factors result in conditions where increased emphasis, improved recognition, or increased legibility would be desirable.

Signs larger than those shown in Table 2B-1 may be used (see Section 2A.12).

**Table 2B-1. Regulatory Sign Sizes (Sheet 1 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
STOP	R1-1	2B.04	750 x 750 (30 x 30)	900 x 900 (36 x 36)	—	600 x 600 (24 x 24)	1200 x 1200 (48 x 48)
YIELD	R1-2	2B.08	900x900x900 (36 x 36 x 36)	1200 x 1200 x 1200 (48 x48 x 48)	1500 x 1500 x 1500 (60 x 60 x 60)	750 x 750 x 750 (30 x30 x 30)	—
TO ONCOMING TRAFFIC	R1-2a	2B.08	600 X 450 (24 X 18)	—	—	—	—
4-WAY	R1-3	2B.04	300 x 150 (12 x 6)	—	—	—	—
ALL WAY	R1-4	2B.04	450 x 150 (18 x 6)	—	—	—	—
Yield Here To Peds (symbol)	R1-5	2B.11	450 x 450 (18 x 18)	—	—	—	—
YIELD HERE TO PEDESTRIANS	R1-5a	2B.11	450 x 600 (18 x 24)	—	—	—	—
In-Street Pedestrian Crossing	R1-6	2B.12	300 x 900 (12 x 36)	—	—	—	—
Speed Limit	R2-1	2B.13	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
Truck Speed Limit	R2-2	2B.14	600 x 600 (24 x 24)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	—	—
VEHICLES OVER 4 TONS ...	R2-H2a	2B.14	—	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
SPEED LIMIT 65 VEHICLES OVER ...	R2-H2b	2B.13	—	900 x 1800 (36 x 72)	1200 x 2400 (48 x 96)	—	—
Night Speed Limit	R2-3	2B.15	600 x 600 (24 x 24)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	—	—
Min. Speed Limit	R2-4	2B.16	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
Combined Speed Limit	R2-4a	2B.16	600 x 1200 (24 x 48)	900 x 1800 (36 x 72)	1200 x 2400 (48 x 96)	—	—
FINES HIGHER	R2-6	2B.16	600 x 600 (24 x 24)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	—	—
Turn Prohibition	R3- 1, 2, 3, 4, 18	2B.19	600 x 600 (24 x 24)	900 x 900 (36 x 36)	—	—	1200 x 1200 (48 x 48)
Mandatory Movement Lane Control	R3-5 series	2B.21	750 x 900 (30 x 36)	—	—	—	—
Optional Movement Lane Control	R3-6	2B.22	750 x 900 (30 x 36)	—	—	—	—
Man. Movement Lane Control	R3-7	2B.21	750 x 750 (30 x 30)	—	—	—	—
Advance Intersection Lane Control	R3-8, 8a, 8b	2B.23	Variable x 750 (Variable x 30)	—	—	—	—
Two-Way Left Turn Only (overhead mt'd)	R3-9a	2B.24	750 x 900 (30 x 36)	—	—	—	—
Two-Way Left Turn Only (ground mt'd)	R3-9b	2B.24	600 x 900 (24 x 36)	—	—	—	900 x 1200 (36 x 48)
Reversible Lane Control (symbol)	R3-9d	2B.25	2700 x 1200 (108 x 48)	—	—	—	—
Rev. Lane Control (ground mt'd)	R3-9f	2B.25	750 x 1050 (30 x 42)	—	—	—	—
Advance Rev. Lane Control Transition Signing	R3-9g, 9h	2B.25	2700 x 900 (108 x 36)	—	—	—	—

**Table 2B-1. Regulatory Sign Sizes (Sheet 2 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
END REVERSE LANE	R3-9i	2B.25	2700 x 1200 (108 x 48)	—	—	—	—
Preferential Only Lane Ahead (ground mt'd)	R3-10 series	2B.26	750 x 1050 (30 x 42)	900 x 1500 (36 x 60)	1950 x 2400 (78 x 96)	—	—
Preferential Only Lane Operation (ground mounted)	R3-11 series	2B.26	750 x 1050 (30 x 42)	—	1950 x 2400 (78 x 96)	—	—
Preferential Only Lane Ends (ground mounted)	R3-12 series	2B.26	750 x 1050 (30 x 42)	900 x 1500 (36 x 60)	1200 x 2100 (48 x 84) 1200 X 2400 (48 x 95)	—	—
Preferential Only Lane Ahead (overhead mounted)	R3-13 series	2B.26	1650 x 900 (66 x 36)	2100 x 1200 (84 x 48)	3600 x 1950 (144 x 78) 3600 x 2400 (144 x 96)	—	—
Preferential Only Lane Operation (overhead mounted)	R3-14 (series)	2B.26	1800 x 1500 (66 x 36)	2400 x 1800 (84 x 48)	3600 x 2650 (144 x 106) 3600 x 3100 (144 x 124) 3600 x 2250 (144 x 90)	—	—
HOV 2+ Lane Ends (overhead mounted)	R3-15 series	2B.26	1650 x 900 (66 x 36)	2100 x 1200 (84 x 48)	2550 x 1500 (102 x 60)	—	—
DO NOT PASS	R4-1	2B.29	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	450 x 600 (18 x 24)	—
PASS WITH CARE	R4-2	2B.30	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	450 x 600 (18 x 24)	—
SLOWER TRAFFIC KEEP RIGHT	R4-3	2B.31	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
TRUCKS USE RIGHT LANE	R4-5	2B.32	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 1500 (48 x 60)	—	—
TRUCK LANE XX FEET	R4-6	2B.32	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
Keep Right	R4-7, 7a, 7b	2B.33	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	450 x 600 (18 x 24)	—
Keep Left	R4-8	2B.33	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	450 x 600 (18 x 24)	—
THROUGH TRAFFIC KEEP RIGHT	R4-H11	2B.33.1	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
THROUGH TRAFFIC KEEP LEFT	R4-H12	2B.33.1	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
DO NOT ENTER	R5-1	2B.34	750 x 750 (30 x 30)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	—	—
WRONG WAY	R5-1a	2B.35	900 x 600 (36 x 24)	900 x 600 (36 x 24)	1050 x 750 (42 x 30)	—	—
No Trucks	R5-2, 2a	2B.36	600 x 600 (24 x 24)	750 x 750 (30 x 30)	900 x 900 (36 x 36)	—	1200 x 1200 (48 x 48)
THROUGH TRUCKS PROHIBITED	R5-H2b	2B.36	600 x 600 (24 x 24)	—	—	—	900 x 900 (36 x 36)
THROUGH TRAFFIC PROHIBITED	R5-H2c	2B.36	600 x 600 (24 x 24)	—	—	—	900 x 900 (36 x 36)
NO MOTOR VEHICLES	R5-3	2B.36	600 x 600 (24 x 24)	—	—	—	—
Commercial Vehicles Excluded	R5-4	2B.36	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—

**Table 2B-1. Regulatory Sign Sizes (Sheet 3 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
VEHICLES WITH LUGS PROHIBITED	R5-5	2B.36	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
No Bicycles	R5-6	2B.36	600 x 600 (24 x 24)	750 x 750 (30 x 30)	900 x 900 (36 x 36)	—	1200 x 1200 (48 x 48)
NON-MOTORIZED TRAFFIC PROHIBITED	R5-7	2B.36	750 x 600 (30 x 24)	1050 x 600 (42 x 24)	1200 x 750 (48 x 30)	—	—
MOTOR-DRIVEN CYCLES PROHIBITED	R5-8	2B.36	750 x 600 (30 x 24)	1050 x 600 (42 x 24)	1200 x 750 (48 x 30)	—	—
PEDESTRIANS, BICYCLES, MOTOR-DRIVEN CYCLES PROHIBITED	R5-10a	2B.36	750 x 900 (30 x 36)	—	—	—	—
PEDESTRIANS AND BICYCLES PROHIBITED	R5-10b	2B.36	750 x 450 (30 x 18)	—	—	—	—
PEDESTRIANS PROHIBITED	R5-10c	2B.36	600 x 300 (24 x 12)	—	—	—	—
PROHIBITED PEDESTRIANS, FARM MACHINERY, ANIMALS...	R5-H10d	2B.36	—	—	900 X 900 (36 X 36)	—	—
PROHIBITED PEDESTRIANS, BICYCLES...	R5-H10e	2B.36	—	—	750 X 750 (30 X 30)	—	—
SNOWMOBILES, ALL PURPOSE VEHICLES...	R5-H10f	2B.36	750 X 600 (30 X 24)	900 X 750 (36 X 30)	900 X 750 (36 X 30)	—	—
ONE WAY	R6-1	2B.37	900 x 300 (36 x 12)	1350 x 450 (54 x 18)	1350 x 450 (54 x 18)	—	—
ONE WAY	R6-2	2B.37	600 x 750 (24 x 30)	900 x 1200 (36 x 30)	900 x 1200 (36 x 30)	450 x 600 (18 x 24)	—
Divided Highway Crossing	R6-3, 3a	2B.38	750 x 600 (30 x 24)	900 x 750 (36 x 30)	—	600 x 450 (24 x 18)	—
No Parking	R7-1, 2, 2a, 3, 4, 5, 6, 7, 8, 107, 108	2B.39	300 x 450 (12 x 18)	—	—	—	—
VAN ACCESSIBLE	R7-8a, 8b	2B.40	450 x 225 (18 x 9)	—	—	300 x 150 (12 x 6)	—
\$250 FINE MINIMUM	R7-H8b	2B.39	300 x 150 (12 x 6)	—	—	—	—
No Parking, Bike Lane	R7-9, 9a	9B.09	300 x 450 (12 x 18)	—	—	—	—
No Parking (with transit logo)	R7-107a	2B.39	300 x 750 (12 x 30)	—	—	—	—
No Parking / Restricted Parking (combined sign)	R7-200	2B.40	600 x 450 (24 x 18) 300 x 750 (12 x 30)	—	—	—	—
TOW-AWAY ZONE	R7-201, 201a	2B.40	300 x 150 (12 x 6)	—	—	—	—
THIS SIDE OF SIGN	R7-202	2B.39	300 x 150 (12 x 6)	—	—	—	—
Emergency Snow Route	R7-203	2B.40	600 x 750 (24 x 30)	—	—	450 x 600 (18 x 24)	—

**Table 2B-1. Regulatory Sign Sizes (Sheet 4 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
NO PARKING ON PAVEMENT	R8-1	2B.39	600 750 (24 X 30)	900 X1200 (36 X 48)	1200 X 1500 (48 X 60)	—	—
NO PARKING EXCEPT ON SHOULDER	R8-2	2B.39	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
NO PARKING	R8-3	2B.39	600 x 750 (24 x 30)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	450 x 600 (18 x 24)	—
No Parking (symbol)	R8-3a	2B.39	600 x 600 (24 x 600)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	300 x 300 (12 x 12)	—
EMERGENCY PARKING ONLY	R8-4	2B.42	750 x 600 (30 x 24)	750 x 600 (30 x 24)	1200 x 900 (48 x 36)	—	—
NO STOPPING ON PAVEMENT	R8-5	2B.39	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
NO STOPPING EXCEPT ON SHOULDER	R8-6	2B.39	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
EMERGENCY STOPPING ONLY	R8-7	2B.42	750 x 600 (30 x 24)	1200 x 900 (48 x 36)	—	—	—
DO NOT STOP ON TRACKS	R8-8	2B.42	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	—	—	—
TRACKS OUT OF SERVICE	R8-9	8B.09	600 x 600 (24 x 24)	900 x 900 (36 x 36)	—	450 x 450 (18 x 18)	—
STOP HERE WHEN FLASHING	R8-10	8B.10	600 x 900 (24 x 36)	—	—	—	—
WALK ON LEFT FACING TRAFFIC	R9-1	2B.43	450 x 600 (18 x 24)	—	—	—	—
CROSS ONLY AT CROSSWALKS	R9-2	2B.44	300 x 450 (12 x 18)	—	—	—	—
NO PEDESTRIAN CROSSING	R9-3	2B.44	300 x 450 (12 x 18)	—	—	—	—
No Pedestrian Crossing (symbol)	R9-3a	2B.44	450 x 450 (18 x 18)	600 x 600 (24 x 24)	750 x 750 (30 x 30)	—	—
USE CROSSWALK	R9-3b	2B.44	450 x 300 (18 x 12)	—	—	—	—
NO HITCH HIKING	R9-4	2B.43	450 x 600 (18 x 24)	—	—	300 x 450 (12 x 18)	—
Hitch Hiking Prohibition (symbol)	R9-4a	2B.43	450 x 450 (18 x 18)	—	—	—	—
Bicyclists (symbol) Use Ped Signal	R9-5	9B.10	300 x 450 (12 x 18)	—	—	—	—
Bicyclists (symbol) Yield to Peds	R9-6	9B.10	300 x 450 (12 x 18)	—	—	—	—
Keep Left/Right to Pedestrians & Bicyclists (symbols) – Travel-path Restriction	R9-7	9B.11	300 x 450 (12 x 18)	—	—	—	—
PEDESTRIAN CROSSWALK	R9-8	6F.12	900 x 450 (36 x 18)	—	—	—	—
SIDEWALK CLOSED	R9-9	6F.13	750 x 450 (30 x 18)	—	—	—	—
SIDEWALK CLOSED, USE OTHER SIDE	R9-10	6F.13	1200 x 600 (48 x 24)	—	—	—	—
SIDEWALK CLOSED AHEAD, CROSS HERE	R9-11	6F.13	1200 x 900 (48 x 36)	—	—	—	—
SIDEWALK CLOSED, CROSS HERE	R9-11a	6F.13	1200 x 600 (48 x 24)	—	—	—	—

**Table 2B-1. Regulatory Sign Sizes (Sheet 5 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
CROSS ON GREEN LIGHT ONLY	R10-1	2B.45	300 x 450 (12 x 18)	—	—	—	—
Pedestrian Traffic Signal Signs	R10-2, 2a, 3, 3a, 3b, 3c, 3d, 4, 4a, 4b	2B.45	225 x 300 (9 x 12)	—	—	—	—
Countdown Pedestrian Sign	R10-3e	2B.45	225 x 375 (9 x 15)	—	—	—	—
LEFT ON GREEN ARROW ONLY	R10-5	2B.45	600 x 750 (24 x 30)	—	—	—	1200 x 1500 (48 x 60)
STOP HERE ON RED	R10-6	2B.45	600 x 900 (24 x 36)	—	—	—	—
STOP HERE ON RED	R10-6a	2B.45	600 x 750 (24 x 30)	—	—	—	—
DO NOT BLOCK INTERSECTION	R10-7	2B.45	600 x 750 (24 x 30)	—	—	—	—
USE LANE WITH GREEN ARROW	R10-8	2B.45	600 x 750 (24 x 30)	900 x 1050 (36 x 42)	—	—	1500 x 1800 (60 x 72)
LEFT (RIGHT) TURN SIGNAL	R10-10	2B.45	600 x 750 (24 x 30)	—	—	—	—
NO TURN ON RED	R10-11, 11a	2B.45	600 x 750 (24 x 30)	—	—	—	900 x 1200 (36 x 48)
NO TURN ON RED	R10-11b	2B.45	600 x 600 (24 x 24)	—	—	—	750 x 750 (30 x 30)
Left Turn Yield on Green	R10-12	2B.45	600 x 750 (24 x 30)	—	—	—	—
EMERGENCY SIGNAL	R10-13	2B.45	900 x 600 (36 x 24)	—	—	—	—
TURNING TRAFFIC MUST YIELD TO PEDESTRIANS	R10-15	2B.45	750 X 900 (30 X 36)	—	—	—	—
U-TURN YIELD TO RIGHT TURNS	R10-16	2B.45	750 X 900 (30 X 36)	—	—	—	—
RIGHT ON RED ARROW AFTER STOP	R10-17a	2B.45	750 X 900 (30 X 36)	—	—	—	—
TRAFFIC LAWS PHOTO ENFORCED	R10-18	2B.46	900 X 450 (36 X 18)	1200 X 750 (48 X 30)	1800 X 900 (72 X 36)	—	—
PHOTO ENFORCED	R10-19	2B.46	600 X 450 (24 X 18)	900 X 750 (36 X 30)	1200 X 900 (48 X 36)	—	—
MON-FRI (and times) (3 lines)	R10-20a	2B.45	600 X 600 (24 X 24)	—	—	—	—
SUNDAY (and times) (2 lines)	R10-20a	2B.45	600 X 450 (24 X 18)	—	—	—	—
LEFT TURN SIGNAL – YIELD ON GREEN	R10-21	2B.45	750 X 900 (30 X 36)	—	—	—	—
Bike Actuation	R10-22	9B.12	300 X 450 (12 X 18)	—	—	—	—
KEEP OFF MEDIAN	R11-1	2B.47	600 x 750 (24 x 30)	—	—	—	—
ROAD CLOSED	R11-2	2B.48	1200 x 750 (48 x 30)	—	—	—	—
Road Closed – Local Traffic Only	R11-3, 3a, 3b, 4	2B.48	1500 x 750 (60 x 30)	—	—	—	—
Weight Limit	R12-1, 2	2B.49	600 x 750 (24 x 30)	900 X 1200 (36 X 48)	—	—	900 x 1200 (36 x 48)

**Table 2B-1. Regulatory Sign Sizes (Sheet 6 of 6)**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
Weight Limit	R12-3	2B.49	600 x 900 (24 x 36)	—	—	—	—
Weight Limit	R12-4	2B.49	900 x 600 (36 x 24)	—	—	—	—
Weight Limit	R12-5	2B.49	600 x 900 (24 x 36)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
Weight Limit	R12-H5	2B.49	750 x 1050 (30 x 42)	900 x 1350 (36 x 54)	1200 x 1800 (48 x 72)	—	—
Weigh Station	R13-H1	2B.50	1800 x 1500 (72 x 60)	3000 x 2400 (120 x 96)	3000 x 2400 (120 x 96)	—	—
Weigh Station	R13-H2	2B.50	1800 x 1200 (72 x 48)	3000 x 1800 (120 x 72)	3000 x 1800 (120 x 72)	—	—
Truck Route	R14-1	2B.51	600 x 450 (24 x 18)	—	—	—	—
Hazardous Material	R14-2, 3	2B.52	600 x 600 (24 x 24)	750 x 750 (30 x 30)	900 x 900 (36 x 36)	—	1050 x 1050 (42 x 42)
Railroad Crossbuck	R15-1	8B.03	1200 x 225 (48 x 9)	—	—	—	—
LOOK	R15-8	8B.16	900 x 450 (36 x 18)	—	—	—	—
Seat Belt Symbol	R16-1	2B.54	375 x 500 (15 x 20)	—	—	—	—
STOP FOR SCHOOL BUS LOADING OR UNLOADING	R16-H2	7B.15	750 x 750 (30 x 30)	—	—	—	1050 x 1050 (42 x 42)

## Notes:

1. Larger signs may be used when appropriate.
2. Dimensions are shown in millimeters followed by inches in parenthesis and are shown as width x height.

**Section 2B.04 STOP Sign (R1-1)****Standard:**

When a sign is used to indicate that traffic is always required to stop, a STOP (R1-1) sign (see Figure 2B-1) shall be used.

The STOP sign shall be an octagon with a white legend and border on a red background. Secondary legends shall not be used on STOP sign faces. If appropriate, a supplemental plaque (R1-3 or R1-4) shall be used to display a secondary legend. Such plaques (see Figure 2B-1) shall have a white legend and border on a red background. If the number of approach legs controlled by STOP signs at an intersection is three or more, the numeral on the supplemental plaque, if used, shall correspond to the actual number of legs controlled by STOP signs.

At intersections where all approaches are controlled by STOP signs (see Section 2B.07), a supplemental plaque (R1-3 or R1-4) shall be mounted below each STOP sign.

**Option:**

The ALL WAY (R1-4) supplemental plaque may be used instead of the 4-WAY (R1-3) supplemental plaque.

**Support:**

The design and application of Stop Beacons are described in Section 4K.05.

Option:

At an intersection, the higher classification street or highway may be used to determine the size of the STOP sign to be erected at that intersection. STOP signs on freeway and expressway ramps may be the 1200 mm (48 in) size.

### **Section 2B.05 STOP Sign Applications**

Guidance:

STOP signs should be used if engineering judgment indicates that one or more of the following conditions exist:

- A. Intersection of a less important road with a main road where application of the normal right-of-way rule would not be expected to provide reasonable compliance with the law;
- B. Street entering a through highway or street (O.R.C. Section 4511.65 provides information on through highways (see Appendix B2));
- C. Unsignalized intersection in a signalized area; and/or
- D. High speeds, restricted view, or crash records indicate a need for control by the STOP sign.

**Standard:**

**Because the potential for conflicting commands could create driver confusion, STOP signs shall not be installed at intersections where traffic control signals are installed and operating except as noted in Section 4D.01.**

**Portable or part-time STOP signs shall not be used except for emergency and temporary traffic control zone purposes.**

Guidance:

STOP signs should not be used for speed control.

STOP signs should be installed in a manner that minimizes the numbers of vehicles having to stop. At intersections where a full stop is not necessary at all times, consideration should be given to using less restrictive measures such as YIELD signs (see Section 2B.08).

Once the decision has been made to install two-way stop control, the decision regarding the appropriate street to stop should be based on engineering judgment. In most cases, the street carrying the lowest volume of traffic should be stopped.

A STOP sign should not be installed on the major street unless justified by a traffic engineering study.


Support:

The following are considerations that might influence the decision regarding the appropriate street upon which to install a STOP sign where two streets with relatively equal volumes and/or characteristics intersect:

- A. Stopping the direction that conflicts the most with established pedestrian crossing activity or school walking routes;
- B. Stopping the direction that has obscured vision, dips, or bumps that already require drivers to use lower operating speeds;
- C. Stopping the direction that has the longest distance of uninterrupted flow approaching the intersection; and
- D. Stopping the direction that has the best sight distance to conflicting traffic.

The use of the STOP sign at highway-railroad grade crossings is described in Section 8B.08. The use of the STOP sign at highway-light rail transit grade crossings is described in Section 10C.04.

**Figure 2B-1. STOP, YIELD, Speed Limit, FINES HIGHER, and Photo Enforcement Signs**



### Section 2B.06 STOP Sign Placement

#### Standard:

The STOP sign shall be installed on the right side of the approach to which it applies. When the STOP sign is installed at this required location and the sign visibility is restricted, a Stop Ahead sign (see Section 2C.29) shall be installed in advance of the STOP sign.

The STOP sign shall be located as close as practical to the intersection it regulates, while optimizing its visibility to the road user it is intended to regulate.

STOP signs and YIELD signs shall not be mounted on the same post.

#### Guidance:

Other than a DO NOT ENTER sign, no sign should be mounted back-to-back with a STOP sign in a manner that obscures the shape of the STOP sign.

#### Support:

Section 2A.16 contains additional information about separate and combined mounting of other signs with STOP signs.

#### Guidance:

Stop lines, when used to supplement a STOP sign, should be located at the point where the road user should stop (see Section 3B.16).

If only one STOP sign is installed on an approach, the STOP sign should not be placed on the far side of the intersection.

Where two roads intersect at an acute angle, the STOP sign should be positioned at an angle, or shielded, so that the legend is out of view of traffic to which it does not apply.

Where there is a marked crosswalk at the intersection, the STOP sign should be installed in advance of the crosswalk line nearest to the approaching traffic.

Option:

At wide-throat intersections or where two or more approach lanes of traffic exist on the signed approach, observance of the stop control may be improved by the installation of an additional STOP sign on the left side of the road and/or the use of a stop line. At channelized intersections, the additional STOP sign may be effectively placed on a channelizing island.

Support:

Figure 2A-2 shows examples of some typical placements of STOP signs.

### **Section 2B.07 Multiway Stop Applications**

Support:

Multiway stop control can be useful as a safety measure at intersections if certain traffic conditions exist. Safety concerns associated with multiway stops include pedestrians, bicyclists, and all road users expecting other road users to stop. Multiway stop control is used where the volume of traffic on the intersecting roads is approximately equal.

The restrictions on the use of STOP signs described in Section 2B.05 also apply to multiway stop applications.

Guidance:

The decision to install multiway stop control should be based on an engineering study.

The following criteria should be considered in the engineering study for a multiway STOP sign installation:

- A. Where traffic control signals are justified, the multiway stop is an interim measure that can be installed quickly to control traffic while arrangements are being made for the installation of the traffic control signal.
- B. A crash problem, as indicated by 5 or more reported crashes in a 12-month period that are susceptible to correction by a multiway stop installation. Such crashes include right- and left-turn collisions as well as right-angle collisions.
- C. Minimum volumes:
  1. The vehicular volume entering the intersection from the major street approaches (total of both approaches) averages at least 300 vehicles per hour for any 8 hours of an average day, and
  2. The combined vehicular, pedestrian, and bicycle volume entering the intersection from the minor street approaches (total of both approaches) averages at least 200 units per hour for the same 8 hours, with an average delay to minor-street vehicular traffic of at least 30 seconds per vehicle during the highest hour, but
  3. If the 85th-percentile approach speed of the major-street traffic exceeds 65 km/h or exceeds 40 mph, the minimum vehicular volume warrants are 70 percent of the above values.
- D. Where no single criterion is satisfied, but where Criteria B, C.1, and C.2 are all satisfied to 80 percent of the minimum values. Criterion C.3 is excluded from this condition.

Option:

Other criteria that may be considered in an engineering study include:

- A. The need to control left-turn conflicts;

- B. The need to control vehicle/pedestrian conflicts near locations that generate high pedestrian volumes;
- C. Locations where a road user, after stopping, cannot see conflicting traffic and is not able to reasonably safely negotiate the intersection unless conflicting cross traffic is also required to stop; and
- D. An intersection of two residential neighborhood collector (through) streets of similar design and operating characteristics where multiway stop control would improve traffic operational characteristics of the intersection.

### **Section 2B.08 YIELD Sign (R1-2)**

#### **Standard:**

**The YIELD (R1-2) sign (see Figure 2B-1) shall be a downward-pointing equilateral triangle with a wide red border and the legend YIELD in red on a white background.**

#### **Support:**

The YIELD sign assigns right-of-way to traffic on certain approaches to an intersection. Vehicles controlled by a YIELD sign need to slow down or stop when necessary to avoid interfering with conflicting traffic.

Figure 6H-11 illustrates the use of the YIELD sign with the TO ONCOMING TRAFFIC (R1-2a) supplemental sign (see Figure 2B-1) in a lane closure application on a two-lane road with low traffic volumes.

### **Section 2B.09 YIELD Sign Applications**

#### **Option:**

YIELD signs may be used instead of STOP signs if engineering judgment indicates that one or more of the following conditions exist:

- A. When the ability to see all potentially conflicting traffic is sufficient to allow a road user traveling at the posted speed, the 85th-percentile speed, or the statutory speed to pass through the intersection or to stop in a reasonably safe manner.
- B. If controlling a merge-type movement on the entering roadway where acceleration geometry and/or sight distance is not adequate for merging traffic operation.
- C. The second crossroad of a divided highway, where the median width at the intersection is 9 m (30 ft) or greater. In this case, a STOP sign may be installed at the entrance to the first roadway of a divided highway, and a YIELD sign may be installed at the entrance to the second roadway.
- D. An intersection where a special problem exists and where engineering judgment indicates the problem to be susceptible to correction by the use of the YIELD sign.

#### **Standard:**

**A YIELD (R1-2) sign shall be used to assign right-of-way at the entrance to a roundabout intersection.**

### **Section 2B.10 YIELD Sign Placement**

#### **Standard:**

**The YIELD sign shall be installed on the right side of the approach to which it applies. YIELD signs shall be placed on both the left and right sides of approaches to roundabout intersections with more than one lane on the signed approach where raised splitter islands are available on the left side of the approach. When the YIELD sign is installed at this required location and the sign visibility is restricted, a Yield Ahead sign (see Section 2C.29) shall be installed in advance of the YIELD sign.**

**The YIELD sign shall be located as close as practical to the intersection it regulates, while optimizing its visibility to the road user it is intended to regulate.**

**YIELD signs and STOP signs shall not be mounted on the same post.**

**Guidance:**

Other than a DO NOT ENTER sign, no sign should be mounted back-to-back with a YIELD sign in a manner that obscures the shape of the YIELD sign.

**Support:**

Section 2A.16 contains additional information about separate and combined mounting of other signs with YIELD signs.

**Guidance:**

Yield lines, when used to supplement a YIELD sign, should be located at a point where the road user should yield (see Section 3B.16).

Where two roads intersect at an acute angle, the YIELD sign should be positioned at an angle, or shielded, so that the legend is out of view of traffic to which it does not apply.

Except at roundabout intersections, where there is a marked crosswalk at the intersection, the YIELD sign should be installed in advance of the crosswalk line nearest to the approaching traffic.

At a roundabout intersection, to prevent circulating vehicles from yielding unnecessarily, the face of the YIELD sign should not be visible from the circulatory roadway.

**Option:**

At wide-throat intersections or where two or more approach lanes of traffic exist on the signed approach, observance of the yield control may be improved by the installation of an additional YIELD sign on the left side of the road and/or the use of a yield line. At channelized intersections, the additional YIELD sign may be effectively placed on a channelizing island.

**Section 2B.11 Yield Here To Pedestrians Signs (R1-5, R1-5a)****Standard:**

**If yield lines are used in advance of an unsignalized marked midblock crosswalk, Yield Here To Pedestrians (R1-5 or R1-5a) signs (see Figure 2B-2) shall be placed 6.1 to 15 m (20 to 50 ft) in advance of the nearest crosswalk line (see Section 3B.16 and Figure 3B-15).**

**Section 2B.12 In-Street Pedestrian Crossing Sign (R1-6)****Option:**

The In-Street Pedestrian Crossing (R1-6) sign (see Figure 2B-2) may be used to remind road users of laws regarding right-of-way at an unsignalized pedestrian crossing. The legend STATE LAW may be shown at the top of the sign. The legend YIELD TO may be used in conjunction with the appropriate symbol.

**Guidance:**

If an island (see Chapter 3G) is available, the In-Street Pedestrian Crossing sign, if used, should be placed on the island.

**Standard:**

**The In-Street Pedestrian Crossing sign shall not be used at signalized locations.**

**If used, the In-Street Pedestrian Crossing sign shall have a black legend (except for the red YIELD sign symbol) and border on either a white and/or fluorescent yellow-green background.**

**If the In-Street Pedestrian Crossing sign is placed in the roadway, the sign support shall comply with the breakaway requirements of the latest edition of AASHTO's "Specification for Structural Supports for Highway Signs, Luminaires, and Traffic Signals" (see the Preface of this Manual).**

## Figure 2B-2. Unsignalized Pedestrian Crosswalk Signs



### Support:

The Provisions of Section 2A.18 concerning mounting height are not applicable for the In-Street Pedestrian Crossing sign.

### Option:

The In-Street Pedestrian Crossing sign may be used seasonably to prevent damage in winter because of plowing operations, and may be removed at night if the pedestrian activity at night is minimal.

### Section 2B.13 Speed Limit Signs (R2-1, R2-H2b, R2-H2c)

#### Support:

Section 4511.21 of the Ohio Revised Code (O.R.C.) establishes statutory speed limits, and prescribes how those speed limits may be altered when an engineering study determines that they do not fit the road and traffic conditions. The process by which an altered speed limit is established is typically referred to as speed zoning.

#### Standard:

**Speed Limits shall be established by or in accordance with O.R.C. Section 4511.21 (see Appendix B2).**

**The Speed Limit (R2-1) sign (see Figure 2B-1) shall display the limit established by law, ordinance, regulation, or as adopted by the authorized agency. The speed limits shown shall be in multiples of 5 mph.**

#### Guidance:

At least once every 5 years, highway agencies should reevaluate non-statutory speed limits on segments of their roadways that have undergone a significant change in roadway characteristics or surrounding land use since the last review.

No more than three speed limits should be displayed on any one Speed Limit sign or assembly.

When a speed limit is to be posted, it should be within 5 mph of the 85th-percentile speed of free-flowing traffic.

The procedures and forms described in Part 12 of the ODOT "Traffic Engineering Manual" (TEM) (see Section 1A.11) should be used to submit speed zoning requests that require the Director of Transportation's approval.

Option:

Factors that may be considered when establishing speed limits include:

- A. Road characteristics, shoulder condition, grade, alignment, and sight distance;
- B. The pace speed;
- C. Roadside development and environment;
- D. Parking practices and pedestrian activity; and
- E. Reported crash experience for at least a 12-month period.

Two types of Speed Limit signs may be used: one to designate passenger car speeds, including any nighttime information or minimum speed limit that might apply; and the other to show any special speed limits for trucks and other vehicles.

A combination 65/55 Speed Limit sign (R2-H2b or R2-H2c) may be used in lieu of a side-by-side installation of the R2-1 with the R2-H2a (see Appendix C).

A changeable message sign that displays to approaching drivers the speed at which they are traveling may be installed in conjunction with a Speed Limit sign.

Guidance:

If a changeable message sign displaying approach speeds is installed, the legend YOUR SPEED XX MPH or such similar legend should be shown. The color of the changeable message legend should be a yellow legend on a black background or the reverse of these colors.

Support:

Information about the speed zoning process and copies of the related forms are also available by contacting the ODOT District Office.

Advisory Speed signs are discussed in Sections 2C.36 and 2C.46 and Temporary Traffic Control Zone Speed signs are discussed in Part 6.

### **Section 2B.14 Truck Speed Limit Signs (R2-2, R2-H2a)**

**Standard:**

**Where a special speed limit applies to trucks or other vehicles, the legend TRUCKS XX or such similar legend shall be shown on the same panel as the Speed Limit sign or on a separate R2-2 sign (see Figure 2B-1) below the standard legend.**

**When used, the VEHICLES OVER 4 TONS EMPTY NON COM BUSES 55 MPH (R2-H2a) sign (see Appendix C) shall be erected adjacent to the Speed Limit sign.**

Option:

As noted in Section 2B.13, a combination 65/55 Speed Limit (R2-H2b or R2-H2c) sign may be used (see Appendix C) instead of a side-by-side installation of the R2-1 with the R2-H2a.


### **Section 2B.15 Night Speed Limit Sign (R2-3)**

**Standard:**

**Where different speed limits are prescribed for day and night, both limits shall be posted.**

Guidance:

A Night Speed Limit (R2-3) sign (see Figure 2B-1) should be reversed using a white retroreflectorized legend and border on a black background.

**Figure 2B-3. Speed Limit and Turn Prohibition Signs**

Option:

A Night Speed Limit sign may be combined with or installed below the standard Speed Limit (R2-1) sign.

### **Section 2B.16 Minimum Speed Limit Sign (R2-4)**

**Standard:**

A Minimum Speed Limit (R2-4) sign (see Figure 2B-3) shall be displayed only in combination with a Speed Limit sign.

Minimum speed limits shall be established in accordance with O.R.C. Section 4511.22 (see Appendix B2).

Option:

Where engineering judgment determines that slow speeds on a highway might impede the normal and reasonable movement of traffic, the Minimum Speed Limit sign may be installed below a Speed Limit (R2-1) sign to indicate the minimum legal speed. If desired, these two signs may be combined on the R2-4a sign (see Figure 2B-3).

### **Section 2B.17 FINES HIGHER Plaque (R2-6)**

Option:

Except as noted in the Standard, the FINES HIGHER (R2-6) plaque (see Figure 2B-1) may be used to advise road users when increased fines are imposed for traffic violations within designated roadway segments.

The FINES HIGHER plaque may be mounted below an applicable regulatory or warning sign in a school zone or other applicable designated zones.

The following may be mounted below the FINES HIGHER plaque:

- A. A supplemental plaque specifying the times that the higher fines are in effect (similar to the S4-1 plaque shown in Figure 7B-1); or
- B. A supplemental plaque WHEN CHILDREN ARE PRESENT; or
- C. A supplemental plaque WHEN FLASHING (similar to the S4-4 plaque shown in Figure 7B-1) if used in conjunction with a yellow flashing beacon.

The legend FINES HIGHER may be replaced by multiple values such as FINES DOUBLE or FINES TRIPLE, or by a specific value such as \$150 FINE.

**Standard:**

**The FINES HIGHER plaque shall be a rectangle with a black legend and border on a white background.**

**All supplemental plaques mounted below the FINES HIGHER plaque shall be rectangles with black legends and borders on white backgrounds.**

**The FINES HIGHER plaque shall include a SCHOOL or other applicable designated zone plaque mounted above the applicable regulatory or warning sign. The SCHOOL supplemental plaque shall be rectangular in shape with a black legend and border on a yellow or fluorescent yellow-green background (same as the S4-3 plaque).**

**Use of this type of signing in work zones shall be as described in Section 6F.14.1.**

**Guidance:**

If used, the FINES HIGHER plaque should be located at the beginning of the school zone or other applicable designated zone and just beyond any interchanges, major intersections, or other major traffic generators.

Agencies should limit the use of the FINES HIGHER plaque to locations where the roadway, shoulder, or other conditions, including the presence of a school, require a speed reduction or extra caution on the part of the road user.

**Section 2B.18 Location of Speed Limit Signs**

**Standard:**

**Speed Limit (R2-1) signs, indicating speed limits for which posting is required by law, shall be located at the points of change from one speed limit to another.**

**At the end of the section to which a speed limit applies, a Speed Limit sign showing the next speed limit shall be installed. Additional Speed Limit signs shall be installed beyond major intersections and at other locations where it is necessary to remind road users of the speed limit that is applicable.**

**Speed Limit signs indicating the statutory speed limits shall be installed at entrances to the State and at jurisdictional boundaries of metropolitan areas.**

**Section 2B.19 Turn Prohibition Signs (R3-1 through R3-4, and R3-18)**

**Standard:**

**Except as noted in the Option, where turns are prohibited, Turn Prohibition signs shall be installed.**

**Guidance:**

Turn Prohibition signs should be placed where they will be most easily seen by road users who might be intending to turn.

If No Right Turn (R3-1) signs (see Figure 2B-3) are used, at least one should be placed either over the roadway or at a right corner of the intersection.

If No Left Turn (R3-2) signs (see Figure 2B-3) are used, at least one should be placed either over the roadway, at the far left corner of the intersection, on a median, or in conjunction with the STOP sign or YIELD sign located on the near right corner.

Except as noted in the Option, if NO TURNS (R3-3) signs (see Figure 2B-3) are used, two signs should be used, one at a location specified for a No Right Turn sign and one at a location specified for a No Left Turn sign.

If No U-Turn (R3-4) signs (see Figure 2B-3) are used, at least one should be used at a location specified for No Left Turn signs.

If combination No U-Turn/No Left Turn (R3-18) signs (see Figure 2B-3) are used, at least one should be used at a location specified for No Left Turn signs.

Option:

If signals are present:

- A. The No Right Turn sign may be installed adjacent to a signal face viewed by road users in the right lane.
- B. The No Left Turn (or No U-Turn or combination No U-Turn/No Left Turn) sign may be installed adjacent to a signal face viewed by road users in the left lane.
- C. A NO TURNS sign may be placed adjacent to a signal face viewed by all road users on that approach, or two signs may be used.

If signals are present, an additional Turn Prohibition sign may be ground mounted to supplement the sign mounted overhead.

Where ONE WAY signs are used (see Section 2B.37), Turn Prohibition signs may be omitted.

When the movement restriction applies during certain time periods only, the following Turn Prohibition signing alternatives may be used and are listed in order of preference:

- A. Changeable message signs, especially at signalized intersections.
- B. Permanently mounted signs incorporating a supplementary legend showing the hours and days during which the prohibition is applicable.
- C. Portable signs, installed by proper authority, located off the roadway at each corner of the intersection. The portable signs are only to be used during the time that the turn prohibition is applicable.

Turn Prohibition signs may be omitted at a ramp entrance to an expressway or a channelized intersection where the design is such as to indicate clearly the one-way traffic movement on the ramp or turning lane.

If both left turns and U-turns are prohibited, the R3-18 sign may be used instead of separate R3-2 and R3-4 signs.

## **Section 2B.20 Intersection Lane Control Signs (R3-5 through R3-8)**

**Standard:**

**Intersection Lane Control signs, if used, shall require road users in certain lanes to turn, shall permit turns from a lane where such turns would otherwise not be permitted, shall require a road user to stay in the same lane and proceed straight through an intersection, or shall indicate permitted movements from a lane.**

**Intersection Lane Control signs (see Figure 2B-4) shall have three applications:**

- A. Mandatory Movement Lane Control (R3-5, R3-5a, and R3-7) signs;**
- B. Optional Movement Lane Control (R3-6) sign; and**
- C. Advance Intersection Lane Control (R3-8 series) signs.**

**Support:**

O.R.C. Section 4511.36 (see Appendix B2) addresses turns at intersections.

**Guidance:**

When Intersection Lane Control signs are mounted overhead, each sign should be placed over the lane or a projection of the lane to which it applies.

**Standard:**

**Use of an overhead sign for one approach lane shall not require installation of overhead signs for the other lanes of that approach.**

**Option:**

Where the number of through lanes on an approach is two or less, the Intersection Lane Control signs (R3-5, R3-6, or R3-8) may be overhead or ground mounted.

Intersection Lane Control signs may be omitted where:

- A. Turning bays have been provided by physical construction or pavement markings, and
- B. Only the road users using such turning bays are permitted to make a similar turn.

**Section 2B.21 Mandatory Movement Lane Control Signs (R3-5, R3-5a, R3-7)****Standard:**

**If used, Mandatory Movement Lane Control (R3-5, R3-5a, and R3-7) signs (see Figure 2B-4) shall indicate only those vehicle movements that are required from each lane and shall be located where the regulation applies. When the mandatory movement applies to lanes exclusively designated for HOV traffic, the R3-5c supplemental plaque shall be used. When the mandatory movement applies to lanes that are not HOV facilities, but are lanes exclusively designated for buses and/or taxis, the word message R3-5d and/or R3-5g supplemental plaques shall be used. The R3-7 word message sign shall be for ground mounting only.**

**If the R3-5 sign is ground mounted on a multi-lane approach, a supplemental plaque (see Figure 2B-4), such as LEFT LANE (R3-5b), HOV 2+ (R3-5c), TAXI LANE (R3-5d), CENTER LANE (R3-5e), RIGHT LANE (R3-5f), BUS LANE (R3-5g), or LEFT 2 LANES, indicating the lane with the appropriate movement shall be added below.**

**The Mandatory Movement Lane Control (R3-7) sign shall include the legend RIGHT (LEFT) LANE MUST TURN RIGHT (LEFT). The Mandatory Movement Lane Control symbol signs (R3-5 and R3-5a) shall include the legend ONLY.**

**Guidance:**

Mandatory Movement Lane Control signs should be accompanied by lane use arrow markings, especially where traffic volumes are high, where there is a high percentage of commercial vehicles, or where other distractions exist.

**Option:**


The Straight Through Only (R3-5a) sign may be used to require a road user in a particular lane to proceed straight through an intersection.

When the Mandatory Movement Lane Control sign for a left-turn lane is installed back-to-back with a Keep Right (R4-7) sign, the dimensions of the Mandatory Movement Lane Control (R3-5) sign may be the same as the Keep Right sign.

Except for the R3-7 sign, Mandatory Movement Lane Control signs may be overhead or ground mounted.

The diamond symbol may be used instead of the word message HOV on the R3-5c supplemental plaque.

**Figure 2B-4. Intersection Lane Control Signs**



\* The diamond symbol may be used instead of the word message "HOV." The minimum vehicle occupancy level may vary, such as 2+, 3+, 4+. The words "LANE" or "ONLY" may be used with this sign when appropriate.

**Section 2B.22 Optional Movement Lane Control Sign (R3-6)**



**Standard:**

If used, the **Optional Movement Lane Control (R3-6)** sign (see Figure 2B-4) shall be used for two or more movements from a specific lane or to emphasize permitted movements. If used, the **Optional Movement Lane Control** sign shall be located at the intersection.

If used, the **Optional Movement Lane Control** sign shall indicate all permissible movements from specific lanes.

**Optional Movement Lane Control** signs shall be used for two or more movements from a specific lane where a movement, not normally allowed, is permitted.

The **Optional Movement Lane Control** sign shall not be used alone to effect a turn prohibition.

**Figure 2B-5. Center and Reversible Lane Control Signs****Section 2B.23 Advance Intersection Lane Control Signs (R3-8 Series)**

Option:

Advance Intersection Lane Control (R3-8, R3-8a, and R3-8b) signs (see Figure 2B-4) may be used to indicate the configuration of all lanes ahead.

The word messages ONLY, THRU, ALL, or HOV 2+ may be used within the border in combination with the arrow symbols of the R3-8 sign series. The HOV 2+ (R3-5c) supplemental plaque may be installed at the top outside border of the R3-8 sign over the applicable lane. The diamond symbol may be used instead of the word message HOV. The minimum allowable vehicle occupancy requirement may vary based on the level established for a particular facility.

Guidance:

If used, an Advance Intersection Lane Control sign should be placed at an adequate distance in advance of the intersection so that road users can select the appropriate lane. If used, the Advance Intersection Lane Control sign should be installed either in advance of the tapers or at the beginning of the turn lane.

**Section 2B.24 Two-Way Left Turn Only Signs (R3-9a, R3-9b)**

Guidance:

Two-Way Left Turn Only (R3-9a or R3-9b) signs (see Figure 2B-5) should be used in conjunction with the required pavement markings where a nonreversible lane is reserved for the exclusive use of left-turning vehicles in either direction and is not used for passing, overtaking, or through travel.

Option:

The ground-mounted R3-9b sign may be used as an alternate to or a supplement to the overhead-mounted R3-9a sign. The legend BEGIN or END may be used within the border of the main sign itself, or on a plaque mounted immediately above it.

## Support:

Signing is especially helpful to drivers in areas where the two-way left turn only maneuver is new, in areas subject to environmental conditions that frequently obscure the pavement markings, and on peripheral streets with two-way left turn only lanes leading to an extensive system of routes with two-way left turn only lanes.

**Section 2B.25 Reversible Lane Control Signs (R3-9d, R3-9f through R3-9i)**

## Option:

A reversible lane may be used for through traffic (with left turns either permitted or prohibited) in alternating directions during different periods of the day, and the lane may be used for exclusive left turns in one or both directions during other periods of the day as well. Reversible Lane Control (R3-9d, R3-9f through R3-9i) signs (see Figure 2B-5) may either be static type or changeable message type. These signs may be either ground or overhead mounted.

**Standard:**

**Ground-mounted Reversible Lane Control signs shall be used only as a supplement to overhead signs or signals. Ground-mounted signs shall be identical in design to the overhead signs and an additional legend such as CENTER LANE shall be added to the sign (R3-9f) to indicate which lane is controlled. For both word messages and symbols, this legend shall be at the top of the sign.**

**Where it is determined by an engineering study that lane-use control signals or physical barriers are not necessary, the lane shall be controlled by overhead Reversible Lane Control signs (see Figure 2B-6).**

## Option:

Reversing traffic flow may be controlled with pavement markings and Reversible Lane Control signs (without the use of lane control signals), when all of the following conditions are met:

- A. Only one lane is being reversed.
- B. An engineering study indicates that the use of Reversible Lane Control signs alone would result in an acceptable level of safety and efficiency.
- C. There are no unusual or complex operations in the reversible lane pattern.

**Standard:**

**Reversible Lane Control signs shall contain the legend or symbols designating the allowable uses of the lane and the time periods such uses are allowed. Where symbols and legend are used, their meanings shall be as shown in Table 2B-2.**

**Reversible Lane Control signs shall consist of a white background with a black legend and border, except for the R3-9d sign, where the color red is used.**

**Symbol signs, such as the R3-9d sign, shall consist of the appropriate symbol in the upper portion of the sign with the appropriate times of the day and days of the week below it. All times of the day and days of the week shall be accounted for on the sign to eliminate confusion to the road user.**


**In situations where more than one message is conveyed to the road user, such as on the R3-9d sign, the sign legend shall be arranged as follows:**

- A. **The prohibition or restriction message is the primary legend and shall be on the top for word message signs and to the far left for symbol signs;**
- B. **The permissive use message shall be shown as the second legend; and**
- C. **The OTHER TIMES message shall be shown at the bottom for word message signs and to the far right for symbol signs.**

## Option:

The symbol signs may also include a downward pointing arrow with the legend THIS LANE. The term OTHER TIMES may be used for either the symbol or word message sign.

**Figure 2B-6. Location of Reversible Two-Way Left-Turn Signs**



**Table 2B-2. Meanings of Symbols and Legends on Reversible Lane Control Signs**

Symbol / Word Message	Meaning
Red X on white background.	Lane Closed
Upward pointing black arrow on white background. If left turns are permitted, the arrow shall be modified to show left / through arrow.	Lane open for through travel and any turns not otherwise prohibited.
Black two-way left turn arrows on white background and legend ONLY.	Lane may be used only for left turns in either direction (i.e., as a two-way left turn lane).
Black single left turn arrow on white background and legend ONLY.	Lane may be used only for left turns in one direction (without opposing left turns in the same lane).

**Standard:**

A Reversible Lane Control sign shall be mounted over the center of the lane that is being reversed and shall be perpendicular to the roadway alignment.

If the vertical or horizontal alignment is curved to the degree that a driver would be unable to see at least one sign, and preferably two signs, then additional overhead signs shall be installed. The placement of the signs shall be such that the driver will have a definite indication of the lanes specifically reserved for use at any given time. Special consideration shall be given to major generators introducing traffic between the normal sign placement.

Transitions at the entry to and exit from a section of roadway with reversible lanes shall be carefully reviewed, and advance signs shall be installed to notify or warn drivers of the boundaries of the reversible lane controls. The R3-9g or R3-9h signs shall be used for this purpose.

Option:

More than one sign may be used at the termination of the reversible lane to emphasize the importance of the message (R3-9i).

**Standard:**

Flashing beacons, if used to accentuate the overhead Reversible Lane Control signs, shall comply with the applicable requirements for flashing beacons in Chapter 4K.

When used in conjunction with Reversible Lane Control signs, the Turn Prohibition signs (R3-1 to R3-4, R3-18) shall be mounted overhead and separate from the Reversible Lane Control signs. The Turn Prohibition signs shall be designed and installed in accordance with Section 2B.19.

Guidance:

For additional emphasis, a supplemental plaque stating the distance of the prohibition, such as NEXT 1 MILE, should be added to the Turn Prohibition signs that are used in conjunction with Reversible Lane Control signs.

If used, overhead signs should be located at intervals not greater than 400 m (0.25 mi). The bottom of the overhead Reversible Lane Control signs should not be more than 5.8 m (19 ft) above the pavement grade.

Where more than one sign is used at the termination of a reversible lane, they should be at least 75 m (250 ft) apart. Longer distances between signs are appropriate for streets with speeds over 60 km/h (35 mph), but the separation should not exceed 300 m (1,000 ft).

Left-turning vehicles have a significant impact on the safety and efficiency of a reversible lane operation. If an exclusive left-turn lane or two-way left-turn lane cannot be incorporated into the lane-use pattern for a particular peak or off-peak period, consideration should be given to prohibiting left turns and U-turns during that time period.

### **Section 2B.26 Preferential Only Lane Signs (R3-10 through R3-15)**

Support:

Preferential only lanes are lanes designated for special traffic uses such as high-occupancy vehicles (HOVs), light rail, buses, taxis, or bicycles. Preferential only lane treatments might be as simple as restricting a turning lane to a certain class of vehicles during peak periods, or as sophisticated as providing a separate roadway system within a highway corridor for certain vehicles.

Information regarding Preferential Only Lane signs for bicycle lanes is contained in Section 9B.04.

Option:

Preferential only lane assignments may be made on a full-time or part-time basis.

Guidance:

Preferential Only Lane sign spacing should be determined by engineering judgment based on prevailing speed, block length, distances from adjacent intersections, and other considerations.

Support:

The symbol and word message that appears on a particular Preferential Only Lane sign will vary based on the specific type of allowed traffic and on other related operational constraints that have been established for a particular lane, such as an HOV lane, a bus lane, or a taxi lane. Section 2B.27 contains information regarding the restriction of the use of the diamond symbol to HOV lanes only. The requirements for guide and regulatory signs in advance of all preferential only lanes on freeways are provided in Section 2E.59.

**Standard:**

**When a preferential only lane is established, the Preferential Only Lane signs (see Figure 2B-7) and pavement markings (see Sections 3B.22 and 3B.23) for these lanes shall be used to advise road users.**

**At the end of a preferential only lane, a Lane Ends (R3-12a or R3-15a) sign shall be used.**

Guidance:

Ground-mounted Preferential Only Lane (R3-10, R3-11, and R3-12 series) signs should be installed where preferential only lanes are implemented on freeways, expressways, and conventional roads.

Support:

The sizes for Preferential Only Lane signs will differ to reflect the design speeds for each type of roadway facility. Table 2B-1 provides sizes for each type of roadway facility.

Guidance:

The size of the ground-mounted Preferential Only Lane Operational (R3-11 series) signs should remain consistent to accommodate any manual addition or subtraction of a single line of text for each sign.

Support:

Consistent sign sizes are beneficial for agencies when ordering sign materials, as well as when making text changes to existing signs if changes occur to operating times or occupancy restrictions in the future. For example, the R3-11c sign has space for one line located below "24 HOURS" if an agency desires to add

additional information (such as "Mon. – Fri."), yet the R3-11c sign has the same dimensions as the other R3-11 series signs.

**Guidance:**

The decision to use a specific ground-mounted or overhead sign for a preferential only lane should be based on an engineering study that considers the available space, the existing signs for adjoining general purpose lanes, roadway and traffic characteristics, the proximity of other overhead signing, the ability to install overhead signs, and any other unique local factors.

**Support:**

Figures 2E-46 through 2E-52 show example signing layouts using the R3-10 through R3-15 series signs for various preferential only lane applications.

**Standard:**

**The R3-10, R3-11, R3-11a, R3-11c, R3-13, R3-13a, R3-14 and R3-14a signs shall be used exclusively with preferential only lanes for high-occupancy vehicles to indicate the particular occupancy requirement and time restrictions applying to that lane. The R3-10a, R3-11b, and R3-14b signs shall be used in situations where a preferential only lane is not an HOV lane, but is designated for use by other types of vehicles (such as bus and/or taxi use).**

**When used, the ground-mounted Preferential Only Lane Operational (R3-11 series) signs shall be located adjacent to the preferential only lane, and the overhead Preferential Only Lane Operational (R3-14 series) signs shall be mounted directly over the lane.**

**The legend format of the ground-mounted Preferential Only Lane Operational (R3-11 series) signs shall have the following sequence:**

- A. Top Lines: Lanes applicable, such as "RIGHT LANE," "RIGHT 2 LANES," or "THIS LANE";**
- B. Middle Lines: Eligible uses, such as "HOV 2+ ONLY" (or 3+ or 4+), "BUSES ONLY," or other applicable turning movements;**
- C. Bottom Lines: Applicable time and day, such as "7 – 9 AM" or "6:30 – 9:30 AM, MON-FRI."**

**The legend format of the overhead Preferential Only Lane Operational (R3-14 series) signs shall have the following sequence:**

- A. Top Line: Eligible uses, such as "HOV 2+ ONLY" (or 3+ or 4+), "BUSES ONLY," or other types of vehicles;**
- B. Bottom Lines: Applicable time and day, with the time and day placed above the down arrow, such as "7 – 9 AM" or "6:30 – 9:30 AM, MON-FRI." When the operating periods exceed the available line width, the hours and days of the week shall be stacked as shown for the R3-14a sign in Figure 2B-7.**

**Option:**

The diamond symbol may be used instead of the word message HOV.

**Standard:**

**When the diamond symbol (or HOV abbreviation) is used without text on the ground-mounted Preferential Only Lane (R3-10 series, R3-11 series, and R3-12 series) signs, it shall be centered on the top line of the sign. When the diamond symbol (or HOV abbreviation) is used with associated text on the ground-mounted Preferential Only Lane (R3-10 series, R3-11 series, and R3-12 series) signs, it shall appear to the left of the associated text. When the diamond symbol is used on the overhead Preferential Only Lane (R3-13, R3-13a, R3-14, and R3-14a) signs, it shall appear in the top left quadrant. The diamond symbol shall not be used on the bus, taxi, or bicycle Preferential Only Lane signs. The diamond symbol for the R3-15 and R3-15a signs shall appear on the left side of the sign.**

**Figure 2B-7. Examples of Preferential Only Lane Signs**


**GROUND-MOUNTED PREFERENTIAL ONLY LANE SIGNS**



R3-10



R3-10a



R3-10b



R3-11



R3-11a



R3-11b



R3-11c



R3-12



R3-12a



R3-12b

**OVERHEAD PREFERENTIAL ONLY LANE SIGNS**



R3-13



R3-13a



R3-14



R3-14a



R3-14b



R3-15



R3-15a

**Notes:**

- The diamond symbol may be used instead of the word message HOV.
- The minimum vehicle occupancy requirement may vary for each facility (such as 2+, 3+, 4+).
- The occupancy requirement may be added to the first line of the R3-12a, R3-15, and R3-15a signs.
- Some of the legends shown on these signs are for example purposes only. The specific legend for a particular application should be based upon local conditions, ordinances, and State statutes.

**Guidance:**

The Preferential Only Lane Ahead (R3-10a, R3-12, and R3-15) signs should be used for advance notification of preferential only lanes.

**Standard:**

**The R3-10, R3-10b, R3-13, and R3-13a signs shall be used in situations where agencies determine it is appropriate to provide a sign that defines the operational strategy (such as minimum occupancy or types of vehicles) that is being used to manage or regulate the vehicles that are permitted to use a preferential only lane.**

**Guidance:**

The legend format of the R3-10 and R3-13 signs should have this sequence:

- A. Top Line: "HOV 2+ ONLY" (or 3+ or 4+ if appropriate);
- B. Bottom Lines: "2 OR MORE PERSONS PER VEHICLE" (or 3 or 4 if appropriate)

**Option:**

Changeable message signs may be used to supplement static signs where travel conditions change or where multiple types of operational strategies (such as variable occupancy requirements, vehicle types, or pricing policies) are used and varied throughout the day or week to manage the use of, control of, or access to preferential only lanes.

**Standard:**

**When changeable message signs (see Section 2A.07) are used as regulatory signs for preferential only lanes, they shall be the required sign size and shall display the required letter height and legend format that corresponds to the type of roadway facility and design speed.**

**Option:**

The ground-mounted Preferential Only Lane Operational (R3-11 series) signs and the overhead Preferential Only Lane Operational (R3-14 series) signs may be used to supplement changeable message signs that are used to convey preferential only lane restrictions.

Where additional movements are permitted from a preferential only lane on an approach to an intersection, the format and words used in the legend in the middle lines on the ground-mounted Preferential Only Lane Operational (R3-11 series) signs and on the overhead Preferential Only Lane Operational (R3-14 series) signs may be modified to accommodate the permitted movements (such as "RIGHT TURNS ONLY").

**Guidance:**

The Inherently Low Emission Vehicle (ILEV) (R3-10b) sign should be used to indicate that it is permissible for a properly labeled and certified ILEV, regardless of the number of occupants, to use an HOV lane. The ILEV signs should be ground-mounted in advance of and at intervals along the HOV lane based upon engineering judgment. The R3-10b sign is only applicable to HOV lanes and should not be used with other preferential only lane applications.

**Support:**

Inherently low emission vehicles are defined by the Environmental Protection Agency (EPA) as vehicles having no fuel vapor (hydrocarbon) emissions. These vehicles must meet the emissions standards and requirements specified in 40 CFR 88-311-93 and 40 CFR 88.312-93 (c).

**Section 2B.27 Preferential Only Lanes for High-Occupancy Vehicles (HOVs)****Standard:**

**The agencies that own and operate preferential only lanes for high-occupancy vehicles (HOV lanes) shall have the authority and responsibility to determine how they are operated and the**

**occupancy requirements for vehicles operating in HOV lanes. The minimum occupancy requirement shall be two occupants per vehicle.**

**The requirements for a minimum number of occupants in a vehicle to use an HOV lane shall be in effect for most, or all, of at least one of the usual times of the day when the demand to travel is greatest (such as morning or afternoon peak travel periods) and the traffic congestion problems on the roadway and adjoining transportation corridor are at their worst.**

**The HOV signs (see Section 2B.26) shall display the minimum allowable vehicle occupancy requirement established for each HOV lane.**

**The vehicle occupancy requirement established for an HOV lane shall be referenced immediately after the word message HOV or the diamond symbol. The diamond symbol shall be restricted for use with HOV lanes only.**

**The Federal Highway Administration (FHWA) shall be consulted if a significant operational change is proposed that could reasonably be expected to affect a specific HOV lane or portions of the HOV system that were funded or approved by FHWA. This shall include portions of the local, regional, or Federal-aid highway system, where operational changes might significantly impact the operation of one HOV lane or portions of the regional HOV system. To assure consistency with the provisions of Titles 23 and 49 of the United States Code (USC), the important issues and possible impacts of any significant operational changes shall be reviewed to determine if any Federal approval is required.**

**In accordance with the “Federal-Aid Highway Program Guidance on High Occupancy Vehicle (HOV) Lanes” (see Section 1A.11), a proposed test or demonstration project that seeks to significantly change the operation of the HOV lanes for any length of time shall require a Federal review as outlined in Section 2 of the “Federal-Aid Highway Program Guidance on High Occupancy Vehicle (HOV) Lanes” prior to initiating such a test or demonstration project. Also in accordance with the Federal-Aid Highway Program Guidance on HOV lanes, any proposal to significantly change the operation of an HOV lane shall require some form of Federal review, which might require potential action.**

Support:

FHWA Division Offices, with involvement from the Federal Transit Administration (FTA), are responsible for reviewing proposals to significantly change the operation of HOV lanes. Federal interests in this review include commitments made during the National Environmental Policy Act process as described in Title 23 CFR, Part 771, in project agreements, transportation planning requirements, and transportation conformity requirements under the Clean Air Act (40 CFR, Part 51).

Proposals to adjust only the HOV lane hours of operation during the day (for example, minor changes in hours during peak travel periods) or the occupancy requirements (for example, HOV 3+ to HOV 2+) are not typically considered significant operational changes and might not require an explicit Federal review or approval.

Any action that has the potential to adversely affect the area’s flow of traffic, roadway and traveler safety, or the environment might be considered to be a significant operational change. Any proposal to significantly adjust the hours of operation, or to convert an HOV lane to a general purpose travel lane, would be considered a significant operational change to the original project design concept or scope.

Examples of significant operational changes could include:

- A. Switching from 24-hour HOV lane operations to only a portion of the day or week;
- B. Implementing a pricing option to an existing HOV lane (such as HOT lane or toll lane);
- C. Significantly reducing the hours of operation of an HOV lane that is operational during only one peak travel period; or
- D. Managing or operating the HOV lane in a manner that renders it functionally inoperable or obsolete (such as not providing enforcement of the occupancy requirement).

**Guidance:**

An engineering study based on the current and estimated future travel demand for a corridor and facility should be the basis for determining when, during a typical day, there should be a minimum occupancy requirement for a vehicle to use an HOV lane.

**Option:**

HOV lanes may be operated on a 24-hour basis for extended periods of the day, during peak travel periods only, during special events, or during other activities.

HOV lanes may take many forms depending on the level of usage and the design of the facility. They may be physically separated from the other travel lanes by a barrier or median, or they may be concurrent with other travel lanes and be separated only by longitudinal pavement markings. Physically separated HOV lanes may be operated in a constant direction or may be operated as reversible lanes.

Agencies may select from either the HOV abbreviation or the diamond symbol to reference the HOV lane designation.

**Support:**

Inherently low emission vehicle (ILEV) eligibility, testing and certification requirements, labeling, and other regulatory provisions are developed and administered through the Environmental Protection Agency (EPA). EPA is the only entity with the authority to certify ILEVs. Vehicle manufacturers must request the EPA to grant an ILEV certification for any vehicle to be considered and labeled as meeting those standards. According to the EPA, 1996 was the first year that they certified any ILEVs. EPA regulations specify that ILEVs must meet the emission standards specified in 40 CFR 88.311-93 and their labeling must be in accordance with 40 CFR 88.312-93(c). EPA established the ILEV concept to recognize vehicles with no fuel vapor (hydrocarbons) emissions. Zero emission vehicles (electric powered vehicles) that have no emissions are the only other type of clean fuel vehicles that are allowed to use HOV lanes.

**Standard:**

**Agencies shall permit a vehicle with less than the required number of occupants to operate on HOV lanes if:**

- A. The vehicle is properly labeled and certified as an ILEV and the lane is not a bus only HOV lane; or**
- B. The HOV lanes are part of a project that is participating in the FHWA Value Pricing Pilot Program (see Section 2 of the “Federal-Aid Highway Program Guidance on High Occupancy Vehicle (HOV) Lanes”).**

**Motorcycles shall be permitted to use HOV lanes that receive Federal-aid program funding.**

**Section 2B.28 Preferential Only Lane Sign Applications and Placement****Standard:**

**Overhead Preferential Only Lane (R3-13 series, R3-14 series, and R3-15 series) signs shall only be installed along preferential only lanes on freeways and expressways. These overhead signs shall be installed on the side of the roadway where the entrance to the preferential only lane is located and any appropriate adjustments shall be made to the sign message. The sign sizes shall differ between freeways and expressways as provided in Table 2B-1 to reflect the different design speeds for each type of roadway.**

**An R3-13 or R3-13a sign, which defines the occupancy requirement, shall be installed at least 800 m (0.5 mi) in advance of the beginning or initial entry point to an HOV lane. These signs shall only be displayed in advance of the beginning or initial entry point to HOV lanes.**

**A ground-mounted Preferential Only Lane Operational (R3-11, R3-11a, R3-11b, or R3-11d) sign shall be installed at the beginning, initial entry point, intermediate access points, and direct access ramps to all types of preferential only lanes. The overhead Preferential Only Lane Operational (R3-14**

series) signs shall be installed only at the beginning or initial entry point to all types of preferential only lanes.

The ground-mounted Preferential Only Lane Ends 800 m (1/2 Mile) (R3-12b) sign shall be installed at least 800 m (0.5 mi) in advance of the termination of an HOV lane. The ground-mounted Preferential Only Lane Ends (R3-12a) sign shall be installed at the point where the preferential only lane restriction ends. All longitudinal pavement markings, as well as word and symbol pavement markings, associated with the preferential only lane shall end where the R3-12a sign designating the end of the preferential only lane restriction is installed.

Option:

Additional ground-mounted Preferential Only Lane (R3-10, R3-11, R3-11a, R3-11b, or R3-11c) signs may be provided along the length of a preferential only lane.

Overhead Preferential Only Lane Ahead (R3-15) signs may be placed approximately 1.6 km (1 mi) and 3.2 km (2 mi) in advance of the beginning or initial entry points to any type of preferential only lane.

The ground-mounted Preferential Only Lane Ahead (R3-12) sign may be installed at a minimum of 1.6 km (1 mi) in advance of the beginning or initial entry point to any type of preferential only lane.

Guidance:

When Preferential Only Lane signs are used, the decision to use a specific ground-mounted or overhead sign should be based on an engineering study that considers the available space, the existing signs for the adjoining general purpose traffic lanes, roadway and traffic characteristics, the proximity to existing overhead signing, the ability to install overhead signs, and any other unique local factors.

**Standard:**

**For all barrier-separated preferential only lanes, an overhead Preferential Only Lane Operational (R3-14 series) sign shall be used at the beginning or initial entry point, and at any intermediate access points or gaps in the barrier where vehicles are allowed to legally access the barrier-separated preferential only lanes. Ground-mounted Preferential Only Lane Operational (R3-11 series) signs shall be used only as a supplement to the overhead signs at the beginning or initial entry point, or at any intermediate access points or gaps in the barrier.**

Guidance:

For all barrier-separated preferential only lanes, an overhead Preferential Only Lane Ahead (R3-15) sign should be installed and located at least 1.6 km (1 mi) in advance of the beginning or initial entry point.

Option:

For barrier-separated preferential only lanes, ground-mounted R3-10 signs defining the occupancy requirement may be alternated in series with Preferential Only Lane Operational (R3-11, R3-11a, R3-11b, or R3-11c) signs. These signs may be located at intervals of approximately 1 km (0.6 mi) along the length of the preferential only lane, at intermediate entry points, and at designated enforcement areas as defined by the operating agency.

For barrier-separated reversible-flow preferential only lanes, Preferential Only Lane signs may be either static or changeable message type.

**Standard:**

**For buffer-separated preferential only lanes (painted buffer of 0.6 m (2 ft) or more), an overhead Preferential Only Lane Operational (R3-14 series) sign shall be used at the beginning or initial entry point, and at intermediate access points or gaps where vehicles are allowed to legally access the buffer-separated preferential only lane. Ground-mounted R3-10 signs defining the occupancy requirement shall be located and alternated with Preferential Only Lane Operational (R3-11 series) signs in series at intervals not greater than 1 km (0.6 mi) along the length of the preferential only lane,**

**at designated gaps in the buffer where vehicles are allowed to legally access the preferential only lane, and within designated enforcement areas as defined by the operating agency.**

Option:

For buffer-separated preferential only lanes, overhead Preferential Only Lane Operational (R3-14 series) signs may be used at specific locations and intervals along the length of the preferential only lane to supplement the ground-mounted R3-10 signs defining the occupancy requirement and the Preferential Only Lane Operational (R3-11 series) signs based on an engineering study.

**Standard:**

**For concurrent-flow preferential only lanes, ground-mounted R3-10 signs defining the occupancy requirement shall be located and alternated with Preferential Only Lane Operational (R3-11 series) signs in series at intervals not greater than 1 km (0.6 mi) along the length of the preferential only lane.**

Option:

For concurrent-flow preferential only lanes, overhead Preferential Only Lane Operational (R3-14 series) signs may be used at specific locations and intervals along the length of the preferential only lane to supplement the ground-mounted R3-10 signs defining the occupancy requirement and the Preferential Only Lane Operational (R3-11 series) signs based on an engineering study.

**Standard:**

**For direct access ramps to preferential only lanes, a ground-mounted R3-10 sign defining the occupancy requirement and a Preferential Only Lane Operational (R3-11 series) sign shall be used at the beginning or initial entry point for all types of direct access ramps that provide access or lead to preferential only lanes.**

Option:

For direct access ramps to preferential only lanes, an overhead Preferential Only Lane Operational (R3-14 series) sign may be used at the beginning or initial entry point to supplement the required ground-mounted signs.

Support:

Section 2B.26 contains provisions regarding the use of changeable message signs for preferential only lanes.

Section 2E.59 contains additional provisions regarding signing for preferential only lanes on freeway and expressway facilities. Figures 2E-46 through 2E-52 show application and placement examples for Preferential Only Lane signs for a variety of preferential only lane situations.

### **Section 2B.29 DO NOT PASS Sign (R4-1)**

Option:

The DO NOT PASS (R4-1) sign (see Figure 2B-8) may be used in addition to pavement markings (see Section 3B.02) to emphasize the restriction on passing. The DO NOT PASS sign may be used at the beginning of, and at intervals within, a zone through which sight distance is restricted or where other conditions make overtaking and passing inappropriate.

If signing is needed on the left side of the roadway for additional emphasis, NO PASSING ZONE (W14-3) signs may be used (see Section 2C.35).

Support:

Standards for determining the location and extent of no-passing zone pavement markings are set forth in Section 3B.02.

**Section 2B.30 PASS WITH CARE Sign (R4-2)**

## Guidance:

The PASS WITH CARE (R4-2) sign (see Figure 2B-8) should be installed at the end of a no-passing zone if a DO NOT PASS sign has been installed at the beginning of the zone.

**Section 2B.31 SLOWER TRAFFIC KEEP RIGHT Sign (R4-3)**

## Option:

The SLOWER TRAFFIC KEEP RIGHT (R4-3) sign (see Figure 2B-8) may be used on multi-lane roadways to reduce unnecessary lane changing.

## Guidance:

If used, the SLOWER TRAFFIC KEEP RIGHT sign should be installed just beyond the beginning of a multi-lane pavement, and at selected locations where there is a tendency on the part of some road users to drive in the left lane (or lanes) below the normal speed of traffic. This sign should not be used on the approach to an interchange or through an interchange area.

**Section 2B.32 Slow Moving Traffic Lane Signs (R4-5, R4-6)**

## Support:

The Slow Moving Traffic Lane signs (see Figure 2B-8) are used to direct vehicles into an extra lane that has been provided for slow-moving vehicles.

## Guidance:

If an extra lane has been provided for slow-moving traffic, a SLOWER TRAFFIC KEEP RIGHT (R4-3) sign, TRUCKS USE RIGHT LANE (R4-5) sign, or other appropriate sign should be installed at the beginning of the lane. A TRUCK LANE (R4-6) sign, with the appropriate distance shown, should be installed in advance of the lane.

## Option:

The SLOWER TRAFFIC KEEP RIGHT sign may be used as a supplement or as an alternative to the TRUCKS USE RIGHT LANE sign. Both signs may be used on multi-lane roadways to improve capacity and reduce lane changing.

## Guidance:

If an extra lane has been provided for slow-moving traffic, a Lane Ends sign (see Section 2C.33) should be installed in advance of the point where the extra lane ends. Appropriate pavement markings should be installed at both the beginning and the end of the extra lane (see Section 3B.09 and Figure 3B-12).

**Section 2B.33 Keep Right and Keep Left Signs (R4-7, R4-8)**

## Option:

The Keep Right (R4-7) sign (see Figure 2B-8) may be used at locations where it is necessary for traffic to pass only to the right of a roadway feature or obstruction. The Keep Left (R4-8) sign (see Figure 2B-8) may be used at locations where it is necessary for traffic to pass only to the left of a roadway feature or obstruction.

## Guidance:

If used, the Keep Right sign should be installed as close as practical to approach ends of raised medians, parkways, islands, underpass piers, and at other locations where it is not readily apparent that traffic is required to keep to the right. The sign should be mounted on the face of or just in front of a pier or other obstruction separating opposite directions of traffic in the center of the highway such that traffic will have to pass to the right of the sign.

**Figure 2B-8. Passing, Keep Right, and Truck Lane Signs**




R4-1




R4-2




R4-3



R4-5



R4-6




R4-7



R4-7a



R4-7b



R4-8



R4-9



R4-10



R4-H11



R4-H12

**Standard:**

**The Keep Right sign shall not be installed on the right side of the roadway in a position where traffic must pass to the left of the sign.**

**Option:**

The Keep Right sign may be omitted at intermediate ends of divisional islands and medians.

Word message KEEP RIGHT (LEFT) with an arrow (R4-7a or R4-7b) signs (see Figure 2B-8) may be used instead of the R4-7 or R4-8 symbol signs.

Where the obstruction obscures the Keep Right sign, the minimum placement height may be increased for better sign visibility.

**Section 2B.33.1 THROUGH TRAFFIC KEEP RIGHT (LEFT) Signs (R4-H11, R4-H12)****Guidance:**

Where through traffic should keep right or left, the THROUGH TRAFFIC KEEP RIGHT (R4-H11) or THROUGH TRAFFIC KEEP LEFT (R4-H12) sign should be used (see Figure 2B-8).

**Section 2B.34 DO NOT ENTER Sign (R5-1)****Standard:**

**The DO NOT ENTER (R5-1) sign (see Figure 2B-9) shall be used where traffic is prohibited from entering a restricted roadway.**

**Guidance:**

The DO NOT ENTER sign, if used, should be placed directly in view of a road user at the point where a road user could wrongly enter a divided highway, one-way roadway, or ramp (see Figure 2B-10). The sign should be mounted on the right side of the roadway, facing traffic that might enter the roadway or ramp in the wrong direction.

If the DO NOT ENTER sign would be visible to traffic to which it does not apply, the sign should be turned away from, or shielded from, the view of that traffic.

**Option:**

The DO NOT ENTER sign may be installed where it is necessary to emphasize the one-way traffic movement on a ramp or turning lane.

A second DO NOT ENTER sign on the left side of the roadway may be used, particularly where traffic approaches from an intersecting roadway (see Figure 2B-10).


For DO NOT ENTER and STOP signs mounted back-to-back, the size of the STOP sign may be increased to enhance the octagonal outline of the STOP sign.

**Section 2B.35 WRONG WAY Sign (R5-1a)****Option:**

The WRONG WAY (R5-1a) sign (see Figure 2B-9) may be used as a supplement to the DO NOT ENTER sign where an exit ramp intersects a crossroad or a crossroad intersects a one-way roadway in a manner that does not physically discourage or prevent wrong-way entry (see Figure 2B-10).

**Guidance:**

If used, the WRONG WAY sign should be placed at a location along the exit ramp or the one-way roadway farther from the crossroad than the DO NOT ENTER sign (see Section 2E.50).

**Figure 2B-9. Traffic Prohibition Signs**

\* An optional word message sign is shown in the "Sign Design Manual."

### **Section 2B. 36 Selective Exclusion Signs**

Support:

Selective Exclusion signs (see Figure 2B-9) give notice to road users that State or local statutes or ordinances exclude designated types of traffic from using particular roadways or facilities.

Section 4511.07 of the Ohio Revised Code (O.R.C.) authorizes local municipalities to regulate the use of streets by vehicles; Section 4511.051 of the O.R.C. addresses prohibitions on the use of freeways; and Section 4519.40 addresses prohibitions pertaining to snowmobiles and all purpose vehicles. These O.R.C. sections have been reprinted in Appendix B2.

**Standard:**


**If used, Selective Exclusion signs shall clearly indicate the type of traffic that is excluded.**

Support:

Typical exclusion messages include (see Figure 2B-9 and Appendix C):

- A. No Trucks (R5-2);
- B. NO MOTOR VEHICLES (R5-3);
- C. COMMERCIAL VEHICLES EXCLUDED (R5-4);

**Figure 2B-10. Example of Wrong-Way Signing for a Divided Highway with a Median Width of 9 m (30 ft) or Greater**



- D. TRUCKS (VEHICLES) WITH LUGS PROHIBITED (R5-5);
- E. No Bicycles (R5-6);
- F. NON-MOTORIZED TRAFFIC PROHIBITED (R5-7);
- G. MOTOR-DRIVEN CYCLES PROHIBITED (R5-8);
- H. Hazardous Material Prohibited (R14-3) (see Section 2B.52);
- I. THROUGH TRUCKS PROHIBITED (R5-H2b); and
- J. THROUGH TRAFFIC PROHIBITED (R5-H2c).

**Option:**


Appropriate combinations or groupings of these legends into a single sign, such as PEDESTRIANS BICYCLES MOTOR-DRIVEN CYCLES PROHIBITED (R5-10a), or PEDESTRIANS AND BICYCLES PROHIBITED (R5-10b) may be used.

**Guidance:**

If an exclusion is governed by vehicle weight, a Weight Limit sign (see Section 2B.49) should be used instead of a Selective Exclusion sign.

The Selective Exclusion sign should be placed on the right side of the roadway at an appropriate distance from the intersection so as to be clearly visible to all road users turning into the roadway that has the exclusion. The PEDESTRIANS PROHIBITED (R5-10c) or No Pedestrian Crossing (R9-3a) sign should be installed so as to be clearly visible to pedestrians at a location where an alternative route is available.

### Figure 2B-11. ONE WAY and Divided Highway Crossing Signs



#### Option:

The NO TRUCKS (R5-2a) sign may be used as an alternate to the No Trucks (R5-2) symbol sign.

The PEDESTRIANS PROHIBITED (R5-10c) or No Pedestrian Crossing (R9-3a) sign may also be used at underpasses or elsewhere where pedestrian facilities are not provided.

#### Section 2B.37 ONE WAY Signs (R6-1, R6-2)

##### Standard:

Except as noted in the Option, the ONE WAY (R6-1 or R6-2) sign (see Figure 2B-11) shall be used to indicate streets or roadways upon which vehicular traffic is allowed to travel in one direction only.

ONE WAY signs shall be placed parallel to the one-way street at all alleys and roadways that intersect one-way roadways as shown in Figures 2B-12 through 2B-15.

##### Guidance:

Where divided highways are separated by median widths at the intersection itself of 9 m (30 ft) or more, ONE WAY signs should be placed, visible to each crossroad approach, on the near right and far left corners of each intersection with the directional roadways as shown in Figures 2B-12 and 2B-13.

##### Option:

ONE WAY signs may be omitted on the one-way roadways of divided highways, where the design of interchanges indicates the direction of traffic on the separate roadways.

ONE WAY signs may be omitted (see Figure 2B-14) at intersections with divided highways that have median widths at the intersection itself of less than 9 m (30 ft).

##### Standard:

At unsignalized intersections, ONE WAY signs shall be placed on the near right and the far left corners of the intersection facing traffic entering or crossing the one-way street.


At signalized intersections, ONE WAY signs shall be placed either near the appropriate signal faces, on the poles holding the traffic signals, on the mast arm or span wire holding the signals, or at the locations specified for unsignalized intersections.

#### Section 2B.38 Divided Highway Crossing Signs (R6-3, R6-3a)


##### Option:

The Divided Highway Crossing (R6-3 or R6-3a) sign (see Figure 2B-11) may be used to advise road users that they are approaching an intersection with a divided highway.


**Figure 2B-12. Examples of Locations of ONE WAY Signs (Sheet 1 of 2)**




**Figure 2B-12. Examples of Locations of ONE WAY Signs (Sheet 2 of 2)**



**Figure 2B-13. Examples of ONE WAY Signing for Divided Highways with Medians of 9 m (30 ft) or Greater**



**Figure 2B-14. Examples of ONE WAY Signing for Divided Highways with Medians Less Than 9 m (30 ft)**




Notes:  
 All signs shown are optional except the STOP signs.  
 See Figure 2B-10 for examples of placing DO NOT ENTER and WRONG WAY signing.



Typical Mounting

**Figure 2B-15. Examples of ONE WAY Signing for Divided Highways with Medians Less Than 9 m (30 ft) and Separated Left-Turn Lanes**



**Notes:**

All signs shown are optional except the STOP signs.

See Figure 2B-10 for examples of placing DO NOT ENTER and WRONG WAY signing.



**Standard:**

**When the Divided Highway Crossing sign is used at a four-legged intersection, the R6-3 sign shall be used. When used at a T-intersection, the R6-3a sign shall be used.**

**Option:**

The Divided Highway Crossing sign may be located on the near right corner of the intersection and may be mounted beneath a STOP or YIELD sign or on a separate support.

**Section 2B.39 Parking, Standing, and Stopping Signs (R7 and R8 Series)****Support:**

Signs governing the parking, stopping, and standing of vehicles cover a wide variety of regulations, and only general guidance can be provided here. The word “standing” when used on the R7 and R8 series of signs refers to the practice of a driver keeping the vehicle in a stationary position while continuing to occupy the vehicle. Typical examples of parking, stopping, and standing signs (see Figures 2B-16 and 2B-17) are as follows:

- A. NO PARKING ANY TIME (R7-1);
- B. NO PARKING 8:30 AM TO 5:30 PM (R7-2);
- C. NO PARKING EXCEPT SUNDAYS AND HOLIDAYS (R7-3);
- D. NO STANDING ANY TIME (R7-4);
- E. ONE HOUR PARKING 9 AM-7 PM (R7-5);
- F. NO PARKING LOADING ZONE (R7-6);
- G. NO PARKING BUS STOP (R7-7, R7-107, R7-107a);
- H. RESERVED PARKING for persons with disabilities (R7-8);
- I. NO PARKING ON PAVEMENT (R8-1);
- J. NO PARKING EXCEPT ON SHOULDER (R8-2);
- K. NO PARKING (R8-3);
- L. No Parking (R8-3a); and
- M. NO STOPPING ON PAVEMENT (R8-5).

Section 4511.68 of the Ohio Revised Code (O.R.C.) (see Appendix B2) addresses parking prohibitions.

**Standard:**

**In accordance with O.R.C. Section 4511.69, the RESERVED PARKING for persons with disabilities (R7-8) sign shall be supplemented with the \$250 FINE MINIMUM (R7-H8b) sign (see Appendix C). The R7-H8b shall be mounted directly below the R7-8.**

**Section 2B.40 Design of Parking, Standing, and Stopping Signs****Support:**

Discussions of parking signs and parking regulations in this Section apply not only to parking, but also to standing and stopping.

**Standard:**

**The legend on parking signs shall state applicable regulations. Parking signs shall conform to the standards of shape, color, and location.**

**Where parking is prohibited at all times or at specific times, the basic design for parking signs shall have a red legend and border on a white background (Parking Prohibition signs). Where only limited-time parking or parking in a particular manner are permitted, the signs shall have a green legend and border on a white background (Permissive Parking signs).**

Figure 2B-16. No Parking Signs (R7 Series)



R7-1



R7-2



R7-2a



R7-3



R7-4



R7-5



R7-6



R7-7



R7-8



R7-8a



R7-8b



R7-107



R7-107a



R7-108



R7-200



OR



R7-201



R7-201a



R7-202



R7-203

**Figure 2B-17. No Parking Signs (R8 Series)****Guidance:**

Parking signs should display the following information from top to bottom of the sign, in the order listed:

- A. The restriction or prohibition;
- B. The times of the day that it is applicable, if not at all hours; and
- C. The days of the week that it is applicable, if not every day.

If the parking restriction applies to a limited area or zone, the limits of the restriction should be shown by arrows or supplemental plaques. If arrows are used and if the sign is at the end of a parking zone, there should be a single-headed arrow pointing in the direction that the regulation is in effect. If the sign is at an intermediate point in a zone, there should be a double-headed arrow pointing both ways. When a single sign is used at the transition point between two parking zones, it should display a right and left arrow pointing in the direction that the respective restrictions apply.

Where special parking restrictions are imposed during heavy snowfall, Snow Emergency signs should be installed. The legend will vary according to the regulations, but the signs should be vertical rectangles, having a white background with the upper part of the plate a red background.

When used to direct drivers to van-accessible parking facilities, a VAN ACCESSIBLE (R7-8b) plaque (see Figure 2B-16) should be mounted below the D9-6 sign. Where parking spaces that are reserved for persons with disabilities are designated to accommodate wheelchair vans, a VAN ACCESSIBLE (R7-8a) plaque (see Figure 2B-16) should be mounted below the R7-8 sign.

**Option:**

To minimize the number of parking signs, blanket regulations that apply to a given district may, if legal, be posted at district boundary lines.

As an alternate to the use of arrows to show designated restriction zones, word messages such as BEGIN, END, HERE TO CORNER, HERE TO ALLEY, THIS SIDE OF SIGN, or BETWEEN SIGNS may be used.

Where parking is prohibited during certain hours and time-limited parking or parking in a particular manner is permitted during certain other time periods, the red Parking Prohibition and green Permissive Parking signs may be designed as follows:

- A. Two 300 x 450 mm (12 x 18 in) parking signs may be used with the red Parking Prohibition sign installed above or to the left of the green Permissive Parking sign; or
- B. The red Parking Prohibition sign and the green Permissive Parking sign may be combined to form an R7-200 sign on a single 600 x 450 mm (24 x 18 in) sign, or on a single 300 x 750 mm (12 x 30 in) sign.

At the transition point between two parking zones, a single sign or two signs mounted side by side may be used.

The words NO PARKING may be used as an alternative to the No Parking symbol. The supplemental educational plaque, NO PARKING, with a red legend and border on a white background, may be used above signs incorporating the No Parking symbol.

Alternate designs for the R7-107 sign may be developed such as the R7-107a sign (see Figure 2B-16). Alternate designs may include, on a single panel, a transit logo, an approved bus symbol, a parking prohibition, the words BUS STOP, and an arrow. The preferred bus symbol color is black, but other dark colors may be used. Additionally, the transit logo may be shown on the bus face in the appropriate colors instead of placing the logo separately. The reverse side of the sign may contain bus routing information.

To make the parking regulations more effective and to improve public relations by giving a definite warning, a sign (see Figure 2B-16) reading TOW-AWAY ZONE (R7-201) may be appended to, or incorporated in, any parking prohibition sign. The Tow-Away Zone (R7-201a) symbol sign may be used instead of the R7-201 word message sign. The R7-201a sign may have either a black or red legend and border on a white background.

In rural areas, the legend NO PARKING ON PAVEMENT (R8-1) is generally suitable and may be used. If a roadway has paved shoulders, the NO PARKING EXCEPT ON SHOULDER sign (R8-2) may be used as it is less likely to cause confusion. The R8-3a symbol sign or the word message NO PARKING (R8-3) sign may be used to prohibit any parking along a given highway. Word message supplemental plaques (see Figure 2B-17), such as ON PAVEMENT (R8-3c) or ON BRIDGE (R8-3d), may be mounted below the R8-3 or R8-3a sign.

### **Section 2B.41 Placement of Parking, Stopping, and Standing Signs**

Guidance:

When signs with arrows are used to indicate the extent of the restricted zones, the signs should be set at an angle of not less than 30 degrees nor more than 45 degrees with the line of traffic flow in order to be visible to approaching traffic.

Spacing of signs should be based on legibility and sign orientation.

If the zone is unusually long, signs showing a double arrow should be used at intermediate points within the zone.

**Standard:**

**If the signs are mounted at an angle of 90 degrees to the curb line, two signs shall be mounted back to back at the transition point between two parking zones, each with the appended message THIS SIDE OF SIGN.**

Guidance:

At intermediate points within a zone, a single sign without any arrow or appended plaque should be used, facing in the direction of approaching traffic. Otherwise the standards of placement should be the same as for signs using directional arrows.

**Section 2B.42 Emergency Restriction Signs (R8-4, R8-7, R8-8)****Option:**

The EMERGENCY PARKING ONLY (R8-4) sign (see Figure 2B-17) or the EMERGENCY STOPPING ONLY (R8-7) sign (see Figure 2B-17) may be used to discourage or prohibit shoulder parking, particularly where scenic or other attractions create a tendency for road users to stop temporarily, even though turnout or rest areas have not been provided.

The DO NOT STOP ON TRACKS (R8-8) sign (see Figure 8B-3) may be used to discourage or prohibit parking or stopping on railroad tracks (see Section 8B.07).

**Standard:**

**Emergency Restriction signs shall be rectangular and shall have a red or black legend and border on a white background.**

**Support:**

Section 4511.712 of the Ohio Revised Code (O.R.C.) (see Appendix B2) addresses the obstruction of railroad grade crossings.

**Section 2B.43 WALK ON LEFT FACING TRAFFIC and No Hitchhiking Signs (R9-1, R9-4, R9-4a)****Option:**

The WALK ON LEFT FACING TRAFFIC (R9-1) sign (see Figure 2B-18) may be used on highways where no sidewalks are provided.

**Standard:**

**If used, the WALK ON LEFT FACING TRAFFIC sign shall be installed on the right side of the road where pedestrians walk on the pavement or shoulder in the absence of pedestrian pathways or sidewalks.**

**Option:**

The No Hitchhiking (R9-4a) sign (see Figure 2B-18) may be used to prohibit standing in or adjacent to the roadway for the purpose of soliciting a ride. The R9-4 word message sign (see Figure 2B-18) may be used as an alternate to the R9-4a symbol sign.

**Section 2B.44 Pedestrian Crossing Signs (R9-2, R9-3)****Option:**

Pedestrian Crossing signs (see Figure 2B-18) may be used to limit pedestrian crossing to specific locations.

**Standard:**

**If used, Pedestrian Crossing signs shall be installed to face pedestrian approaches.**

**Option:**

Where crosswalks are clearly defined, the CROSS ONLY AT CROSSWALKS (R9-2) sign may be used to discourage jaywalking or unauthorized crossing.

The No Pedestrian Crossing (R9-3a) sign may be used to prohibit pedestrians from crossing a roadway at an undesirable location or in front of a school or other public building where a crossing is not designated.

The NO PEDESTRIAN CROSSING (R9-3) word message sign may be used as an alternate to the R9-3a symbol sign. The USE CROSSWALK (R9-3b) supplemental plaque, along with an arrow, may be installed below either sign to designate the direction of the crossing.

Figure 2B-18. Pedestrian Signs



R9-1



R9-2



R9-3



R9-3a




R9-3b



R9-4



R9-4a



R10-1




R10-2a




R10-3




R10-3a




R10-3b



R10-3c



R10-3d



R10-3e



R10-4



R10-4a



R10-4b

**Support:**

One of the most frequent uses of the Pedestrian Crossing signs is at signalized intersections that have three crossings that can be used and one leg that cannot be crossed.

**Guidance:**

The R9-3b sign should not be installed in combination with educational plaques.

**Section 2B.45 Traffic Signal Signs (R10-1 through R10-21)****Option:**

To supplement traffic signal control, Traffic Signal signs R10-1 through R10-21 may be used to regulate road users.

**Guidance:**

When used, Traffic Signal signs should be located adjacent to the signal face to which they apply.

**Standard:**

**Traffic Signal signs applicable to pedestrian actuation (see Figure 2B-18) shall be mounted immediately above or incorporated in pedestrian pushbutton units (see Section 4E.08).**

**Support:**

Traffic Signal signs applicable to pedestrians include:

- A. CROSS ON GREEN LIGHT ONLY (R10-1);
- B. CROSS ON WALK SIGNAL ONLY (R10-2);
- C. PUSH BUTTON FOR GREEN LIGHT (R10-3); and
- D. PUSH BUTTON FOR WALK SIGNAL (R10-4).

**Option:**

The following signs may be used as an alternate for the R10-3 and R10-4 signs:


- A. TO CROSS STREET (arrow), PUSH BUTTON WAIT FOR GREEN LIGHT (R10-3a); and
- B. TO CROSS STREET (arrow), PUSH BUTTON WAIT FOR WALK SIGNAL (R10-4a).

The symbol sign R10-2a may be used as an alternate to sign R10-2. Where symbol-type pedestrian signal indications are used, an educational sign (R10-3b) may be used to improve pedestrian understanding of pedestrian indications at signalized intersections. Where word-type pedestrian signal indications are being retained for the remainder of their useful service life, the legends WALK/DONT WALK may be substituted for the symbols on the educational sign R10-3b, thus creating sign R10-3c. The R10-3d sign may be used if the pedestrian clearance time is sufficient only for the pedestrian to cross to the median. The diagrammatic sign R10-4b may also be used as an alternate to sign R10-4. At intersections where pedestrians cross in two stages using a median refuge island, the word message "CROSS TO MEDIAN" may be placed on the near corner of the refuge island along with the educational plaque.

Traffic Signal signs (see Figure 2B-19) may be installed at certain locations to clarify signal control. Among the legends for this purpose are LEFT ON GREEN ARROW ONLY (R10-5), STOP HERE ON RED (R10-6 or R10-6a) for observance of stop lines, DO NOT BLOCK INTERSECTION (R10-7) for avoidance of traffic obstructions, USE LANE(S) WITH GREEN ARROW (R10-8) for obedience to Lane Control signals, LEFT TURN YIELD ON GREEN (symbolic green ball) (R10-12), and LEFT TURN SIGNAL YIELD ON GREEN (symbolic green ball) (R10-21) (see Section 4D.06).

In situations where traffic control signals are coordinated for progressive timing, the Traffic Signal Speed (I1-1) sign may be used (see Section 2D.47).

**Figure 2B-19. Traffic Signal Signs**



**Standard:**

**The NO TURN ON RED (R10-11a, R10-11b) sign (see Figure 2B-19) shall be used to prohibit a right turn on red (or a left turn on red from a one-way street to a one-way street).**

**Option:**

A symbolic NO TURN ON RED (R10-11) sign (see Figure 2B-19) may be used as an alternate to the R10-11a and R10-11b signs.

**Guidance:**

If used, the NO TURN ON RED sign should be installed near the appropriate signal head.

A NO TURN ON RED sign should be considered when an engineering study finds that one or more of the following conditions exists:

- A. Inadequate sight distance to vehicles approaching from the left (or right, if applicable);
- B. Geometrics or operational characteristics of the intersection that might result in unexpected conflicts;
- C. An exclusive pedestrian phase;
- D. An unacceptable number of pedestrian conflicts with right-turn-on-red maneuvers, especially involving children, older pedestrians, or persons with disabilities; and
- E. More than three right-turn-on-red accidents reported in a 12-month period for the particular approach.

**Option:**

In order to remind drivers who are making turns to yield to pedestrians, especially at intersections where right turn on red is permitted and pedestrian crosswalks are marked, a TURNING TRAFFIC MUST YIELD TO PEDESTRIANS (R10-15) sign may be used (see Figure 2B-19).

A supplemental R10-20a plaque (see Figure 2B-19) showing times of day (similar to the S4-1 plaque shown in Figure 7B-1) with a black legend and border on a white background may be mounted below a NO TURN ON RED sign to indicate that the restriction is in place only during certain times.

**Standard:**

**The EMERGENCY SIGNAL (R10-13) sign (see Figure 2B-19) shall be used in conjunction with emergency-vehicle traffic control signals (see Section 4F.02).**

**Option:**

A U-TURN YIELD TO RIGHT TURN (R10-16) sign (see Figure 2B-19) may be installed near the left-turn signal face if U-turns are allowed on a protected left-turn movement on an approach from which drivers making a right turn from the conflicting approach to their left are simultaneously being shown a right-turn GREEN ARROW signal indication.

**Section 2B.46 Photo Enforced Signs (R10-18, R10-19)****Option:**

A TRAFFIC LAWS PHOTO ENFORCED (R10-18) sign (see Figure 2B-1) may be installed at a jurisdictional boundary to advise road users that some of the traffic regulations within that jurisdiction are being enforced by photographic equipment.

A PHOTO ENFORCED (R10-19) sign (see Figure 2B-1) may be mounted below a regulatory sign to advise road users that the regulation is being enforced by photographic equipment.

**Standard:**

**If used below a regulatory sign, the PHOTO ENFORCED (R10-19) sign shall be a rectangle with a black legend and border on a white background.**

**Section 2B.47 KEEP OFF MEDIAN Sign (R11-1)**

Option:

The KEEP OFF MEDIAN (R11-1) sign (see Figure 2B-20) may be used to prohibit driving into or parking on the median.

Guidance:

The KEEP OFF MEDIAN sign should be installed on the left of the roadway within the median at random intervals as needed wherever there is a tendency for encroachment.

**Section 2B.48 ROAD CLOSED Sign (R11-2) and LOCAL TRAFFIC ONLY Signs (R11-3 Series, R11-4)**

Guidance:

The ROAD CLOSED (R11-2) sign should be installed where roads have been closed to all traffic (except authorized vehicles).

ROAD CLOSED—LOCAL TRAFFIC ONLY (R11-3) or ROAD CLOSED TO THRU TRAFFIC (R11-4) signs should be used where through traffic is not permitted, or for a closure some distance beyond the sign, but where the highway is open for local traffic up to the point of closure.

**Standard:**

**The Road Closed (R11-2, R11-3 series, and R11-4) signs (see Figure 2B-20) shall be designed as horizontal rectangles. These signs shall be preceded by the applicable Advance Road Closed warning sign with the secondary legend AHEAD and, if applicable, an Advance Detour warning sign (see Section 6F.18).**

Option:

The word message BRIDGE OUT may be substituted for the ROAD CLOSED message where applicable.

**Section 2B.49 Weight Limit Signs (R12-1 through R12-5)**

Option:

The Weight Limit (R12-1) sign carrying the legend WEIGHT LIMIT XX TONS may be used to indicate vehicle weight restrictions including load.

Where the restriction applies to axle weight rather than gross load, the legend may be AXLE WEIGHT LIMIT XX TONS or AXLE WEIGHT LIMIT XXXX LBS (R12-2).

To restrict trucks of certain sizes by reference to empty weight in residential districts, the legend may be NO TRUCKS OVER XX TONS EMPTY WT or NO TRUCKS OVER XXXX LBS EMPTY WT (R12-3).


In areas where multiple regulations of the type described above are applicable, a sign combining the necessary messages on a single panel may be used, such as WEIGHT LIMIT XX TONS PER AXLE, XX TONS GROSS (R12-4).

Posting of specific load limits may be accomplished by use of the Weight Limit symbol sign (R12-5). A sign containing the legend WEIGHT LIMIT on the top two lines, and showing three different truck symbols and their respective weight limits for which restrictions apply may be used, with the weight limits shown to the right of each symbol as XX T. A bottom line of legend stating GROSS WT may be included if needed for enforcement purposes.

**Standard:**

**If used, the Weight Limit sign (see Figure 2B-20) shall be located in advance of the applicable section of highway or structure.**

**Figure 2B.20. Road Closed and Weight Limit Signs**



**Guidance:**

If used, the Weight Limit sign with an advisory distance ahead legend should be placed at approach road intersections or other points where prohibited vehicles can detour or turn around.

**Support:**

Section 5591.42 of the Ohio Revised Code (O.R.C.) (see Appendix B2) authorizes reductions in bridge weight limits.

**Option:**


The R12-H5 sign (with four truck symbols) may be used in lieu of the R12-5 sign (see Appendix C).

**Section 2B.50 Weigh Station Signs (R13 Series)**

**Guidance:**

The COMMERCIAL VEHICLES ANY COMBINATION OVER 5 TONS GVW-GVWR ENTER SCALES (R13-H1) and HAZ-MAT PLACARDED VEHICLES ENTER SCALES (R13-H2) signs (see Figure 2B-21) should be used to direct appropriate traffic into a weigh station.

The R13-H1 and R13-H2 signs should be supplemented by the D8 series of guide signs (see Section 2D.44).

**Figure 2B-21. Truck Signs**

R13-H1



R13-H2



R14-1



R14-2



R14-3



M4-4

**Section 2B.51 TRUCK ROUTE Sign (R14-1)**

Guidance:

The TRUCK ROUTE (R14-1) sign (see Figure 2B-21) should be used to mark a route that has been designated to allow truck traffic.

Option:

On a numbered highway, the TRUCK auxiliary sign may be used (see Section 2D.20).

**Section 2B.52 Hazardous Material Signs (R14-2, R14-3)**

Option:

The Hazardous Material Route (R14-2) sign (see Figure 2B-21) may be used to identify routes that have been designated by proper authority for vehicles transporting hazardous material.

On routes where the transporting of hazardous material is prohibited, the Hazardous Material Prohibition (R14-3) sign (see Figure 2B-21) may be used.

Guidance:

If used, the Hazardous Material Prohibition sign should be installed on a street or roadway at a point where vehicles transporting hazardous material have the opportunity to take an alternate route.

**Section 2B.53 National Network Signs**

Support:

All state highways in Ohio have been designated as part of the National Network. Therefore, the special truck routing National Network signs addressed in Section 2B.53 of the Manual on Uniform Traffic Control Devices published by FHWA are not used in Ohio.

**Section 2B.54 Other Regulatory Signs****Support:**

Information regarding other regulatory signs related to temporary traffic control areas, school areas, highway-rail grade crossings, bicycle facilities and highway-light rail grade crossings are addressed in Parts 6, 7, 8, 9 and 10 of this Manual, respectively. Appendix C presents a graphic index and cross-reference guide for the signs discussed in this Manual.

**Option:**

Regulatory word message signs other than those classified and specified in this Manual and the “Sign Design Manual” (SDM) (see Section 1A.11) may be developed to aid the enforcement of other laws or regulations.

Except for symbols on regulatory signs, minor modifications in the design may be permitted provided that the essential appearance characteristics are met.

**Standard:**

**When a seat belt symbol is used, the symbol shown in Figure 2B-22 shall be used.**

**Guidance:**

The seat belt symbol should not be used alone but in connection with mandatory seat belt regulatory messages.

---

***Figure 2B-22. Seat Belt Symbol***



Intentionally blank.

## CHAPTER 2C. WARNING SIGNS

### Section 2C.01 Function of Warning Signs

Support:

Warning signs call attention to unexpected conditions on or adjacent to a highway or street and to situations that might not be readily apparent to road users. Warning signs alert road users to conditions that might call for a reduction of speed or an action in the interest of safety and efficient traffic operations.

### Section 2C.02 Application of Warning Signs

**Standard:**

**The use of warning signs shall be based on an engineering study or on engineering judgment.**

Guidance:

The use of warning signs should be kept to a minimum as the unnecessary use of warning signs tends to breed disrespect for all signs. In situations where the condition or activity is seasonal or temporary, the warning sign should be removed or covered when the condition or activity does not exist.

Support:

The categories of warning signs are shown in Table 2C-1.

Warning signs specified herein cover most of the conditions that are likely to be encountered. Additional warning signs for low-volume roads (as defined in Section 5A.01), temporary traffic control zones, school areas, highway-rail grade crossings, bicycle facilities, and highway-light rail transit grade crossings are discussed in Parts 5 through 10, respectively.

Option:

Word message warning signs other than those specified in this Manual may be developed and installed by State and local highway agencies.

### Section 2C.03 Design of Warning Signs

**Standard:**

**All warning signs shall be diamond-shaped (square with one diagonal vertical) with a black legend and border on a yellow background unless specifically designated otherwise. Warning signs shall be designed in accordance with the sizes, shapes, colors, and legends contained in the “Sign Design Manual” (SDM) (see Section 1A.11).**

Option:

Warning signs regarding conditions associated with pedestrians, bicyclists, playgrounds, school buses, and schools may have a black legend and border on a yellow background or a black legend and border on a fluorescent yellow-green background.

### Section 2C.04 Size of Warning Signs

**Standard:**

**The sizes for warning signs shall be as shown in Table 2C-2.**

Guidance:

The Conventional Road size should be used on conventional roads.

The Freeway and Expressway sizes should be used for higher-speed applications to provide larger signs for increased visibility and recognition.

**Table 2C-1. Categories of Warning Signs**

Category	Group	Section	Signs	Sign Codes
Roadway Related	Changes in Horizontal Alignment	2C.06	Turn, Curve, Reverse Turn, Reverse Curve, Winding Road, Hairpin Curve, 270-Degree Curve	W1-1 through W1-5, W1-11, W1-15
		2C.07	Combination Horizontal Alignment/Advisory Speed	W1-1a, W1-2a
		2C.08	Combination Horizontal Alignment/Intersection	W1-10
		2C.09	Large Arrow (one direction)	W1-6
		2C.10	Chevron Alignment	W1-8
		2C.11	Truck Rollover	W1-13
	Vertical Alignment	2C.12	Hill	W7-1, W7-1a, W7-1b
		2C.13	Truck Escape Ramp	W7-4, W7-4a
		2C.14	HILL BLOCKS VIEW	W7-6
	Cross Section	2C.15	ROAD NARROWS	W5-1
		2C.16-17	NARROW BRIDGE, ONE LANE BRIDGE	W5-2, W5-3
		2C.18-20	Divided Road, Divided Road Ends, Double Arrow	W6-1, W6-2, W12-1
		2C.21	DEAD END, NO OUTLET	W14-1, W14-1a, W14-2, W14-2a
		2C.22	Low Clearance	W12-2, W12-2p
	Roadway Surface Conditions	2C.-	BUMP, DIP, SPEED HUMP	W8-1, W8-2, W17-1
		2C.25	Pavement Ends	W8-3
		2C.26	Shoulder	W8-4, W8-9, W8-9a
2C.27		Slippery When Wet	W8-5	
2C.28		BRIDGE ICES BEFORE ROAD	W8-13	
Traffic Related		Advance Traffic Control	2C.29-30 4I.02	Stop Ahead, Yield Ahead, Signal Ahead, BE PREPARED TO STOP, Speed Reduction, and DRAWBRIDGE AHEAD
	Traffic Flow	2C.31-35	Merge, Lane Ends, Added Lane, Two-Way Traffic, Right Lane Ends, Lane Ends Merge Left, No Passing Zone	W4-1, W4-2, W4-3, W4-5, W4-6, W6-3, W9-1, W9-2, W14-3
	Change in Speed	2C.36	Advisory Speed	W13-2, W13-3, W13-5
	Intersections	2C.37	Cross Road, Side Roads, T, Y, and Circular Intersection	W2-1 through W2-6
		2C.38	Large Arrow (two directions)	W1-7
		2C.39	Oncoming Extended Green	W25-1, W25-2
	Vehicular Traffic	2C.40	Trucks Crossing, Truck (symbol), Emergency Vehicle, Tractor, Bicycle, Golf Cart, Horse-Drawn Vehicle	W8-6, W11-1, W11-5, W11-5a, W11-8, W11-10, W11-11, W11-12p, W11-14
	Nonvehicular	2C.41-42	Pedestrian, Deer, Cattle, Snowmobile, Horse, Wheelchair, Playground	W11-2, W11-3, W11-4, W11-6, W11-7, W11-9, W15-1
Supplemental Plaques	Distance	2C.45	XX Feet, XX Miles, Next XX Feet, Next XX MI	W16-2, W16-3, W16-4, W7-3a
	Speed	2C.46	Advisory Speed	W13-1
	Arrow	2C.47	Advance Arrow, Directional Arrow, Diagonal Arrow	W16-5p, W16-6p, W16-7p
	Hill Related	2C.48	Trucks Use Low Gear, X% Grade	W7-2, W7-3
	Street Name Plaque	2C.49	Advance Street Name	W16-8
	Intersection	2C.50	CROSS TRAFFIC DOES NOT STOP	W4-4p
	Share the Road	2C.51	SHARE THE ROAD	W16-1
	HOV	2C.52	High-Occupancy Vehicle	W16-11
	Photo Enforced	2C.53	Photo Enforced	W16-10
Traffic Circle	2C.37	Traffic Circle	W16-12p	

**Table 2C-2. Warning Sign Sizes**

Description		Conventional Road	Express-way	Freeway	Minimum	Oversized
Shape	Sign Series					
Diamond	W1, W2, W7, W8, W9, W11, W14, W15-1, W17-1	750 x 750 (30 x 30)	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	600 x 600 (24 x 24)	—
	W1 Combination, W3, W4, W5, W6, W8-3, W10, W12	900 x 900 (36 x 36)	1200 x 1200 (48 x 48)	1200 x 1200 (48 x 48)	750 x 750 (30 x 30)	—
Rectangular	W1- Arrows	1200 x 600 (48 x 24)	1500 x 750 (60 x 30)	—	900 x 450 (36 x 18)	1500 x 750 (60 x 30)
	W1- Chevron	450 x 600 (18 x 24)	750 x 900 (30 x 36)	900 x 1200 (36 x 48)	300 x 450 (12 x 18)	—
	W7-4	1950 x 1200 (78 x 24)	1950 x 1200 (78 x 48)	1950 x 1200 (78 x 48)	—	—
	W7-4b, 4c	1950 x 1500 (78 x 60)	1950 x 1500 (78 x 60)	1950 x 1500 (78 x 60)	—	—
	W10-9, 10	600 x 450 (24 x 18)	—	—	—	—
	W12-2p	2100 x 600 (84 x 24)	2100 x 600 (84 x 24)	2100 x 600 (84 x 24)	—	—
	W13-2, 3, 5, W25	600 x 750 (24 x 30)	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	600 x 750 (24 x 30)	1200 x 1500 (48 x 60)
Pennant	W14-3	900 x 1200 x 1200 (36 x 48 x 48)	—	—	750 x 1000 x 1000 (30 x 40 x 40)	1200 x 1600 x 1600 (48 x 64 x 64)
Circular	W10-1	900 (36) Dia.	1200 (48) Dia.	—	750 (30) Dia.	1200 (48) Dia.

- Notes: 1. Larger signs may be used when appropriate.  
 2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height.

**Option:**

The Minimum size may be used on low-speed roadways where the reduced legend size would be adequate for the warning or where physical conditions preclude the use of the other sizes.

Oversized signs and larger sizes may be used for those special applications where speed, volume, or other factors result in conditions where increased emphasis, improved recognition, or increased legibility would be desirable.

**Standard:**

**The minimum size for supplemental warning plaques shall be as shown in Table 2C-3.**

**Table 2C-3. Minimum Size of Supplemental Warning Plaques**

Size of Warning Sign	Size of Supplemental Plaque			
	Rectangular			Square
	1 Line	2 Lines	Arrow	
600 x 600 (24 x 24)	600 x 300	600 x 450	600 x 300	450 x 450
750 x 750 (30 x 30)	(24 x 12)	(24 x 18)	(24 x 12)	(18 x 18)
900 x 900 (36 x 36)	750 x 450	750 x 600	750 x 450	600 x 600
1200 x 1200 (48x 48)	(30 x 18)	(30 x 24)	(30 x 18)	(24 x 24)

- Notes: 1. Larger supplemental plaques may be used when appropriate.  
 2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height.

Option:

Signs larger than those shown in Tables 2C-2 and 2C-3 may be used (see Section 2A.12).

### **Section 2C.05 Placement of Warning Signs**

Support:

For information on placement of warning signs, see Sections 2A.16 to 2A.21.

The total time needed to perceive and complete a reaction to a sign is the sum of the times necessary for Perception, Identification (understanding), Emotion (decision making), and Volition (execution of decision), and is called the PIEV time. The PIEV time can vary from several seconds for general warning signs to 6 seconds or more for warning signs requiring high road user judgment.

Table 2C-4 lists suggested sign placement distances for two conditions. This table is provided as an aid for determining warning sign location.

Guidance:

Warning signs should be placed so that they provide adequate PIEV time. The distances contained in Table 2C-4 are for guidance purposes and should be applied with engineering judgment. Warning signs should not be placed too far in advance of the condition, such that drivers might tend to forget the warning because of other driving distractions, especially in urban areas.

Minimum spacing between warning signs with different messages should be based on the estimated PIEV time for driver comprehension of and reaction to the second sign.

The effectiveness of the placement of warning signs should be periodically evaluated under both day and night conditions.

Option:


Warning signs that advise road users about conditions that are not related to a specific location, such as Deer Crossing or SOFT SHOULDER, may be installed in an appropriate location, based on engineering judgment, since they are not covered in Table 2C-4.

**Table 2C-4. Guidelines for Advance Placement of Warning Signs**

Posted or 85th-Percentile Speed	Advance Placement Distance <sup>1</sup>								
	Condition A: Speed Reduction and lane changing in heavy traffic <sup>2</sup>	Condition B: Deceleration to the listed advisory speed (mph) for the condition <sup>4</sup>							
		0 <sup>3</sup>	10	20	30	40	50	60	70
20 mph	225 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–	–	–	–
25 mph	325 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–	–	–
30 mph	450 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–	–	–
35 mph	550 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–	–
40 mph	650 ft	125 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–	–
45 mph	750 ft	175 ft	125 ft	N/A <sup>5</sup>	N/A <sup>5</sup>	N/A <sup>5</sup>	–	–	–
50 mph	850 ft	250 ft	200 ft	150 ft	100 ft	N/A <sup>5</sup>	–	–	–
55 mph	950 ft	325 ft	275 ft	225 ft	175 ft	100 ft	N/A <sup>5</sup>	–	–
60 mph	1100 ft	400 ft	350 ft	300 ft	250 ft	175 ft	N/A <sup>5</sup>	–	–
65 mph	1200 ft	475 ft	425 ft	400 ft	350 ft	275 ft	175 ft	N/A <sup>5</sup>	–
70 mph	1250 ft	550 ft	525 ft	500 ft	425 ft	350 ft	250 ft	150 ft	–
75 mph	1350 ft	650 ft	625 ft	600 ft	525 ft	450 ft	350 ft	250 ft	100 ft

Notes:

- <sup>1</sup> The distances are adjusted for a sign legibility distance of 175 ft for Condition A. The distances for Condition B have been adjusted for a sign legibility distance of 250 ft, which is appropriate for an alignment warning symbol sign.
- <sup>2</sup> Typical conditions are locations where the road user must use extra time to adjust speed and change lanes in heavy traffic because of a complex driving situation. Typical signs are Merge and Right Lane Ends. The distances are determined by providing the driver a PIEV time of 14 to 14.5 seconds for vehicle maneuvers (2001 AASHTO Policy, Exhibit 3-3, Decision Sight Distance, Avoidance Maneuver E) minus the legibility distance of 175 ft for the appropriate sign.
- <sup>3</sup> Typical condition is the warning of a potential stop situation. Typical signs are Stop Ahead, Yield Ahead, Signal Ahead, and Intersection Warning signs. The distances are based on the 2001 AASHTO Policy, Stopping Sight Distance, Exhibit 3-1, providing a PIEV time of 2.5 seconds, a deceleration rate of 11.2 ft/second<sup>2</sup>, minus the sign legibility distance of 175 ft.
- <sup>4</sup> Typical Conditions are locations where the road user must decrease speed to maneuver through the warned condition. Typical signs are Turn, Curve, Reverse Turn, or Reverse Curve. The distance is determined by providing a 2.5 second PIEV time, a vehicle deceleration rate 10 ft/second<sup>2</sup>, minus the sign legibility distance of 250 ft.
- <sup>5</sup> No suggested distances are provided for these speeds, as placement location is dependent on site conditions and other signing to provide an adequate advance warning for the driver.

**Figure 2C-1. Horizontal Alignment Signs****Section 2C.06 Horizontal Alignment Signs (W1-1 through W1-5, W1-11, W1-15)****Option:**

The horizontal alignment Turn (W1-1), Curve (W1-2), Reverse Turn (W1-3), Reverse Curve (W1-4), or Winding Road (W1-5) signs (see Figure 2C-1) may be used in advance of situations where the horizontal roadway alignment changes. A One-Direction Large Arrow (W1-6) sign (see Figure 2C-1 and Section 2C.09) may be used on the outside of the turn or curve.

If the change in horizontal alignment is 135 degrees or more, the Hairpin Curve (W1-11) sign (see Figure 2C-1) may be used.

If the change in horizontal alignment is approximately 270 degrees, such as on a cloverleaf interchange ramp, the 270-degree Loop (W1-15) sign (see Figure 2C-1) may be used.

**Guidance:**

The application of these signs should conform to Table 2C-5.

**Table 2C-5. Horizontal Alignment Sign Usage**

Number of Alignment Changes	Advisory Speed	
	≤ 30 MPH	> 30 MPH
1	Turn (W1-1) <sup>1</sup>	Curve (W1-2) <sup>1</sup>
2 <sup>2</sup>	Reverse Turn <sup>3</sup> (W1-3)	Reverse Turn <sup>3</sup> (W1-4)
3 or more <sup>2</sup>	Winding Road <sup>3</sup> (W1-5)	

## Notes:

- <sup>1</sup> Engineering judgment should be used to determine whether the Turn or Curve sign should be used.
- <sup>2</sup> Alignment changes are in opposite directions and are separated by a tangent distance of 180 m (600 ft) or less.
- <sup>3</sup> A Right Reverse Turn (W1-3R), Right Reverse Curve (W1-4R), or Right Winding Road (W1-5R) sign is used if the first change in alignment is to the right; a Left Reverse Turn (W1-3L), Left Reverse Curve (W1-4L), or Left Winding Road (W1-5L) sign is used if the first change in alignment is to the left.

When the Hairpin Curve sign or the 270-degree Loop sign is installed, either a One-Direction Large Arrow (W1-6) sign or Chevron Alignment (W1-8) signs should be installed on the outside of the turn or curve.

## Option:

An Advisory Speed (W13-1) plaque (see Section 2C.46) may be used to indicate the speed for the change in horizontal alignment. The supplemental distance plaque NEXT XX MILES (W7-3a) may be installed below the Winding Road sign where continuous roadway curves exist (see Section 2C.45). The combination Horizontal Alignment/Advisory Speed sign (see Section 2C.07), combination Horizontal Alignment/Intersection sign (see Section 2C.08), or the Curve Speed sign (see Section 2C.36) may also be used.

**Standard:**

**When engineering judgment determines the need for a horizontal alignment sign, one of the W1-1 through W1-5, W1-10, W1-11 or W1-15 signs shall be used.**

## Option:

If the reduction in speed is 20 km/h (15 mph) or greater, a supplemental combination Horizontal Alignment/Advisory Speed sign or Curve Speed (W13-5) sign may be installed as near as practical to the point of curvature. If the reduction in speed is 40 km/h (25 mph) or greater, one or more additional Curve Speed signs may be installed along the curve.

**Section 2C.07 Combination Horizontal Alignment/Advisory Speed Signs (W1-1a, W1-2a)**

## Option:

The Turn (W1-1) sign or the Curve (W1-2) sign may be combined with the Advisory Speed (W13-1) plaque (see Section 2C.46) to create a combination Turn /Advisory Speed (W1-1a) sign (see Figure 2C-1), or combination Curve/Advisory Speed (W1-2a) sign (see Figure 2C-1).

**Standard:**

When used, the combination Horizontal Alignment/Advisory Speed sign shall supplement other advance warning signs and shall be installed at the beginning of the turn or curve.

**Section 2C.08 Combination Horizontal Alignment/Intersection Sign (W1-10)****Option:**

The Turn (W1-1) sign or the Curve (W1-2) sign may be combined with the Cross Road (W2-1) sign or the Side Road (W2-2 or W2-3) sign to create a combination Horizontal Alignment/Intersection (W1-10) sign (see Figure 2C-1) that depicts the condition where an intersection occurs within a turn or curve.

**Guidance:**

Elements of the combination Horizontal Alignment/Intersection sign related to horizontal alignment should conform to Section 2C.06, and elements related to intersection configuration should conform to Section 2C.37. No more than one Cross Road or two Side Road symbols should be shown on any one combination Horizontal Alignment/Intersection sign.

**Section 2C.09 One-Direction Large Arrow Sign (W1-6)****Option:**

A One-Direction Large Arrow (W1-6) sign (see Figure 2C-1) may be used to delineate a change in horizontal alignment.

**Standard:**

**The One-Direction Large Arrow sign shall be a horizontal rectangle with an arrow pointing to the left or right.**

**If used, the One-Direction Large Arrow sign shall be installed on the outside of a turn or curve in line with and at approximately a right angle to approaching traffic.**

**The One-Direction Large Arrow sign shall not be used where there is no alignment change in the direction of travel, such as at the beginnings and ends of medians or at center piers.**

**Guidance:**

The One-Direction Large Arrow sign should be visible for a sufficient distance to provide the road user with adequate time to react to the change in alignment.

**Section 2C.10 Chevron Alignment Sign (W1-8)****Option:**

The Chevron Alignment (W1-8) sign (see Figure 2C-1) may be used to provide additional emphasis and guidance for a change in horizontal alignment. A Chevron Alignment sign may be used as an alternate or supplement to standard delineators on curves or to the One-Direction Large Arrow (W1-6) sign.

**Standard:**

**The Chevron Alignment sign shall be a vertical rectangle. No border shall be used on the Chevron Alignment sign.**

**If used, Chevron Alignment signs shall be installed on the outside of a turn or curve, in line with and at approximately a right angle to approaching traffic.**

**Option:**

A Chevron Alignment sign may be used on the far side of an intersection to inform drivers of a change of horizontal alignment for through traffic.

**Guidance:**

Spacing of Chevron Alignment signs should be such that the road user always has at least two in view, until the change in alignment eliminates the need for the signs.

Chevron Alignment signs should be visible for a sufficient distance to provide the road user with adequate time to react to the change in alignment.

**Section 2C.11 Truck Rollover Warning Sign (W1-13)****Option:**

A Truck Rollover Warning (W1-13) sign (see Figure 2C-1) may be used to warn drivers of vehicles with a high center of gravity, such as trucks, tankers, and recreational vehicles, of a curve or turn having geometric conditions that are prone to cause such vehicles to lose control and overturn.

**Standard:**

**When the Truck Rollover Warning (W1-13) sign is used, it shall be accompanied by an Advisory Speed (W13-1) plaque indicating the recommended speed for vehicles with a higher center of gravity.**

**Option:**

The Truck Rollover Warning sign may be displayed either as a static sign, a static sign supplemented by a flashing warning beacon, or as a changeable message sign activated by the detection of an approaching vehicle with a high center of gravity that is traveling in excess of the recommended speed for the condition.

**Support:**

The curved arrow on the Truck Rollover Warning sign shows the direction of roadway curvature. The truck tips in the opposite direction.

**Section 2C.12 Hill Signs (W7-1, W7-1a, W7-1b)****Guidance:**

The Hill (W7-1) sign (see Figure 2C-2) should be used in advance of a downgrade where the length, percent of grade, horizontal curvature, and/or other physical features require special precautions on the part of road users.

The Hill sign and supplemental grade (W7-3) plaque (see Section 2C.48) used in combination, or the W7-1b sign used alone, should be installed in advance of downgrades for the following conditions:


- A. 5% grade that is more than 900 m (3,000 ft) in length;
- B. 6% grade that is more than 600 m (2,000 ft) in length;
- C. 7% grade that is more than 300 m (1,000 ft) in length;
- D. 8% grade that is more than 230 m (750 ft) in length; or
- E. 9% grade that is more than 150 m (500 ft) in length.

These signs should also be installed for steeper grades or where crash experience and field observations indicate a need.

Supplemental plaques (see Section 2C.48) and larger signs should be used for emphasis or where special hill characteristics exist. On longer grades, the use of the Hill sign with a distance (W7-3a) plaque or the combination distance/grade (W7-3b) plaque at periodic intervals of approximately 1.6 km (1 mi) spacing should be considered.

**Standard:**

**When the percent grade is shown, the message X% plaque shall be placed below the inclined ramp/truck symbol (W7-1) or the word message HILL (W7-1a) sign.**

**Figure 2C-2. Vertical Grade Signs****Option:**

The word message HILL (W7-1a) sign may be used as an alternate to the symbol (W7-1) sign. The percent grade message may be included within these signs.

**Section 2C.13 Truck Escape Ramp Signs (W7-4 Series)****Guidance:**

Where applicable, truck escape (or runaway truck) ramp advance warning signs (see Figure 2C-2) should be located approximately 1.6 km (1 mi), and 800 m (0.5 mi) in advance of the grade, and of the ramp. A sign also should be placed at the gore. A RUNAWAY VEHICLES ONLY (R4-10) sign (see Figure 2B-8) should be installed near the ramp entrance to discourage other road users from entering. No Parking (R8-3) signs should be placed near the ramp entrance.

**Standard:**

**When truck escape ramps are installed, at least one of the W7-4 series signs shall be used.**

**Option:**

A SAND (W7-4d), GRAVEL (W7-4e), or PAVED (W7-4f) supplemental plaque (see Figure 2C-2) may be used to describe the ramp surface. Highway agencies may develop appropriate word message signs for the specific situation.

**Section 2C.14 HILL BLOCKS VIEW Sign (W7-6)****Option:**

A HILL BLOCKS VIEW (W7-6) sign (see Figure 2C-2) may be used in advance of a crest vertical curve to advise road users to reduce speed as they approach and traverse the hill as only limited stopping sight distance is available.

**Figure 2C-3. Miscellaneous Warning Signs**



**Guidance:**

When a HILL BLOCKS VIEW sign is used, it should be supplemented by an Advisory Speed (W13-1) plaque indicating the recommended speed for traveling over the hillcrest based on available stopping sight distance.

**Section 2C.15 ROAD NARROWS Sign (W5-1)**

**Guidance:**

A ROAD NARROWS (W5-1) sign (see Figure 2C-3) should be used in advance of a transition on two-lane roads where the pavement width is reduced abruptly to a width such that vehicles might not be able to pass without reducing speed.

## Option:

Additional emphasis may be provided by the use of object markers and delineators (see Chapters 3C and 3D). The Advisory Speed (W13-1) plaque (see Section 2C.46) may be used to indicate the recommended speed.

**Section 2C.16 NARROW BRIDGE Sign (W5-2)**

## Guidance:

A NARROW BRIDGE (W5-2) sign (see Figure 2C-3) should be used in advance of any bridge or culvert having a two-way roadway clearance width of 4.9 to 5.5 m (16 to 18 ft), or any bridge or culvert having a roadway clearance less than the width of the approach travel lanes.

Additional emphasis should be provided by the use of object markers, delineators, and/or pavement markings.

## Option:

A NARROW BRIDGE sign may be used in advance of a bridge or culvert on which the approach shoulders are narrowed or eliminated.

**Section 2C.17 ONE LANE BRIDGE Sign (W5-3)**

## Guidance:

A ONE LANE BRIDGE (W5-3) sign (see Figure 2C-3) should be used on two-way roadways in advance of any bridge or culvert:

- A. Having a clear roadway width of less than 4.9 m (16 ft); or
- B. Having a clear roadway width of less than 5.5 m (18 ft) when commercial vehicles constitute a high proportion of the traffic; or
- C. Having a clear roadway width of 5.5 m (18 ft) or less where the sight distance is limited on the approach to the structure.

Additional emphasis should be provided by the use of object markers, delineators, and/or pavement markings. However, as noted in Section 3B.01, centerline markings should not be applied within 45.8 m (150 ft) of a one-lane bridge.

**Section 2C.18 Divided Highway (Road) Sign (W6-1)**

## Guidance:

A Divided Highway (W6-1) symbol sign (see Figure 2C-3) should be used on the approaches to a section of highway (not an intersection or junction) where the opposing flows of traffic are separated by a median or other physical barrier.

## Option:

The word message DIVIDED HIGHWAY (W6-1a) or DIVIDED ROAD (W6-1b) sign (see Figure 2C-3) may be used as an alternate to the symbol sign.

**Section 2C.19 Divided Highway (Road) Ends Sign (W6-2)**

## Guidance:

A Divided Highway Ends (W6-2) symbol sign (see Figure 2C-3) should be used in advance of the end of a section of physically divided highway (not an intersection or junction) as a warning of two-way traffic ahead.

## Option:

The Two-Way Traffic (W6-3) symbol sign (see Section 2C.34) may be used to give warning and notice of the transition to a two-lane, two-way section.

The word message DIVIDED HIGHWAY ENDS (W6-2a) or DIVIDED ROAD ENDS (W6-2b) sign (see Figure 2C-3) may be used as an alternate to the symbol sign.

### **Section 2C.20 Double Arrow Sign (W12-1)**

Option:

The Double Arrow (W12-1) sign (see Figure 2C-3) may be used to advise road users that traffic is permitted to pass on either side of an island, obstruction, or gore in the roadway. Traffic separated by this sign may either rejoin or change directions.

Guidance:

If used on an island, the Double Arrow sign should be mounted near the approach end.

If used in front of a pier or obstruction, the Double Arrow sign should be mounted on the face of, or just in front of, the obstruction. Where stripe markings are used on the obstruction, they should be discontinued to leave a 75 mm (3 in) space around the outside of the sign.

### **Section 2C.21 DEAD END/NO OUTLET Signs (W14-1, W14-1a, W14-2, W14-2a)**

Option:

The DEAD END (W14-1) sign (see Figure 2C-3) may be used at the entrance of a single road or street that terminates in a dead end or cul-de-sac. The NO OUTLET (W14-2) sign may be used at the entrance to a road or road network from which there is no other exit.

The DEAD END (W14-1a) or NO OUTLET (W14-2a) signs (see Figure 2C-3) may be used in combination with the Street Name (D3-1) signs (see Section 2D.38) to warn turning traffic that the cross street ends in the direction indicated by the arrow.

At locations where the cross street does not have a name, the W14-1a or W14-2a signs may be used alone in place of a street name sign.

**Standard:**

**When the W14-1 or W14-2 sign is used, the sign shall be posted as near as practical to the entry point or at a sufficient advance distance to permit the road user to avoid the dead end or no outlet condition by turning off, if possible, at the nearest intersecting street.**

**The DEAD END (W14-1a) or NO OUTLET (W14-2a) signs shall not be used instead of the W14-1 or W14-2 signs where traffic can proceed straight through the intersection into the dead end street or no outlet area.**

### **Section 2C.22 Low Clearance Signs (W12-2 and W12-2p)**

**Standard:**

**The Low Clearance (W12-2) sign (see Figure 2C-3) shall be used to warn road users of clearances less than 300 mm (12 in) above the statutory maximum vehicle height.**

Guidance:

The actual clearance should be shown on the Low Clearance sign to the nearest 25 mm (1 in) not exceeding the actual clearance. However, in areas that experience changes in temperature causing frost action, a reduction, not exceeding 75 mm (3 in), should be used for this condition.

Where the clearance is less than the legal maximum vehicle height, the W12-2 sign with a supplemental distance plaque should be placed at the nearest intersecting road or wide point in the road at which a vehicle can detour or turn around.

In the case of an arch or other structure under which the clearance varies greatly, two or more signs should be used as necessary on the structure itself to give information as to the clearances over the entire roadway.

Clearances should be evaluated periodically, particularly when resurfacing operations have occurred.

Option:

The Low Clearance sign may be installed on or in advance of the structure. If a sign is placed on the structure, it may be a rectangular shape (W12-2p) with the appropriate legend (see Figure 2C-3).

### **Section 2C.23 BUMP and DIP Signs (W8-1, W8-2)**

Guidance:

BUMP (W8-1) and DIP (W8-2) signs (see Figure 2C-4) should be used to give warning of a sharp rise or depression in the profile of the road.

Option:

These signs may be supplemented with an Advisory Speed plaque (see Section 2C.46).

**Standard:**

**The DIP sign shall not be used at a short stretch of depressed alignment that might momentarily hide a vehicle.**

Guidance:

A short stretch of depressed alignment that might momentarily hide a vehicle should be treated as a no-passing zone when centerline striping is provided on a two-lane or three-lane road (see Section 3B.02).

### **Section 2C.24 SPEED HUMP Sign (W17-1)**

Guidance:

The SPEED HUMP (W17-1) sign (see Figure 2C-4) should be used to give warning of a vertical deflection in the roadway that is designed to limit the speed of traffic.

If used, the SPEED HUMP sign should be supplemented by an Advisory Speed plaque (see Section 2C.46).

Option:

If a series of speed humps exists in close proximity, an Advisory Speed plaque may be eliminated on all but the first SPEED HUMP sign in the series.

The legend SPEED BUMP may be used instead of the legend SPEED HUMP on the W17-1 sign.

.Support:

Speed humps generally provide more gradual vertical deflection than speed bumps. Speed bumps limit the speed of traffic more severely than speed humps. However, this difference in engineering terminology is not well known by the public, so for signing purposes the terms are interchangeable.

### **Section 2C.25 PAVEMENT ENDS Sign (W8-3)**


Guidance:

A PAVEMENT ENDS (W8-3) word message sign (see Figure 2C-4) should be used where a paved surface changes to either a gravel treated surface or an earth road surface.

Option:

An Advisory Speed plaque (see Section 2C.46) may be used when the change in roadway condition requires a reduced speed.

**Figure 2C-4. Roadway Condition and Advance Traffic Control Signs**



\*An optional word message sign is shown in the "Sign Design Manual" (SDM).

**Section 2C.26 Shoulder Signs (W8-4, W8-9, W8-9a)**

Option:

The SOFT SHOULDER (W8-4) sign (see Figure 2C-4) may be used to warn of a soft shoulder condition.

The LOW SHOULDER (W8-9) sign (see Figure 2C-4) may be used to warn of a shoulder condition where there is an elevation difference of less than 75 mm (3 in) between the shoulder and the travel lane.

Guidance:

The SHOULDER DROP OFF (W8-9a) sign (see Figure 2C-4) should be used when an unprotected shoulder drop-off, adjacent to the travel lane, exceeds 75 mm (3 in) in depth for a significant continuous length along the roadway, based on engineering judgment.

Additional shoulder signs should be placed at appropriate intervals along the road where the condition continually exists.

**Standard:**

**When used, shoulder signs shall be placed in advance of the condition (see Table 2C-4).**

**Section 2C.27 Slippery When Wet Sign (W8-5)****Option:**

The Slippery When Wet (W8-5) sign (see Figure 2C-4) may be used to warn that a slippery condition might exist.

**Guidance:**

When used, a Slippery When Wet sign should be placed in advance of the beginning of the affected section (see Table 2C-4), and additional signs should be placed at appropriate intervals along the road where the condition exists.

**Section 2C.28 BRIDGE ICES BEFORE ROAD Sign (W8-13)****Option:**

A BRIDGE ICES BEFORE ROAD (W8-13) sign (see Figure 2C-4) may be used in advance of bridges to advise bridge users of winter weather conditions.

The BRIDGE ICES BEFORE ROAD sign may be removed or covered during seasons of the year when its message is not relevant.

**Section 2C.29 Advance Traffic Control Signs (W3-1, W3-2, W3-3, W3-4)****Standard:**

**The Advance Traffic Control symbol signs (see Figure 2C-4) include the Stop Ahead (W3-1), Yield Ahead (W3-2), and Signal Ahead (W3-3) signs. These signs shall be installed on an approach to a primary traffic control device that is not visible for a sufficient distance to permit the road user to respond to the device (see Table 2C-4). The visibility criteria for a traffic control signal shall be based on having a continuous view of at least two signal faces for the distance specified in Table 4D-1.**

**Support:**

Permanent obstructions causing the limited visibility might include roadway alignment or structures. Intermittent obstructions might include foliage or parked vehicles.

**Guidance:**

Where intermittent obstructions occur, engineering judgment should determine the treatment to be implemented.

**Option:**

An Advance Traffic Control sign may be used for additional emphasis of the primary traffic control device, even when the visibility distance to the device is satisfactory.

Word messages (W3-1a, W3-2a, W3-3a) may be used as alternates to the Advance Traffic Control symbol signs.


A supplemental street name plaque (see Section 2C.49) may be installed above or below an Advance Traffic Control sign.

A warning beacon may be used with an Advance Traffic Control sign.

A BE PREPARED TO STOP (W3-4) sign (see Figure 2C-4) may be used to warn of stopped traffic caused by a traffic control signal or in advance of a section of roadway that regularly experiences traffic congestion.

**Standard:**

**When a BE PREPARED TO STOP sign is used in advance of a traffic control signal, it shall be used in addition to a Signal Ahead sign.**

**Figure 2C-5. Advisory Speed and Speed Reduction Signs****Option:**

The BE PREPARED TO STOP sign may be supplemented with a warning beacon (see Section 4K.03).

**Guidance:**

When the warning beacon is interconnected with a traffic control signal or queue detection system, the BE PREPARED TO STOP sign should be supplemented with a WHEN FLASHING plaque.

**Section 2C.30 Speed Reduction Signs (W3-5, W3-5a)****Guidance:**

A Speed Reduction (W3-5 or W3-5a) sign (see Figure 2C-5) should be used to inform road users of a reduced speed zone when engineering judgment indicates the need for advance notice to comply with the posted speed limit ahead.

**Standard:**


**If used, Speed Reduction signs shall be followed by a Speed Limit (R2-1) sign installed at the beginning of the zone where the speed limit applies.**

**The speed limit displayed on the Speed Reduction sign shall be identical to the speed limit displayed on the subsequent Speed Limit sign.**

**Section 2C.31 Merge Signs (W4-1, W4-5)****Option:**

A Merge (W4-1) sign (see Figure 2C-6) may be used to warn road users on the major roadway that merging movements might be encountered in advance of a point where lanes from two separate roadways converge as a single traffic lane and no turning conflict occurs.

A Merge sign may also be installed on the side of the entering roadway to warn road users on the entering roadway of the merge condition.

**Figure 2C-6. Merging and Passing Signs****Guidance:**

The Merge sign should be installed on the side of the major roadway where merging traffic will be encountered and in such a position as to not obstruct the road user's view of entering traffic.

Where two roadways of approximately equal importance converge, a Merge sign should be placed on each roadway.

When a Merge sign is to be installed on an entering roadway that curves before merging with the major roadway, such as a ramp with a curving horizontal alignment as it approaches the major roadway, the Entering Roadway Merge (W4-5) sign (see Figure 2C-6) should be used to better portray the actual geometric conditions to road users on the entering roadway.

The Merge sign should not be used where two roadways converge and merging movements are not required.

The Merge sign should not be used in place of a Lane Ends sign where lanes of traffic moving on a single roadway must merge because of a reduction in the actual or usable pavement width (see Section 2C.33).

**Section 2C.32 Added Lane Signs (W4-3, W4-6)****Guidance:**

The Added Lane (W4-3) sign (see Figure 2C-6) should be installed in advance of a point where two roadways converge and merging movements are not required. When possible, the Added Lane sign should be placed such that it is visible from both roadways; if this is not possible, an Added Lane sign should be placed on the side of each roadway.

When an Added Lane sign is to be installed on a roadway that curves before converging with another roadway that has a tangent alignment at the point of convergence, the Entering Roadway Added Lane (W4-6) sign (see Figure 2C-6) should be used to better portray the actual geometric conditions to road users on the curving roadway.

### **Section 2C.33 Lane Ends Signs (W4-2, W9-1, W9-2)**

#### **Guidance:**

The LANE ENDS MERGE LEFT (RIGHT) (W9-2) word sign, or the Lane Ends (W4-2) symbol sign, should be used to warn of the reduction in the number of traffic lanes in the direction of travel on a multi-lane highway (see Figure 2C-6).

#### **Option:**

The RIGHT (LEFT) LANE ENDS (W9-1) word sign (see Figure 2C-6) may be used in advance of the Lane Ends (W4-2) symbol sign or the LANE ENDS MERGE LEFT (RIGHT) (W9-2) word sign as additional warning or to emphasize that the traffic lane is ending and that a merging maneuver will be required.

On one-way streets or on divided highways where the width of the median will permit, two Lane Ends signs may be placed facing approaching traffic, one on the right side and the other on the left side or median.

The reduction in the number of traffic lanes may also be delineated with roadway edge lines (see Section 3B.09) and/or roadway delineation (see Chapter 3D).

#### **Guidance:**

Where an extra lane has been provided for slower moving traffic (see Section 2B.32), a Lane Ends word sign or a Lane Ends (W4-2) symbol sign should be installed in advance of the end of the extra lane.

Lane Ends signs should not be installed in advance of the end of an acceleration lane.

### **Section 2C.34 Two-Way Traffic Sign (W6-3)**

#### **Guidance:**

A Two-Way Traffic (W6-3) sign (see Figure 2C-6) should be used to warn road users of a transition from a multi-lane divided section of roadway to a two-lane, two-way section of roadway.

A Two-Way Traffic (W6-3) sign with an AHEAD (W16-9p) plaque (see Figure 2C-6) should be used to warn road users of a transition from a one-way street to a two-lane, two-way section of roadway (see Figure 2B-12, Sheet 2 of 2).

#### **Option:**

The Two-Way Traffic sign may be used at intervals along a two-lane, two-way roadway and may be used to supplement the Divided Highway (Road) Ends (W6-2) sign discussed in Section 2C.19.

### **Section 2C.35 NO PASSING ZONE Sign (W14-3)**

#### **Standard:**

The NO PASSING ZONE (W14-3) sign (see Figure 2C-6) shall be a pennant-shaped isosceles triangle with its longer axis horizontal and pointing to the right. When used, the NO PASSING ZONE sign shall be installed on the left side of the roadway at the beginning of no-passing zones identified by either pavement markings or DO NOT PASS signs or both (see Sections 2B.29 and 3B.02).

### **Section 2C.36 Advisory Exit, Ramp, and Curve Speed Signs (W13-2, W13-3, W13-5)**

#### **Standard:**

Advisory Exit, Ramp, and Curve Speed signs shall be vertical rectangles. The advisory Exit Speed (W13-2), Ramp Speed (W13-3), or Curve Speed (W13-5) signs (see Figure 2C-5) shall be used where engineering judgment indicates the need to advise road users of the recommended speed on an exit, a ramp, or a curve.

**Guidance:**

When used, the Exit Speed sign should be installed along the deceleration lane.

The Exit Speed sign should be visible in time for the road user to make a reasonably safe slowing and exiting maneuver.

The Ramp Speed sign should be visible in time for the road user to reduce to the recommended speed.

**Option:**

One or more Ramp Speed signs may be used along the deceleration lane, beyond the gore, or and along the ramp (see Figure 2C-7). Based on engineering judgment, the Ramp Speed sign may be installed on the inside or outside of the curve to enhance its visibility.

A Turn (W1-1) or Curve (W1-2) sign with an Advisory Speed (W13-1) plaque may be used in place of a Ramp Speed sign if it is located such that it clearly does not apply to drivers on the main roadway.

A Curve Speed sign may be used at and beyond the beginning of a curve following a Horizontal Alignment and Advisory Speed sign combination, or when there is a need to remind road users of the recommended speed, or where the recommended speed changes because of a change in curvature (see Section 2C.06). Based on engineering judgment, the Curve Speed sign may be installed on the inside or outside of the curve to enhance its visibility.

The advisory speed may be the 85th-percentile speed of free-flowing traffic, the speed corresponding to a 16-degree ball bank indicator reading, or the speed otherwise determined by an engineering study because of unusual circumstances.

**Support:**

A 10-degree ball-bank indicator reading, formerly used in determining advisory speeds, is based on research from the 1930s. In modern vehicles, the 85th-percentile speed on curves approximates a 16-degree reading. This is the speed at which most drivers' judgment recognizes incipient instability along a ramp or curve.

**Section 2C.37 Intersection Warning Signs (W2-1 through W2-6)****Option:**

A Cross Road (W2-1) symbol, Side Road (W2-2 or W2-3) symbol, T-Symbol (W2-4), or Y-Symbol (W2-5) sign (see Figure 2C-8) may be used in advance of an intersection to indicate the presence of an intersection and the possibility of turning or entering traffic. The Circular Intersection (W2-6) symbol sign accompanied by an educational TRAFFIC CIRCLE (W16-12p) plaque (see Figure 2C-8) may be installed in advance of a circular intersection.

The relative importance of the intersecting roadways may be shown by different widths of lines in the symbol.

An advance street name plaque (see Section 2C.49) may be installed above or below an Intersection Warning sign.


**Guidance:**


The Intersection Warning sign should illustrate and depict the general configuration of the intersecting roadway, such as cross road, side road, T-intersection, or Y-intersection.

Intersection Warning signs, other than the Circular Intersection symbol (W2-6) sign and the T-intersection symbol (W2-4) sign should not be used on approaches controlled by STOP signs, YIELD signs, or signals. The Circular Intersection symbol (W2-6) sign should be installed on the approach to a YIELD sign controlled roundabout intersection.

Where the side roads are not opposite of each other, the symbol for the intersection should indicate a slight offset.

**Figure 2C-7. Example of Advisory Speed Signing for an Exit Ramp**



**Figure 2C-8. Intersection Warning Signs****Section 2C.38 Two-Direction Large Arrow Sign (W1-7)****Standard:**

The Two-Direction Large Arrow (W1-7) sign (see Figure 2C-8) shall be a horizontal rectangle.

If used, it shall be installed on the far side of a T-intersection in line with, and at approximately a right angle to, approaching traffic.

The Two-Direction Large Arrow sign shall not be used where there is no change in the direction of travel such as at the beginnings and ends of medians or at center piers.

**Guidance:**

The Two-Direction Large Arrow sign should be visible for a sufficient distance to provide the road user with adequate time to react to the intersection configuration.

**Section 2C.39 Traffic Signal Signs (W25-1, W25-2)****Standard:**

Unless a separate left-turn signal face is provided and is operated as described in Section 4D.06, if the possibility exists that a CIRCULAR YELLOW signal indication could be displayed to an approach from which drivers are turning left permissively without the simultaneous display of a CIRCULAR YELLOW signal indication to the opposing approach (see Section 4D.05), either a W25-1 or a W25-2 sign (see Figure 2C-8) shall be installed near the left-most signal head. If the operation described in the previous sentence occurs on a cycle-by-cycle basis during all times that the traffic control signal is operated in the stop-and-go mode, the ONCOMING TRAFFIC HAS EXTENDED GREEN (W25-1) sign shall be used; if the operation occurs only occasionally, the ONCOMING TRAFFIC MAY HAVE EXTENDED GREEN (W25-2) sign shall be used.

### **Section 2C.40 Vehicular Traffic Signs (W8-6, W11-1, W11-5, W11-5a, W11-8, W11-10, W11-11, W11-12p, W11-14)**

#### Option:

Vehicular Traffic (W8-6, W11-1, W11-5, W11-5a, W11-8, W11-10, W11-11, W11-12p, W11-14) signs (see Figure 2C-9) may be used to alert road users to locations where unexpected entries into the roadway by trucks, bicyclists, farm vehicles, emergency vehicles, golf carts, horse-drawn vehicles, or other vehicles might occur. The TRUCK CROSSING (W8-6) word message sign may be used as an alternate to the Truck Crossing symbol (W11-10) sign.

#### Support:

These locations might be relatively confined or might occur randomly over a segment of roadway.

#### Guidance:

Vehicular Traffic signs should be used only at locations where the road user's sight distance is restricted, or the condition, activity, or entering traffic would be unexpected.

If the condition or activity is seasonal or temporary, the Vehicular Traffic sign should be removed or covered when the condition or activity does not exist.

#### Option:

Supplemental plaques (see Section 2C.43) with legends such as AHEAD, XX FEET, NEXT XX MILES, or SHARE THE ROAD may be mounted below Vehicular Traffic signs to provide advance notice to road users of unexpected entries.

#### Standard:

**The Emergency Vehicle (W11-8) sign with the EMERGENCY SIGNAL AHEAD (W11-12p) supplemental plaque (see Figure 2C-9) shall be placed in advance of all emergency-vehicle traffic control signals (see Chapter 4F).**

#### Option:

The Emergency Vehicle (W11-8) sign, or a word message sign indicating the type of emergency vehicle (such as rescue squad), may be used in advance of the emergency vehicle station when no emergency-vehicle traffic control signal is present.

### **Section 2C. 41 Nonvehicular Traffic Signs (W11-2, W11-3, W11-4, W11-6, W11-7, W11-9)**

#### Option:

Nonvehicular signs (see Figure 2C-10) may be used to alert road users in advance of locations where unexpected entries into the roadway or shared use of the roadway by pedestrians, animals, and other crossing activities might occur.

#### Support:

These conflicts might be relatively confined, or might occur randomly over a segment of roadway.

#### Option:

When used in advance of a crossing, Nonvehicular warning signs may be supplemented with supplemental plaques (see Section 2C.43) with the legend AHEAD, XX FEET, or NEXT XX MILES to provide advance notice to road users of crossing activity.

#### Standard:

**When used at the crossing, Nonvehicular signs shall be supplemented with a diagonal downward pointing arrow (W16-7p) plaque (see Figure 2C-11) showing the location of the crossing.**

**Figure 2C-9. Vehicular Traffic Signs**



W8-6



W11-1



W11-5



W11-5a



W11-8



W11-10



W11-11



W11-12p



W11-14

**Figure 2C-10. Nonvehicular Traffic Signs**



W11-2



W11-3



W11-4



W11-6




W11-7



W11-9



W15-1

**Figure 2C-11. Supplemental Warning Plaques****Option:**

The crossing location may be defined with crosswalk markings (see Section 3B.17).

Pedestrian, Bicycle, and School signs and their related supplemental plaques may have a fluorescent yellow-green background with a black legend and border.

**Guidance:**

When a fluorescent yellow-green background is used, a systematic approach featuring one background color within a zone or area should be used. The mixing of standard yellow and fluorescent yellow-green backgrounds within a selected site area should be avoided.

Nonvehicular signs should be used only at locations where the crossing activity is unexpected or at locations not readily apparent.

**Section 2C.42 Playground Sign (W15-1)****Option:**

The Playground (W15-1) sign (see Figure 2C-10) may be used to give advance warning of a designated children's playground that is located adjacent to the road. The Playground sign may have a fluorescent yellow-green background with a black legend and border.

**Guidance:**

If the access to the playground area requires a roadway crossing, the application of crosswalk pavement markings (see Section 3B.17) and Nonvehicular signs (see Section 2C.41) should be considered.

**Section 2C.43 Use of Supplemental Plaques****Option:**

A supplemental plaque may be displayed with a warning sign when engineering judgment indicates that road users require additional information beyond that contained in the main message of the warning sign.

**Standard:**

**Supplemental plaques shall be used only in combination with warning or regulatory signs. They shall not be mounted alone or displayed alone. If used, a supplemental plaque shall be installed on the same post(s) as the warning sign.**

**Section 2C.44 Design of Supplemental Plaques****Standard:**

**A supplemental plaque shall have the same color legend, border, and background as the warning sign with which it is displayed. Supplemental plaques shall be square or rectangular.**

**Section 2C.45 Distance Plaques (W16-2 Series, W16-3 Series, W16-4, W7-3a)****Option:**

The Distance Ahead (W16-2 series and W16-3 series) plaques (see Figure 2C-11) may be used to inform the road user of the distance to the condition indicated by the warning sign.

The Next Distance (W7-3a and W16-4) plaques (see Figures 2C-2 and 2C-11) may be used to inform road users of the length of roadway over which the condition indicated by the warning sign exists.

**Section 2C.46 Advisory Speed Plaque (W13-1)****Option:**

The Advisory Speed (W13-1) plaque (see Figure 2C-5) may be used to supplement any warning sign to indicate the advisory speed for a condition.

**Standard:**

**The Advisory Speed plaque shall be used where an engineering study indicates a need to advise road users of the advisory speed for a condition.**

**If used, the Advisory Speed plaque shall carry the message XX MPH. The speed shown shall be a multiple of 5 mph.**

**Except in emergencies or when the condition is temporary, an Advisory Speed plaque shall not be installed until the advisory speed has been determined by an engineering study.**

**Guidance:**

Because changes in conditions, such as roadway geometrics, surface characteristics, or sight distance, might affect the advisory speed, each location should be periodically evaluated and the Advisory Speed plaque changed if necessary.

**Option:**

The advisory speed may be the 85th-percentile speed of free-flowing traffic, the speed corresponding to a 16-degree ball bank indicator reading, or the speed otherwise determined by an engineering study because of unusual circumstances.

**Support:**

A 10-degree ball-bank indicator reading, formerly used in determining advisory speeds, is based on research from the 1930s. In modern vehicles, the 85th-percentile speed on curves approximates a 16-degree

reading. This is the speed at which most drivers' judgment recognizes incipient instability along a ramp or curve.

### **Section 2C.47 Supplemental Arrow Plaques (W16-5p, W16-6p, W16-7p)**

Guidance:

If the condition indicated by a warning sign is located on an intersecting road and the distance between the intersection and condition is not sufficient to provide adequate advance placement of the warning sign, a Supplemental Arrow (W16-5p, W16-6p, W16-7p) plaque (see Figure 2C-11) should be used below the warning sign.

**Standard:**

**Supplemental Arrow plaques (see Figure 2C-11) shall have the same legend design as the Advance Turn Arrow and Directional Arrow auxiliary signs (see Sections 2D.25 and 2D.26) except that they shall have a black legend and border on a yellow or fluorescent yellow-green background, as appropriate.**

### **Section 2C.48 Hill-Related Plaques (W7-2 Series, W7-3 Series)**

Guidance:

Hill-Related (W7-2 series, W7-3 series) plaques (see Figure 2C-11) or other appropriate legends and larger signs should be used for emphasis or where special hill characteristics exist.

On longer grades, the use of the distance plaque (W7-3a or W7-3b) at periodic intervals of approximately 1.6 km (1 mi) spacing should be considered.

### **Section 2C.49 Advance Street Name Plaques (W16-8, W16-8a)**

Option:

An Advance Street Name (W16-8 or W16-8a) plaque (see Figure 2C-11) may be used with any Intersection sign (W2 series) or Advance Traffic Control (W3 series) sign to identify the name of the intersecting street.

### **Section 2C.50 CROSS TRAFFIC DOES NOT STOP Plaque (W4-4p)**

Option:

The CROSS TRAFFIC DOES NOT STOP (W4-4p) plaque (see Figure 2C-8) may be used in combination with a STOP sign when engineering judgment indicates that conditions are present that are causing or could cause drivers to misinterpret the intersection as an all-way stop.

Alternate messages such as TRAFFIC FROM LEFT (RIGHT) DOES NOT STOP or ONCOMING TRAFFIC DOES NOT STOP may be used on the W4-4p plaque when such messages more accurately describe the traffic controls established at the intersection.

**Standard:**

**If the W4-4p plaque is used, it shall be installed below the STOP sign.**

### **Section 2C.51 SHARE THE ROAD Plaque (W16-1)**

Option:

In situations where there is a need to warn drivers to watch for other slower forms of transportation traveling along the highway, such as bicycles, golf carts, horse-drawn vehicles, or farm machinery, a SHARE THE ROAD (W16-1) plaque (see Figure 2C-11) may be used as an alternative to legends such as AHEAD (W16-9p), NEXT XX FT (W16-4), and NEXT XX MILES (W7-3a).

**Section 2C.52 High-Occupancy Vehicle (HOV) Plaque (W16-11)****Option:**

In situations where there is a need to warn drivers in an HOV lane of a specific condition, an HOV (W16-11) plaque (see Figure 2C-11) may be used. The HOV plaque may be used to differentiate a warning sign specific for HOV lanes when the sign is also visible to traffic on the adjoining general purpose roadway. Among the warning signs that may be possible applications of the HOV plaque are the Advisory Speed, Advisory Exit Speed, Added Lane, and Merge signs.

The diamond symbol may be used instead of the word message HOV on the W16-11 plaque. When appropriate, the words LANE or ONLY may be used on this plaque.

**Section 2C.53 PHOTO ENFORCED Plaque (W16-10)****Option:**

A PHOTO ENFORCED (W16-10) plaque (see Figure 2C-11) may be mounted below a warning sign to advise road users that the regulations associated with the condition being warned about (such as a traffic control signal or a toll plaza) are being enforced by photographic equipment.

**Standard:**

**If used below a warning sign, the PHOTO ENFORCED plaque shall be a rectangle with a black legend and border on a yellow background.**

## CHAPTER 2D. GUIDE SIGNS—CONVENTIONAL ROADS

### Section 2D.01 Scope of Conventional Road Guide Sign Standards

#### Standard:

**Standards for conventional road guide signs shall apply to any road or street other than low-volume roads (as defined in Section 5A.01), expressways, and freeways.**

### Section 2D.02 Application

#### Support:

Guide signs are essential to direct road users along streets and highways, to inform them of intersecting routes, to direct them to cities, towns, villages, or other important destinations, to identify nearby rivers and streams, parks, forests, and historical sites, and generally to give such information as will help them along their way in the most simple, direct manner possible.

Chapter 2A addresses placement, location, and other general criteria for signs.

### Section 2D.03 Color, Retroreflection, and Illumination

#### Support:

Requirements for illumination, retroreflection, and color are stated under the specific headings for individual guide signs or groups of signs. General provisions are given in Sections 2A.08, 2A.09, and 2A.11.

#### Standard:

**Except where otherwise specified herein for individual signs or groups of signs, guide signs on streets and highways shall have a white message and border on a green background. All messages, borders, and legends shall be retroreflective and all backgrounds shall be retroreflective or illuminated.**

#### Support:

Color coding is sometimes used to help road users distinguish between multiple potentially confusing destinations. Examples of valuable uses of color coding include guide signs for roadways approaching or inside an airport property with multiple terminals serving multiple airlines, and wayfinding signs for various traffic generator destinations within a community or area.

#### Standard:

**Different color sign backgrounds shall not be used to provide color coding of destinations. The color coding shall be accomplished by the use of different colored square or rectangular panels on the face of the guide signs.**

#### Option:

The different colored panels may include a black or white (whichever provides the better contrast with the panel color) letter, numeral, or other appropriate designation to identify the airport terminal or other destination.

#### Support:

Two examples of color-coded sign assemblies are shown in Figure 2D-1.

### Section 2D.04 Size of Signs

#### Support:

For most guide signs, the legends are so variable that a standardized size is not appropriate. The sign size is determined primarily by the length of the message, and the size of lettering and spacing necessary for proper legibility. However, for signs with standardized designs, such as route signs, it is practical to use the prescribed sizes that are given in the "Sign Design Manual" (SDM) (see Section 1A.11).

## Figure 2D-1. Examples of Color-Coded Destination Guide Signs

### a - Freeway or Expressway – Airport Terminals



### b - Conventional Road or Street – Urban Areas



#### Option:

Reduced letter height, reduced interline spacing, and reduced edge spacing may be used on guide signs if sign size must be limited by factors such as lane width or vertical or lateral clearance.

#### Guidance:

Reduced spacing between the letters or words on a line of legend should not be used as a means of reducing the overall size of a guide sign, except where determined necessary by engineering judgment to meet unusual lateral space constraints. In such cases, the legibility distance of the sign legend should be the primary consideration in determining whether to reduce the spacing between the letters or the words or between the words and the sign border, or to reduce the letter height.

When a reduction in the prescribed size is necessary, the design used should be as similar as possible to the design for the standard size.

### Section 2D.05 Lettering Style

#### Standard:

The design of upper-case letters, lower-case letters, capital letters, numerals, route shields, and spacing shall be as provided in the “Sign Design Manual” (SDM) (see Section 1A.11).

The lettering for names of places, streets, and highways on conventional road guide signs shall be a combination of lower-case letters with initial upper-case letters, or all capital letters (see Section 2A.14). When a combination of upper- and lower-case letters are used, the initial upper-case letters shall be approximately 1.33 times the “loop” height of the lower-case letters.

All other word legends on conventional road guide signs shall be in capital letters.

## **Section 2D.06 Size of Lettering**

### **Support:**

Sign legibility is a direct function of letter size and spacing. Legibility distance has to be sufficient to give road users enough time to read and comprehend the sign. Under optimum conditions, a guide sign message can be read and understood in a brief glance. The legibility distance includes a reasonable safety factor for inattention, blocking of view by other vehicles, unfavorable weather, inferior eyesight, or other causes for delayed or slow reading. Where conditions permit, repetition of guide information on successive signs gives the road user more than one opportunity to obtain the information needed.

### **Standard:**

**Design layouts for conventional road guide signs showing interline spacing, edge spacing, and other specification details shall be as shown in the SDM (see Section 1A.11).**

**The principal legend on guide signs shall be in letters and numerals at least 150 mm (6 in) in height for all capital letters, or a combination of 150 mm (6 in) in height for upper-case letters with 113 mm (4.5 in) in height for lower-case letters. On low-volume roads (as defined in Section 5A.01), and on urban streets with speeds of 40 km/h (25 mph) or less, the principal legend shall be in letters at least 100 mm (4 in) in height.**

### **Guidance:**

Lettering sizes should be consistent on any particular class of highway.

The minimum lettering sizes specified herein should be exceeded where conditions indicate a need for greater legibility.

## **Section 2D.07 Amount of Legend**

### **Support:**

The longer the legend on a guide sign, the longer it will take road users to comprehend it, regardless of letter size.

### **Guidance:**

Guide signs should be limited to three lines of principal legend. Where two or more signs are included in the same overhead display, the amount of legend should be minimized. The principal legend should include only place names, route numbers, and street names.

### **Option:**

Symbols, action information, cardinal directions, and exit numbers may be used in addition to the principal legend where sign space is available.

## **Section 2D.08 Arrows**


### **Support:**

Arrows are used for lane assignment and to indicate the direction toward designated routes or destinations. Figure 2D-2 shows the up-arrow and the down-arrow designs that have been approved for use on guide signs. Detailed drawings of these arrows are shown in the SDM (see Section 1A.11).

### **Standard:**

**On overhead signs where it is desirable to indicate a lane to be followed, a down arrow shall point downward toward the center of that lane. Down arrows shall be used only on overhead guide signs that restrict the use of specific lanes to traffic bound for the destination(s) and/or route(s) indicated by these arrows. Down arrows shall not be used unless an arrow can be pointed to each lane that can be used to reach the destination shown on the sign.**

**Figure 2D-2. Arrows for Use on Guide Signs**



**Where a roadway is leaving the through lanes, an up arrow shall point upward at an angle representative of the alignment of the exit roadway.**

Guidance:

Arrows used on guide signs to indicate the directions toward designated routes or destinations should be pointed at the appropriate angle to clearly convey the direction to be taken. A horizontally oriented up-arrow design should be used at right-angle intersections.

On a ground-mounted guide sign, a directional arrow for a straight-through movement should point upward. For a turn, the arrow on a guide sign should point upward and at an angle related to the sharpness of the turn.

Option:

Arrows may be placed below the principal sign legend or on the appropriate side of the legend.

Guidance:

At an exit, an arrow should be placed at the side of the sign which will reinforce the movement of exiting traffic. The up-arrow design should be used.

The width across the arrowhead should be at least equal to the height of the largest letter on the sign. For short downward pointing arrows on overhead signs, the width across the arrowhead should be 1.75 times the letter height.

Diagrammatic signing used on conventional roads should follow the principles set forth in Section 2E.19.

### **Section 2D.09 Numbered Highway Systems**

Support:

The purpose of numbering and signing highway systems is to identify routes and facilitate travel.

The Interstate and United States (U.S.) highway systems are numbered by the American Association of State Highway and Transportation Officials (AASHTO) upon recommendations of the State highway organizations because the respective States own these systems. State and County road systems are numbered by the appropriate authorities.

The basic policy for numbering the U.S. and Interstate highway systems is contained in the following Purpose and Policy statements published by AASHTO (see the Preface for AASHTO's address):

- A. "Establishment and Development of United States Numbered Highways"; and
- B. "Establishment of a Marking System of the Routes Comprising the National System of Interstate and Defense Highways."

Guidance:

The principles of these policies should be followed in establishing the above highway systems and any other systems, with effective coordination between adjacent jurisdictions. Care should be taken to avoid the use of numbers or other designations that have been assigned to Interstate, U.S., or State Routes in the same geographic area. Overlapping numbered routes should be kept to a minimum.

**Standard:**

**Route systems shall be given preference in this order: Interstate, United States, State, and County. The preference shall be given by installing the highest-priority legend on the top or the left of the sign panel.**

### **Section 2D.10 Route Signs and Auxiliary Signs**

Support:

Signing for National Scenic Byways is addressed in Section 2D.52 and signing for the Ohio Byways program is discussed in Section 2D.53. Section 2D.49 addresses named highways.

**Standard:**

**All numbered highway routes shall be identified by route signs and auxiliary signs.**

**The signs for each system of numbered highways, which are distinctive in shape and color, shall be used only on that system and the approaches thereto.**

**Route signs and any auxiliary signs that accompany them shall be retroreflective.**

Option:

Route signs and auxiliary signs may be proportionally enlarged where greater legibility is needed.

Support:

Route signs are typically mounted in assemblies with auxiliary signs.

### **Section 2D.11 Design of Route Signs**

**Standard:**

**The SDM (see Section 1A.11) shall be used for designing route signs. Other route sign designs shall be established by the authority having jurisdiction.**

**Interstate Route signs (see Figure 2D-3) shall consist of a cutout shield, with the route number in white letters on a blue background, the word INTERSTATE in white capital letters on a red background, and a white border. This sign shall be used on all Interstate routes and in connection with route sign assemblies on intersecting highways.**

**A 600 x 600 mm (24 x 24 in) minimum sign size shall be used for Interstate route numbers with one or two digits, and a 750 x 600 mm (30 x 24 in) minimum sign size shall be used for Interstate route numbers having three digits.**

**Off-Interstate Business Route signs (see Figure 2D-3) shall consist of a cutout shield carrying the number of the connecting Interstate route and the words BUSINESS and either LOOP or SPUR in capital letters. The legend and border shall be white on a green background, and the shield shall be the same shape and dimensions as the Interstate Route sign. In no instance shall the word INTERSTATE appear on the Off-Interstate Business Route sign.**

**Option:**

The Off-Interstate Business Route sign may be used on a major highway that is not a part of the Interstate system, but one that serves the business area of a City from an interchange on the system. When used on a green guide sign, a white square or rectangle may be placed behind the shield to improve contrast.

**Standard:**

**U.S. Route signs (see Figure 2D-3) shall consist of black numerals on a white shield surrounded by a black background without a border. This sign shall be used on all U.S. routes and in connection with route sign assemblies on intersecting highways.**

**A 600 x 600 mm (24 x 24 in) minimum sign size shall be used for U.S. route numbers with one or two digits, and a 750 x 600 mm (30 x 24 in) minimum sign size shall be used for U.S. route numbers having three digits.**

**State Route signs shall consist of black numerals on a white representation of the State of Ohio surrounded by a black background without a border. A design detail is provided in the SDM (see Section 1A.11). This sign shall be used on all State Routes and in connection with route sign assemblies on intersecting highways.**

**A 600 x 600 mm (24 x 24 in) minimum sign size shall be used for State Route numbers with one or two digits, and a 750 x 600 mm (30 x 24 in) minimum sign size shall be used for State Route numbers having three digits.**

**Standard:**

**If County road authorities elect to establish and identify a special system of important County roads, a statewide policy for such signing shall be established that includes a uniform numbering system to uniquely identify each route. The County Route (M1-6) sign (see Figure 2D-3) shall consist of a pentagon shape with a yellow County name and route number and border on a blue background. County Route signs displaying two digits or the equivalent (letter and numeral, or two letters) shall be a minimum size of 450 x 450 mm (18 x 18 in); those carrying three digits or the equivalent shall be a minimum size of 600 x 600 mm (24 x 24 in).**

**If a jurisdiction uses letters instead of numbers to identify routes, all references to numbered routes in this Chapter shall be interpreted to also include lettered routes.**

**Guidance:**

If used with other route signs in common assemblies, the County Route sign should be of a size compatible with that of the other route signs.

**Option:**

When used on a green guide sign, a yellow square or rectangle may be placed behind the County Route sign to improve contrast.

The alternate County Route (M1-H6a) sign may be used on County Roads, and the Township Route (M1-H6b) sign may be used on Township Roads. These signs have a minimum size of 450 x 450 mm (18 x 18 in) for two and three digit routes (see Figure 2D-3).

**Guidance:**

If used with other route signs in common assemblies, the alternate design County Route sign and Township Route sign should be of a size compatible with that of the other route signs.

**Standard:**

**Route signs (see Figure 2D-3) for park and forest roads shall be designed with adequate distinctiveness and legibility and of a size compatible with other route signs used in common assemblies.**

**Figure 2D-3. Route Signs**Interstate Route Sign  
M1-1Off-Interstate Business Route Sign  
M1-2 (Loop)  
M1-3 (Spur)U.S. Route Sign  
M1-4State Route Sign  
M1-5County Route Sign  
M1-6Alternate County Route Sign  
M1-H6aTownship Route Sign  
M1-H6bForest Route Sign  
M1-7**Section 2D.12 Design of Route Sign Auxiliaries****Standard:**

Route sign auxiliaries carrying word legends, except the JCT sign, shall have a standard size of 600 x 300 mm (24 x 12 in). Those carrying arrow symbols, or the JCT sign, shall have a standard size of 525 x 375 mm (21 x 15 in). All route sign auxiliaries shall match the color combination of the route sign that they supplement.

**Guidance:**

Auxiliary signs carrying word messages and mounted with 750 x 600 mm (30 x 24 in) Interstate Route signs should be 750 x 375 mm (30 x 15 in). With route signs of larger sizes, auxiliary signs should be suitably enlarged, but not such that they exceed the width of the route sign.

**Option:**

A route sign and any auxiliary signs used with it may be combined on a single panel.

**Section 2D.13 Junction Auxiliary Sign (M2-1)****Standard:**

The Junction (M2-1) auxiliary sign (see Figure 2D-4) shall carry the abbreviated legend JCT and shall be mounted at the top of an assembly (see Section 2D.27) either directly above the route sign or above a sign for an alternative route (see Section 2D.16) that is part of the route designation. The

**minimum size of the Junction auxiliary sign shall be 525 x 375 mm (21 x 15 in) for compatibility with auxiliary signs carrying arrow symbols.**

#### **Section 2D.14 Combination Junction Sign (M2-2)**

Option:

As an alternative to the standard Junction assembly where more than one route is to be intersected or joined, a rectangular sign may be used carrying the word JUNCTION above the route numbers.

Other designs may be used to accommodate State and County Route signs.

**Standard:**

**The Combination Junction (M2-2) sign (see Figure 2D-4) shall have a green background with white border and lettering for the word JUNCTION.**

Guidance:

Where U.S. or State Route signs are used as components of guide signs, only the outline of the shield or other distinctive shape should be used.

Although the size of the Combination Junction sign will depend on the number of routes involved, the numerals should be large enough for clear legibility and should be of a size comparable with those in the individual route signs.

#### **Section 2D.15 Cardinal Direction Auxiliary Signs (M3-1 through M3-4)**

Guidance:

Cardinal Direction auxiliary signs (see Figure 2D-4) carrying the legend NORTH, EAST, SOUTH, or WEST should be used to indicate the general direction of the entire route.

**Standard:**

**To improve the readability, the first letter of the cardinal direction words shall be ten percent larger, rounded up to the nearest whole number size.**

**If used, the Cardinal Direction auxiliary sign shall be mounted directly above a route sign or an auxiliary sign for an alternative route.**

#### **Section 2D.16 Auxiliary Signs for Alternative Routes (M4 Series)**

Option:

Auxiliary signs, carrying legends such as ALTERNATE, BY-PASS, BUSINESS, or TRUCK, may be used to indicate an alternate route of the same number between two points on that route.

**Standard:**

**If used, the auxiliary signs for alternative routes shall be mounted directly above a route sign.**

#### **Section 2D.17 ALTERNATE Auxiliary Signs (M4-1, M4-1a)**

Option:

The ALTERNATE (M4-1) or the ALT (M4-1a) auxiliary sign (see Figure 2D-4) may be used to indicate an officially designated alternate routing of a numbered route between two points on that route.


**Standard:**

**If used, the ALTERNATE or ALT auxiliary sign shall be mounted directly above a route sign.**

Guidance:

The shorter (time or distance) or better-constructed route should retain the regular route number, and the longer or worse-constructed route should be designated as the alternate route.

**Figure 2D-4. Route Sign Auxiliaries**



**Section 2D.18 BY-PASS Auxiliary Sign (M4-2)**

Option:

The BY-PASS (M4-2) auxiliary sign (see Figure 2D-4) may be used to designate a route that branches from the numbered route through a City, bypasses a part of the City or congested area, and rejoins the numbered route beyond the City.

**Standard:**

**If used, the BY-PASS auxiliary sign shall be mounted directly above a route sign.**

**Section 2D.19 BUSINESS Auxiliary Sign (M4-3)**

Option:

The BUSINESS (M4-3) auxiliary sign (see Figure 2D-4) may be used to designate an alternate route that branches from a numbered route, passes through the business portion of a City, and rejoins the numbered route beyond that area.

**Standard:**

**If used, the BUSINESS auxiliary sign shall be mounted directly above a route sign.**

**Section 2D.20 TRUCK Auxiliary Sign (M4-4)**

Option:

The TRUCK (M4-4) auxiliary sign (see Figure 2D-4) may be used to designate an alternate route that branches from a numbered route, when it is desirable to encourage or require commercial vehicles to use the alternate route.

**Standard:**

**If used, the TRUCK auxiliary sign shall be mounted directly above a route sign.**

**Section 2D.21 TO Auxiliary Sign (M4-5)**

Option:

The TO (M4-5) auxiliary sign (see Figure 2D-4) may be used to provide directional guidance to a particular road facility from other highways in the vicinity (see Section 2D.32).

**Standard:**

**If used, the TO auxiliary sign shall be mounted directly above a route sign or an auxiliary sign for an alternative route.**

**Section 2D.22 END Auxiliary Sign (M4-6)**

Guidance:

The END (M4-6) auxiliary sign (see Figure 2D-4) should be used where the route being traveled ends, usually at a junction with another route.

**Standard:**

**If used, the END auxiliary sign shall be mounted either directly above a route sign or above a sign for an alternative route that is part of the designation of the route being terminated.**

**Section 2D.23 TEMPORARY Auxiliary Signs (M4-7 , M4-7a)**

Option:

The TEMPORARY (M4-7) or the TEMP (M4-7a) auxiliary sign (see Figure 2D-4) may be used for an interim period to designate a section of highway that is not planned as a permanent part of a numbered route, but that connects completed portions of that route.

**Standard:**

**If used, the TEMPORARY or TEMP auxiliary sign shall be mounted either directly above the route sign, above a Cardinal Direction sign, or above a sign for an alternate route that is a part of the route designation.**

**TEMPORARY or TEMP auxiliary signs shall be promptly removed when the temporary route is abandoned.**

**Section 2D.24 Temporary Detour and Auxiliary Signs**

Support:

Chapter 6F contains information regarding Temporary Detour and Auxiliary signs.

**Section 2D.25 Advance Turn Arrow Auxiliary Signs (M5-1, M5-2)**


**Standard:**

**If used, the Advance Turn Arrow auxiliary sign (see Figure 2D-5) shall be mounted directly below the route sign in Advance Route Turn assemblies, and displays a right or left arrow, the shaft of which is bent at a 90-degree angle (M5-1) or at a 45-degree angle (M5-2).**

**Section 2D.26 Directional Arrow Auxiliary Signs (M6 Series)**

**Standard:**

**If used, the Directional Arrow auxiliary sign (see Figure 2D-5) shall be mounted below the route sign in directional assemblies, and displays a single- or double-headed arrow pointing in the general direction that the route follows.**

**Figure 2D-5. Directional Arrow Auxiliary Signs****Section 2D.27 Route Sign Assemblies****Standard:**

A Route Sign assembly shall consist of a route sign and auxiliary signs that further identify the route and indicate the direction. Route Sign assemblies shall be installed on all approaches to numbered routes that intersect with other numbered routes.

Where two or more routes follow the same section of highway, the route signs for Interstate, U.S., State, and County Routes shall be mounted in that order from the left in horizontal arrangements and from the top in vertical arrangements. Subject to this order of precedence, route signs for lower-numbered routes shall be placed at the left or top.

Within groups of assemblies, information for routes intersecting from the left shall be mounted at the left in horizontal arrangements and at the top or center of vertical arrangements. Similarly, information for routes intersecting from the right shall be at the right or bottom, and for straight-through routes at the center in horizontal arrangements or top in vertical arrangements.

Route Sign assemblies shall be mounted in accordance with the general specifications for highway signs (Chapter 2A), with the lowest sign in the assembly at the height prescribed for single signs.

**Guidance:**

Assemblies for two or more routes, or for different directions on the same route, should be mounted in groups on a common support.

**Option:**

Route Sign assemblies may be installed on the approaches to numbered routes on unnumbered roads and streets that carry an appreciable amount of traffic destined for the numbered route.

If engineering judgment indicates that groups of assemblies that include overlapping routes or multiple turns might be confusing, route signs or auxiliary signs may be omitted or combined, provided that clear directions are given to road users.

**Support:**

Figure 2D-6 shows typical placements of route signs.

## **Section 2D.28 Junction Assembly**

### **Standard:**

A Junction assembly shall consist of a Junction auxiliary sign and a route sign. The route sign shall carry the number of the intersected or joined route.

The Junction assembly shall be installed in advance of every intersection where a numbered route is intersected or joined by another numbered route. In urban areas it shall be installed in the block preceding the intersection, and in rural areas it shall be installed at least 120 m (400 ft) in advance of the intersection. In rural areas, the minimum distance between the Destination sign and the Route Turn assembly shall be 60 m (200 ft), and the minimum distance between the Route Turn assembly and the Junction assembly shall be 60 m (200 ft).

### **Guidance:**

In urban areas where speeds are low, the Junction assembly should not be installed more than 90 m (300 ft) in advance of the intersection.

Where prevailing speeds are high, greater spacings should be used.

### **Option:**

Where two or more routes are to be indicated, a single Junction auxiliary sign may be used for the assembly and all route signs grouped in a single mounting, or a Combination Junction sign (see Section 2D.14) may be used.

## **Section 2D.29 Advance Route Turn Assembly**

### **Standard:**

An Advance Route Turn assembly shall consist of a route sign, an Advance Turn Arrow or word message auxiliary sign, and a Cardinal Direction auxiliary sign, if needed. It shall be installed in advance of an intersection where a turn must be made to remain on the indicated route.

### **Option:**

The Advance Route Turn assembly may be used to supplement the required Junction assembly in advance of intersecting routes.

### **Guidance:**

Where a multiple-lane highway approaches an interchange or intersection with a numbered route, the Advance Route Turn assembly should be used to pre-position turning vehicles in the correct lanes from which to make their turn.

In low-speed areas, the Advance Route Turn assembly should be installed not less than 60 m (200 ft) in advance of the turn. In high-speed areas, the Advance Route Turn assembly should be installed not less than 90 m (300 ft) in advance of the turn.

### **Standard:**

An assembly that includes an Advance Turn Arrow auxiliary sign shall not be placed where there is an intersection between it and the designated turn.

### **Guidance:**

Sufficient distance should be allowed between the assembly and any preceding intersection that could be mistaken for the indicated turn.

## **Section 2D.30 Directional Assembly**

### **Standard:**

**A Directional assembly shall consist of a route sign, a Directional Arrow auxiliary sign, and a Cardinal Direction auxiliary sign, if needed. The various uses of Directional assemblies shall be as outlined below:**

- A. Turn movements (indicated in advance by an Advance Route Turn assembly) shall be marked by a Directional assembly with a route sign displaying the number of the turning route and a single-headed arrow pointing in the direction of the turn.**
- B. The beginning of a route (indicated in advance by a Junction assembly) shall be marked by a Directional assembly with a route sign displaying the number of that route and a single-headed arrow pointing in the direction of the route.**
- C. The end of a route shall be marked by a Directional assembly with an END auxiliary sign and a route sign displaying the number of that route.**
- D. An intersected route (indicated in advance by a Junction assembly) shall be designated by:**
  - 1. Two Directional assemblies, each with a route sign displaying the number of the intersected route, a Cardinal Direction auxiliary sign, and a single-headed arrow pointing in the direction of movement on that route; or**
  - 2. A Directional assembly with a route sign displaying the number of the intersected route and a double-headed arrow, pointing at appropriate angles to the left, right, or ahead.**

### **Guidance:**

Straight-through movements should be indicated by a Directional assembly with a route sign displaying the number of the continuing route and a vertical arrow. A Directional assembly should not be used for a straight-through movement in the absence of other assemblies indicating right or left turns, as the Confirming assembly sign beyond the intersection normally provides adequate guidance.

Directional assemblies should be located on the near right corner of the intersection. At major intersections and at Y or offset intersections, additional Directional assemblies should be installed on the far right or left corner to confirm the near-side assemblies. When the near-corner position is not practical for Directional assemblies, the far right corner should be the preferred alternative, with oversized signs, if necessary, for legibility. Where unusual conditions exist, the location of a Directional assembly should be determined by engineering judgment with the goal being to provide the best possible combination of view and safety.

### **Support:**

It is more important that guide signs be readable at the right time and place than to be located with absolute uniformity.

Figure 2D-6 shows typical placements of Directional assemblies.

## **Section 2D.31 Confirming or Reassurance Assemblies**

### **Standard:**

**If used, Confirming or Reassurance assemblies shall consist of a Cardinal Direction auxiliary sign and a route sign.**


### **Guidance:**

A Confirming assembly should be installed just beyond intersections of numbered routes. It should be placed 7.6 to 60 m (25 to 200 ft) beyond the far shoulder or curb line of the intersected highway.

If used, Reassurance assemblies should be installed between intersections in urban districts as needed, and beyond the built-up area of any incorporated City or town.

Route signs for either confirming or reassurance purposes should be spaced at such intervals as necessary to keep road users informed of their routes.


**Figure 2D-6. Illustration of Directional Assemblies and Other Route Signs (For One Direction of Travel Only) (Sheet 1 of 3)**



Notes: Lettering on Destination and Distance signs may be a combination of upper-case and lower-case letters, or in all capital letters (see Section 2D.05). See Sections 2D.28 through 2D.31 and Section 2D.35 for low-speed and/or urban conditions.

Section 2D.34 indicates that assemblies of separate Destination sign panels may be used. Figures 2D-3 and 2D-4 show the correct design of an Ohio State Route Sign.


**Figure 2D-6. Illustration of Directional Assemblies and Other Route Signs (For One Direction of Travel Only) (Sheet 2 of 3)**



Notes: Lettering on Destination and Distance signs may be a combination of upper-case and lower-case letters, or in all capital letters (see Section 2D.05).  
See Sections 2D.28 through 2D.31 and Section 2D.35 for low-speed and/or urban conditions.

Section 2D.34 indicates that assemblies of separate Destination sign panels may be used. Figures 2D-3 and 2D-4 show the correct design of an Ohio State Route Sign.

**Figure 2D-6. Illustration of Directional Assemblies and Other Route Signs (For One Direction of Travel Only) (Sheet 3 of 3)**



Notes: Lettering on Destination and Distance signs may be a combination of upper-case and lower-case letters, or in all capital letters (see Section 2D.05). See Sections 2D.28 through 2D.31 and Section 2D.35 for low-speed and/or urban conditions.

Section 2D.34 indicates that assemblies of separate Destination sign panels may be used. Figures 2D-3 and 2D-4 show the correct design of an Ohio State Route Sign.

Support:

Confirming and Reassurance assemblies are considered to be a type of Directional assembly.

### **Section 2D.32 Trailblazer Assembly**

Support:

Trailblazer assemblies provide directional guidance to a particular road facility from other highways in the vicinity. This is accomplished by installing Trailblazer assemblies at strategic locations to indicate the direction to the nearest or most convenient point of access. The use of the word TO indicates that the road or street where the sign is posted is not a part of the indicated route, and that a road user is merely being directed progressively to the route.

**Standard:**

**A Trailblazer assembly shall consist of a TO auxiliary sign, a route sign (or a special road facility symbol), and a single-headed Directional Arrow auxiliary sign pointing in the direction leading to the route.**

Option:

A Cardinal Direction auxiliary sign may be used with a Trailblazer assembly.

Guidance:

The TO auxiliary sign, Cardinal Direction auxiliary sign, and Directional Arrow auxiliary sign should be of the standard size specified for auxiliary signs of their respective type. The route sign should be the size specified in Section 2D.11.

Option:

Trailblazer assemblies may be installed with other Route Sign assemblies, or alone, in the immediate vicinity of the designated facilities.

### **Section 2D.33 Destination and Distance Signs**

Support:

In addition to guidance by route numbers, it is desirable to supply the road user information concerning the destinations that can be reached by way of numbered or unnumbered routes. This is done by means of Destination signs and Distance signs.

Option:

Route and Cardinal Direction auxiliary signs may be included on the Destination sign panel with the destinations and arrows.

Guidance:

The size of the route signs and Cardinal Direction auxiliary signs should be at least the minimum size specified for these signs.

### **Section 2D.34 Destination Signs (D1 Series)**


**Standard:**

**Except where special interchange signing is prescribed, the Destination (D1 Series) sign (see Figure 2D-7), if used, shall be a horizontal rectangle carrying the name of a City, town, village, or other traffic generator, and a directional arrow.**

Guidance:

In order to control proliferation of destination signs, each responsible jurisdiction should establish a policy similar to the traffic generator policy established by the Ohio Department of Transportation (ODOT) in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

## Figure 2D-7. Examples of Destination and Distance Signs



Note: Lettering on Destination and Distance signs may be in a combination of upper-case and lower-case, or in all capital letters (see Section 2D.05)

Multiple destinations may be shown using an assembly of separate panels or a single sign.

### Option:

The distance (see Section 2D.36) to the place named may also be shown on the Destination sign (see Figure 2D-7). If several destinations are to be shown at a single point, the several names may be placed on a single panel with an arrow (and the distance, if desired) for each name. If more than one destination lies in the same direction, a single arrow may be used for such a group of destinations.

### Guidance:

Adequate separation should be made between any destinations or group of destinations in one direction and those in other directions by suitable design of the arrow, spacing of lines of legend, heavy lines entirely across the panel, or separate panels.

### Standard:

**An arrow pointing to the right shall be at the extreme right of the sign, and an arrow pointing left or up shall be at the extreme left. The distance figures, if used, shall be placed to the right of the destination names.**

### Guidance:

Unless a sloping arrow will convey a clearer indication of the direction to be followed, the directional arrows should be horizontal or vertical.

If several individual name panels are assembled into a group, all panels in the assembly should be of the same length.

Destination signs should be used:

- A. At the intersections of U.S. or State numbered routes with Interstate, U.S., or State numbered routes; and
- B. At points where they serve to direct traffic from U.S. or State numbered routes to the business section of towns, or to other destinations reached by unnumbered routes.

**Standard:**

**Where a total of three or less destinations are provided on the Advance Guide (see Section 2E.30) and Supplemental Guide (see Section 2E.32) signs, not more than three destination names shall be used on a Destination sign. Where four destinations are provided by the Advance Guide and Supplemental Guide signs, not more than four destination names shall be used on a Destination sign.**

## Guidance:

If space permits, four destinations should be displayed as two separate sign panels.

## Option:

Where space does not permit, or where all four destinations are in one direction, a single sign assembly may be used.

**Standard:**

**Where a single four-name sign assembly is used, a heavy line entirely across the panel or separated sign panels shall be used to separate destinations by direction.**

## Guidance:

The next closest destination lying straight ahead should be at the top of the sign or assembly, and below it the closest destinations to the left and to the right, in that order. The destination shown for each direction should ordinarily be the next County seat or the next principal City, rather than a more distant destination. In the case of overlapping routes, there should be shown only one destination in each direction for each route.

**Standard:**

**If there is more than one destination shown in the same direction, the name of the nearest destination shall appear above the names of any destinations that are further away.**

## Support:

The SDM (see Section 1A.11) contains designs for the signs shown here and variations not depicted, such as provisions for two-line legends for long names.

For additional information about destination guide signs for recreational and cultural interest areas, see Chapter 2H.

**Section 2D.35 Location of Destination Signs**

## Guidance:

When used in high-speed areas, Destination signs should be located 60 m (200 ft) or more in advance of the intersection, and following any Junction or Advance Route Turn assemblies that may be required.

## Option:

In urban areas, shorter advance distances may be used.

Because the Destination sign is of lesser importance than the Junction, Advance Route Turn, or Directional assemblies, the Destination sign may be eliminated when sign spacing is critical.

## Support:

Figure 2D-6 shows typical placements of Destination signs.

**Section 2D.36 Distance Signs (D2 Series)****Standard:**

**If used, the Distance (D2-H1 through D2-H3) sign (see Figure 2D-7) shall be a horizontal rectangle of a size appropriate for the required legend, carrying the names of not more than three Cities, towns, junctions, or other traffic generators, and the distance (to the nearest kilometer or mile) to those places.**

**Guidance:**

The distance shown should be selected on a case-by-case basis by the jurisdiction that owns the road. A well-defined central area or central business district should be used where one exists. In other cases, the layout of the community should be considered in relation to the highway being signed and the decision based on where it appears that most drivers would feel that they are in the center of the community in question.

The top name on the Distance sign should be that of the next place on the route having a post office or a railroad station, a route number or name of an intersected highway, or any other significant geographical identity. The bottom name on the sign should be that of the next major destination or control city (see Section 2E.12 for more information about control cities). If three destinations are shown, the middle line should be used to indicate communities of general interest along the route or important route junctions.

**Option:**

The choice of names for the middle line may be varied on successive Distance signs to give road users additional information concerning communities served by the route.

**Guidance:**

The control city (see Section 2E.12) should remain the same on all successive Distance signs throughout the length of the route until that City is reached.

**Option:**

If more than one distant point may properly be designated, such as where the route divides at some distance ahead to serve two destinations of similar importance, and if these two destinations cannot appear on the same sign, the two names may be alternated on successive signs.

On a route continuing into another State, destinations in the adjacent State may be shown.

**Section 2D.37 Location of Distance Signs****Guidance:**

If used, Distance signs should be installed on important routes leaving municipalities and just beyond intersections of numbered routes in rural areas. If used, they should be placed just outside the municipal limits or at the edge of the built-up district if it extends beyond the limits.

Where overlapping routes separate a short distance from the municipal limits, the Distance sign at the municipal limits should be omitted. The Distance sign should be installed approximately 90 m (300 ft) beyond the separation of the two routes.

Where, just outside of an incorporated municipality, two routes are concurrent and continue concurrently to the next incorporated municipality, the top name on the Distance sign should be that of the place where the routes separate; the bottom name should be that of the City to which the greater part of the through traffic is destined.

**Support:**

Figure 2D-6 shows typical placements of Distance signs.

**Section 2D.38 Street Name Sign (D3-1)****Guidance:**

Street Name (D3-1) signs (see Figure 2D-8) should be installed in urban areas at all street intersections regardless of other route signs that may be present and should be installed in rural areas to identify important roads that are not otherwise signed.

Lettering on ground-mounted Street Name signs should be at least 150 mm (6 in) high in capital letters, or 150 mm (6 in) upper-case letters with 113 mm (4.5 in) lower-case letters.

On multi-lane streets with speed limits greater than 60 km/h (40 mph), the lettering on ground-mounted Street Name signs should be at least 200 mm (8 in) high in capital letters, or 200 mm (8 in) upper-case letters with 150 mm (6 in) lower-case letters.

**Option:**

For local roads with speed limits of 40 km/h (25 mph) or less, the lettering height may be a minimum of 100 mm (4 in).

Supplementary lettering to indicate the type of street (such as Street, Avenue, or Road) or the section of the City (such as NW) may be in smaller lettering, at least 75 mm (3 in) high. Conventional abbreviations (see Section 1A.14) may be used except for the street name itself.

A symbol or letter designation may be used on a Street Name sign to identify the governmental jurisdiction, area of jurisdiction, or other government-approved institution.

**Standard:**

**If a symbol or letter designation is used, the height and width of the symbol or letter designation shall not exceed the letter height of the sign.**

**Guidance:**

The symbol or letter designation should be positioned to the left of the street name.

**Standard:**

**The Street Name sign shall be retroreflective or illuminated to show the same shape and similar color both day and night. The legend and background shall be of contrasting colors.**

**Guidance:**

Street Name signs should have a white legend on a green background. A border, if used, should be the same color as the legend.

In business districts and on principal arterials, Street Name signs should be placed at least on diagonally opposite corners. In residential areas, at least one Street Name sign should be mounted at each intersection. Signs naming both streets should be installed at each intersection. They should be mounted with their faces parallel to the streets they name.

**Option:**

To optimize visibility, Street Name signs may be mounted overhead. Street Name signs may also be placed above a regulatory or STOP or YIELD sign with no required vertical separation.

At intersection crossroads where the same road has two different street names for each direction of travel, both street names may be shown on the same sign along with directional arrows.

**Guidance:**

In urban or suburban areas, especially where Advance Street Name signs are not used, the use of overhead-mounted Street Name signs should be considered. If overhead Street Name signs are used, the lettering should be at least 300 mm (12 in) high in capital letters, or 300 mm (12 in) upper-case letters with 225 mm (9 in) lower-case letters.

**Support:**

Information regarding the use of street names on supplemental plaques for use with intersection-related warning signs is contained in Section 2C.49.


**Figure 2D-8. Examples of Street Name and Parking Signs**



OR



OR



D4-1



D4-2



D3-1

D3-2

**Section 2D.39 Advance Street Name Signs (D3-2)**

Support:

Advance Street Name (D3-2) signs (see Figure 2D-8) identify an upcoming intersection. Although this is often the next intersection, it could also be several intersections away in cases where the next signalized intersection is referenced.

**Standard:**

**Advance Street Name (D3-2) signs, if used, shall supplement rather than be used instead of the Street Name (D3-1) signs at the intersection.**

Option:

Advance Street Name (D3-2) signs may be installed in advance of signalized or unsignalized intersections to provide road users with advance information to identify the name(s) of the next intersecting

street to prepare for crossing traffic and to facilitate timely deceleration and/or lane changing in preparation for a turn.

**Guidance:**

On arterial highways in rural areas, Advance Street Name signs should be used in advance of all signalized intersections and in advance of all intersections with exclusive turn lanes.

In urban areas, Advance Street Name signs should be used in advance of all signalized intersections on major arterial streets, except where signalized intersections are so closely spaced that advance placement of the signs is impractical.

The heights of the letters on Advance Street Name signs should be the same as those used for Street Name signs (see Section 2D.38)

**Standard:**

**If used, Advance Street Name signs shall have a white legend and border on a green background.**

**If used, Advance Street Name signs shall provide the name(s) of the intersecting street(s) on the top line(s) of the legend and the distance to the intersecting streets or messages such as NEXT SIGNAL, NEXT INTERSECTION, or directional arrow(s) on the bottom line of the legend.**

**Option:**

Directional arrow(s) may be placed to the right or left of the street name or message such as NEXT SIGNAL, as appropriate, rather than on the bottom line of the legend.

For intersecting crossroads where the same road has a different street name for each direction of travel, the different street names may be shown on the same Advance Street Name sign along with directional arrows.

In advance of two closely spaced intersections where it is not practical to install separate Advance Street Name signs, the Advance Street Name sign may include the street names for both intersections along with appropriate supplemental legends for both street names, such as NEXT INTERSECTION, 2ND INTERSECTION, or NEXT LEFT and NEXT RIGHT, or advance directional arrows.

An Advance Street Name (W16-8) plaque with black legend on a yellow background, installed supplemental to an Intersection (W2) or Advance Traffic Control (W3) series warning sign may be used instead of an Advance Street Name guide sign (see Section 2C.49).

**Section 2D.40 Parking Area Sign (D4-1)**

**Option:**

The Parking Area (D4-1) sign (see Figure 2D-8) may be used to show the direction to a nearby public parking area.

**Standard:**

**If used, the sign shall be a horizontal rectangle with a standard size of 750 x 600 mm (30 x 24 in), or with a smaller size of 450 x 375 mm (18 x 15 in) for minor, low-speed streets. It shall carry the word PARKING, with the letter P five times the height of the remaining letters, and a directional arrow. The legend and border shall be green on a retroreflectorized white background.**

**Guidance:**

If used, the Parking Area sign should be installed on major thoroughfares at the nearest point of access to the parking facility and where it can advise drivers of a place to park. The sign should not be used more than four blocks from the parking area.

**Section 2D.41 PARK & RIDE Sign (D4-2)****Option:**

PARK & RIDE (D4-2) signs (see Figure 2D-8) may be used to direct road users to park and ride facilities.

**Standard:**

**The signs shall contain the word message PARK & RIDE and direction information (arrow or word message).**

**Option:**

PARK & RIDE signs may contain the local transit logo and/or carpool symbol within the sign border.

**Standard:**

**If used, the local transit logo and/or carpool symbol shall be located in the top part of the sign above the message PARK & RIDE. In no case shall the vertical dimension of the local transit logo and/or carpool symbol exceed 450 mm (18 in).**

**Guidance:**

If the function of the parking facility is to provide parking for persons using public transportation, the local transit logo symbol should be used on the guide sign. If the function of the parking facility is to serve carpool riders, the carpool symbol should be used on the guide sign. If the parking facility serves both functions, both the logo and carpool symbol should be used.

**Standard:**

**These signs shall have a retroreflective white legend and border on a rectangular green background. The carpool symbol shall be as shown for sign D4-2. The color of the transit logo shall be selected by the local transit authority.**

**Option:**

To increase the target value and contrast of the transit logo, and to allow the local transit logo to retain its distinctive color and shape, the logo may be included within a white border or placed on a white background.

**Section 2D.42 Rest Area Signs (D5 Series)****Standard:**


**Rest Area signs (see Figure 2D-9 and Appendix C) shall be used only where parking and restroom facilities are available. Signs for this purpose shall have retroreflective white letters, symbols, and border on a blue background.**

**Guidance:**

If used, Rest Area signs should be installed in advance of roadside parks or rest areas to permit the driver to reduce speed and leave the highway reasonably safely.

**Option:**

Messages such as REST AREA X MILE (D5-1 and D5-H1b), REST AREA (D5-2 and D5-H2b), PARKING AREA X MILE (D5-3), PARKING AREA (D5-4), ROADSIDE TABLE X MILE (D5-5e), ROADSIDE PARK X MILE (D5-5d), and PICNIC AREA (D5-5c) may be used, as well as other appropriate messages.

**Figure 2D-9. Examples of Rest Area and Scenic Overlook Signs**

Note: D6-1 through D6-3 signs may use legend AREA, VIEW, or OVERLOOK.

### **Section 2D.43 Scenic Area Signs (D6 Series)**

Option:

Scenic areas may be marked by signs (see Figure 2D-9 and Appendix C) carrying the message SCENIC AREA, SCENIC VIEW, SCENIC OVERLOOK, or the equivalent, together with appropriate directional information.

Guidance:

The design of the signs should be consistent with that specified for rest areas in Section 2D.42 and should be white letters, symbols, and border on a blue background. An advance sign and an additional sign at the turnoff point should be used for this kind of attraction.

### **Section 2D.44 Weigh Station Signing (D8 Series)**

Support:

The general concept for Weigh Station signing is similar to Rest Area signing (see Section 2D.42) because in both cases traffic using either area remains within the right-of-way.

**Standard:**

**The standard installation for Weigh Station signing shall include three basic signs:**

- A. Advance sign (D8-1);**
- B. Exit Direction sign (D8-2 or D8-H2); and**
- C. Gore sign (D8-3).**

Support:


Example locations of these signs are shown in Figure 2D-10.

The Exit Direction sign D8-H2 incorporates a changeable message OPEN or CLOSED within the face of the sign.

Guidance:

The R13-H1 and R13-H2 regulatory signs (see Section 2B.50) should be used in advance of the Weigh Station Exit Direction sign following the Advance sign (see Figure 2D-10).

**Figure 2D-10. Example of Weigh Station Signing**



The Exit Direction sign or the Advance sign should display, either within the sign border or on a supplemental panel, the changeable message OPEN or CLOSED.

### **Section 2D.45 General Service Signs (D9 Series)**

Support:

On conventional roads, commercial services such as gas, food, and lodging generally are within sight and are available to the road user at reasonably frequent intervals along the route. Consequently, on this class of road there usually is no need for special signs calling attention to these services. Moreover, General Service signing is usually not required in urban areas except for hospitals, law enforcement assistance, tourist information centers, and camping.

Option:

General Service signs (see Figure 2D-11) may be used where such services are infrequent and are found only on an intersecting highway or crossroad.

**Standard:**

**All General Service signs and supplemental panels shall have white letters, symbols, and borders on a blue background.**

Guidance:

General Service signs should be installed at a suitable distance in advance of the turn-off point or intersecting highway.

In addition to the information in this Manual, local jurisdictions electing to use General Service signing should follow the related standards and guidelines established in Part 2 of the ODOT "Traffic Engineering Manual" (see Section 1A.11).

Option:

Signs may be installed for whatever alternative fuels are available at appropriate locations.

**Standard:**

**General Service signs, if used at intersections, shall be accompanied by a directional message.**

Option:

The General Service legends may be either symbols or word messages.

**Standard:**

**Symbols and word message General Service legends shall not be intermixed on the same sign.**

Guidance:

If used, the word message TRUCK PARKING (D9-16) sign should be placed on a separate panel below the other general motorist services.

Support:

Formats for displaying different combinations of these services are presented in Section 2E.51.

Option:

If the distance to the next point at which services are available is 16 km (10 mi) or more, a sign NEXT SERVICES XX MILES (D9-17) may be used as a separate panel installed below the General Service sign (see Figure 2E-43).

**Figure 2D-11. General Service Signs**

The International Symbol of Accessibility for the Handicapped (D9-6) sign may be used beneath General Service signs where paved ramps and rest room facilities accessible to, and usable by, the physically handicapped are provided.

The Recreational Vehicle Sanitary Station (D9-12) sign may be used as needed to indicate the availability of facilities designed for the use of dumping wastes from recreational vehicle holding tanks.

The Litter Container (D9-4) sign may be placed in advance of roadside turnouts or rest areas, unless it distracts the driver's attention from other more important regulatory, warning, or directional signs.

A Carpool Information (D12-2) sign (see Figure 2D-12) may be installed as needed (see Section 2E.57).

A Channel 9 Monitored (D12-3) sign may be installed as needed. Official public agencies or their designees may be shown as the monitoring agency on the sign (see Section 2E.56). An EMERGENCY DIAL XXX (D12-4) sign along with the appropriate number to dial, may be used for cellular phone communications.

A TRAVEL INFO CALL 511 (D12-5) sign (see Figure 2D-12) may be installed if a 511 travel information services telephone number is available to road users for obtaining traffic, public transportation, weather, construction, or road condition information.

The logo of the transportation agency or the travel information service or program that is providing the travel information may be incorporated within the D12-5 sign either above or below the TRAVEL INFO CALL 511 legend.

**Standard:**

**The logo of a commercial entity shall not be incorporated within the TRAVEL INFO CALL 511 sign.**

**The TRAVEL INFO CALL 511 sign shall have a white legend and border on a blue background.**

## Guidance:

If the logo of the transportation agency or the travel information service or program is used, the logo's maximum height should not exceed two times the letter height used in the legend of the sign.

## Option:

The Emergency Medical Services (D9-13) symbol sign may be used to identify medical service facilities that have been included in the Emergency Medical Services system under a signing policy developed by the State and/or local highway agency.

**Standard:**

**The Emergency Medical Services symbol sign shall not be used to identify services other than qualified hospitals, ambulance stations, and qualified free-standing emergency medical treatment centers. If used, the Emergency Medical Services symbol shall be supplemented by a sign identifying the type of service provided.**

## Option:

The Emergency Medical Services symbol sign may be used above the HOSPITAL (D9-13a) word message sign or H (D9-2) symbol sign or above a sign with either the legend AMBULANCE STATION (D9-13b) or EMERGENCY MEDICAL CARE (D9-13c). The Emergency Medical Services symbol sign may also be used to supplement Telephone (D9-1), Channel 9 Monitored (D12-3), or POLICE (D9-14) signs.

**Standard:**

**The legend EMERGENCY MEDICAL CARE shall not be used for services other than qualified free-standing emergency medical treatment centers.**

## Guidance:

Each highway agency electing to use the Emergency Medical Service symbol sign should develop guidelines for its implementation.

The following guidelines should be considered in the preparation of such a policy:

## A. AMBULANCE

1. 24-hour service, 7 days per week.
2. Staffed by two State-certified persons trained at least to the basic level.
3. Vehicular communications with a hospital emergency department.
4. Operator should have successfully completed an emergency vehicle operator training course.

## B. HOSPITAL

1. 24-hour service, 7 days per week.
2. Emergency department facilities with a physician (or emergency care nurse on duty within the emergency department with a physician on call) trained in emergency medical procedures on duty.
3. Licensed or approved for definitive medical care by an appropriate State authority.
4. Equipped for radio voice communications with ambulances and other hospitals.

## C. Channel 9 Monitored

1. Provided by either professional or volunteer monitors.
2. Available 24 hours per day, 7 days per week.
3. The service should be endorsed, sponsored, or controlled by an appropriate government authority to guarantee the level of monitoring.

## **Section 2D.46 Reference Location Signs (D10-1 through D10-3) and Intermediate Reference Location Signs (D10-1a through D10-3a)**

### Support:

There are two types of reference location signs:

- A. Reference Location signs (D10-1, 2, and 3) show an integer distance point along a highway; and
- B. Intermediate Reference Location signs (D10-1a, 2a, and 3a) also show a decimal between integer distance points along a highway.

### Option:

Reference Location (D10-1 to D10-3) signs (see Figure 2D-13) may be installed along any section of a highway route or ramp to assist road users in estimating their progress, to provide a means for identifying the location of emergency incidents and traffic crashes, and to aid in highway maintenance and servicing.

To augment the reference location sign system, Intermediate Reference Location (D10-1a to D10-3a) signs (see Figure 2D-13), which show the tenth of a mile with a decimal point, may be installed at one tenth of a mile intervals, or at some other regular spacing.

### Standard:

**When Intermediate Reference Location (D10-1a to D10-3a) signs are used to augment the reference location sign system, the reference location sign at the integer mile point shall display a decimal point and a zero numeral.**

**When placed on freeways or expressways, Reference Location (D10-1 to D10-3) signs shall contain 250 mm (10 in) white numerals on a 300 mm (12 in) wide green background with a white border. The signs shall be 600, 900, or 1200 mm (24, 36, or 48 in) in height for one, two, or three digits, respectively, and shall contain the word MILE in 100 mm (4 in) white letters.**

**When placed on conventional roads, Reference Location (D10-1 to D10-3) signs shall contain 150 mm (6 in) white numerals on a green background that is at least 250 mm (10 in) wide with a white border. The signs shall contain the word MILE in 100 mm (4 in) white letters.**

**The design details for reference location signs shall be as shown in the SDM (see Section 1A.11).**

**Reference location signs shall have a minimum mounting height of 1.2 m (4 ft) to the bottom of the sign in accordance with the mounting height requirements of delineators (see Section 3D.04), and shall not be governed by the mounting height requirements prescribed in Section 2A.18.**

**The distance numbering shall be continuous for each route within a State, except where overlaps occur (see Section 2E.28). Where routes overlap, reference location sign continuity shall be established for only one of the routes. If one of the overlapping routes is an Interstate route, that route shall be selected for continuity of distance numbering.**


**For divided highways, the distance measurement shall be made on the northbound and eastbound roadways. The reference location signs for southbound or westbound roadways shall be set at locations directly opposite the reference location signs for the northbound or eastbound roadways.**

### Guidance:

Zero distance should begin at the south and west State lines, or at the south and west terminus points where routes begin within a State.

On a route without reference location sign continuity, the first reference location sign beyond the overlap should indicate the total distance traveled on the route so that road users will have a means of correlating their travel distance between reference location sign with that shown on their odometer.

**Figure 2D-12. General Information Signs**




**Standard:**

Except as provided in the option below, reference location signs shall be installed on the right side of the roadway.

**Option:**

Where conditions limit or restrict the use of reference location signs on the right side of the roadway, they may be installed in the median. On two-lane conventional roadways, reference location signs may be installed on one side of the roadway only and may be installed back-to-back. Reference location signs may be placed up to 9 m (30 ft) from the edge of the pavement.

If a reference location sign cannot be installed in the correct location, it may be moved in either direction as much as 15 m (50 ft).

**Figure 2D-13. Reference Location Signs****Guidance:**

If a reference location sign cannot be placed within 15 m (50 ft) of the correct location, it should be omitted.

**Option:**

Enhanced reference location signs (see Section 2E.54) may also be used on conventional roads.

**Section 2D.47 Traffic Signal Speed Sign (I1-1)****Option:**

The Traffic Signal Speed (I1-1) sign (see Figure 2D-12), reading SIGNALS SET FOR XX MPH, may be used to indicate a section of street or highway on which the traffic control signals are coordinated into a

progressive system timed for a specified speed at all hours during which they are operated in a coordinated mode.

Guidance:

If used, the sign should be mounted as near as practical to each intersection where the timed speed changes, and at intervals of several blocks throughout any section where the timed speed remains constant.

**Standard:**

**The Traffic Signal Speed sign shall be a minimum of 300 x 450 mm (12 x 18 in) with the longer dimension vertical. It shall have a white message and border on a green background.**

### **Section 2D.48 General Information Signs (I Series)**

Support:

Of interest to the traveler, though not directly necessary for guidance, are numerous kinds of information that can properly be conveyed by general information signs (see Figure 2D-12 and Appendix C). They include such items as State lines, City limits, other political boundaries, time zones, stream names, elevations, landmarks, and similar items of geographical interest, and safety and transportation-related messages. Chapter 2H contains recreational and cultural interest area symbol signs that are sometimes used in combination with general information signs.

Guidance:

A State Line (I-2 or I-H2) sign should be erected where a route enters the State of Ohio from another state.

The Corporation Limit (I-H2a) sign should be installed where a route enters a municipality.

Option:

Where a route leaves a municipality and subsequently re-enters the same municipality within a relatively short distance, the ENTER CORP (I-H2b) sign may be used at the re-entry location.

The LEAVE CORP (I-H2c) sign may be used at a location where a route leaves a municipality.

The Unincorporated Community (I-H2d) sign may be used to identify unincorporated communities of regional significance.

Guidance:

When used, the Unincorporated Community sign should be placed near the edge of the community.

Option:

The Township Limit (I-H2e) sign may be used to identify the boundaries of a township located outside municipal corporation limits.

**Standard:**

**In accordance with the provisions of Section 503.61 of the Ohio Revised Code, when requested by a township, ODOT shall erect Township Limit signs on state routes outside municipal corporations.**

**When used, the Township Limit sign shall be placed where a route enters a township.**

Guidance:

The Internal County Line (I-H2f) sign should be installed where a route leaves one Ohio county and enters another Ohio county.

Option:

The External County Line (I-H2g) sign may be installed where a route enters an Ohio county from another state.

**Guidance:**

When used, the External County Line sign should be erected beneath a State Line sign.

**Standard:**

The **WELCOME TO OHIO (I-H2) sign shall have a standard size of 1500 x 750 mm (60 x 30 in). The Corporation Limit (I-H2a) sign, Unincorporated Community (I-H2d) sign, Township Limit (I-H2e) sign, and Internal County Line (I-H2f) sign shall have a standard size of 1000 x 500 mm (40 x 20 in). The ENTER CORP (I-H2b) sign and LEAVE CORP (I-H2c) sign shall have a standard size of 600 x 450 mm (24 x 18 in). The External County Line (I-H2g) sign shall have a standard size of 1500 x 300 mm (60 x 12 in).**

**Option:**

The 300 x 300 mm (12 x 12 in) ENTER CORP (I-H2b) and LEAVE CORP (I-H2c) signs may be used instead of the standard size where space is limited.

**Guidance:**

General information signs should not be installed within a series of guide signs or at other equally critical locations, unless there are specific reasons for orienting the road user or identifying control points for activities that are clearly in the public interest. On all such signs, the designs should be simple and dignified, devoid of any advertising, and in general conformance with other guide signing.

**Option:**

An information symbol sign (I-5 through I-8, I-11) may be used to identify a route leading to a transportation or general information facility, or to provide additional guidance to the facility. The symbol sign may be supplemented by an educational plaque where necessary; also, the name of the facility may be used if needed to distinguish between similar facilities.

Guide signs for commercial service airports and noncarrier airports may be provided from the nearest Interstate, other freeway, or conventional highway intersection directly to the airport, normally not to exceed 25 km (15 mi). The Airport (I-5) symbol sign along with a supplemental plaque may be used to indicate the specific name of the airport. An Airport symbol sign, with or without a supplemental name plaque or the word AIRPORT, and an arrow may be used as a trailblazer.

**Standard:**

**Adequate trailblazer signs shall be in place prior to installing the airport guide signs.**

**Support:**

Location and placement of all airport guide signs depends upon the availability of longitudinal spacing on highways.

**Standard:**

**When a sign is used to display a safety or transportation-related message, the display format shall not be of a type that would be considered similar to advertising displays. Messages and symbols that resemble any official traffic control device shall not be used on safety or transportation-related message signs.**

**Option:**

Political jurisdiction logos may be placed on the political boundary general information signs. The logo may have different colors and shapes but should be simple, dignified, and devoid of any advertising.

**Standard:**

**Except for political boundary and scenic by-way logos and signs, general information signs shall have white legends and borders on green rectangular-shaped backgrounds.**

**Option:**

The Recycling Collection Center (I-11) symbol sign may be used to direct road users to recycling collection centers.

**Guidance:**

The Recycling Collection Center symbol sign should not be used on freeways and expressways.

**Standard:**

**If used on freeways or expressways, the Recycling Collection Center symbol sign shall be considered one of the supplemental sign destinations.**

**Section 2D.49 Signing of Named Highways****Support:**

Legislative bodies will occasionally adopt an act or resolution memorializing a highway, bridge, or other component of the highway. The methods by which memorial highways and bridges can be designated in Ohio are discussed in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

**Guidance:**

Such memorial names should not appear on or along a highway, or be placed on bridges or other highway components. The requirement for signing should be carried out by placing a memorial plaque in a rest area, scenic overlook, recreational area, or other appropriate location where parking is provided with the signing inconspicuously located relative to vehicle operations along the highway.

**Option:**

If the installation of a memorial plaque off the main roadway is not practical, memorial signs may be installed on the mainline.

**Standard:**

**Where such memorial signs are installed on the mainline, (1) memorial names shall not appear on directional guide signs, (2) memorial signs shall not interfere with the placement of any other necessary highway signing, and (3) memorial signs shall not compromise the safety or efficiency of traffic flow. The memorial signing shall be limited to one sign at an appropriate location in each route direction. The sign, when installed on the mainline, shall be similar in design to that shown for state highways in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).**

**Option:**

Guide signs may contain street or highway names if the purpose is to enhance driver communication and guidance; however, they are to be considered as supplemental information to route numbers.

**Standard:**

**Highway names shall not replace official numeral designations. Memorial names shall not appear on supplemental signs or on any other information sign either on or along the highway or its intersecting routes.**

**The use of route signs shall be restricted to signs officially used for guidance of traffic in accordance with this Manual and the "Purpose and Policy" statement of the American Association of State Highway and Transportation Officials that applies to Interstate and U.S. numbered routes (see the Preface for AASHTO's address).**

**Option:**

Unnumbered routes having major importance to proper guidance of traffic may be signed if carried out in accordance with the aforementioned policies. For unnumbered highways, a name to enhance route guidance may be used where the name is applied consistently throughout its length.

**Guidance:**

Only one name should be used to identify any highway, whether numbered or unnumbered.

**Section 2D.50 Trail Signs****Support:**

Trail signs are informational signs, plaques, or shields designed to provide road users with route guidance in following a trail of particular cultural, historical, or educational significance.

**Guidance:**

Primary guidance should be in the form of printed literature and strip maps rather than trail signing.

**Option:**

Trail signs may be installed on a highway if they have been approved by the appropriate transportation agency.

**Section 2D.51 Crossover Signs (D13 Series)****Option:**

Crossover signs may be installed on divided highways to identify median openings not otherwise identified by warning or other guide signs.

**Standard:**

**A CROSSOVER (D13-1) sign (see Figure 2D-12) shall not be used to identify a median opening that is permitted to be used only by official or authorized vehicles. If used, the sign shall be a horizontal rectangle of appropriate size to carry the word CROSSOVER and a horizontal directional arrow. The CROSSOVER sign shall have a white legend and border on a green background.**

**Guidance:**

If used, the CROSSOVER sign should be installed immediately beyond the median opening, either on the right side of the roadway or in the median.

**Option:**

The Advance Crossover (D13-2) sign (see Figure 2D-12) may be installed in advance of the CROSSOVER sign to provide advance notice of the crossover.

**Standard:**

**If used, the Advance Crossover sign shall be a horizontal rectangle of appropriate size to carry the word CROSSOVER and the distance to the median opening. The sign shall have white legend and border on a green background.**

**Guidance:**

The distance shown on the Advance Crossover sign should be 1 MILE, 1/2 MILE, or 1/4 MILE), unless unusual conditions require some other distance. If used, the sign should be installed either on the right side of the roadway or in the median at approximately the distance shown.

**Section 2D.52 National Scenic Byways Signs (D6-4, D6-4a)****Support:**

Certain roads have been designated by the U.S. Secretary of Transportation as National Scenic Byways or All-American Roads based on their archeological, cultural, historic, natural, recreational, or scenic qualities.

**Option:**

Highway agencies may install the National Scenic Byways (D6-4 or D6-4a) signs at entrance points to a route that has been recognized by the U.S. Secretary of Transportation as a National Scenic Byway or an All-American Road. The D6-4 or D6-4a sign may be installed on route sign assemblies (see Figure 2D-14) or as part of larger roadside structures. National Scenic Byways signs may also be installed at periodic intervals along the designated route and at intersections where the designated route turns or follows a different numbered highway. At locations where roadside features have been developed to enhance the traveler's experience such as rest areas, historic sites, interpretive facilities, or scenic overlooks, the National Scenic Byways sign may be placed on the associated sign assembly to inform travelers that the site contributes to the byway travel experience.

**Standard:**

**When a National Scenic Byways sign is installed on a National Scenic Byway or an All-American Road, the design shown for the D6-4 or D6-4a sign in Figure 2D-14 shall be used. Use of this design shall be limited to routes that have been designated as a National Scenic Byway or All-American Road by the U.S. Secretary of Transportation.**

**If used, the D6-4 or D6-4a sign shall be placed such that the roadway route signs have primary visibility for the road user.**

**Section 2D.53 Ohio Byway Signs (M8-H3, M8-H3p)****Support:**

Certain roads have been designated by the Ohio Department of Transportation (ODOT) as Ohio Byways based on their archeological, cultural, historic, natural, recreational, or scenic qualities.

**Standard:**

**A route designated by ODOT as an Ohio Byway shall be signed.**

**Guidance:**

The Ohio Byway (M8-H3) sign should be used to mark these designated routes (see Appendix C).

The sign should be installed in a manner similar to other route signs. Ohio Byway signs should be installed in both directions along an established route. A sign should be installed at the beginning of the route, in advance of and at turns in the route, and an Ohio Byways sign with an END (M4-6) auxiliary sign should be installed at the end of the route. Additional signs should be installed at 8 to 15 km (5 to 10 mi) intervals and at other key locations along the route.

Auxiliary signs used with Ohio Byway signs should have a white legend on a green background.

**Option:**

An Ohio Byway sign may be installed after a turn to confirm the routing, and on major intersecting highways advising of the junction with the designated route.

The Ohio Byway sign may be installed in an assembly with other route signs.

The Ohio Byway (M8-H3p) supplemental sign may be used to identify the name of the byway (see Appendix C).

**Guidance:**

If used, the M8-H3p supplemental sign should be mounted below the Ohio Byway sign.

**Figure 2D-14. Examples of Use of the National Scenic Byways Sign**



D6-4



D6-4a



## **CHAPTER 2E. GUIDE SIGNS—FREEWAYS AND EXPRESSWAYS**

### **Section 2E.01 Scope of Freeway and Expressway Guide Sign Standards**

#### **Support:**

These standards provide a uniform and effective system of highway signing for high-volume, high-speed motor vehicle traffic on freeways and expressways. The requirements and specifications for expressway signing exceed those for conventional roads (see Chapter 2D), but are less than those for freeway signing. Since there are many geometric design variables to be found in existing roads, a signing concept commensurate with prevailing conditions is the primary consideration. Section 2A.01 includes definitions of freeway and expressway.

Guide signs for freeways and expressways are identified by the sign type and/or code number. Ohio's Freeway and Expressway Guide Sign Design Method is detailed in Appendix C of the "Sign Design Manual" (SDM) (see Section 1A.11). It is based on a Sign Level system. Types of signs are assigned different levels (i.e., 0, 1, 2, 3 and 4). For example, an overhead-mounted Pull-Thru Sign is a level 1 sign and a Memorial Highway sign is level 3. The level assignment is used to determine the size of elements used in the design of the sign. The design method described in Appendix C of the SDM also applies to entrance ramp approach signs on roads intersecting freeways and expressways.

#### **Standard:**

**The standards prescribed herein for freeway or expressway guide signing shall apply to any highway that meets the definition of such facilities.**

### **Section 2E.02 Freeway and Expressway Signing Principles**

#### **Support:**

The development of a signing system for freeways and expressways is approached on the premise that the signing is primarily for the benefit and direction of road users who are not familiar with the route or area. The signing furnishes road users with clear instructions for orderly progress to their destinations. Sign installations are an integral part of the facility and, as such, are best planned concurrently with the development of highway location and geometric design. For optimal results, plans for signing are analyzed during the earliest stages of preliminary design, and details are correlated as final design is developed. The excessive signing found on many major highways usually is the result of using a multitude of signs that are too small and that are poorly designed and placed to accomplish the intended purpose.

Freeway and expressway signing is to be considered and developed as a planned system of installations. An engineering study is sometimes necessary for proper solution of the problems of many individual locations, but, in addition, consideration of an entire route is necessary.

#### **Guidance:**

Road users should be guided with consistent signing on the approaches to interchanges, when they drive from one State to another, and when driving through rural or urban areas. Because geographical, geometric, and operating factors regularly create significant differences between urban and rural conditions, the signing should take these conditions into account.

Guide signs on freeways and expressways should serve distinct functions as follows:

- A. Give directions to destinations, or to streets or highway routes, at intersections or interchanges;
- B. Furnish advance notice of the approach to intersections or interchanges;
- C. Direct road users into appropriate lanes in advance of diverging or merging movements;
- D. Identify routes and directions on those routes;
- E. Show distances to destinations;
- F. Indicate access to general motorist services, rest, scenic, and recreational areas; and
- G. Provide other information of value to the road user.

### **Section 2E.03 General**

Support:

Signs are designed so that they are legible to road users approaching them and readable in time to permit proper responses. Desired design characteristics include: (a) long visibility distances, (b) large lettering and symbols, and (c) short legends for quick comprehension.

**Standard:**

**Standard shapes and colors shall be used so that traffic signs can be promptly recognized by road users.**

### **Section 2E.04 Color of Guide Signs**

**Standard:**

**Guide signs on freeways and expressways, except as noted herein, shall have white letters, symbols, and borders on a green background.**

Support:

Color requirements for route signs and trailblazers, signs with blank-out or changeable messages, signs for services, rest areas, park and recreational areas, and for certain miscellaneous signs are specified in the individual sections dealing with the particular sign or sign group.

### **Section 2E.05 Retroreflection or Illumination**

**Standard:**

**Letters, numerals, symbols, and borders of all guide signs shall be retroreflectorized. The background of all guide signs that are not independently illuminated shall be retroreflective.**

Support:

Where there is no serious interference from extraneous light sources, retroreflectorized ground-mounted signs usually provide adequate nighttime visibility.

On freeways and expressways where much driving at night is done with low-beam headlights, the amount of headlight illumination incident to an overhead sign display is relatively small.

Guidance:

Overhead sign installations should be illuminated unless an engineering study shows that retroreflectorization alone will perform effectively. The type of illumination chosen should provide effective and reasonably uniform illumination of the sign face and message.

### **Section 2E.06 Characteristics of Urban Signing**

Support:

Urban conditions are characterized not so much by City limits or other arbitrary boundaries, as by the following features:

- A. Mainline roadways with more than two lanes in each direction;
- B. High traffic volumes on the through roadways;
- C. High volumes of traffic entering and leaving interchanges;
- D. Interchanges closely spaced;
- E. Roadway and interchange lighting;
- F. Three or more interchanges serving the major City;
- G. A loop, circumferential, or spur serving a sizable portion of the urban population; and
- H. Visual clutter from roadside development.

Operating conditions and road geometrics on urban freeways and expressways usually make special sign treatments desirable, including:

- A. Use of Interchange Sequence signs (see Section 2E.37);
- B. Use of sign spreading to the maximum extent possible (see Section 2E.10);
- C. Elimination of service signing (see Section 2E.51);
- D. Reduction to a minimum of post-interchange signs (see Section 2E.35);
- E. Display of advance signs at distances closer to the interchange, with appropriate adjustments in the legend (see Section 2E.30);
- F. Use of overhead signs on roadway structures and independent sign supports (see Section 2E.22);
- G. Use of diagrammatic signs in advance of intersections and interchanges (see Section 2E.19); and
- H. Frequent use of street names as the principal message in guide signs.

Lower speeds which are often characteristic of urban operations do not justify lower signing standards. Typical traffic patterns are more complex for the road user to negotiate, and large, easy-to-read legends are, therefore, just as necessary as on rural highways.

### **Section 2E.07 Characteristics of Rural Signing**

Support:

Rural areas ordinarily have greater distances between interchanges, which permits adequate spacing for the sequences of signs on the approach to and departure from each interchange. However, the absence of traffic in adjoining lanes and on entering or exiting ramps often adds monotony or inattention to rural driving. This increases the importance of signs that call for decisions or actions.

Guidance:

Where there are long distances between interchanges and the alignment is relatively unchanging, signs should be positioned for their best effect on road users. The tendency to group all signing in the immediate vicinity of rural interchanges should be avoided by considering the entire route in the development of sign plans. Extra effort should be given to the placement of signs at natural target locations to command the attention of the road user, particularly when the message requires an action by the road user.

### **Section 2E.08 Memorial Highway Signing (E8-H5, M1-10)**

Support:

See Section 2D.49 and Part 2 of the ODOT "Traffic Engineering Manual" (see Section 1A.11) for background information on memorializing highways or bridges in Ohio.

Guidance:

Freeways and expressways should not be signed as memorial highways. If a route, bridge, or highway component is officially designated as a memorial, and if notification of the memorial is to be made on the highway right-of-way, such notification should consist of installing a memorial plaque in a rest area, scenic overlook, recreational area, or other appropriate location where parking is provided with the signing inconspicuously located relative to vehicle operations along the highway.

Option:


If the installation of a memorial plaque off the main roadway is not practical, a memorial sign may be installed on the mainline.

The Eisenhower Interstate System (M1-10) sign (see Figure 2E-11) is a special Route sign that may be used off the main roadway on Interstate Routes nationally.

**Standard:**

**Where such memorial signs are installed on the mainline, (1) memorial names shall not appear on directional guide signs, (2) memorial signs shall not interfere with the placement of any other necessary highway signing, and (3) memorial signs shall not compromise the safety or efficiency of**

**Figure 2E-1. Example of Guide Sign Spreading**



**Figure 2E-2. Pull-Through Signs**



traffic flow. The memorial signing shall be limited to one sign at an appropriate location in each route direction.

If used on the mainline, the sign shall be similar to the E8-H5 used on ODOT-maintained freeways and expressways (see Appendix C).

### **Section 2E.09 Amount of Legend on Guide Signs**

Guidance:

No more than two destination names or street names should be shown on any Advance Guide sign or Exit Direction sign.

The route and destination information on Advance Guide signs and Exit Direction signs should be limited to a total of three lines. This is in addition to the distance information on the Advance Guide sign and the directional arrow on the Exit Direction signs.

The legend sequence from top to bottom should be route shield information, street name(s), and the destination name(s). This sequence should remain the same even when one or more of these components is not included.

When appropriate, cardinal direction information should be included either above or beside the shield(s). Regardless of the number of route shields used, and the presence or absence of cardinal direction information, the route shield component of the sign is considered as one line.

**Option:**

Sign legends may include symbols, route numbers, arrows, cardinal directions, and exit instructions.

Community names may be included on signs which contain street names, or on signs which contain route shield information and a street name.

Where insufficient space exists, destination names may be included on a Supplemental Guide sign.

**Section 2E.10 Number of Signs at an Overhead Installation and Sign Spreading**

**Guidance:**

If overhead signs are warranted, as set forth in Section 2A.17, the number of signs at these locations should be limited to only those essential in communicating pertinent destination information to the road user. Exit Direction signs for a single exit and the Advance Guide signs should have only one panel with one or two destinations. Regulatory signs, such as speed limits, should not be used in conjunction with overhead guide sign installations. Because road users have limited time to read and comprehend sign messages, there should not be more than three guide signs displayed at any one location either on the overhead structure or its support.

**Option:**

At overhead locations, more than one sign may be installed to advise of a multiple exit condition at an interchange. If the roadway ramp or crossing roadway has complex or unusual geometrics, additional signs with confirming messages may be provided to properly guide the road user.

**Support:**

Sign spreading is a concept where major overhead signs are spaced so that road users are not overloaded with a group of signs at a single location. Figure 2E-1 illustrates an example of sign spreading.

**Guidance:**

Where overhead signing is used, sign spreading should be used at all single exit interchanges and to the extent possible at multi-exit interchanges. Sign spreading should be accomplished by use of the following:

- A. The Exit Direction sign should be the only sign used in the vicinity of the gore (other than the Gore sign). It should be located overhead near the theoretical gore and generally on an overhead sign support structure.
- B. The Advance Guide sign to indicate the next interchange exit should be placed near the crossroad location. If the crossroad goes over the mainline, the Advance Guide sign should be placed on the overcrossing structure.

**Section 2E.11 Pull-Through Signs (E6-H2)**

**Support:**

Pull-Through signs (see Figure 2E-2) are overhead lane use signs intended for through traffic.

**Guidance:**

Pull-Through signs should be used where the geometrics of a given interchange are such that it is not clear to the road user as to which is the through roadway, or where additional route guidance is desired. Pull-Through signs with down arrows should be used where the alignment of the through lanes is curved and the exit direction is straight ahead, where the number of through lanes is not readily evident, and at multi-lane exits where there is a reduction in the number of through lanes.

## **Section 2E.12 Designation of Destinations**

### **Standard:**

**The direction of a freeway and the major destinations or control cities (see Section 2D.34) along it shall be clearly identified through the use of appropriate destination legends. Successive freeway guide signs shall provide continuity in destination names and consistency with available map information. At any decision point, a given destination shall be indicated by way of only one route.**

### **Guidance:**

Control city legends should be used in the following situations along a freeway:

- A. At interchanges between freeways;
- B. At separation points of overlapping freeway routes;
- C. On directional signs on intersecting routes, to guide traffic entering the freeway;
- D. On Pull-Through signs; and
- E. On the bottom line of post-interchange distance signs.

### **Support:**

Continuity of destination names is also useful on expressways serving long-distance or intrastate travel.

The determination of major destinations or control cities is important to the quality of service provided by the freeway. Control cities on freeway guide signs are selected by the States and are contained in the "List of Control Cities for Use in Guide Signs on Interstate Highways," published and available from American Association of State and Highway Transportation Officials (see the Preface for AASHTO's address). Additional information, including a list of the control cities identified for Ohio's Interstate Highway System is provided in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

## **Section 2E.13 Size and Style of Letters and Signs**

### **Standard:**

**With all freeway and expressway signs, the message dimensions shall be determined first, and the outside sign dimensions secondarily. Word messages in the legend of expressway guide signs shall be in letters at least 200 mm (8 in) high. Larger lettering shall be used for major guide signs at or in advance of interchanges and for all overhead signs. Minimum numeral and letter sizes for freeway and expressway guide signs are provided in Appendix C of the SDM. All names of places, streets, and highways on freeway and expressway guide signs shall be composed of lower-case letters with initial upper-case letters. The letters and the numerals used shall be Series E(M) as shown in the SDM (see Section 1A.11). Other word legends shall be in capital letters.**

**Lettering size on freeway and expressway signs shall be the same for both rural and urban conditions.**

### **Support:**

Sign size is determined primarily in terms of the length of the message and the size of the lettering necessary for proper legibility. Letter style and height, and arrow design have been standardized for freeway and expressway signs to assure uniform and effective application.

Designs for upper-case, lower-case, and capital alphabets together with tables of recommended letter spacing, are shown in the SDM (see Section 1A.11).

### **Guidance:**

Where upper- and lower-case lettering is used, the initial upper-case letters should be approximately 1.33 times the "loop" height of the lower-case letters. Freeway lettering sizes should be used when expressway geometric design is comparable to freeway standards.

Other sign letter size requirements not specifically identified elsewhere in this Manual should be guided by these specifications. Abbreviations should be kept to a minimum.

Support:

A sign mounted over a particular roadway lane to which it applies might have to be limited in horizontal dimension to the width of the lane, so that another sign can be placed over an adjacent lane. The necessity to maintain proper vertical clearance might also place a further limitation on the size of the overhead sign and the legend that can be accommodated.

#### **Section 2E.14 Interline and Edge Spacing**

Guidance:

The interline and edge spacings specified in Ohio's Freeway and Expressway Guide Sign Design Method described in Appendix C of the SDM (see Section 1A.11) should be used.

#### **Section 2E.15 Sign Borders**

**Standard:**

**Signs shall have a border of the same color as the legend in order to outline their distinctive shape and thereby give them easy recognition and a finished appearance.**

Guidance:

The border color, border widths and corner radii specified in Ohio's Freeway and Expressway Guide Sign Design Method described in Appendix C of the SDM (see Section 1A.11) should be used.

Option:

The sign material in the area outside of the corner radius may be trimmed.

#### **Section 2E.16 Abbreviations**

Guidance:

Abbreviations should be kept to a minimum; however, they are useful when complete destination messages produce excessively long signs. If used, abbreviations should be unmistakably recognized by road users (see Section 1A.14).

Periods should not be used unless a cardinal direction is abbreviated as part of a destination name.

**Standard:**

**The words NORTH, SOUTH, EAST, and WEST shall not be abbreviated when used with route signs to indicate cardinal directions on guide signs.**

#### **Section 2E.17 Symbols**

**Standard:**

**Symbol designs shall be essentially like those shown in this Manual and in Appendix A of the SDM (see Section 1A.11).**

Guidance:

A special effort should be made to balance legend components for maximum legibility of the symbol with the rest of the sign.

Option:

Educational plaques may be used below symbol signs where needed.

#### **Section 2E.18 Arrows for Interchange Guide Signs**

**Standard:**

**On all Exit Direction signs, both overhead and ground mounted, arrows shall be upward slanting and shall be located on the side of the sign consistent with the direction of the exiting movement.**

**Downward pointing arrows shall be used only for overhead guide signs to prescribe lane assignment for traffic bound for a destination or route that can be reached only by being in the designated lane(s).**

Option:

Downward pointing arrows may be tilted where it is desired to emphasize the separation of roadways.

Support:

Examples of arrows for use on guide signs are shown in Figure 2D-2. Detailed dimensions of arrows are provided in the SDM (see Section 1A.11).

### **Section 2E.19 Diagrammatic Signs (E4-H1)**

Support:

Diagrammatic signs are guide signs that show a graphic view of the exit arrangement in relationship to the main highway. Use of such guide signs has been shown to be superior to conventional guide signs for some interchanges.

**Standard:**

**Diagrammatic (E4-H1) signs shall be designed in accordance with the following criteria:**

- A. The graphic legend shall be of a plan view showing the off-ramp arrangement (see Figure 2E-3).**
- B. No other symbols or route shields shall be used as a substitute for arrowheads.**
- C. They shall not be installed at the exit direction location (see Section 2E.33).**
- D. The EXIT ONLY panel shall not be used on diagrammatic signs at any major split.**

Guidance:

Diagrammatic signs should be designed in accordance with the following additional criteria:

- A. The graphic should not depict deceleration lanes.
- B. No more than one destination should be shown for each arrowhead, and no more than two destinations should be shown per sign.
- C. A black on yellow EXIT ONLY panel should be used to supplement a lane drop graphic.
- D. The shaft for the exit ramp movement should be shorter than, but not separated from, the through movement graphic. Where the movements are freeway splits rather than exits, the shafts should be equal in length.
- E. Arrow shafts should contain lane lines where appropriate.
- F. Route shields, cardinal directions, and destinations should be clearly related to the arrowhead, and the arrowhead should point toward the route shield for the off movement.
- G. The cardinal direction should be placed adjacent to the route shield, and the destination should be placed below and justified with the route shield.

Diagrammatic signs should be used at the Advance Guide sign location(s) for the following:

- A. Left exits (see Figure 2E-3).
- B. Splits where the off-route movement is to the left (see Figure 2E-4).
- C. Optional lane splits for non-overlapping routes (see Figure 2E-5).
- D. Where a two-lane exit has an optional lane that carries the through route (see Figures 2E-6 and 2E-7). These interchanges create serious expectancy problems for drivers who are unfamiliar with the interchange.
- E. Left exit interchange lane drop situations. In this situation, an EXIT ONLY (E11-1c) panel should be used without a down arrow for Advance Guide signs (see Figures 2E-8 and 2E-9).

**Standard:**

**Diagrammatic signs have been shown to be inferior to conventional signs at cloverleaf interchanges and shall not be used at these locations.**

**Figure 2E-3. Diagrammatic Sign for a Single-Lane Left Exit**

E4-H1

\* The upper half of a Left Exit plaque, which contains the word LEFT, may have a black legend and border on a yellow background.

**Support:**

Specific guidelines for more detailed design of diagrammatic signs are contained in Appendix C of the SDM (see Section 1A.11).

**Section 2E.20 Signing for Interchange Lane Drops****Standard:**

**Major guide signs for all lane drops at interchanges shall be mounted overhead. An EXIT ONLY panel shall be used for all interchange lane drops at which the through route is carried on the mainline.**

**Guidance:**

On all signing of lane drops for right exits, the bottom portion of the Advance Guide signs should be yellow with black legend EXIT ONLY (down arrow) and a black border (see Figure 2E-10). For lane drops on the left side, diagrammatic signing with the EXIT ONLY (E11-1c) panel (see Figure 2E-9) should be used without a down arrow for Advance Guide signs (see Figure 2E-8).


**Standard:**

**The Exit Direction sign (see Figure 2E-20) with the bottom portion of the sign yellow with black legend of EXIT ONLY and a black border shall be of the format shown in Figures 2E-8 and 2E-10 for all lane drops. The standard slanted up arrow (left or right side) shall be included on the Exit Direction sign.**


**Guidance:**

On the yellow portion of the Advance Guide and Exit Direction signs, the black border should extend to the edge of the signs to provide continuity with the white border on the green portion of the signs.


**Figure 2E-4. Diagrammatic Signs for Split with Dedicated Lanes**




**Figure 2E-5. Diagrammatic Signs for Split with Optional Lanes**



**Figure 2E-6. Diagrammatic Signs for Two-Lane Exit with Optional Lane**




**Figure 2E-7. Diagrammatic Signs for Two-Lane Exit with Optional Lane**



Note: Figures 2D-3 and 2D-4 show the correct design of an Ohio State Route Sign.

**Figure 2E-8. EXIT ONLY on Left with Diagrammatic Sign for Left Lane Dropped at an Interchange**



\* The upper half of a Left Exit plaque, which contains the word LEFT, may have a black legend and border on a yellow background.  
 \*\* Designs for the EXIT ONLY panels are available in the "Sign Design Manual."

**Figure 2E-9. EXIT ONLY Panels**

E11-1



E11-1a



E11-1b



E11-1c

Note: Additional variations in design of EXIT ONLY panels are shown in Appendix C of the SDM. For new signs, the EXIT ONLY message is typically designed as part of the overall sign; therefore, code numbers for the E11-1 and E11-1a are shown here only for descriptive purposes.

#### Option:

EXIT ONLY messages of either E11-1b or E11-1c formats may be used to retrofit existing signing to warn of a lane drop situation ahead.

#### Standard:

**If used on an existing sign, the E11-1b panel (see Figure 2E-9) shall be placed on either side of a white down arrow. The E11-1c panel, if used on an existing nondiagrammatic sign, shall be placed between the lower destination message and the white down arrow.**

#### Guidance:

Advance Guide signs for lane drops within 2 km or 1 mile of the interchange should not contain the distance message.

Wherever the dropped lane carries the through route, diagrammatic signs should be used without the EXIT ONLY panel.

### Section 2E.21 Changeable Message Signs


#### Standard:

**Changeable message signs shall be capable of displaying several messages in a sequence. Such messages shall be changed manually, by remote control, or by automatic controls. Changeable message signs shall display pertinent traffic operational and guidance information only, not advertising.**

#### Support:

Because technology for changeable message signs continues to advance, a specific standard for changeable message signs is not practical. Considerations that influence the selection of the best sign for a particular application include conspicuity, legibility, operation, and maintenance of the changeable message sign. This Section applies to signs for use on freeway and expressway mainlines. It is recognized that similar signs might be used on ramps and at ramp terminals where smaller letter heights and the number of messages might differ from the provisions of this Section.

**Figure 2E-10. EXIT ONLY Panels for Right Lane Dropped at an Interchange**



Notes: Figures 2D-3 and 2D-4 show the correct design of an Ohio State Route Sign. Designs for the EXIT ONLY panels are in the "Sign Design Manual."

**Guidance:**

To the extent practical, the design and application of changeable message signs should conform to the general principles of this Manual. Within the context of Section 2A.07, these practices should be followed for mainline freeway and expressway applications:

- A. Changeable message signs should be capital letters and have a desirable letter size of 450 mm (18 in) or a minimum letter size of 265 mm (10.6 in). Signs should be limited to not more than 3 lines with not more than 20 characters per line.
- B. No more than two displays should be used within any message cycle.
- C. Each display should convey a single thought.
- D. The entire message cycle should be readable at least twice by drivers traveling at the posted speed, the off-peak 85th-percentile speed, or the operating speed.

**Standard:**

**Messages shall be centered within each line of legend. If more than one changeable message sign is visible to road users, then only one such sign shall display a sequential message at any given time.**

**A three-line changeable message sign shall be limited to not more than two messages. Techniques of message display such as fading, exploding, dissolving, or moving messages shall not be used.**

**Section 2E.22 Overhead Sign Installations****Support:**

Specifications for the design and construction of structural supports for highway signs have been standardized by the American Association of State Highway and Transportation Officials (AASHTO). Overcrossing structures can often serve for the support of overhead signs, and might in some cases be the only practical location that will provide adequate viewing distance. Use of these structures as sign supports will eliminate the need for additional sign supports along the roadside. Factors justifying the installation of overhead signs are given in Section 2A.17. Vertical clearance of overhead signs is discussed in Section 2A.18.

**Section 2E.23 Lateral Offset****Standard:**

**The minimum lateral clearance outside the usable roadway shoulder for ground-mounted freeway and expressway signs or for overhead sign supports, either to the right or left side of the roadway, shall be 1.8 m (6 ft). This minimum clearance shall also apply outside of a barrier curb. If located within the clear zone, the signs shall be mounted on crashworthy supports or shielded by appropriate crashworthy barriers.**

**Guidance:**


Where practical, a sign should not be less than 3 m (10 ft) from the edge of the nearest traffic lane. Large guide signs especially should be farther removed, preferably 9 m (30 ft) or more from the nearest traffic lane.

Where an expressway median is 3.7 m (12 ft) or less in width, consideration should be given to spanning both roadways without a center support.

Where overhead sign supports cannot be placed a reasonably safe distance away from the line of traffic or in an otherwise protected site, they should either be designed to minimize the impact forces, or be adequately shielded by a physical barrier or guardrail of suitable design.

**Standard:**

**Butterfly-type sign supports and other overhead noncrashworthy sign supports shall not be installed in gores or other unprotected locations within the clear zone.**

**Figure 2E-11. Interstate and U.S. Route Signs****Option:**

Lesser clearances, but not generally less than 1.8 m (6 ft), may be used on connecting roadways or ramps at interchanges.

**Section 2E.24 Guide Sign Classification****Support:**

Freeway and expressway guide signs are classified and treated in the following categories:

- A. Route signs and Trailblazer Assemblies (see Section 2E.25);
- B. At-Grade Intersection signs (see Section 2E.26);
- C. Interchange signs (see Sections 2E.27 through 2E.36);
- D. Interchange Sequence signs (see Section 2E.37);
- E. Community Interchanges Identification signs (see Section 2E.38);
- F. NEXT X EXITS signs (see Section 2E.39);
- G. General Service signs (see Section 2E.51);
- H. Rest and Scenic Area signs (see Section 2E.52);
- I. Tourist Information and Welcome Center signs (see Section 2E.53);
- J. Reference Location signs (see Section 2E.54);
- K. Miscellaneous guide signs (see Section 2E.55);
- L. Radio Information signing (see Section 2E.56);
- M. Carpool and Ridesharing signing (see Section 2E.57);
- N. Weigh Station signing (see Section 2E.58);
- O. Specific Service signs (see Chapter 2F); and
- P. Recreational and Cultural Interest Area signs (see Chapter 2H).

## **Section 2E.25 Route Signs and Trailblazer Assemblies**

### **Standard:**

**The official Route sign for the Interstate Highway System shall be the red, white, and blue retroreflective distinctive shield adopted by the American Association of State Highway and Transportation Officials (see Section 2D.11).**

### **Guidance:**

Route signs (see Figure 2E-11) should be incorporated as cut-out shields or other distinctive shapes on large directional guide signs. Where the Interstate shield is displayed in an assembly or on the face of a guide sign with U.S. or State Route signs, the Interstate numeral should be at least equal in size to the numerals on the other Route signs. The use of independent Route signs should be limited primarily to route confirmation assemblies.

Route signs and auxiliary signs showing junctions and turns should be used for guidance on approach roads, for route confirmation just beyond entrances and exits, and for reassurance along the freeway or expressway. When used along the freeway or expressway, the Route signs should be enlarged as shown in the SDM (see Section 1A.11). When independently mounted Route signs are used in place of Pull-Through signs, they should be located just beyond the exit.

### **Option:**

The standard Trailblazer Assembly (see Section 2D.32) may be used on roads leading to the freeway or expressway. Component parts of the Trailblazer Assembly may be included on a single sign panel. Independently mounted Route signs may be used instead of Pull-Through signs as confirmation information (see Section 2E.11). The commonly used name or trailblazer symbol for a toll facility may be displayed on nontoll sections of the Interstate Highway System at:

- A. The last exit before entering a toll section of the Interstate Highway System;
- B. The interchange or connection with a toll facility, whether or not the toll facility is a part of the Interstate Highway System; and
- C. Other locations within a reasonable approach distance of toll facilities when the name or trailblazer symbol for the toll facility would provide better guidance to road users unfamiliar with the area than would place names and route numbers.

The toll facility name or symbol may be included as a part of the guide sign installations on intersecting highways and approach roads to indicate the interchange with a toll section of an Interstate route. Where needed for the proper direction of traffic, a trailblazer for a toll facility that is part of the Interstate Highway System may be displayed with the Interstate Trailblazer Assembly.

## **Section 2E.26 Signs for Intersections at Grade**

### **Guidance:**

If there are intersections at grade within the limits of an expressway, guide sign types specified in Chapter 2D should be used. However, such signs should be of a size compatible with the size of other signing on the expressway.

### **Support:**

Additional information about this type of signing on ODOT-maintained highways is provided in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

### **Option:**

Advance Guide signs for intersections at grade may take the form of diagrammatic layouts depicting the geometrics of the intersection along with essential directional information.

## **Section 2E.27 Interchange Guide Signs**

### **Standard:**

**The signs at interchanges and on their approaches shall include Advance Guide signs and Exit Direction signs. Consistent destination messages shall be displayed on these signs.**

### **Guidance:**

New destination information should not be introduced into the major sign sequence for one interchange, nor should destination information be dropped.

Reference should be made to Section 2E.10 and Sections 2E.30 through 2E.39 for a detailed description of the signs in the order that they should appear at the approach to and beyond each interchange. Guide signs placed in advance of an interchange deceleration lane should be spaced at least 245 m (800 ft) apart.

Supplemental guide signing should be used sparingly as provided in Section 2E.32.

## **Section 2E.28 Interchange Exit Numbering (E1-H5)**

### **Support:**

Interchange exit numbering provides valuable orientation for the road user on a freeway or expressway. The feasibility of numbering interchanges or exits on an expressway will depend largely on the extent to which grade separations are provided. Where there is appreciable continuity of interchange facilities, interrupted only by an occasional intersection at grade, the numbering will be helpful to the expressway user.

### **Standard:**

**Except as noted in the Option below, interchange numbering shall be used in signing each freeway interchange exit. Interchange exit numbers shall be displayed with each Advance Guide sign, Exit Direction sign, and Gore sign. The exit number shall be displayed on a separate plaque at the top of the Advance Guide or Exit Direction sign. The standard exit number plaque shall include the word EXIT, the appropriate exit number, and the suffix letter (on multi-exit interchanges) separated from the exit number by a space in a single-line format on a plaque (see Figure 2E-15). Exit numbers shall not include the cardinal initials corresponding to the directions of the cross route. Designs for Exit number plaques (E1-H5) are shown in Appendix C of the SDM (see Section 1A.11). If used, the interchange numbering system for expressways shall conform to the provisions prescribed for freeways.**

**The reference location sign numbering system shall be used in designating exit numbers.**

### **Option:**

For routes which are not continuous as freeways for their entire length within the State, or are continuous as freeways for their entire length within the State but are shorter than 40 km (25 mi) in length, the use of interchange exit numbering is not required.

### **Support:**


Exit numbers may also be used with Supplemental Guide signs and Road User Service signs.

### **Guidance:**


Exit number plaques should be located toward the top left edge of the sign for a left exit and toward the top right edge for right exits.

Because road users might not expect a left exit and might have difficulty in maneuvering to the left, the word LEFT should be added to the exit number plaque (see Figure 2E-3). Where a left exit is not numbered (no exit number plaque), a plaque with the word LEFT should be added to the top left edge of the sign.


**Figure 2E-12. Example of Interchange Numbering for Mainline and Circumferential Routes**



**Figure 2E-13. Example of Interchange Numbering for Mainline, Loop, and Spur Routes**



**Figure 2E-14. Example of Interchange Numbering If Routes Overlap**



**Option:**

The portion of the exit number plaque containing the word LEFT may have a black legend and border on a yellow background.

**Support:**

The general plan for numbering interchange exits is shown in Figures 2E-12 through 2E-14.

Example exit number plaque designs are shown in Figures 2E-3 and 2E-15. Figures 2E-1, 2E-20, 2E-23, 2E-27 through 2E-32, and 2E-42 illustrate the incorporation of exit number plaques on guide signs.

**Standard:**

**Where a route originates within Ohio, the southernmost or westernmost terminus shall be the beginning point for numbering. If a loop, spur, or circumferential route crosses State boundaries, the sequence of numbering shall be coordinated by the States to provide continuous numbering.**

**For circumferential routes, the numbering of interchanges shall be in a clockwise direction. The numbering shall begin with the first interchange west of the south end of an imaginary north-south line bisecting the circumferential route, at a radial freeway or other Interstate route, or some other conspicuous landmark in the circumferential route near a south polar location (see Figure 2E-12). The interchange numbers on loop routes shall begin at the loop interchange nearest the south or west mainline junction and increase in magnitude toward the north or east mainline junction (see Figure 2E-13). Spur route interchanges shall be numbered in ascending order starting at the interchange where the spur leaves the mainline of the principal route (see Figure 2E-13).**

**Where numbered routes overlap, continuity of interchange numbering shall be established for only one of the routes (see Figure 2E-14). If one of the routes is an Interstate, the Interstate route shall maintain continuity of interchange numbering.**

**Guidance:**

The route chosen for continuity of interchange numbering should also have reference location sign continuity (see Figure 2E-14).

**Section 2E.29 Interchange Classification****Support:**

For signing purposes, interchanges are sometimes classified as major, intermediate, and minor. However, Ohio's Freeway and Expressway Guide Sign Design Method is not dependent on interchange classifications.

**Section 2E.30 Advance Guide Signs (E1-H1)****Support:**


The Advance Guide (E1-H1) sign gives notice well in advance of the exit point of the principal destinations served by the next interchange and the distance to that interchange (see Figure 2E-15).

**Guidance:**

Advance Guide signs should be placed at 1 km or 0.5 miles and at 2 km or 1 mile in advance of the exit with a third Advance Guide sign placed at 4 km (2 mi) in advance of the exit if spacing permits. If the sign is located less than 1 km or 0.5 miles from the exit, the distance shown should be to the nearest 1/4 mile. Fractions of a mile, rather than decimals, should be shown in all cases.

Where Advance Guide signs are provided for a left exit, diagrammatic signs should be used (see Figure 2E-3).


**Figure 2E-15. Examples of Interchange Advance Guide Signs**



E1-H1

E1-H1

Note: Delete word EXIT(S) if exit number is used.



E1-H1

E1-H1



E1-H5  
Exit Number Plaque

**Figure 2E-16. Next Exit Supplemental Advance Guide Signs**

E2-H1



E2-H1a

**Standard:**

When used, Advance Guide signs shall contain the distance message. The legend on the Advance Guide signs shall be the same as the legend on the Exit Direction sign, except that the last line shall read EXIT X MILES. If the interchange has two or more exit roadways, the bottom line shall read EXITS X MILES.

**Option:**

Where interchange exit numbers are used, the word EXIT may be omitted from the bottom line. Where the distance between interchanges is more than 2 km or 1 mile, but less than 4 km or 2 miles, the first Advance Guide sign may be closer than 4 km or 2 miles, but not placed so as to overlap the signing for the previous exit. Duplicate Advance Guide signs or Interchange Sequence Series signs may be placed in the median on the opposite side of the roadway and are not included in the minimum requirements of interchange signing.

**Guidance:**

Where there is less than 245 m (800 ft) between interchanges, Interchange Sequence Series signs should be used instead of Advance Guide signs for the affected interchanges.

**Section 2E.31 Next Exit Supplemental Signs (E2-H1, E2-H1a)****Option:**

Where the distance to the next interchange is unusually long, Next Exit supplemental (E2-H1, E2-H1a) signs may be installed to inform road users of the distance to the next interchange (see Figure 2E-16).

**Guidance:**

The Next Exit supplemental sign should not be used unless the distance between successive interchanges is more than 8 km (5 mi).

**Standard:**

**The Next Exit supplemental sign shall carry the legend NEXT EXIT X MILES. If the Next Exit supplemental sign is used, it shall be placed below the Advance Guide sign nearest the interchange. It shall be mounted so as to not adversely affect the breakaway feature of the sign support structure.**

Option:

**The legend for the Next Exit supplemental sign may be displayed in either one or two lines. The one-line message is the more desirable choice unless the message causes the sign to have a horizontal dimension greater than that of the Advance Guide sign.**

**Section 2E.32 Other Supplemental Guide Signs (D4-H2a, D4-H2b, E3-H1)**

Support:

Supplemental Guide signs can be used to provide information regarding destinations accessible from an interchange, other than places shown on the standard interchange signing. However, such Supplemental Guide signing can reduce the effectiveness of other more important guide signing because of the possibility of overloading the road user's capacity to receive visual messages and make appropriate decisions.

Guidelines used to identify destinations that qualify as traffic generators for which guide signs may be erected on freeways and expressways are addressed in "The AASHTO Guidelines for the Selection of Supplemental Guide Signs for Traffic Generators Adjacent to Freeways" (see the Preface for AASHTO's address) and Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

Guidance:

No more than one Supplemental Guide sign should be used on each interchange approach.

A Supplemental Guide sign (see Figure 2E-17) should not list more than two destinations. Destination names should be followed by the interchange number (and suffix), or if interchanges are not numbered, by the legend NEXT RIGHT or SECOND RIGHT or both, as appropriate. The Supplemental Guide sign should be installed as an independent guide sign assembly.

Where two or more Advance Guide signs are used, the Supplemental Guide sign should be installed approximately midway between two of the Advance Guide signs. If only one Advance Guide sign is used, the Supplemental Guide sign should follow it by at least 245 m (800 feet). If the interchanges are numbered, the interchange number should be used for the action message.

To control proliferation of these signs, and to aid in uniformity, each highway agency should develop an appropriate policy similar to ODOT's for installing supplemental signs (see Part 2 of ODOT's "Traffic Engineering Manual"). In developing policies for such signing, such items as population, amount of traffic generated, distance from the route, and the significance of the destination should be taken into account.

**Standard:**

**Guide signs directing drivers to park and ride facilities (D4-H2a, D4-H2b) shall be considered as Supplemental Guide signs (see Figures 2E-18 and 2E-19).**

**Section 2E.33 Exit Direction Signs (E1-H3)**

Support:

The Exit Direction (E1-H3) sign repeats the route and destination information that was shown on the Advance Guide sign(s) for the next exit, and thereby assures road users of the destination served and indicates whether they exit to the right or the left for that destination.

**Standard:**

**Exit Direction signs (see Figure 2E-20) shall be used at all interchanges. Population figures or other similar information shall not be used on Exit Direction signs.**

**Figure 2E-17. Supplemental Guide Signs for Multi-exit Interchanges**



E3-H1

**Figure 2E-18. Supplemental Guide Sign for a Park and Ride Facility  
(Route without Exit Numbering)**




D4-H2a

**Figure 2E-19. Supplemental Guide Sign for a Park and Ride Facility  
(Route with Exit Numbering)**



D4-H2b

**Figure 2E-20. Interchange Exit Direction Sign**



E1-H3

**Guidance:**

Ground-mounted Exit Direction signs should be installed at the beginning of the deceleration lane. If there is less than 90 m (300 ft) from the beginning of the deceleration lane to the theoretical gore (see Figure 3B-8), the Exit Direction sign should be installed overhead over the exiting lane in the vicinity of the theoretical gore.

**Standard:**

**Where a through lane is being terminated (dropped) at an exit, the Exit Direction sign shall be placed overhead at the theoretical gore (see Figures 2E-8 and 2E-10).**

**The following provisions shall govern the design and application of the overhead Exit Direction sign:**

- A. The sign shall carry the exit number (if used), the route number, cardinal direction, and destination with an appropriate upward slanting arrow (see Figure 2E-20).**
- B. The message EXIT ONLY in black on a yellow panel shall be used on the overhead Exit Direction sign to advise road users of a lane drop situation. The sign shall conform to the provisions of Section 2E.20.**
- C. Diagrammatic signs shall not be employed at the exit direction location.**

**Guidance:**

Exit number plaques should be located toward the left edge of the sign for a left exit and toward the right edge for right exits.

**Option:**

In some cases, principally in urban areas, where restricted sight distance because of structures or unusual alignment make it impossible to locate the Exit Direction sign without violating the required minimum spacing (see Section 2E.30) between major guide signs, Interchange Sequence signs (see Section 2E.37) may be substituted for an Advance Guide sign.

**Guidance:**

At multi-exit interchanges, the Exit Direction sign should be located directly over the exiting lane for the first exit. At the same location, and normally over the right through lane, an Advance Guide sign for the second exit should be located. Only for those conditions where the through movement is not evident should a confirmatory message (Pull-Through sign as shown in Figure 2E-2) be used over the left lane(s) to guide road users traveling through an interchange. In the interest of sign spreading, three signs on one structure should not be used. When the freeway or expressway is on an overpass, the Exit Direction sign should be installed on an overhead support over the exit lane in advance of the gore point.

**Option:**


If the second exit is beyond an underpass, the Exit Direction sign may be mounted on the face of the overhead structure.

**Section 2E.34 Exit Gore Signs (E5-H1, E5-H1a, E5-H1b, E5-H1c)****Support:**

The Exit Gore (E5-H1, E5-H1a, E5-H1b, E5-H1c) sign in the gore indicates the exiting point or the place of departure from the main roadway. Consistent application of this sign at each exit is important.

**Standard:**

**The gore shall be defined as the area located between the main roadway and the ramp just beyond where the ramp branches from the main roadway. The Exit Gore sign shall be located in the gore and shall carry the word EXIT or EXIT XX (if interchange numbering is used) and an appropriate upward slanting arrow (see Figure 2E-21). Breakaway or yielding supports shall be used.**

**Figure 2E-21. Exit Gore Signs****Guidance:**

The arrow should be aligned to approximate the angle of departure. Each gore should be treated similarly, whether the interchange has one exit roadway or multiple exits.

**Option:**

Where extra emphasis of an especially low advisory ramp speed is needed, an E13-1 panel indicating the advisory speed may be mounted below the Exit Gore sign (see Figure 2E-21) to supplement, but not to replace, the exit or ramp advisory speed warning signs.

For narrow or single support installations, the E5-H1b Exit Gore sign may be used for unnumbered exits and the E5-H1c Exit Gore sign for numbered exits (see Appendix C).

**Section 2E.35 Post-Interchange Signs****Guidance:**

If space between interchanges permits, as in rural areas, and where undue repetition of messages will not occur, a fixed sequence of signs should be displayed beginning 150 m (500 ft) beyond the end of the acceleration lane. At this point a Route sign assembly should be installed followed by a Speed Limit sign and a Distance sign, each at a spacing of 300 m (1,000 ft).

If space between interchanges does not permit placement of these three post-interchange signs without encroaching on or overlapping the Advance Guide signs necessary for the next interchange, or in rural areas where the interchanging traffic is primarily local, one or more of the post-interchange signs should be omitted.

Usually the Distance sign will be of less importance than the other two signs and may be omitted, especially if Interchange Sequence signs are used. If the sign for through traffic on an overhead assembly already contains the route sign, the post-interchange route sign assembly may also be omitted.

**Figure 2E-22. Post-Interchange Distance Sign**

E7-H1

**Section 2E.36 Distance Signs (E7-H1)****Standard:**

If used, the post-interchange Distance (E7-H1) sign shall consist of a two- or three-line sign carrying the names of significant destination points and the distances to those points. The top line of the sign shall identify the next meaningful interchange with the name of the community near or through which the route passes, or if there is no community, the route number or name of the intersected highway (see Figure 2E-22).

**Support:**

The minimum sizes of the route shields identifying a significant destination point are prescribed in the SDM.

**Option:**

The text identification of a route may be shown instead of a route shield, such as "US XX", "State Route XX", or "County Route X".

**Guidance:**

If a second line is used, it should be reserved for communities of general interest that are located on or immediately adjacent to the route or for major traffic generators along the route.

**Option:**

The choice of names for the second line, if it is used, may be varied on successive Distance signs to give road users maximum information concerning communities served by the route.

**Standard:**

The third, or bottom line, shall contain the name and distance to a control city (if any) that has national significance for travelers using the route.

**Guidance:**

Distances to the same destinations should not be shown more frequently than at 8 km (5 mi) intervals. The distances displayed on these signs should be the actual distance to the destination points and not to the exit from the freeway or expressway.

**Section 2E.37 Interchange Sequence Signs (E7-H2)****Guidance:**

If there is less than 245 m (800 ft) between interchanges, Interchange Sequence (E7-H2) signs should be used instead of the Advance Guide signs for the affected interchanges. If used, Interchange Sequence signs should be used over the entire length of a route in an urban area. They should not be used on a single interchange basis.

**Option:**

If interchanges are closely spaced, particularly through large urban areas, so that guide signs cannot be adequately spaced, Interchange Sequence signs identifying the next two or three interchanges may be used.

**Support:**

Interchange Sequence signs are generally supplemental to Advance Guide signs. Signing of this type is illustrated in Figures 2E-23 and 2E-24, and is compatible with the sign spreading concept.

These signs are installed in a series and display the next two or three interchanges by name or route number with distances to the nearest 1/4 mile.

**Standard:**

**If used, the first sign in the series shall be located in advance of the first Advance Guide sign for the first interchange.**

**Where the exit direction is to the left, interchange names or route numbers shown on such signs shall be followed by the legend LEFT or LEFT EXIT in black letters on a yellow rectangular background.**

**Interchange Sequence signs shall not be substituted for Exit Direction signs.**

**Guidance:**

Interchange Sequence signs should be located in the median. After the first of the series, Interchange Sequence signs should be placed approximately midway between interchanges.

**Standard:**

**Interchange Sequence signs located in the median shall be installed at overhead sign height.**

**Option:**

Interchange numbers may be shown to the left of the interchange name or route number.


**Section 2E.38 Community Interchanges Identification Signs (E7-H3)****Support:**

For suburban or rural communities served by two or three interchanges, Community Interchanges Identification (E7-H3) signs are useful (see Figure 2E-25).

**Guidance:**

In these cases, the name of the community followed by the word EXITS should be shown on the top line; the lines below should display the destination, road name or route number, and the corresponding distances to the nearest 1/4 mile.

**Figure 2E-23. Signing of Closely Spaced Interchanges Using Interchange Sequence Signs**



**Figure 2E-24. Interchange Sequence Sign**



E7-H2

**Figure 2E-25. Community Interchanges Identification Sign**



E7-H3

**Figure 2E-26. NEXT EXITS Sign**



E7-H4

The sign should be located in advance of the first Advance Guide sign for the first interchange within the community.

Option:

If interchanges are not conveniently identifiable or if there are more than three interchanges to be identified, the NEXT X EXITS sign (see Section 2E.39) may be used.

### **Section 2E.39 NEXT X EXITS Sign (E7-H4)**

Support:

Many freeways or expressways pass through historical or recreational regions, or urban areas served by a succession of several interchanges.

Option:

Such regions or areas may be indicated by a NEXT X EXITS (E7-H4) sign (see Figure 2E-26) located in advance of the Advance Guide sign or signs for the first interchange.

Guidance:

The sign legend should identify the region or area followed by the words NEXT X EXITS.

### **Section 2E.40 Signing by Type of Interchange**

Support:

Road users need signs to help identify the location of the exit, as well as to obtain route, direction, and destination information for specific exit ramps. Figures 2E-27 through 2E-32 show examples of guide signs for common types of interchanges. The interchange layouts shown in most of the figures illustrate only the major guide signs for one direction of traffic on the through road and on the crossroad.

**Standard:**

**Interchange guide signing shall be consistent for each type of interchange along a route.**

Guidance:

The signing layout for all interchanges having only one exit ramp in the direction of travel should be similar, regardless of the interchange type (see Figures 2E-8, 2E-10, and Figures 2E-27 through 2E-32). For the sake of uniform application, the significant features of the signing plan for each of the more frequent kinds of interchanges (illustrated in Figures 2E-27 through 2E-32) should be followed as closely as possible. Even when unusual geometric features exist, variations in signing layout should be held to a minimum.

### **Section 2E.41 Freeway-to-Freeway Interchange**

Support:


Freeway-to-freeway interchanges are major decision points where the effect of taking a wrong ramp cannot be easily corrected. Reversing direction on the connecting freeway or reentering to continue on the intended course is usually not possible. Figure 2E-27 shows examples of guide signs at a freeway-to-freeway interchange.

Guidance:


The sign messages should contain only the route shield, cardinal direction, and the name of the next control city on the route. Arrows should point as indicated in Section 2D.08, unless a diagrammatic representation of the interchange layout requires otherwise.

At splits where the off-route movement is to the left or where there is an optional lane split, expectancy problems usually result, and diagrammatic signs should be used at the Advance Guide sign location.

**Figure 2E-27. Examples of Freeway-to-Freeway Interchange Guide Signs**




**Figure 2E-28. Examples of Guide Signs for Full Cloverleaf Interchange**




Note: See Figure 2E-38 for examples of multi-lane crossroad signing for cloverleaf interchanges.

**Figure 2E-29. Examples of Guide Signs for Full Cloverleaf Interchange With Collector-Distributor Roadways**




Note: See Figure 2E-38 for examples of multi-lane crossroad signing for cloverleaf interchanges.

**Figure 2E-30. Examples of Partial Cloverleaf Interchange Guide Signs**




Note: See Figure 2E-37 for examples of multi-lane crossroad signing for partial cloverleaf interchanges. See Figures 2D-3 and 2D-4 for the correct design of an Ohio State Route Sign.

**Figure 2E-31. Examples of Diamond Interchange Guide Signs**



Note: See Figures 2E-34 and 2E-36 for examples of crossroad signing for one-lane approaches and examples of multi-lane crossroad signing for diamond interchanges.

**Figure 2E-32. Examples of Diamond Interchange Guide Signs in an Urban Area**



Note: See Figures 2E-34 and 2E-36 for examples of crossroad signing for one-lane approaches and examples of multi-lane crossroad signing for diamond interchanges.

Diagrammatic signs (see Section 2E.19) also should be used at the Advance Guide sign locations for interchanges where two-lane exits with an optional lane carry the through route on the exiting lanes.

**Standard:**

**Overhead signs shall be used at a distance of 2 km or 1 mile and at the theoretical gore of each connecting ramp. When diagrammatic signs are used, they shall conform to the provisions of Section 2E.19.**

**Option:**

Overhead signs may also be used at the 1 km or 0.5 mile and 4 km or 2 mile points.

The arrow and/or the name of the control city may be omitted on signs that indicate the straight-ahead continuation of a route.

An Exit Speed sign may be used where an engineering study shows that it is necessary to display a speed reduction message for ramp signing (see Section 2C.36).

**Section 2E.42 Cloverleaf Interchange**

**Support:**

A cloverleaf interchange has two exits for each direction of travel. The exits are closely spaced and have common Advance Guide signs. Examples of guide signs for cloverleaf interchanges are shown in Figure 2E-28.

**Guidance:**

The Advance Guide signs should include two place names, one corresponding to each exit ramp, with the name of the place served by the first exit on the upper line.

**Standard:**

**An Overhead Guide sign shall be placed at the theoretical gore point of the first exit ramp, with an upward slanting arrow on the exit direction sign for that exit and the message XX MILE on the Advance Guide sign for the second exit, as shown in Figure 2E-28. The second exit shall be indicated by an overhead Exit Direction sign over the auxiliary lane. An Exit sign shall also be used at each gore (see Section 2E.34).**

**Interchanges with more than one exit from the main line shall be numbered as described in Section 2E.28 with an appropriate suffix.**

**Diagrammatic signs shall not be used for cloverleaf interchanges.**

**Guidance:**

As shown in Figure 2E-28, the overhead Exit Direction sign for the second exit should be mounted on the structure if the mainline passes under the crossroad and the exit roadway is located beyond the structure.

**Section 2E.43 Cloverleaf Interchange with Collector-Distributor Roadways**

**Support:**

Examples of guide signs for full cloverleaf interchanges with collector-distributor roadways are shown in Figure 2E-29.

**Guidance:**

Signing on the collector-distributor roadways should be the same as the signing on the mainline of a cloverleaf interchange.

**Standard:**

**Guide signs at exits from the collector-distributor roadways shall be overhead and located at the theoretical gore of the collector-distributor roadway and the exit ramp.**

**Option:**

Exits from the collector-distributor roadways may be numbered with an appropriate suffix. The Advance Guide signs may include two place names and their corresponding exit numbers or may use the singular EXIT.

**Section 2E.44 Partial Cloverleaf Interchange****Support:**

Examples of guide signs for partial cloverleaf interchanges are shown in Figure 2E-30.

**Guidance:**

As shown in Figure 2E-30, the overhead Exit Direction sign should be placed on the structure if the mainline passes under the crossroad and the exit roadway is located beyond the structure.

**Standard:**

**A ground-mounted Exit Gore sign shall also be installed in the ramp gore.**

**Section 2E.45 Diamond Interchange****Support:**

Examples of guide signs for diamond interchanges are shown in Figure 2E-31.

**Standard:**

**The singular message EXIT shall be used on the Advance Guide and Exit Direction signs. Exit numbers shall not include the cardinal initials corresponding to the direction of the cross route.**

**Support:**

The typical diamond interchange ramp departs from the mainline roadway such that a speed reduction generally is not necessary in order for a driver to reasonably safely negotiate an exit maneuver from the mainline onto the ramp roadway.

**Guidance:**

When a speed reduction is not necessary, an exit speed sign should not be used.

**Option:**

An Exit Speed sign may be used where an engineering study shows that it is necessary to display a speed reduction message for ramp signing (see Section 2C.36).

**Guidance:**

The Exit Speed sign should be located along the deceleration lane or along the ramp such that it is visible to the driver far enough in advance so that a reasonably safe slowing and exiting maneuver can be made.

**Option:**

A Stop Ahead or Signal Ahead warning sign may be placed, where engineering judgment indicates a need, along the ramp in advance of the cross street, to give notice to the driver (see Section 2C.29).

**Guidance:**

When used on two-lane ramps, Stop Ahead or Signal Ahead signs should be used in pairs with one sign on each side of the ramp.

### **Section 2E.46 Diamond Interchange in Urban Area**

#### Support:

Examples of guide signs for diamond interchanges in an urban area are shown in Figure 2E-32. This example includes the use of the Community Interchanges Identification sign (see Section 2E.38) which might be useful if two or more interchanges serve the same community.

In urban areas, street names are often shown as the principal message in destination signs.

#### Option:

If interchanges are too closely spaced to properly locate the Advance Guide signs, they may be placed closer to the exit, and the distance figures adjusted accordingly.

### **Section 2E.47 Closely Spaced Interchanges**

#### Option:

When a series of interchanges is closely spaced, the advance guide sign for the next interchange may be mounted on an overhead structure located downstream from the gore of the preceding interchange.

#### Guidance:

Interchange Sequence signs should be used at closely spaced interchanges. When used, they should identify and show street names and distances for the next two or three exits as shown in Figure 2E-23.

#### **Standard:**

**Advance Guide signs for closely spaced interchanges shall show information for only one interchange.**

### **Section 2E.48 Minor Interchange**

#### Support:

Examples of guide signs for minor interchanges are shown in Figures 2E-33 and 2E-35. This type of interchange customarily serves very low volumes of local traffic (for example, where the sum of exit volumes is less than 100 vehicles per day in an average year).

There are no interchanges in Ohio that would be considered "Minor." However, a traveler in some of the western states might see this type of situation.

### **Section 2E.49 Signing of Approaches and Connecting Roadways**

#### Support:


Because there are a number of different ramp configurations that are commonly used at interchanges with conventional roads, drivers on the conventional road cannot reliably predict whether they will be required to turn left or right in order to enter the correct ramp to access the freeway or expressway in the desired direction of travel. Consistently applied signing for conventional road approaches to freeway or expressway interchanges is highly desirable.

#### Guidance:

The signing of conventional roads with one lane of traffic approaching an interchange should consist of a sequence containing the following signs (see Figure 2E-34):


- A. Junction Assembly
- B. Destination sign
- C. Directional Assembly or Entrance Direction sign for the first ramp
- D. Advance Route Turn Assembly or Advance Entrance Direction sign with an advance turn arrow
- E. Directional Assembly or Entrance Direction sign for the second ramp

**Figure 2E-33. Examples of Minor Interchange Guide Signs**




Note: See Figure 2E-35 for example of minor interchange crossroad signing.


**Figure 2E-34. Example of Crossroad Signing for One-Lane Approach**




**Figure 2E-35. Example of Minor Interchange Crossroad Signing**




**Figure 2E-36. Examples of Multi-lane Crossroad Signing for Diamond Interchange**



**Figure 2E-37. Examples of Multi-lane Crossroad Signing for Partial Cloverleaf Interchange**



**Figure 2E-38. Examples of Multilane Crossroad Signing for Cloverleaf Interchange**



**Standard:**

**If used, the Entrance Direction sign shall consist of a white legend and border on a green background. It shall contain the freeway or expressway route shield(s), cardinal direction, and directional arrow(s).**

**Option:**

The Entrance Direction sign may contain a destination(s) and/or an action message such as NEXT RIGHT.

At minor interchanges, the following sequence of signs may be used (see Figure 2E-35):

- A. Junction Assembly
- B. Directional Assembly for the first ramp
- C. Directional Assembly for the second ramp

**Guidance:**

On multi-lane conventional roads approaching an interchange, the sign sequence should contain the following signs (see Figures 2E-36, 2E-37, and 2E-38):

- A. Junction Assembly
- B. Advance Entrance Direction sign(s) for both directions (if applicable) of travel on the freeway or expressway
- C. Entrance Direction sign for first ramp
- D. Advance Turn Assembly
- E. Entrance Direction sign for the second ramp

**Support:**

Advance Entrance signs are used to direct road users to the appropriate lane(s).

**Standard:**

**The Advance Entrance sign shall consist of a white legend and border on a green background. It shall contain the freeway or expressway route shield(s) and cardinal direction(s).**

**Option:**

The Advance Entrance sign may have destinations, directional arrows, and/or an action message such as LEFT LANE, NEXT LEFT, or SECOND RIGHT. Signs in this sequence may be mounted overhead to improve visibility.

**Section 2E.50 Wrong-Way Traffic Control at Interchange Ramps****Standard:**

**At interchange exit ramp terminals where the ramp intersects a crossroad in such a manner that wrong-way entry could inadvertently be made, the following signs shall be used (see Figure 2E-39):**


- A. **At least one ONE WAY sign for each direction of travel on the crossroad shall be placed where the exit ramp intersects the crossroad.**
- B. **At least one DO NOT ENTER sign shall be conspicuously placed near the end of the exit ramp in positions appropriate for full view of a road user starting to enter wrongly.**
- C. **At least one WRONG WAY sign shall be placed on the exit ramp facing a road user traveling in the wrong direction.**

**Guidance:**


In addition, the following pavement markings should be used (see Figure 2E-39):

- A. On two-lane paved crossroads at interchanges, double solid yellow lines should be used as a centerline for an adequate distance on both sides approaching the ramp intersections.

**Figure 2E-39. Examples of Regulatory Signing and Pavement Markings at Exit Ramp Termination to Deter Wrong-Way Entry**



**Figure 2E-40. Examples of Regulatory Signing and Pavement Markings at Entrance Ramp Terminal Where Design Does Not Clearly Indicate the Direction of Flow**



- B. Where crossroad channelization or ramp geometrics do not make wrong-way movements difficult, a lane-use arrow should be placed in each lane of an exit ramp near the crossroad terminal where it will be clearly visible to a potential wrong-way road user.

**Option:**

The following traffic control devices may be used to supplement the above signs and pavement markings:

- A. Additional ONE WAY signs may be placed, especially on two-lane rural crossroads, appropriately in advance of the ramp intersection to supplement the required ONE WAY sign(s).
- B. Additional WRONG WAY signs may be used.
- C. Slender, elongated wrong-way arrow pavement markings (see Figure 3B-21) intended primarily to warn wrong-way road users that they are traveling in the wrong direction may be placed upstream from the ramp terminus (see Figure 2E-39) to indicate the correct direction of traffic flow. Wrong-way arrow pavement markings may also be placed on the exit ramp at appropriate locations near the crossroad junction to indicate wrong-way movement. The wrong-way arrow markings may consist of pavement markings or bidirectional red-and-white raised pavement markers or other units that show red to wrong-way road users and white to other road users (see Figure 3B-21).
- D. Lane-use arrow pavement markings may be placed on the exit ramp and crossroad near their intersection to indicate the permissive direction of flow.
- E. Guide signs may be used on entrance ramps near the crossroad to inform road users of the freeway or expressway entrance, as appropriate (see Figure 2E-37).

**Guidance:**

On interchange entrance ramps where the ramp merges with the through roadway and the design of the interchange does not clearly make evident the direction of traffic on the separate roadways or ramps, a ONE WAY sign visible to traffic on the entrance ramp and through roadway should be placed on each side of the through roadway near the entrance ramp merging point as illustrated in Figure 2E-40.

**Option:**

At locations where engineering judgment determines that a special need exists, other standard warning or prohibitive methods and devices may be used as a deterrent to the wrong-way movement.

**Support:**

Section 2B.35 contains further information on signing to avoid wrong-way movements at at-grade intersections on expressways.

### **Section 2E.51 General Service Signs**

**Support:**

General Service signs (see Figure 2D-11) are generally not appropriate at major interchanges (see Section 2E.29 for definition) and in urban areas.

Additional guidelines and standards for the use of General Service signs on state highways are located in Part 2 of the ODOT "Traffic Engineering Manual" (see Section 1A.11).

**Option:**

If interchanges are not numbered, an action message such as NEXT EXIT or SECOND RIGHT may be used (see Figure 2E-41).

**Standard:**

**General Service signs shall have white letters, symbols, and borders on a blue background. Signs shall conform to the designs provided in the SDM (see Section 1A.11). All approved symbols shall be permitted as alternatives to word messages, but symbols and word service messages shall not be intermixed. If the services are not visible from the ramp of a single-exit interchange, the service**

**signing shall be repeated in smaller size at the intersection of the exit ramp and the crossroad. Such service signs shall use arrows to indicate the direction to the services.**

Guidance:

Distance to services should be shown on General Service signs where distances are more than 2 km or 1 mile.

General Service signing should only be provided at locations where the road user can return to the freeway or expressway and continue in the same direction of travel.

Only services that fulfill the needs of the road user should be shown on General Service signs. Each highway agency that elects to provide General Service signing should establish a policy for such signing, similar to that published by ODOT in the "Traffic Engineering Manual" (see Section 1A.11).

**Standard:**

**For any service that is operated on a seasonal basis only, the General Service signs shall be removed or covered during periods when the service is not available.**

**The General Service signs shall be mounted in an effective location, between the Advance Guide sign and the Exit Direction sign, in advance of the exit leading to the available services.**

Guidance:

The General Service sign should contain the interchange number, if any, as illustrated in Figure 2E-42.

Option:

If the distance to the next point where services are available is greater than 16 km (10 miles), a NEXT SERVICES XX MILES (D9-17) sign (see Figure 2E-43), may be used as a separate sign panel installed below the Exit Direction sign.

**Standard:**

**Signs for services shall conform to the format for General Service signs (see Section 2D.45) and as specified herein. No more than six general road user services shall be displayed on one sign, which includes any appended sign panels. General Service signs shall carry the legends for one or more of the following services: Food, Gas, Lodging, Camping, Phone, Hospital, or Tourist Information.**

**The qualified services available shall be shown at specific locations on the sign.**

**To provide flexibility for the future when the service might become available, the sign space normally reserved for a given service symbol or word shall be left blank when that service is not present.**

Guidance:

The standard display of word messages should be FOOD and PHONE in that order on the top line, and GAS and LODGING on the second line. If used, HOSPITAL and CAMPING should be on separate lines (see Figure 2E-42).

Option:

Signing for DIESEL, LP-Gas, or other alternative fuel services may be substituted for any of the general services or appended to such signs. The International Symbol of Accessibility for the Handicapped (D9-6) sign may be used for facilities that qualify.

Guidance:

When symbols are used for the road user services, they should be displayed as follows:

- A. Six services:
  1. Top row—GAS, FOOD, and LODGING
  2. Bottom row—PHONE, HOSPITAL, and CAMPING
- B. Four services:
  1. Top row—GAS and FOOD

2. Bottom row—LODGING and PHONE
- C. Three services:
  1. Top row—GAS, FOOD, and LODGING

Option:

Substitutions of other services for any of the services shown above may be made by placing the substitution in the lower right (four or six services) or extreme right (three services) portion of the sign panel. An action message or an interchange number may be used for symbol signs in the same manner as they are used for word message signs. The Diesel Fuel (D9-11) symbol or the LP-Gas (D9-15) symbol may be substituted for the symbol representing fuel or appended to such assemblies. The Information (D9-10) symbol may be substituted on any of the above configurations in the last position.

At rural interchange areas where limited road user services are available and where it is unlikely that additional services will be provided within the near future, a sign panel having one to three services (words or symbols) may be appended to ground mounted interchange guide signs.

**Standard:**

**If more than three services become available at rural interchange areas where limited road user services were anticipated, any appended sign panel shall be removed and replaced with an independently mounted General Service sign as described in this Section.**

Option:

A separate Telephone Service (D9-1) sign may be installed if telephone facilities are located adjacent to the route at places where public telephones would not normally be expected.

The Recreational Vehicle Sanitary Station (D9-12) sign may be used as needed to indicate the availability of facilities designed for dumping wastes from recreational vehicle holding tanks.

In some locations, signs may be used to indicate that services are not available.

A TRUCK PARKING (D9-16) sign may be used on a separate sign panel below the other general road user services to direct truck drivers to designated parking areas.

**Section 2E.52 Rest and Scenic Area Signs (D5 Series, D6 Series)**

Guidance:

Signing for rest areas and scenic areas should conform to the provisions set forth in Sections 2D.42 and 2D.43. However, the signs should be suitably enlarged for freeway or expressway application. A roadside area that does not contain restroom facilities should be signed to indicate the major road user service that is provided. For example, an area with only parking should be signed with a PARKING AREA (D5-4) sign (see Figure 2E-44). An area with picnic tables and parking should be signed with a PICNIC AREA (D5-5c) sign or a Picnic Table Area (D5-5a) symbol sign.


Rest areas that have tourist information and welcome centers should be signed as discussed in Section 2E.53.

Scenic area signing should be consistent with that specified for rest areas. Standard messages should read SCENIC AREA (D6-1), SCENIC VIEW (D6-2), SCENIC OVERLOOK (D6-3), or the equivalent.


**Standard:**

**All signs for rest and scenic areas shall have white letters, symbols, and borders on a blue background. Signs shall conform to the designs in the SDM (see Section 1A.11). On the approach to rest areas, a REST AREA advance guide sign (D5-H1, D5-1a) shall be placed 2 km or 1 mile and/or 4 km or 2 miles in advance of the rest area. At the rest area exit gore, there shall be a sign (D5-H2b) with a message REST AREA together with an arrow indicating the appropriate turn as shown in Figure 2E-44.**

**Figure 2E-41. Examples of General Service Signs  
(without Exit Numbering)**



**Figure 2E-42. Examples of General Service Signs  
(with Exit Numbering)**



**Figure 2E-43. Example of Next Service Signs**



**Figure 2E-44. Examples of Rest Area, Scenic Overlook, and Welcome Center Signs**



D5-H1



D5-1a



D5-1b



D5-2a



D5-H2b



D5-3



D5-4



D5-6



D5-H6



D5-7



D5-7a



D5-8



D5-9



D5-9a



D5-10



D5-11

**Option:**

If the rest area has facilities for the physically impaired (see Section 2D.45), the International Symbol of Accessibility for the Handicapped (D9-6) sign may be placed with or beneath the REST AREA advance guide sign.

Between the REST AREA advance guide sign and the gore of the rest area exit, a REST AREA NEXT RIGHT (D5-1b) or REST AREA with upward slanting arrow (D5-2a) sign (see Figure 2E-44) may be used.

To provide the road user with information on the location of succeeding rest areas, a NEXT REST AREA XX MILES (D5-6, D5-H6) sign (see Figure 2E-44) may be installed independently, or the D5-6 sign as a supplemental sign panel mounted below one of the REST AREA advance guide signs.

**Section 2E.53 Tourist Information and Welcome Center Signs****Support:**

Tourist information and welcome centers have been constructed within rest areas on freeways and expressways and are operated by either a State or a private organization. Others have been located within close proximity to these facilities and operated by civic clubs, chambers of commerce, or private enterprise.

**Guidance:**

An excessive number of supplemental panels should not be installed with Tourist Information or Welcome Center signs so as not to overload the road user.

**Standard:**

**Tourist Information or Welcome Center signs (see Figure 2E-44) shall have a white legend and border on a blue background. Continuously staffed or unstaffed operation at least 8 hours per day, 7 days per week, shall be required.**

**If operated only on a seasonal basis, the Tourist Information or Welcome Center signs shall be removed or covered during the off seasons.**

**Guidance:**

For freeway or expressway rest area locations that also serve as tourist information or welcome centers, the following signing criteria should be used:

- A. The locations for tourist information and welcome center Advance Guide, Exit Direction, and Exit Gore signs should meet the General Service signing requirements described in Section 2E.51.
- B. If the signing for the tourist information or welcome center is to be accomplished in conjunction with the initial signing for the rest areas, the message on the Advance Guide sign should be REST AREA, TOURIST INFO CENTER, XX MILES or REST AREA, WELCOME CENTER XX MILES. On the Exit Direction sign the message should be REST AREA, TOURIST INFO CENTER with an upward sloping arrow (or NEXT RIGHT), or REST AREA, WELCOME CENTER with an upward sloping arrow (or NEXT RIGHT).
- C. If the initial rest area Advance Guide and Exit Direction signing is in place, these signs should include, on supplemental sign panels, the legend TOURIST INFO CENTER or OHIO (optional), WELCOME CENTER.
- D. The Gore sign should contain only the legend REST AREA with the arrow and should not be supplemented with any legend pertaining to the tourist information center or welcome center.

**Option:**

An alternative to the supplemental TOURIST INFO CENTER legend is the Information Symbol (D9-10) sign, which may be appended beneath the REST AREA advance guide sign. The name of the State or local jurisdiction may appear on tourist information/welcome center signs if the jurisdiction controls the operation of the tourist information or welcome center and the center meets the operating criteria set forth herein and is consistent with State policies (see Part 2 of ODOT's "Traffic Engineering Manual"). The State name may be used on the Advance Guide and the Exit Direction signs.

**Figure 2E-45. Enhanced Reference Location Signs****Guidance:**

For tourist information centers located off the freeway or expressway facility, additional signing criteria should be as follows:

- A. The tourist information center should be located a maximum of 1.6 km (1 mi) from the interchange in order to be included on official signs.
- B. The location of signing should be in accordance with requirements pertaining to General Service signing (see Section 2E.51).
- C. Signing along the crossroad should be installed to guide the road user from the interchange to the tourist information center and back to the interchange.

**Option:**

As an alternative, the Information (D9-10) symbol sign may be appended to the guide signs for the exit providing access to the tourist information center. As a second alternative, the Information symbol sign may be combined with General Service signing.

**Section 2E.54 Reference Location Signs and Enhanced Reference Location Signs (D10-4, D10-5, D10-H5a)**

**Support:**

Reference Location (D10-1 through D10-3) signs and Intermediate Reference Location (D10-1a through D10-3a) signs and their applications are described in Section 2D.46.

There are two types of enhanced reference location signs:

- A. Enhanced Reference Location signs (D10-4), and
- B. Intermediate Enhanced Reference Location signs (D10-5).

**Standard:**

**Except as provided in the option below, Reference Location (D10-1 through D10-3) signs (see Section 2D.46) shall be placed on all freeway facilities to assist road users in estimating their progress,**

**to provide a means for identifying the location of emergency incidents and traffic crashes, and to aid in highway maintenance and servicing.**

Option:

Reference Location signs may be installed on expressways.

Reference Location signs may be omitted for routes which are not continuous as freeways for their entire length within the State, or are continuous as freeways for their entire length within the State but are shorter than 40 km (25 mi) in length.

Enhanced Reference Location (D10-4) signs (see Figure 2E-45), which enhance the reference location sign system by identifying the route, may be placed on freeways or expressways (instead of Reference Location signs) or on conventional roads.

To augment an enhanced reference location sign system, Intermediate Enhanced Reference Location (D10-5) signs (see Figure 2E-45), which show the tenth of a mile with a decimal point, may be installed along any section of a highway route or ramp at one tenth of a mile intervals, or at some other regular spacing.

The D10-H5a signs (see Appendix C) may be used as an Intermediate Reference Location sign on ramps.

**Standard:**

**If enhanced reference location signs are used, they shall be vertical panels having blue or green backgrounds with white numerals, letters, and borders, except for the route shield, which shall be the standard color and shape. The top line shall consist of the cardinal direction for the roadway. The second line shall consist of the applicable route shield for the roadway. The third line shall identify the mile reference for the location and the bottom line of the Intermediate Enhanced Reference Location sign shall give the tenth of a mile reference for the location. The bottom line of the Intermediate Enhanced Reference Location sign shall contain a decimal point. The height of the legend on enhanced reference location signs shall be a minimum of 150 mm (6 in). The height of the route shield on enhanced reference location signs shall be a minimum of 300 mm (12 in).**

**The background color shall be the same for all enhanced reference location signs within a jurisdiction.**

**The design details for enhanced reference location signs shall be as shown in the SDM (see Section 1A.11).**

**Enhanced reference location signs shall have a minimum mounting height of 1.2 m (4 ft) to the bottom of the sign in accordance with the mounting height requirements of delineators (see Section 3D.04), and shall not be governed by the mounting height requirements prescribed in Section 2A.18.**

**The distance numbering shall be continuous for each route within any State, except where overlaps occur (see Section 2E.28). Where routes overlap, enhanced reference location sign continuity shall be established for only one of the routes. If one of the overlapping routes is an Interstate route, that route shall be selected for continuity of distance numbering.**

**The distance measurement shall be made on the northbound and eastbound roadways. The enhanced reference location signs for southbound or westbound roadways shall be set at locations directly opposite the enhanced reference location signs for the northbound or eastbound roadways.**

Guidance:

The route selected for continuity of distance numbering should also have continuity in interchange exit numbering (see Section 2E.28). On a route without enhanced reference location sign continuity, the first enhanced reference location sign beyond the overlap should indicate the total distance traveled on the route so that road users will have a means of correlating their travel distance between enhanced reference location signs with that shown on their odometer.

**Standard:**

**Except as provided in the option below, enhanced reference location signs shall be installed on the right side of the roadway.**

## Option:

Where conditions limit or restrict the use of enhanced reference location signs on the right side of the roadway, they may be installed in the median. In urban areas, Intermediate Enhanced Reference Location signs may be installed on the right side of the roadway, in the median, or on ramps to replace or to supplement the reference location signs. Enhanced Reference Location signs may be installed back-to-back in median locations.

**Section 2E.55 Miscellaneous Guide Signs**

## Support:

Miscellaneous Guide signs are used to point out geographical features, such as rivers and summits, and other jurisdictional boundaries (see Section 2D.48).

## Option:

Miscellaneous Guide signs may be used if they do not interfere with signing for interchanges or other critical points.

## Guidance:

Miscellaneous Guide signs should not be installed unless there are specific reasons for orienting the road users or identifying control points for activities that are clearly in the public interest. If Miscellaneous Guide signs are to be of value to the road user, they should be consistent with other freeway or expressway guide signs in design and legibility. On all such signs, the design should be simple and dignified, devoid of any tendency toward flamboyant advertising, and in general conformance with other freeway and expressway signing.

A State Line (E8-H1) sign should be erected where a route enters the State of Ohio from another state.

The Corporation Limit (E8-H2) sign should be installed where a route enters a municipality.

## Option:

Where a route leaves a municipality and subsequently re-enters the same municipality within a relatively short distance, the ENTER CORP (I-H2b) sign may be used at the re-entry location.

The LEAVE CORP (I-H2c) sign may be used at a location where a route leaves a municipality.

## Guidance:

The County Line (E8-H3) sign should be installed where a route enters an Ohio county from another Ohio county or another state.

**Standard:**

**The State Line (E8-H1) sign shall have a standard size of 6900 x 2100 mm (276 x 84 in). The Corporation Limit (E8-H2) sign shall have a standard height of 900 mm (36 in) with a variable width. The Enter Corp (I-H2b) sign and Leave Corp (I-H2c) sign shall have a standard size of 900 x 600 mm (36 x 24 in). The County Line (E8-H3) sign shall have a standard height of 1200 mm (48 in) with a variable width.**

**Section 2E.56 Radio Information Signing**

## Option:

Radio-Weather Information (D12-1) signs may be used in areas where difficult driving conditions commonly result from weather systems. Radio-Traffic Information signs may be used in conjunction with traffic management systems.

**Standard:**

**Radio-Weather and Radio-Traffic Information signs shall have a white legend and border on a blue background. Only the numerical indication of the radio frequency shall be used to identify a station broadcasting travel-related weather or traffic information. No more than three frequencies shall be shown on each sign. Only radio stations whose signal will be of value to the road user and who agree to broadcast either of the two items below shall be identified on Radio-Weather and Radio-Traffic Information signs:**

- A. Periodic weather warnings at no more than 15-minute intervals during periods of adverse weather; or**
- B. Driving condition information (affecting the roadway being traveled) at a rate of at least once every 15 minutes, or when required, during periods of adverse traffic conditions, and when supplied by an official agency having jurisdiction.**

**If a station to be considered operates only on a seasonal basis, its signs shall be removed or covered during the off season.**

## Guidance:

The radio station should have a signal strength to adequately broadcast 110 km (70 mi) along the route. Signs should be spaced as needed for each direction of travel at distances determined by an engineering study. The stations to be included on the signs should be selected in cooperation with the association(s) representing major broadcasting stations in the area to provide: (1) maximum coverage to all road users on both AM and FM frequencies; and (2) consideration of 24 hours per day, 7 days per week broadcast capability.

## Option:

In roadway rest area locations, a smaller sign using a greater number of radio frequencies, but of the same general design, may be used.

**Standard:**

**Radio-Weather and Radio-Traffic Information signs installed in rest areas shall be positioned such that they are not visible from the main roadway.**

## Option:

A Channel 9 Monitored (D12-3) sign or cellular phone sign may be installed as needed.

**Standard:**

**Only official public agencies or their designee shall be shown as the monitoring agency on the Channel 9 Monitored sign.**

## Support:

Section 2D.45 contains information about the use and application of TRAVEL INFO CALL 511 (D12-5) signs.

**Section 2E.57 Carpool and Ridesharing Signing**

## Option:

In areas having carpool matching services, Carpool Information (D12-2) signs (see Figure 2D-12) may be provided adjacent to highways with preferential lanes or along any other highway.

Carpool Information signs may include Internet addresses or telephone numbers of more than four characters within the legend.

## Guidance:

Because this is an information sign related to road user services, the Carpool Information sign should have a white legend and border on a blue background.

**Standard:**

If a local transit logo or carpool symbol is incorporated into the Carpool Information sign, the maximum vertical dimension of the logo or symbol shall not exceed 450 mm (18 in).

**Section 2E.58 Weigh Station Signing****Standard:**

Weigh Station signing on freeways and expressways shall be the same as that specified in Section 2D.44, except for lettering size and the advance posting distance for the Exit Direction (D8-2 or D8-H2) sign, which shall be located a minimum of 450 m (1,500 ft) in advance of the gore.

**Support:**

Weigh Station sign layouts for freeway and expressway applications are shown in the SDM (see Section 1A.11).

**Section 2E.59 Preferential Only Lane Signs****Support:**

Additional guidance and standards related to the designation, operational considerations, signing, pavement markings, and other considerations for preferential only lanes is provided in Sections 2B.26, 2B.27, 2B.28, 2C.52, 3B.22, and 3B.23.

**Standard:**

Ground-mounted advance guide signs shall be provided at least 800 m (0.5 mi) prior to the beginning or initial entry point to all types of preferential only lanes (including barrier-separated, buffer-separated, and concurrent flow). Ground-mounted guide signs shall be provided at the beginning or initial entry point and at intermediate access points to all types of preferential only lanes.

A combination of guide and regulatory signs shall be used in advance of all preferential only lanes. The advance guide signs for preferential only lanes shall be consistent with the requirements of Section 2E.30.

Reversible flow or express lanes that do not have any specific vehicle occupancy or designation restrictions shall be consistent with the requirements of Chapters 2B and 3B.

Overhead preferential only lane guide signs shall be used only as a supplement to ground-mounted preferential only lane guide signs unless an engineering study identifies that ground-mounted guide signs are not appropriate for a particular situation or location.

Either the HOV abbreviation or the diamond symbol shall appear in the legend of each preferential only lane sign at the designated entry and exit points for all types of HOV lanes (including barrier- and buffer-separated, concurrent flow, and direct access ramps) in order to alert motorists that there is a minimum allowable vehicle occupancy requirement for vehicles to use the HOV lanes and to inform them of the times during which these vehicle occupancy requirements are in effect.

**Guidance:**

Because consistency in signing and pavement markings for preferential only lanes within a State or metropolitan area plays a critical role in building public awareness, understanding, and acceptance, and makes enforcement more effective, an engineering study should be conducted to determine the appropriate combinations of overhead signs, ground-mounted signs, and pavement markings for a specific preferential only lane application.

Existing sign and bridge structures should be used to the extent practical for the installation of preferential only lane signs. Where possible, advance guide and guide signs that are provided for preferential only lanes should share sign structures spanning the preferential only lanes and the adjoining freeway facility.

The preferential only lane signing should be designed to avoid overloading the road user. Based on the importance of the sign, the following priority should be given: regulatory, advance regulatory, guide, then next exit supplemental signs.

**Option:**

Overhead advance guide signs and overhead guide signs may be used in advance of, at the beginning or initial entry point, and at designated intermediate access points to any type of preferential only lane. Advance guide signs may be installed and located approximately 1.6 km (1 mi) and 3.2 km (2 mi) in advance of the beginning or initial entry point to any type of preferential only lane.

**Guidance:**

Where conditions restrict the ability to provide more than one advance guide sign in advance of any type of preferential only lane, the advance guide sign that is installed should be placed at least 800 m (0.5 mi) in advance of the beginning or entry point to the preferential only lane.

Advance destination guide signs, identifying downstream exit locations, should be installed in advance of designated entry points and along the length of access restricted preferential only lanes (such as barrier- and buffer-separated). In addition to the routes that typically appear on advance destination guide signs, these signs should also include destinations. These signs should be located based on the priority of the message, the available space, the existing signs on adjoining general purpose traffic lanes, roadway and traffic characteristics, the proximity to existing overhead signs, the ability to install overhead signs, and other unique local factors.

**Option:**

Advance guide signs may be provided for preferential only lanes with unrestricted access, such as concurrent flow preferential only lanes.

**Guidance:**

The use of guide signs for preferential only lanes at freeway interchanges should conform to the regulatory and guide sign requirements established in this Manual.

**Option:**

Changeable message signs may be used to supplement static signs where travel conditions change or where multiple types of operational strategies (such as variable occupancy requirements, vehicle types, or pricing policies) are used and varied throughout the day or week to manage the use of, control of, or access to preferential only lanes.

**Standard:**

**When changeable message signs (see Section 2A.07) are used as regulatory or guide signs for preferential only lanes, they shall be the required sign size and shall display the required letter height and legend format that corresponds to the type of roadway facility and design speed.**

**Ground-mounted and overhead advance guide signs, guide signs, and exit signs applicable to HOV lanes and direct access ramps to HOV lanes shall contain the HOV diamond symbol in the upper left corner of the sign as shown in Figures 2E-46 through 2E-52. The diamond symbol shall not be used with lanes designated for bus or taxi traffic.**

**Option:**

Agencies may select from either the HOV abbreviation or the diamond symbol to reference the HOV lane designation.

**Guidance:**

Where lateral clearance is limited, such as when a ground-mounted Preferential Only Lane sign is installed on a median barrier, the edges of the sign should not project beyond the outer edges of the barrier.

**Option:**

Where lateral clearance is limited, Preferential Only Lane (R3-10, R3-11, and R3-12 series) signs that are 1800 mm (72 in) or less in width may be skewed up to 45 degrees in order to fit within the barrier width or may be mounted at a height of 4.3 m (14 ft) or more above the roadway.

**Guidance:**

Where lateral clearance is limited, Preferential Only Lane signs that are wider than 1800 mm (72 in) should be mounted at a height of at least 4.3 m (14 ft) above the roadway.

**Standard:**

**For barrier-separated preferential only lanes, overhead advance guide and overhead guide signs shall be provided in advance of and at the beginning or initial entry point to the preferential only lanes (see Figure 2E-46 for HOV lanes). Overhead guide signs shall also be used at all intermediate entry points to barrier-separated preferential only lanes (see Figure 2E-47 for HOV lanes).**

**For barrier-separated preferential only lanes, ground-mounted advance exit and ground-mounted exit signs shall be installed prior to and at the intermediate exit points of the preferential only lanes (see Figure 2E-47 for HOV lanes). Ground-mounted guide signs shall be mounted in the median or on median barriers that separate two directions of traffic.**

**Option:**

For barrier-separated preferential only lanes, an advance destination guide sign may be used in the vicinity of designated intermediate entry and exit points.

**Guidance:**

For barrier-separated preferential only lanes where conditions restrict the ability to provide more than one advance guide sign prior to the entrance to the preferential only lane, the sign should be placed approximately 800 m (0.5 mi) in advance of the exit. In these situations, the installation of the corresponding regulatory and next exit supplemental signs should be located based on the priority of the message and the available space.

**Standard:**

**For buffer-separated preferential only lanes (painted buffer of 0.6 m (2 ft) or more) where access is restricted to designated entry points, ground-mounted guide signs shall be mounted in the median or on median barriers separating two directions of traffic. Ground-mounted advance exit and ground-mounted exit signs shall be installed prior to and at the intermediate exit points of buffer-separated preferential only lanes (see Figure 2E-47 for HOV lanes).**

**Option:**

For buffer-separated preferential only lanes, an advance destination guide sign may be used in the vicinity of designated intermediate entry and exit points.

**Guidance:**

For buffer-separated HOV lanes, guide and regulatory signs should be provided to alert HOV lane users and non-users of the minimum allowable vehicle occupancy requirement and the locations of the designated entry and exit points.

**Standard:**

**For concurrent flow preferential only lanes, including those where a preferential only lane is added to the roadway (see Figure 2E-48 for HOV lanes) and those where a general purpose lane transitions into a preferential only lane on the roadway (see Figure 2E-49 for HOV lanes), an overhead regulatory (R3-14 or R3-14a) sign shall be used.**

**For concurrent flow HOV lanes on the left side of the roadway with unrestricted access, advance guide and guide signs shall only be used on direct access ramps, such as HOV lane only ramps or ramps to park & ride lots (see Figures 2E-50 and 2E-51 for HOV lanes).**

**For direct access ramps to HOV lanes, advance guide signs shall be provided along the adjoining surface streets to direct traffic into a transit facility (such as a park & ride lot or a transit station or terminal) that ultimately leads to HOV lanes (see Figure 2E-50 for HOV lanes).**


**Because direct access ramps for preferential only lanes at interchanges connecting two freeways are typically left side exits and typically have design speeds similar to the preferential only lane, overhead advance guide signs and overhead guide signs shall be provided in advance of and at the entry point to each preferential only lane ramp (see Figure 2E-52 for HOV lanes).**

Support:


Figures 2E-50 through 2E-52 provide examples of recommended uses and layouts of signs for HOV lanes for direct access ramps, park & ride lots, access from surface streets, and exclusive preferential only lane ramps at interchanges that directly connect two freeway facilities. Direct access ramps to preferential only lanes sometimes form a three or four-legged intersection that is controlled by either static signs or traffic control signals.

The use of advance guide and guide signs for direct access ramps for preferential only lanes at interchanges connecting two freeways is similar to a connecting ramp between two freeway facilities.


**Figure 2E-46. Example of Signing for the Entrance to Barrier-Separated HOV Lanes**




**Figure 2E-47. Example of Signing for the Intermediate Entry to and Exit from Barrier- or Buffer-Separated HOV Lanes**




**Figure 2E-48. Example of Signing for the Entrance to and Exit from an Added HOV Lane**



**Figure 2E-49. Example of Signing for the Entrance to and Exit from a General Purpose Lane that Becomes an HOV Lane**




**Figure 2E-50. Example of Signing for a Direct Access Ramp to an HOV Lane from a Park & Ride Facility**



NOTES:


1. Reference Sections 3B.22 and 3B.23 for additional pavement marking information.
  2. Reference Sections 2B.26 through 2B.28 and 2E.59 for appropriate text information.
  3. Additional advisory and warning signs are required.
  4. Direction of HOV traffic is inbound.
  5. Sign locations are approximate.
  6. The word message HOV may be used instead of the diamond symbol.
  7. The minimum vehicle occupancy requirement on the sign may vary for each facility.
  8. Overhead HOV signs should supplement ground-mounted HOV signs.
  9. Additional signs may be required to direct drivers from the surrounding streets into the park & ride lot and HOV lane.
  10. Additional signs are required on the adjoining surface streets to inform non-HOVs that they should not enter the HOV facility.
- \* For access restricted facilities. Destinations may be augmented to accompany routes on Interchange Sequence signs (see Figure 2E-24).

**Figure 2E-51. Example of Signing for a Direct Access Ramp to an HOV Lane from a Local Street**



\* For access restricted facilities. Destinations may be augmented to accompany routes on interchange Sequence signs (see Figure 2E-24).

**Figure 2E-52. Example of Signing for a Direct Access Ramp between HOV Lanes on Separate Freeways**



## CHAPTER 2F. SPECIFIC SERVICE SIGNS

### Section 2F.01 Eligibility

Support:

Pursuant to Section 4511.101 of the Ohio Revised Code (O.R.C.), and based on the standards and guidelines noted herein, the Ohio Department of Transportation (ODOT) has established “a program for placement of business logos for identification purposes on state directional signs within the rights-of-way of divided, multi-lane, limited access highways in both rural and urban areas.” This is commonly referred to as the Logo Program.

**Standard:**

**Specific Service signs shall be defined as guide signs that provide road users with business identification and directional information for eligible services (i.e., gas, food, lodging, camping, and attractions).**

**Specific Service signs shall not be installed at an interchange where the road user cannot conveniently reenter the freeway or expressway and continue in the same direction of travel.**

**Eligible service facilities shall comply with laws concerning the provisions of public accommodations without regard to race, religion, color, age, sex, or national origin, and laws concerning the licensing and approval of service facilities.**

**The attraction services shall include only facilities which have the primary purpose of providing amusement, historical, cultural, or leisure activities to the public.**

**Eligible gas, food, lodging, camping and attraction services shall be located in accordance with the distance criteria established by ODOT.**

**If local agencies elect to provide Specific Service signing, the ODOT policy for such signing and criteria for the availability of the various types of services shall be used.**

Support:

Additional information about ODOT's Logo Program is in Part 2 of the ODOT “Traffic Engineering Manual” (TEM) (see Section 1A.11). Information about the rules and specifications for ODOT's Logo Program is available by contacting the ODOT Office of Traffic Engineering at the address noted in the front of this Manual.

### Section 2F.02 Application

**Standard:**

**The number of Specific Service signs along an approach to an interchange or intersection, regardless of the number of service types displayed, shall be limited to a maximum of four. In the direction of traffic, successive Specific Service signs shall be for attraction, camping, lodging, food, and gas services, in that order.**

**A Specific Service sign shall display the word message GAS, FOOD, LODGING, CAMPING, or ATTRACTION, an appropriate directional legend such as the word message EXIT XX, NEXT RIGHT, SECOND RIGHT, or directional arrows, and the related logo sign panels. No more than three types of services shall be represented on any sign or sign assembly. If three types of services are shown on one sign, then the logo panels shall be limited to two for each service (for a total of six logo panels). The legend and logo panels applicable to a service type shall be displayed such that the road user will not associate them with another service type on the same sign. No service type shall appear on more than one sign. The signs shall have a blue background, a white border, and white legends of upper-case letters, numbers, and arrows.**

**Guidance:**

The Specific Service signs should be located to take advantage of natural terrain, to have the least impact on the scenic environment, and to avoid visual conflict with other signs within the highway right-of-way.

**Option:**

General Service signs (see Sections 2D.45 and 2E.51) may be used in conjunction with Specific Service signs for eligible types of services that are not represented by a Specific Service sign.

**Support:**

Examples of Specific Service signs are shown in Figure 2F-1. Examples of sign locations are shown in Figure 2F-2.

**Section 2F.03 Logos and Logo Panels****Standard:**

**A logo shall be either an identification symbol/trademark or a word message. Each logo shall be placed on a separate logo panel which shall be attached to the Specific Service sign. Symbols or trademarks used alone for a logo shall be reproduced in the colors and general shape consistent with customary use, and any integral legend shall be in proportionate size. A logo that resembles an official traffic control device shall not be used.**

**Guidance:**

A word message logo, not using a symbol or trademark, should have a blue background with white legend and border.

**Option:**

Where business identification symbols or trademarks are used alone for a logo, the border may be omitted from the logo panel.

A portion at the bottom of a GAS logo panel may be used to display the supplemental legends DIESEL, DIESEL ONLY, OPEN 24 HOURS and/or alternative fuels (see Section 2E.51), when appropriate. A portion at the bottom of a FOOD logo panel may be used to display the word CLOSED and the day of the week when the facility is closed.

**Standard:**

**The minimum height of these supplemental legends on mainline logo panels shall be 175 mm (7 in), and 75 mm (3 in) on ramp logo sign panels.**


**Section 2F.04 Number and Size of Logos and Signs****Guidance:**

Sign sizes should be determined by the amount and height of legend and the number and size of logo panels attached to the sign. All logo panels on a sign should be the same size.

**Standard:**

**Each Specific Service sign or sign assembly shall be limited to no more than six logo panels. There shall be no more than four logo panels for one of the two service types on the same sign or sign assembly.**

**Figure 2F-1. Examples of Specific Service Signs**



SINGLE-EXIT INTERCHANGE  
(ONE SERVICE)



SINGLE-EXIT INTERCHANGE  
(TWO SERVICES)




DOUBLE-EXIT INTERCHANGE



LOGO PANEL

Note: Design information for these signs, as well as for ramp and trailblazer signs, is available from ODOT, Office of Traffic Engineering upon request.

**Figure 2F-2. Examples of Specific Service Sign Locations**



**Support:**

Section 2F.08 contains information regarding Specific Service signs for double-exit interchanges.

**Standard:**

Each logo panel attached to a Specific Service sign shall have a rectangular shape with a width longer than the height. A logo panel on signs for freeways and expressways shall not exceed 1200 mm (48 in) in width and 900 mm (36 in) in height. A logo panel on signs for ramps shall not exceed 600 mm (24 in) in width and 450 mm (18 in) in height. The vertical and horizontal spacing between logo panels shall not exceed 200 mm (8 in) and 300 mm (12 in), respectively.

**Support:**

Sections 2A.15, 2E.14, and 2E.15 contain information regarding borders, interline spacing, and edge spacing.

**Section 2F.05 Size of Lettering****Standard:**

All letters and numerals on Specific Service signs, except on the logo panels, shall be a minimum height of 250 mm (10 in) for signs on freeways and expressways, and 150 mm (6 in) for signs on ramps.

**Guidance:**

Any legend on a symbol/trademark should be proportional to the size of the symbol/trademark.

**Section 2F.06 Signs at Interchanges****Standard:**

The Specific Service signs shall be installed between the previous interchange and at least 245 m (800 ft) in advance of the Exit Direction sign at the interchange from which the services are available (see Figure 2F-2).

**Guidance:**

There should be at least a 245 m (800 ft) spacing between the Specific Service signs, except for Specific Service ramp signs. However, excessive spacing is not desirable.

**Standard:**

Except as noted in the Option, Specific Service ramp signs shall be spaced at least 60 m (200 ft) from the exit gore sign, from each other, and from the ramp terminal.

**Option:**

Specific Service ramp signs may be placed on alternating sides of the ramp at 30 m (100 ft) spacing.

**Section 2F.07 Single-Exit Interchanges****Standard:**

At single-exit interchanges, the name of the service type followed by the exit number shall be displayed on one line above the logo panels. At unnumbered interchanges, the directional legend NEXT RIGHT (LEFT) shall be used.

At single-exit interchanges, Specific Service ramp signs shall be installed along the ramp or at the ramp terminal for facilities that have logo panels displayed along the main roadway if the facilities are not readily visible from the ramp terminal. Directions to the service facilities shall be indicated by arrows on the ramp signs. Logo panels on Specific Service ramp signs shall be duplicates of those displayed on the Specific Service signs located in advance of the interchange, but shall be reduced in size.

**Specific Service ramp signs shall include distances to the service facilities.**

### **Section 2F.08 Double-Exit Interchanges**

Guidance:

At double-exit interchanges, the Specific Service signs should consist of two sections, one for each exit (see Figure 2F-1).

**Standard:**

**At a double-exit interchange, the top section shall display the logo panels for the first exit and the bottom section shall display the logo panels for the second exit. The name of the service type and the exit number shall be displayed above the logo panels in each section. At unnumbered interchanges, the word message NEXT RIGHT (LEFT) and SECOND RIGHT (LEFT) shall be used in place of the exit number. The number of logo panels on the sign (total of both sections) or the sign assembly shall be limited to six.**

Option:

At a double-exit interchange where there are four logo panels to be displayed for one of the exits and one or two logo panels to be displayed for the other exit, the logo panels may be arranged in three rows with two logo panels per row.

At a double-exit interchange, where a service is to be signed for only one exit, one section of the Specific Service sign may be omitted, or a single exit interchange sign may be used.

### **Section 2F.09 Signs at Intersections**

**Standard:**

**Specific Service signs shall not be used at intersections.**

Support:

See Chapter 2G for information about tourist-oriented directional signs (TODS). These signs are used to display the business identification of and directional information to business, service, and activity facilities on conventional roads.

### **Section 2F.10 Signing Policy**

Support:

As noted in Section 2F.01, Section 4511.101 of the O.R.C. requires ODOT to establish a Specific Service signing program. ODOT has established a policy for such signing, criteria for the availability of the various types of services, sign specifications and program rules.

**Standard:**

**Each highway agency that elects to use Specific Service signs shall use the Specific Service signing guidelines, criteria and sign specifications established by ODOT.**

## CHAPTER 2G. TOURIST-ORIENTED DIRECTIONAL SIGNS

### Section 2G.01 Purpose and Application

Support:

Tourist-oriented directional signs are guide signs (TODS) with one or more panels that display the business identification of and directional information for business, service, and activity facilities.

Pursuant to Sections 4511.102 through 4511.105 of the Ohio Revised Code (O.R.C.), the Ohio Department of Transportation (ODOT) has, in conformance with the federal "Manual on Uniform Traffic Control Devices," established the provisions noted in this chapter to carry out "a program for the placement of tourist-oriented directional signs and trailblazer markers within the rights-of-way of those portions of rural state highways that are not on the interstate system."

O.R.C. Section 4511.106 requires that any local authority electing to establish a TODS program conform to the rules and specifications contained in the program established by ODOT.

**Standard:**

**A facility shall be eligible for tourist-oriented directional signs only if it derives its major portion of income or visitors during the normal business season from road users not residing within 10 miles of the facility and attendance at which is no less than 2,000 in any consecutive twelve month period.**

Option:

Tourist-oriented directional signs may include businesses involved with seasonal agricultural products.

**Standard:**

**When used, tourist-oriented directional signs shall be used only at intersections on rural conventional roads and expressways. They shall not be used at intersections on conventional roads or expressways in urban areas nor at interchanges on freeways or expressways.**

Option:

Tourist-oriented directional signs may be used in conjunction with General Service signs (see Section 2D.45).

### Section 2G.02 Design

**Standard:**

**Tourist-oriented directional signs shall have one or more panels for the purpose of displaying the business identification of and directional information for eligible facilities. Each panel shall be rectangular in shape and shall have a white legend and border on a blue background.**

**The content of the legend on each panel shall be limited to the business identification and directional information for not more than one eligible business, service, or activity facility. The legends shall not include promotional advertising.**

Guidance:

Each panel should have a maximum of two lines of legend including not more than one symbol, a separate directional arrow, and the distance to the facility shown beneath the arrow. Arrows pointing to the left or up should be at the extreme left of the sign. Arrows pointing to the right should be at the extreme right of the sign. Symbols, when used, should be to the left of the word legend or logo.

**Standard:**

**The tourist-oriented directional sign shall have the word message TOURIST ACTIVITIES at the top of the sign.**

**The TOURIST ACTIVITIES word message shall be a white legend and border on a blue background. It shall be placed above and in addition to the panels.**

**Option:**

The General Service sign symbols (see Section 2D.44) and the symbols for recreational and cultural interest area signs (see Chapter 2H) may be used.

Logos for specific businesses, services, and activities may also be used. Based on engineering judgment, the hours of operation may be added on the panels.

**Standard:**

**When used, symbols and logos shall be an appropriate size (see Section 2G.04). Logos resembling official traffic control devices shall not be permitted.**

**Support:**

Examples of tourist-oriented directional signs are shown in Figures 2G-1 and 2G-2.

**Section 2G.03 Style and Size of Lettering****Guidance:**

All letters and numbers on tourist-oriented directional signs, except on the logos, should be upper-case and at least 150 mm (6 in) in height. Any legend on a logo should be proportional to the size of the logo.

**Standard:**

**Design standards for upper-case letters, lower-case letters, numerals, and spacing shall be as provided in the "Sign Design Manual" (SDM) (see Section 1A.11).**

**Section 2G.04 Arrangement and Size of Signs****Standard:**

**The size of a tourist-oriented directional sign shall be limited to a maximum height of 2.4 m (8 ft). However, additional height shall be allowed to accommodate the addition of the TOURIST ACTIVITIES message discussed in Section 2G.02 and the directional word messages discussed in Section 2G.05.**

**The number of intersection approach signs (one sign for tourist-oriented destinations to the left, one for destinations to the right, and one for destinations straight ahead) installed at an intersection shall not exceed three. The left and right assemblies shall be located in advance of the intersection, the ahead assembly on the far side.**

**The number of panels installed on each sign shall not exceed four.**


**Guidance:**

The panels for right-turn, left-turn, and straight-ahead destinations should be on separate signs. The left-turn destination sign should be located farthest from the intersection, then the right-turn destination sign, with the straight-ahead destination sign located closest to the intersection (see Figure 2G-2).

**Standard:**


**Signs for facilities in the straight-ahead direction shall be considered only when there are signs for similar facilities in either the left or right direction.**

**Figure 2G-1. Examples of Tourist-Oriented Directional Signs**



Note : Series of lettering depends upon length of legend. Maximum length of business name per line is 1600 mm (64 in). ReflectORIZED white legend on reflectORIZED blue background.

**Figure 2G-2. Examples of Intersection Approach Signs and Advance Signs for Tourist-Oriented Directional Signs**



(1) Use if there is an intervening road

**Guidance:**

When it is appropriate to combine the left-turn and right-turn destination panels on a single sign, the left-turn destination panels should be above the right-turn destination panels (see Figure 2G-1). When there are multiple destinations in the same direction, they should be in order based on their distance from the intersection.

A straight-ahead panel should not be combined with a sign displaying left- and/or right-turn facilities.

The panels should not exceed the size necessary to accommodate two lines of legend without crowding. Symbols and logos on a panel should not exceed the height of two lines of word legends.

**Standard:**

**All panels and other parts of the sign shall be the same width, which shall not exceed 1.8 m (6 ft).**

**Option:**

At intersection approaches where three or fewer facilities are shown, the left-turn, right-turn, and straight-ahead destination panels may be combined on the same sign.

**Section 2G.05 Advance Signs****Guidance:**

Advance signs should be limited to those situations where sight distance, intersection vehicle maneuvers, or other vehicle operating characteristics require advance notification of the services.

The design of the advance sign should be identical to the design of the intersection approach sign. However, the directional arrows and distances to the facilities should be omitted. The directional word messages NEXT RIGHT, NEXT LEFT, or AHEAD should be placed on the sign above the business identification panels. The directional word messages should have the same letter height as the other word messages on the panels (see Figures 2G-1 and 2G-2).

**Standard:**

**The directional word messages shall be a white legend and border on a blue background.**

**Option:**

The legend RIGHT 1/2 MILE or LEFT 1/2 MILE may be used on advance signs when there are intervening minor roads.

The height required to add the directional word messages recommended for the advance sign may be added to the maximum sign height of 2.4 m (8 ft).

**Section 2G.06 Sign Locations****Standard:**

**If used, the intersection approach signs shall be located at least 60 m (200 ft) in advance of the intersection. Signs shall be spaced at least 60 m (200 ft) apart and at least 60 m (200 ft) from other traffic control devices.**

**If used, advance signs shall be located approximately 1 km or 0.5 mi from the intersection with 240 m (800 ft) between these signs.**

**Guidance:**

In the direction of travel, the order of advance sign placement should be to show the facilities to the left first, then facilities to the right, and last, the facilities straight ahead.

Position, height, and lateral clearance of signs should be governed by Chapter 2A except as permitted in this Section.

**Option:**

Tourist-oriented directional signs may be placed further from the edge of the road than other traffic control signs.

**Standard:**

**The location of other traffic control devices shall take precedence over the location of tourist-oriented directional signs.**

**Section 2G.07 State Policy****Standard:**

**To be eligible for tourist-oriented directional signing, facilities shall comply with applicable State or Federal laws concerning the provisions of public accommodations without regard to race, religion, color, age, sex, or national origin, and laws concerning the licensing and approval of service facilities.**

**Pursuant to O.R.C. Section 4511.106, any local authority electing to establish a TODS program shall conform to the rules and specifications contained in the program established by ODOT.**

**Support:**

As noted in Section 2G.01, pursuant to Sections 4511.102 through 4511.105 of the Ohio Revised Code (O.R.C.) (see Appendix B2), the Ohio Department of Transportation (ODOT) established a State policy regarding tourist-oriented directional signs. That policy is reflected in this chapter. Additional information specific to ODOT's application of this policy is located in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

## **CHAPTER 2H. RECREATIONAL AND CULTURAL INTEREST AREA SIGNS**

### **Section 2H.01 Scope**

Support:

Recreational or cultural interest areas are attractions or traffic generators that are open to the general public for the purpose of play, amusement, or relaxation. Recreational attractions include such facilities as parks, campgrounds, gaming facilities, and ski areas, while examples of cultural attractions include museums, art galleries, and historical buildings or sites.

The purpose of recreation and cultural interest area signs is to guide road users to a general area and then to specific facilities or activities within the area.

Option:

Recreational and cultural interest area signs that depict significant traffic generators may be used on freeways and expressways where there is direct access to these areas as discussed in Section 2H.09.

Recreational and cultural interest area signs may be used off the road network, as appropriate.

### **Section 2H.02 Application of Recreational and Cultural Interest Area Signs**

Support:

Standards for signing recreational or cultural interest areas are subdivided into two different types of signs: (1) symbol signs and (2) destination guide signs.

Guidance:

When highway agencies decide to provide recreational and cultural interest area signing, these agencies should have a policy for such signing. The policy should establish signing criteria for the eligibility of the various types of services, accommodations, and facilities. These signs should not be used where they might be confused with other traffic control signs.

Option:

Recreational and cultural interest area signs may be used on any road to direct persons to facilities, structures, and places, and to identify various services available to the general public. These signs may also be used in recreational or cultural interest areas for signing nonvehicular events and amenities such as trails, structures, and facilities.

### **Section 2H.03 Regulatory and Warning Signs**

Standard:

All regulatory and warning signs installed on public roads and streets within recreational and cultural interest areas shall conform to the requirements of Chapters 2A, 2B, and 2C.

### **Section 2H.04 General Design Requirements for Recreational and Cultural Interest Area Symbol Signs**

Standard:

Recreational and cultural interest area symbol signs shall be square or rectangular in shape and shall have a white symbol or message and white border on a brown background. The symbols shall be grouped into the following usage and series categories (see the "Sign Design Manual" (SDM) for design details):

- A. General Information (RG Series)
- B. Motorist Services (RM Series)
- C. Accommodation Services (RA Series)
- D. Land Recreation (RL series)
- E. Water Recreation (RW Series), and

## **F. Winter Recreation (RS Series)**

### **Support:**

Table 2H-1 contains a listing of the symbols within each series category. Drawings for these symbols are found in the SDM (see Section 1A.11).

### **Option:**

Mirror images of symbols may be used where the reverse image will better convey the message.

## **Section 2H.05 Symbol Sign Sizes**

### **Guidance:**

Recreational and cultural interest area symbol signs should be 600 x 600 mm (24 x 24 in). Where greater visibility or emphasis is needed, larger sizes should be used. Symbol sign enlargements should be in 150 mm (6 in) increments.

Recreational and cultural interest area symbol signs should be 750 x 750 mm (30 x 30 in) when used on freeways or expressways.

### **Option:**

A smaller size of 450 x 450 mm (18 x 18 in) may be used on low-speed, low-volume roadways and on nonroad applications.

## **Section 2H.06 Use of Educational Plaques**

### **Guidance:**

Educational plaques should accompany all initial installations of recreational and cultural interest area symbol signs. The educational plaque should remain in place for at least 3 years after the initial installation. If used, the educational plaque should be the same width as the symbol sign.

### **Option:**

Symbol signs that are readily recognizable by the public may be installed without educational plaques.

### **Support:**

Figure 2H-1 illustrates some examples of the use of educational plaques.

## **Section 2H.07 Use of Prohibitive Slash**

### **Standard:**

**The red diagonal slash, if used on a recreational and cultural interest area sign, shall be placed from the upper left corner to the lower right corner of the sign face (see Figure 2H-1). Requirements for retroreflection of the red slash shall be the same as those requirements for legends, symbols, and borders.**

### **Option:**

Where it is necessary to indicate a restriction within a recreational or cultural interest area, a red diagonal slash may be used to indicate that the activity is prohibited.

### **Support:**

Figure 2H-1 illustrates some examples of the use of prohibitive slashes.

**Table 2H-1. Category Chart for Symbols**

<b><u>General Information</u></b>		<b><u>Accommodation Services</u></b>		<b><u>Water Recreation</u></b>	
Automobile	RG-010	Airport	RA-010	Boat Tours	RW-010
Bear Viewing Area	RG-020	Bus Stop	RA-020	Canoeing	RW-020
Dam	RG-030	Campfire	RA-030	Diving	RW-030
Deer Viewing Area	RG-040	Elevator *	RA-040	Diving (Scuba)	RW-040
Drinking Water	RG-050	Kennel	RA-050	Fishing	RW-050
Environmental Study Area	RG-060	Laundry	RA-060	Marine Recreation Area	RW-060
Falling Rocks *	RG-070	Locker *	RA-070	Motorboating	RW-070
Firearms	RG-080	Parking	RA-080	Ramp (Launch)	RW-080
Fish Hatchery	RG-090	Rest Room (Men) *	RA-090	Rowboating	RW-090
Information	RG-100	Rest Room (Women) *	RA-100	Sailboating	RW-100
Leashed Pets *	RG-110	Shelter (Sleeping) *	RA-110	Skiing (water)	RW-110
Lighthouse	RG-120	Shelter (Trail) *	RA-120	Surfing	RW-120
Litter Container	RG-130	Showers *	RA-130	Swimming	RW-130
Lookout Tower	RG-140	Family Rest Room *	RA-150	Wading	RW-140
Ped Xing *	RG-150	Helicopter	RA-160	Fishing Pier	RW-160
Point of Interest	RG-160	<b><u>Land Recreation</u></b>		Hand Launch	RW-170
Ranger Station	RG-170	Amphitheater	RL-010	Kayak	RW-190
Smoking *	RG-180	Climbing	RL-020	Wind Surf	RW-210
Truck	RG-190	Climbing (Rock)	RL-030	<b><u>Winter Recreation</u></b>	
Tunnel	RG-200	Hunting	RL-040	Skating (Ice)	RS-010
Dog	RG-240	Playground	RL-050	Ski Jumping	RS-020
Seaplane	RG-260	Rock Collecting	RL-060	Skiing (Bobbing)	RS-030
<b><u>Motorist Services</u></b>		Spelunking	RL-070	Skiing (Cross Country)	RS-040
Camping (tent)	RM-010	Stable	RL-080	Skiing (Downhill)	RS-050
Camping (trailer)	RM-020	Trail (Bicycle)	RL-090	Sledding	RS-060
Ferry	RM-030	Trail (Hiking)	RL-100	Snowmobiling	RS-070
First Aid	RM-040	Trail (Horse)	RL-110	Snowshoeing	RS-080
Food	RM-050	Trail (Interpretive, Auto)	RL-120	Winter Recreation Area	RS-090
Gas	RM-060	Trail (Interpretive, Ped.)	RL-130	Chairlift	RS-100
Grocery Store	RM-070	Trail/Road (4 WD Veh.)	RL-140		
Handicapped	RM-080	Trail (Trail Bike)	RL-150		
Lodging	RM-090	Tramway	RL-160		
Mechanical	RM-100	All-Terrain Vehicle	RL-170		
Post Office	RM-110	Archer	RL-190		
Picnic Area	RM-120	Hang Glider	RL-210		
Picnic Shelter	RM-130				
Rest Room	RM-140				
Telephone	RM-150				
Trailer Sanitary Station	RM-160				
Viewing Area	RM-170				
Motor Home	RM-200				
Group Camping	RM-210				
Group Picnicking	RM-220				

\* For Non-Road Use

**Figure 2H-1. Examples of Use of Educational Plaques, Prohibitory Slashes, and Arrows**




**Figure 2H-2. Examples of General Directional Guide Signs for Conventional Roads**




\* Optional shape

**Figure 2H-3. Height and Lateral Position of Signs Located Within Recreational and Cultural Interest Areas**



Note:  
See Section 2A.19 for reduced lateral offset distances that may be used in areas where lateral offsets are limited, and in urban areas where sidewalk width is limited or where existing poles are close to the curb.

**Figure 2H-4. Examples of Symbol Signing Layout**




**Figure 2H-5. Recreational and Cultural Interest Area Symbol Signs**  
(Sheet 1 of 5)



RG-010  
Automobile



RG-020  
Bear Viewing Area



RG-030  
Dam



RG-040  
Deer Viewing Area



RG-050  
Drinking Water




RG-060  
Environmental  
Study Area



RG-070  
Falling Rocks



RG-080  
Firearms



RG-090  
Fish Hatchery



RG-100  
Information



RG-110  
Leashed Pets



RG-120  
Lighthouse



RG-130  
Litter Container



RG-140  
Lookout Tower



RG-150  
Ped Xing



RG-160  
Point of Interest



RG-170  
Ranger Station



RG-180  
Smoking



RG-190  
Truck



RG-200  
Tunnel



RG-240  
Dog



RG-260  
Seaplane



RM-010  
Camping (Tent)




RM-020  
Camping (Trailer)



RM-030  
Ferry

**Figure 2H-5. Recreational and Cultural Interest Area Symbol Signs**  
(Sheet 2 of 5)



RM-040  
First Aid



RM-050  
Food



RM-060  
Gas



RM-070  
Grocery Store



RM-080  
Handicapped




RM-090  
Lodging



RM-100  
Mechanic



RM-110  
Post Office



RM-120  
Picnic Area



RM-130  
Picnic Shelter




RM-140  
Rest Room



RM-150  
Telephone




RM-160  
Trailer  
Sanitary Station



RM-170  
Viewing Area



RM-200  
Motor Home



**GROUP  
CAMPING**

RM-210  
Group Camping



**GROUP  
PICNICKING**

RM-220  
Group Picnicking



RA-010  
Airport



RA-020  
Bus Stop




RA-030  
Campfire



RA-040  
Elevator



RA-050  
Kennel



RA-060  
Laundry



RA-070  
Locker



RA-080  
Parking

**Figure 2H-5. Recreational and Cultural Interest Area Symbol Signs**  
(Sheet 3 of 5)




RA-090  
Rest Room (Men)



RA-100  
Rest Room (Women)



RA-110  
Shelter (Sleeping)




RA-120  
Shelter (Trail)




RA-130  
Showers



RA-150  
Family Rest Room



RA-160  
Helicopter



RL-010  
Amphitheater



RL-020  
Climbing



RL-030  
Climbing (Rock)



RL-040  
Hunting



RL-050  
Playground



RL-060  
Rock Collecting



RL-070  
Spelunking



RL-080  
Stable



RL-090  
Trail  
(Bicycle)



RL-100  
Trail  
(Hiking)



RL-110  
Trail  
(Horse)



RL-120  
Trail  
(Interpretive, Auto)




RL-130  
Trail  
(Interpretive, Ped.)



RL-140  
Trail/Road  
(4 WD Veh.)



RL-150  
Trail  
(Trail Bike)



RL-160  
Tramway



RL-170  
All-Terrain Vehicle




RL-190  
Archer

**Figure 2H-5. Recreational and Cultural Interest Area Symbol Signs**  
(Sheet 4 of 5)



RL-210  
Hang Glider



RW-010  
Boat Tours



RW-020  
Canoeing



RW-030  
Diving



RW-040  
Diving (Scuba)



RW-050  
Fishing



RW-060  
Marine Recreation  
Area



RW-070  
Motorboating



RW-080  
Ramp (Launch)



RW-090  
Rowboating



RW-100  
Sailboating



RW-110  
Skiing (Water)



RW-120  
Surfing



RW-130  
Swimming



RW-140  
Wading



RW-160  
Fishing Pier



RW-170  
Hand Launch



RW-190  
Kayak



RW-210  
Wind Surf



RS-010  
Skating (Ice)



RS-020  
Ski Jumping



RS-030  
Skiing  
(Bobbing)



RS-040  
Skiing  
(Cross Country)



RS-050  
Skiing  
(Downhill)



RS-060  
Sledding

## **Figure 2H-5. Recreational and Cultural Interest Area Symbol Signs** (Sheet 5 of 5)



RS-070  
Snowmobiling



RS-080  
Snowshoeing



RS-090  
Winter Recreation  
Area



RS-100  
Chairlift

### **Section 2H.08 Placement of Recreational and Cultural Interest Area Symbol Signs**

#### **Standard:**

If used, recreational and cultural interest area symbol signs shall be placed in accordance with the general requirements contained in Chapter 2A. The symbol(s) shall be placed in the uppermost part of the sign assembly and the directional information shall be placed below the symbol(s).

Where the name of the recreational or cultural interest area facility or activity is shown on a general directional guide sign and a symbol is used, the symbol shall be placed below the name (see Figure 2H-2).

Recreational and cultural interest area symbols installed for nonroad use shall be placed in accordance with the general sign position requirements of the authority having jurisdiction.

#### **Support:**

Figure 2H-3 illustrates typical height and lateral mounting positions. Figure 2H-4 illustrates some examples of the placement of symbol signs within a recreational or cultural interest area. Figure 2H-5 illustrates some of the symbols that can be used.

#### **Guidance:**

The number of symbols used in a single sign assembly should not exceed four.

#### **Option:**

Symbols for recreational or cultural interest areas may be used as legend components for a directional sign assembly. The symbols may be used singularly, or in groups of two, three, or four on a single sign assembly (see Figures 2H-1, 2H-3, and 2H-4). Smaller-size secondary symbols (see Figure 2H-1) may be placed beneath the primary symbols, where needed.

### **Section 2H.09 Destination Guide Signs**

#### **Guidance:**

When recreational or cultural interest area destinations are shown on supplemental guide signs, the sign should be rectangular or trapezoidal in shape. The order of preference for use of shapes and colors should be as follows: (1) rectangular with a white legend and border on a green background; (2) rectangular with a white legend and border on a brown background; or (3) trapezoidal with a white legend and border on a brown background.

In order to control proliferation of destination signs, each responsible jurisdiction should establish a policy similar to the traffic generator policy established by the Ohio Department of Transportation (ODOT) in Part 2 of ODOT's "Traffic Engineering Manual" (see Section 1A.11).

**Standard:**

**Whenever the trapezoidal shape is used, the color combination shall be a white legend and border on a brown background.**

## Option:

White-on-brown destination guide signs may be posted at the first point where an access or crossroad intersects a highway where recreational or cultural interest areas are a significant destination along conventional roads, expressways, or freeways. White-on-brown supplemental guide signs may be used along conventional roads, expressways, or freeways to direct road users to recreational or cultural interest areas. Where access or crossroads lead exclusively to the recreational or cultural interest area, the advance guide sign and the exit direction sign may be white-on-brown.

**Standard:**

**Linear parkway-type highways that primarily function as arterial connectors, even if they also provide access to recreational or cultural interest areas, shall not qualify for the use of white-on-brown destination guide signs. Directional guide signs used on these highways shall conform to Chapter 2D.**

**All gore signs shall have a white legend and border on a green background. The background color of the interchange exit number panel shall match the background color of the guide sign. Design characteristics of conventional road, expressway, or freeway guide signs shall conform to Chapter 2D or 2E except as specified in this Section for color combination.**

**The advance guide sign and the Exit Direction sign shall retain the white-on- green color combination where the crossroad leads to a destination other than a recreational or cultural interest area.**

## Support:

Figure 2H-2 illustrates destination guide signs commonly used for identifying recreational or cultural interest areas or facilities. The D7-H4 and D7-H4a shown in Appendix C are also examples of common destination guide signs used for this purpose.

White-on-brown supplemental guide signs designed in accordance with the Freeway and Expressway Guide Sign Design Method described in Appendix C of the SDM (see Section 1A.11) are identified with the code number E3-H2 (see Appendix C).

Intentionally blank.

## CHAPTER 2I. EMERGENCY MANAGEMENT SIGNING

### **Section 2I.01 Emergency Management**

Guidance:

Contingency planning for an emergency evacuation should be considered by all State and local jurisdictions and should consider the use of all applicable roadways.

In the event of a disaster where highways that cannot be used will be closed, a successful contingency plan should account for the following elements: a controlled operation of certain designated highways, the establishment of traffic operations for the expediting of essential traffic, and the provision of emergency centers for civilian aid.

### **Section 2I.02 Design of Emergency Management Signs**

**Standard:**

**Emergency Management signs shall be used to guide and control highway traffic during an emergency.**

**Emergency Management signs shall not permanently displace any of the standard signs that are normally applicable.**

**Advance planning for transportation operations' emergencies shall be the responsibility of State and local authorities. The Federal Government shall provide guidance to the States as necessitated by changing circumstances.**

**The sizes for Emergency Management signs shall be as shown in Table 2I-1.**

Guidance:

As conditions permit, the Emergency Management signs should be replaced or augmented by standard signs.

The background of Emergency Management signs should be retroreflective.

Because Emergency Management signs might be needed in large numbers for temporary use during an emergency, consideration should be given to their fabrication from any light and economical material that can serve through the emergency period.

Option:

Any Emergency Management sign may be accompanied by a standard triangular plaque for marking areas contaminated by biological and chemical warfare agents and radioactive fallout.

### **Section 2I.03 EVACUATION ROUTE Sign (EM-1)**

**Standard:**

**The EVACUATION ROUTE (EM-1) sign (see Figure 2I-1) shall be a rectangular sign with a blue circular symbol with a directional arrow and the legend EVACUATION ROUTE.**

Option:

An approved Emergency Management symbol may appear near the bottom of the sign with a diameter of 87 mm (3.5 in).

**Standard:**

**The legend and arrow of the EVACUATION ROUTE sign shall be white on a blue circular background. The corners of the sign outside of the circle shall be white. The entire sign shall be retroreflective. The arrow designs shall include a straight, vertical arrow pointing upward, a straight**

**Table 2I-1. Emergency Management Sign Sizes**

Sign	Code No.	Section	Conventional Road	Expressway	Freeway	Minimum	Oversized
EVACUATION ROUTE	EM-1	2I.03	600 x 600 (24 x 24)	—	—	450 x 450 (18 x 18)	—
AREA CLOSED	EM-2	2I.04	750 x 600 (30 x 24)	—	—	—	—
TRAFFIC CONTROL POINT	EM-3	2I.05	750 x 600 (30 x 24)	—	—	—	—
MAINTAIN TOP SAFE SPEED	EM-4	2I.06	600 x 750 (24 x 30)	—	—	—	—
Permit Required	EM-5	2I.07	600 x 750 (24 x 30)	—	—	—	—
Emergency Aid Center	EM-6a to EM-6d	2I.08	750 x 600 (30 x 24)	—	—	—	—
Shelter Directional	EM-7a to EM-7d	2I.09	750 x 600 (30 x 24)	—	—	—	—

## Notes:

1. Larger sizes may be used when appropriate.
2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height.

**horizontal arrow pointing to the left or right, or a bent arrow pointing to the left or right for advance warning of a turn.**

**If used, the EVACUATION ROUTE sign, with the appropriate arrow, shall be installed 45 to 90 m (150 to 300 ft) in advance of, and at, any turn in an approved evacuation route. The sign shall also be installed elsewhere for straight-ahead confirmation where needed.**

**If used in urban areas, the EVACUATION ROUTE sign shall be mounted at the right-hand side of the roadway, not less than 2.1 m (7 ft) above the top of the curb, and at least 0.3 m (1 ft) back from the face of the curb. If used in rural areas, it shall be not less than 2.1 m (7 ft) above the pavement and 1.8 to 3 m (6 to 10 ft) to the right side of the roadway edge.**

**EVACUATION ROUTE signs shall not be placed where they will conflict with other signs. Where conflict in placement would occur between the EVACUATION ROUTE sign and a standard regulatory sign, the regulatory sign shall take precedence.**

## Option:

The legend on the EVACUATION ROUTE sign may be modified to describe the type of evacuation route, such as HURRICANE.

In case of conflict with guide or warning signs, the Emergency Management sign may take precedence.

## Guidance:

Placement of EVACUATION ROUTE signs should be made under the supervision of the officials having jurisdiction over the placement of other traffic signs. Coordination with Emergency Management authorities and agreement between contiguous political entities should occur to assure continuity of routes.

## Option:

The arrow may be a separate panel attached to the face of the sign.

**Section 2I.04 AREA CLOSED Sign (EM-2)****Standard:**

The AREA CLOSED (EM-2) sign (see Figure 2I-1) shall be used to close a roadway in order to prohibit traffic from entering the area. It shall be installed on the shoulder as near as practical to the right edge of the roadway, or preferably, on a portable mounting or barricade partly or entirely in the roadway.

**Guidance:**

For best visibility, particularly at night, the sign height should not exceed 1.2 m (4 ft) from the pavement to the bottom of the sign. Unless adequate advance warning signs are used, it should not be placed to create a complete and unavoidable blocked route. Where feasible, the sign should be located at an intersection that provides a detour route.

**Section 2I.05 TRAFFIC CONTROL POINT Sign (EM-3)****Standard:**

The TRAFFIC CONTROL POINT (EM-3) sign (see Figure 2I-1) shall be used to designate a location where an official traffic control point has been set up to impose such controls as are necessary to limit congestion, expedite emergency traffic, exclude unauthorized vehicles, or protect the public.

The sign shall be installed in the same manner as the AREA CLOSED sign (see Section 2I.04), and at the point where traffic must stop to be checked.

The standard STOP (R1-1) sign shall be used in conjunction with the TRAFFIC CONTROL POINT sign. The TRAFFIC CONTROL POINT sign shall consist of a black legend and border on a retroreflectorized white background.

**Guidance:**

The TRAFFIC CONTROL POINT sign should be mounted directly below the STOP sign.

**Section 2I.06 MAINTAIN TOP SAFE SPEED Sign (EM-4)****Option:**

The MAINTAIN TOP SAFE SPEED (EM-4) sign (see Figure 2I-1) may be used on highways where conditions are such that it is prudent to evacuate or traverse an area as quickly as possible.

Where an existing Speed Limit (R2-1) sign is in a suitable location, the MAINTAIN TOP SAFE SPEED sign may conveniently be mounted directly over the face of the speed limit sign that it supersedes.

**Support:**


Since any speed zoning would be impractical under such emergency conditions, no minimum speed limit can be prescribed by the MAINTAIN TOP SAFE SPEED sign in numerical terms. Where traffic is supervised by a traffic control point, official instructions will usually be given verbally, and the sign will serve as an occasional reminder of the urgent need for maintaining the proper reasonably safe speed.

**Guidance:**

The sign should be installed as needed, in the same manner as other standard speed signs.

**Standard:**

If used in rural areas, the MAINTAIN TOP SAFE SPEED sign shall be mounted on the right side of the road with its lower edge not less than 1.5 m (5 ft) above the pavement, 1.8 to 3 m (6 to 10 ft) from the roadway edge. If used in urban areas, the height shall be not less than 2.1 m (7 ft), and the nearest edge of the sign shall be not less than 0.3 m (1 ft) back from the face of the curb.

**Figure 2I-1. Emergency Management Signs**

\* Legend may be modified to describe the type of evacuation route (see Section 2I.03).

### **Section 2I.07 ROAD (AREA) USE PERMIT REQUIRED FOR THRU TRAFFIC Sign (EM-5)**

Support:

The intent of the ROAD (AREA) USE PERMIT REQUIRED FOR THRU TRAFFIC (EM-5) sign (see Figure 2I-1) is to notify road users of the presence of the traffic control point so that those who do not have priority permits issued by designated authorities can take another route, or turn back, without making a needless trip and without adding to the screening load at the post. Local traffic, without permits, can proceed as far as the traffic control post.

**Standard:**

**If used, the ROAD (AREA) USE PERMIT REQUIRED FOR THRU TRAFFIC (EM-5) sign shall be used at an intersection that is an entrance to a route on which a traffic control point is located.**

**If used, the sign shall be installed in a manner similar to that of the MAINTAIN TOP SAFE SPEED sign (see Section 2I.06).**

## **Section 2I.08 Emergency Aid Center Signs (EM-6 Series)**

### **Standard:**

In the event of emergency, State and local authorities shall establish various centers for civilian relief, communication, medical service, and similar purposes. To guide the public to such centers a series of directional signs shall be used.

Emergency Aid Center (EM-6 series) signs (see Figure 2I-1) shall carry the designation of the center and an arrow indicating the direction to the center. They shall be installed as needed, at intersections and elsewhere, on the right side of the roadway, at a height in urban areas of at least 2.1 m (7 ft), and not less than 0.3 m (1 ft) back from the face of the curb, and in rural areas at a height of 1.5 m (5 ft), 1.8 to 3 m (6 to 10 ft) from the roadway edge.

Emergency Aid Center signs shall carry one of the following legends, as appropriate, or others designating similar emergency facilities:

- A. MEDICAL CENTER (EM-6a)
- B. WELFARE CENTER (EM-6b)
- C. REGISTRATION CENTER (EM-6c)
- D. DECONTAMINATION CENTER (EM-6d)

The Emergency Aid Center sign shall be a horizontal rectangle. The identifying word and the word CENTER, the directional arrow, and the border shall be black on a white background.

## **Section 2I.09 Shelter Directional Signs (EM-7 Series)**

### **Standard:**

Shelter Directional (EM-7 Series) signs (see Figure 2I-1) shall be used to direct the public to selected shelters that have been licensed and marked for emergency use.

The installation of Shelter Directional signs shall conform to established highway signing standards. Where used, the signs shall not be installed in competition with other necessary highway guide, warning, and regulatory signs.

The Shelter Directional sign shall be a horizontal rectangle. The identifying word and the word SHELTER, the directional arrow, the distance to the shelter, and the border shall be black on a white background.

### **Option:**

The distance to the shelter may be omitted from the sign when appropriate.

Shelter Directional signs may carry one of the following legends, or others designating similar emergency facilities:

- A. EMERGENCY (EM-7a)
- B. HURRICANE (EM-7b)
- C. FALLOUT (EM-7c)
- D. CHEMICAL (EM-7d)

If appropriate, the name of the facility may be used.

The Shelter Directional signs may be installed on the Interstate Highway System or any other major highway system when it has been determined that a need exists for such signs as part of a State or local shelter plan.

The Shelter Directional signs may be used to identify different routes to a shelter to provide for rapid movement of large numbers of persons.

**Guidance:**

The Shelter Directional sign should be used sparingly and only in conjunction with approved plans of State and local authorities.

As a general rule, the Shelter Directional sign should not be posted more than 8 km (5 mi) from a shelter.

## PART 3. MARKINGS

### TABLE OF CONTENTS

		<u>Page</u>
<b>CHAPTER 3A.</b>	<b>GENERAL</b>	
Section 3A.01	Functions and Limitations .....	3A-1
Section 3A.02	Standardization of Application .....	3A-1
Section 3A.03	Materials .....	3A-1
Section 3A.04	Colors.....	3A-2
Section 3A.05	Widths and Patterns of Longitudinal Pavement Markings .....	3A-2
<b>CHAPTER 3B.</b>	<b>PAVEMENT AND CURB MARKINGS</b>	
Section 3B.01	Centerline Pavement Markings and Warrants .....	3B-1
Section 3B.02	No-Passing Zone Pavement Markings and Warrants .....	3B-2
Section 3B.03	Other Yellow Longitudinal Pavement Markings.....	3B-6
Section 3B.04	Lane Line Pavement Markings and Warrants.....	3B-8
Section 3B.05	Other White Longitudinal Pavement Markings.....	3B-12
Section 3B.06	Edge Line Pavement Markings.....	3B-13
Section 3B.07	Warrants for Use of Edge Lines .....	3B-18
Section 3B.08	Extensions Through Intersections or Interchanges.....	3B-18
Section 3B.09	Lane Reduction Transition Markings .....	3B-21
Section 3B.10	Approach Markings for Obstructions .....	3B-21
Section 3B.11	Raised Pavement Markers.....	3B-22
Section 3B.12	Raised Pavement Markers as Vehicle Positioning Guides with Other Longitudinal Markings .....	3B-26
Section 3B.13	Raised Pavement Markers Supplementing Other Markings .....	3B-26
Section 3B.14	Raised Pavement Markers Substituting for Pavement Markings .....	3B-27
Section 3B.15	Transverse Markings.....	3B-28
Section 3B.16	Stop and Yield Lines.....	3B-28
Section 3B.17	Crosswalk Markings .....	3B-30
Section 3B.18	Parking Space Markings .....	3B-31
Section 3B.19	Pavement Word and Symbol Markings .....	3B-36
Section 3B.20	Speed Measurement Markings.....	3B-42
Section 3B.21	Curb Markings .....	3B-42
Section 3B.22	Preferential Lane Word and Symbol Markings .....	3B-43
Section 3B.23	Preferential Lane Longitudinal Markings for Motor Vehicles.....	3B-44
Section 3B.24	Markings for Roundabout Intersections .....	3B-48
Section 3B.25	Markings for Other Circular Intersections.....	3B-49
Section 3B.26	Speed Hump Markings .....	3B-49
Section 3B.27	Advance Speed Hump Markings .....	3B-49
<b>CHAPTER 3C.</b>	<b>OBJECT MARKERS AND END-OF-ROADWAY MARKERS</b>	
Section 3C.01	Object Marker Design and Placement Height .....	3C-1
Section 3C.02	Markings for Objects in the Roadway .....	3C-1
Section 3C.03	Markings for Objects Adjacent to the Roadway.....	3C-2
Section 3C.04	End-of-Roadway Markers.....	3C-2
<b>CHAPTER 3D.</b>	<b>DELINEATORS</b>	
Section 3D.01	Delineators .....	3D-1
Section 3D.02	Delineator Design .....	3D-1
Section 3D.03	Delineator Application.....	3D-1

Section 3D.04	Delineator Placement and Spacing .....	3D-2
<b>CHAPTER 3E.</b>	<b>COLORED PAVEMENTS</b>	
Section 3E.01	General .....	3E-1
<b>CHAPTER 3F.</b>	<b>BARRICADES AND CHANNELIZING DEVICES</b>	
Section 3F.01	Barricades .....	3F-1
Section 3F.02	Channelizing Devices .....	3F-1
<b>CHAPTER 3G.</b>	<b>ISLANDS</b>	
Section 3G.01	General .....	3G-1
Section 3G.02	Approach-End Treatment .....	3G-1
Section 3G.03	Island Marking Application .....	3G-1
Section 3G.04	Island Marking Colors .....	3G-2
Section 3G.05	Island Object Markers .....	3G-2
Section 3G.06	Island Delineators .....	3G-2

## **FIGURES**

<b>CHAPTER 3B.</b>	<b>PAVEMENT AND CURB MARKING</b>	
Figure 3B-1	Examples of Two-Lane, Two-Way Marking Applications .....	3B-3
Figure 3B-2	Examples of Four-or-More Lane, Two-Way Marking Applications .....	3B-4
Figure 3B-3	Examples of Three-Lane, Two-Way Marking Applications .....	3B-5
Figure 3B-4	Example of Three-Lane, Two-Way Marking for Changing Direction of the Center Lane .....	3B-7
Figure 3B-5	Method of Locating and Determining the Limits of No-Passing Zones at Curves .....	3B-9
Figure 3B-6	Example of Reversible Lane Marking Application .....	3B-10
Figure 3B-7	Example of Two-Way Left-Turn Lane Marking Applications .....	3B-11
Figure 3B-8	Examples of Channelizing Line Applications for Exit Ramp Markings .....	3B-14
Figure 3B-9	Examples of Channelizing Line Applications for Entrance Ramp Markings ....	3B-16
Figure 3B-10	Example of Lane Drop Markings at Exit Ramps .....	3B-17
Figure 3B-11	Examples of Extensions through Intersections .....	3B-19
Figure 3B-12	Examples of Lane Reduction Markings .....	3B-23
Figure 3B-13	Examples of Markings for Obstructions in the Roadway .....	3B-24
Figure 3B-14	Examples of Yield Line Layouts .....	3B-29
Figure 3B-15	Examples of Yield Lines at Unsignalized Midblock Crosswalks .....	3B-30
Figure 3B-16	Examples of Crosswalk Markings .....	3B-32
Figure 3B-17	Example of Crosswalk Markings for Exclusive Pedestrian Phase That Permits Diagonal Crossing .....	3B-32
Figure 3B-18	Examples of Parking Space Markings .....	3B-33
Figure 3B-19	International Symbol of Accessibility Parking Space Marking with Blue Background and White Border Options .....	3B-34
Figure 3B-20	Example of Elongated Letters for Word Pavement Markings .....	3B-34
Figure 3B-21	Examples of Standard Arrows for Pavement Markings .....	3B-35
Figure 3B-22	Examples of Lane Use Control Word and Symbol Markings .....	3B-37
Figure 3B-23	Examples of Arrow Markings at Exit Ramp Terminals .....	3B-38
Figure 3B-24	Examples of Arrow Markings at Entrance Ramp Terminals .....	3B-39
Figure 3B-25	Yield Ahead Triangle Symbols .....	3B-40
Figure 3B-26	Examples of Markings for Preferential Lanes .....	3B-46
Figure 3B-27	Examples of Markings for Roundabout Intersections with One-Lane Approaches .....	3B-50

Figure 3B-28 Examples of Markings for Roundabout Intersections with Two-Lane Approaches ..... 3B-51

Figure 3B-29 Examples of Pavement Markings for Speed Humps Without Crosswalks ..... 3B-52

Figure 3B-30 Examples of Pavement Markings for Speed Tables or Speed Humps With Crosswalks ..... 3B-53

Figure 3B-31 Examples of Advance Warning Markings for Speed Humps ..... 3B-54

**CHAPTER 3C. OBJECT MARKERS**

Figure 3C-1 Object Markers and End-of-Roadway Markers..... 3C-3

**CHAPTER 3D. DELINEATORS**

Figure 3D-1 Examples of Delineator Placement..... 3D-4

**TABLES**

**CHAPTER 3B. PAVEMENT AND CURB MARKINGS**

Table 3B-1 Minimum Passing Sight Distances ..... 3B-8

Table 3B-2 Standard Edge Line Lane Markings for Preferential Lanes ..... 3B-45

**CHAPTER 3D. DELINEATORS**

Table 3D-1 Approximate Spacing for Delineators on Horizontal Curves..... 3D-3

Intentionally blank.

## CHAPTER 3A. GENERAL

### Section 3A.01 Functions and Limitations

Support:

Markings on highways have important functions in providing guidance and information for the road user. Major marking types include pavement and curb markings, object markers, delineators, colored pavements, barricades, channelizing devices and islands. In some cases, markings are used to supplement other traffic control devices such as signs, signals and other markings. In other instances, markings are used alone to effectively convey regulations, guidance, or warnings in ways not obtainable by the use of other devices.

Markings have limitations. Visibility of the markings can be limited by snow, debris, and water on or adjacent to the markings. Marking durability is affected by material characteristics, traffic volumes, weather, and location. However, under most highway conditions, markings provide important information while allowing minimal diversion of attention from the roadway.

Pavement markings can enhance roadway delineation with the addition of audible and tactile features such as bars, differential surface profiles, raised pavement markers, or other devices intended to alert the road user that a delineation on the roadway is being traversed.

The general functions of longitudinal lines are:

- A. A double line indicates maximum or special restrictions,
- B. A solid line discourages or prohibits crossing (depending on the specific application),
- C. A broken line indicates a permissive condition, and
- D. A dotted line provides guidance.

### Section 3A.02 Standardization of Application

Standard:

**Each standard marking shall be used only to convey the meaning prescribed for that marking in this Manual. When used for applications not described herein, markings shall conform in all respects to the principles and standards set forth herein.**

Guidance:

Before any new highway, paved detour, or temporary route is opened to traffic, all necessary markings should be in place.

Standard:

**Markings that are no longer applicable for roadway conditions or restrictions and that might cause confusion for the road user shall be removed or obliterated to be unidentifiable as a marking as soon as practical. Markings that must be visible at night shall be retroreflective unless ambient illumination assures that the markings are adequately visible. All markings on Interstate highways shall be retroreflective.**

Option:

Markings may be temporarily masked with tape until they can be removed or obliterated.

### Section 3A.03 Materials

Support:

Pavement and curb markings are commonly placed by using paints or thermoplastics; however, other suitable marking materials, including raised pavement markers and colored pavements, are also used. Delineators, object markers, barricades, and channelizing devices are visibly placed in a vertical position similar to signs above the roadway.

**Guidance:**

The materials used for markings should provide the specified color throughout their useful life.

Consideration should be given to selecting pavement marking materials that will minimize tripping or loss of traction for pedestrians, bicyclists and motorcyclists.

Object markers and delineators should not present a vertical or horizontal clearance obstacle for pedestrians.

**Section 3A.04 Colors****Standard:**

**Markings shall be yellow, white, red, or blue. The colors for markings shall conform to the standard highway colors. Black in conjunction with one of the above colors shall be a usable color.**

**When used, white markings for longitudinal lines shall delineate:**

- A. The separation of traffic flows in the same direction.**
- B. The right edge of the roadway.**

**When used, yellow markings for longitudinal lines shall delineate:**

- A. The separation of traffic traveling in opposite directions.**
- B. The left edge of the roadways of divided and one-way highways and ramps.**
- C. The separation of two-way left turn lanes and reversible lanes from other lanes.**

**When used, red raised pavement markers shall delineate roadways that shall not be entered or used.**

**When used, blue markings shall supplement white markings for parking spaces for persons with disabilities. When used, blue raised pavement markers shall indicate locations of fire hydrants along a roadway.**

**Option:**

Black may be used in combination with the above colors where a light-colored pavement does not provide sufficient contrast with the markings.

**Support:**

When used in combination with other colors, black is not considered a marking color, but only a contrast-enhancing system for the markings.

**Section 3A.05 Widths and Patterns of Longitudinal Pavement Markings****Standard:**

**The widths and patterns of longitudinal lines shall be as follows:**

- A. A normal line is 100 to 150 mm (4 to 6 in) wide.**
- B. A wide line is at least twice the width of a normal line. The width of the line indicates the degree of emphasis.**
- C. A double line consists of two parallel lines separated by a discernible space.**
- D. A broken line consists of normal line segments separated by gaps.**
- E. A dotted line shall consist of noticeably shorter line segments separated by shorter gaps than used for a broken line. The width of a dotted line shall be at least the same as the width of the line it extends.**

**Guidance:**

Broken lines should consist of 3 m (10 ft) line segments and 9 m (30 ft) gaps, or dimensions in a similar ratio of line segments to gaps as appropriate for traffic speeds and need for delineation.

**Option:**

A dotted line for line extensions may consist of 0.6 m (2 ft) line segments and 0.6 m (2 ft) to 1.8 m (6 ft) gaps. A dotted line for lane drop/add markings may consist of a 0.9 m (3 ft) line segments and 2.7 m (9 ft) gaps.

Intentionally blank.

## CHAPTER 3B. PAVEMENT AND CURB MARKINGS

### Section 3B.01 Centerline Pavement Markings and Warrants

#### Standard:

**Centerline pavement markings, when used, shall be the pavement markings used to delineate the separation of traffic lanes that have opposite directions of travel on a roadway and shall be yellow.**

#### Option:

Centerline pavement markings may be placed at a location that is not the geometric center of the roadway.

On roadways without continuous centerline pavement markings, short sections may be marked with centerline pavement markings to control the position of traffic at specific locations, such as around curves, over hills, on approaches to highway-railroad grade crossings, at highway-railroad grade crossings, and at bridges.

#### Standard:

**The centerline markings on two-lane, two-way roadways shall be one of the following as shown in Figure 3B-1:**

- A. Two-direction passing zone markings consisting of a normal broken yellow line where crossing the centerline markings for passing with care is permitted for traffic traveling in either direction;**
- B. One-direction no-passing zone markings consisting of a normal broken yellow line and a normal solid yellow line where crossing the centerline markings for passing with care is permitted for the traffic traveling adjacent to the broken line, but is prohibited for traffic traveling adjacent to the solid line; and**
- C. Two-direction no-passing zone markings consisting of two normal solid yellow lines where crossing the centerline markings for passing is prohibited for traffic traveling in either direction.**

**The centerline markings on undivided two-way roadways with four or more lanes for moving motor vehicle traffic always available shall be the two-direction no-passing zone markings consisting of two normal solid yellow lines as shown in Figure 3B-2.**

#### Guidance:

On two-way roadways with three through lanes for moving motor vehicle traffic, two lanes should be designated for traffic in one direction by using one- or two-direction no-passing zone markings as shown in Figure 3B-3.

#### Standard:

**Centerline markings shall be placed on all paved urban arterials and collectors that have a traveled way of 6.1 m (20 ft) or more in width and an ADT of 6,000 vehicles per day or greater. Centerline markings shall also be placed on all paved two-way streets or highways that have three or more lanes for moving motor vehicle traffic.**

#### Guidance:

Centerline markings should be placed on paved urban arterials and collectors that have a traveled way of 6.1 m (20 ft) or more in width and an ADT of 4,000 vehicles per day or greater. Centerline markings should also be placed on all rural arterials and collectors that have a traveled way of 5.5 m (18 ft) or more in width and an ADT of 3,000 vehicles per day or greater. Centerline markings should also be placed on other traveled ways where an engineering study indicates such a need.

Centerline markings should not be applied within 45.8 m (150 ft) of a one-lane bridge.

Engineering judgment should be used in determining whether to place centerline markings on traveled ways that are less than 4.9 m (16 ft) wide because of the potential for traffic encroaching on the pavement edges, traffic being affected by parked vehicles, and traffic encroaching into the opposing traffic lane.

Option:

Centerline markings may be placed on other paved two-way traveled ways that are 4.9 m (16 ft) or more in width.

If a traffic count is not available, the ADTs described in this Section may be estimates that are based on engineering judgment.

### **Section 3B.02 No-Passing Zone Pavement Markings and Warrants**

**Standard:**

**No-passing zones shall be marked by either the one direction no-passing zone pavement markings or the two-direction no-passing zone pavement markings described previously and shown in Figures 3B-1 and 3B-3.**

**When centerline markings are used, no-passing zone markings shall be used on two-way roadways at lane reduction transitions (see Section 3B.09) and on approaches to obstructions that must be passed on the right (see Section 3B.10).**

**There is explicitly no requirement under this Manual that no-passing zones shall be marked at intersections, notwithstanding the provisions of any other section of this Manual**

Option:

No-passing zones may be marked at rural and urban intersections when engineering judgment so dictates.

Guidance:

The decision as to whether or not a no-passing zone should be marked at intersections is a matter of discretionary engineering judgment. When used, the no-passing zone should start at least 30.5 m (100 ft) in advance of the intersection.

The no-passing zone marking should not be less than 150 m (500 ft) in length, except in advance of an intersection, or as a result of a special engineering study. If the actual no-passing zone distance is less than 150 m (500 ft), an additional length of marking should be added at the beginning of the zone. The distance between successive no-passing zones should be 120 m (400 ft) for speeds less than 50 miles per hour and 180 m (600 ft) for speeds 50 miles per hour or greater. When the distances are less than these, the single or double no-passing lines should be extended to connect the zones.

No-passing markings should be used on approaches to other locations where passing should be prohibited

**Standard:**

**In locations where there are dips or undulations in the profile of the pavement which create areas where the actual pavement surface is more than 1.07 m (3.5 ft) below the line of sight, the no-passing line shall be extended as required.**

**Where centerline markings are used, no-passing zone markings shall be used on approaches to highway-rail grade crossings in conformance with Section 8B.20.**



Option:

In addition to pavement markings, no-passing zone signs (see Sections 2B.29, 2B.30, and 2C.35) may be used to emphasize the existence and extent of a no-passing zone.

### Figure 3B-1. Examples of Two-Lane, Two-Way Marking Applications

a - Typical two-lane, two-way marking with passing permitted in both directions

b - Typical two-lane, two-way marking with no passing zones




Legend  
→ Direction of travel


Note:  
See Section 3B.07  
for edge line warrants.

### Figure 3B-2. Examples of Four-or-More Lane, Two-Way Marking Applications

a - Typical multi-lane, two-way marking



b - Typical multi-lane, two-way marking with single lane left turn channelization





- Legend
- \* Optional
  - Direction of travel

Note:  
See Section 3B.07  
for edge line warrants.

### Figure 3B-3. Examples of Three-Lane, Two-Way Marking Applications

a - Typical three-lane, two-way marking with passing permitted in single-lane direction

b - Typical three-lane, two-way marking with passing prohibited in single-lane direction



Legend  
→ Direction of travel

**Standard:**

On two-way, two- or three-lane roadways where centerline markings are installed, no-passing zones shall be established at vertical and horizontal curves and other locations where an engineering study indicates that passing must be prohibited because of inadequate sight distances or other special conditions.

On three-lane roadways where the direction of travel in the center lane transitions from one direction to the other, a no-passing buffer zone shall be provided in the center lane as shown in Figure 3B-4. A lane transition shall be provided at each end of the buffer zone.

The buffer zone shall be a median island that is at least 15 m (50 ft) in length.

**Guidance:**

For three-lane roadways having a posted or statutory speed limit of 70 km/h (45 mph) or greater, the lane transition taper length should be computed by the formula  $L = 0.62 WS$  for speeds in km/h ( $L = WS$  for speeds in mph). For roadways where the posted or statutory speed limit is less than 70 km/h (45 mph), the formula  $L = WS^2/155$  for speeds in km/h ( $L = WS^2/60$  for speeds in mph) should be used to compute taper length. Under both formulas, L equals the taper length in meters (feet), W equals the width of the center lane or offset distance in meters (feet), and S equals the 85th-percentile speed or the posted or statutory speed limit, whichever is higher.

**Standard:**

The minimum lane transition taper length shall be 30 m (100 ft) in urban areas and 60 m (200 ft) in rural areas.

On roadways with centerline markings, no-passing zone markings shall be used at horizontal or vertical curves where the passing sight distance is less than the minimum necessary for reasonably safe passing at the 85th-percentile speed or the posted or statutory speed limit as shown in Table 3B-1. The passing sight distance on a vertical curve is the distance at which an object 1.07 m (3.5 ft) above the pavement surface can be seen from a point 1.07 m (3.5 ft) above the pavement (see Figure 3B-5). Similarly, the passing sight distance on a horizontal curve is the distance measured along the centerline (or right-hand lane line of a three-lane roadway) between two points 1.07 m (3.5 ft) above the pavement on a line tangent to the embankment or other obstruction that cuts off the view on the inside of the curve (see Figure 3B-5).

**Support:**

The beginning of a no-passing zone at point “a” in Figure 3B-5 is that point where the sight distance first becomes less than that specified in Table 3B-1. The end of the no-passing zone at point “b” in Figure 3B-5 is that point at which the sight distance again becomes greater than the minimum specified.


**Section 3B.03 Other Yellow Longitudinal Pavement Markings****Standard:**

If reversible lanes are used, the lane line pavement markings on each side of reversible lanes shall consist of a normal double broken yellow line to delineate the edge of a lane in which the direction of travel is reversed from time to time, such that each of these markings serve as the centerline markings of the roadway during some period (see Figure 3B-6).

Signs (see Section 2B.25), lane-use control signals (see Chapter 4J), or both shall be used to supplement reversible lane pavement markings.

If a two-way left-turn lane that is never operated as a reversible lane is used, the lane line pavement markings on each side of the two-way left-turn lane shall consist of a normal broken yellow line and a normal solid yellow line to delineate the edges of a lane that can be used by traffic in either direction as part of a left-turn maneuver. These markings shall be placed with the broken line toward the two-way left-turn lane and the solid line toward the adjacent traffic lane as shown in Figure 3B-7.

**Figure 3B-4. Example of Three-Lane, Two-Way Marking for Changing Direction of the Center Lane**



**Table 3B-1. Minimum Passing Sight Distances**

85th- Percentile or Posted or Statutory Speed Limit (km/h)	Minimum Passing Sight Distance  (Meters)	85th- Percentile or Posted or Statutory Speed Limit (mph)	Minimum Passing Sight Distance  (feet)
40	140	25	450
50	160	30	500
60	180	35	550
70	210	40	600
80	245	45	700
90	280	50	800
100	320	55	900
110	355	60	1,000
120	395	65	1,100
		70	1,200

**Option:**

Pavement marking arrows may be used in conjunction with the two-way left-turn lane markings as shown in Figure 3B-7.

**Guidance:**

Signs should be used in conjunction with the two-way left turn markings (see Section 2B.24).

**Standard:**

If a continuous median island formed by pavement markings separating travel in opposite directions is used, two sets of double solid yellow lines shall be used to form the island as shown in Figures 3B-2 and 3B-4. Other markings in the median island area shall also be yellow, except crosswalk markings which shall be white (see Section 3B.17).

**Section 3B.04 Lane Line Pavement Markings and Warrants****Standard:**

When used, lane line pavement markings delineating the separation of traffic lanes that have the same direction of travel shall be white.


**Support:**

Examples of lane line markings are shown in Figures 3B-2, 3B-3, 3B-7 through 3B-13, 3B-22, 3B-24, and 3B-26.

**Standard:**

Where crossing the lane line markings with care is permitted, the lane line markings shall consist of a normal broken white line.


**Figure 3B-5. Method of Locating and Determining the Limits of No-Passing Zones at Curves**



**Profile View**

Note: No-passing zones in opposite directions may or may not overlap, depending on alignment

**b- No-passing zone at HORIZONTAL CURVE.**




**Plan View**


Note: No-passing zones in opposite directions may or may not overlap, depending on alignment

Not to scale

**Figure 3B-6. Example of Reversible Lane Marking Application**



**Figure 3B-7. Example of Two-Way Left-Turn Lane Marking Applications**



**Where crossing the lane line markings is discouraged, the lane line markings shall consist of a normal solid white line.**

Option:

Solid white lane line markings may be used to separate through traffic lanes from auxiliary lanes, such as uphill truck lanes, left- or right-turn lanes, and preferential lanes. They may also be used to separate traffic lanes approaching an intersection.

Wide solid lane line markings may be used for greater emphasis.

**Standard:**

**Where crossing the lane line markings is prohibited, the lane line markings shall consist of two normal solid white lines.**

**Lane line markings shall be used on all freeways and Interstate highways.**

Guidance:

Lane line markings should be used on all roadways with two or more adjacent traffic lanes that have the same direction of travel. Lane line markings should also be used at congested locations where the roadway will accommodate more traffic lanes with lane line markings than without the markings..

### **Section 3B.05 Other White Longitudinal Pavement Markings**

**Standard:**

**A channelizing line shall be a wide or double solid white line.**

Option:

Channelizing lines may be used to form channelizing islands where traffic traveling in the same direction is permitted on both sides of the island.

**Standard:**

**Other pavement markings in the channelizing island area shall be white.**

Support:

Examples of channelizing line applications are shown in Figures 3B-8, 3B-9, and 3B-13.

Channelizing lines at exit ramps as shown in Figure 3B-8 define the neutral area, direct exiting traffic at the proper angle for smooth divergence from the main lanes into the ramp, and reduce the probability of colliding with objects adjacent to the roadway.

Channelizing lines at entrance ramps as shown in Figure 3B-9 promote reasonably safe and efficient merging with the through traffic.

**Standard:**

**For exit ramps, channelizing lines shall be placed along the sides of the neutral area adjacent to the through traffic lane and the ramp lane. With a parallel deceleration lane, a lane line shall be extended from the beginning of the channelizing line upstream for a distance of one-half the length of the full-width deceleration lane as shown in Figure 3B-8.**

Option:

White chevron markings may be placed in the neutral area for special emphasis as shown in Figure 3B-8.

Guidance:

For entrance ramps, a channelizing line should be placed along the side of the neutral area adjacent to the ramp lane.

For entrance ramps with a parallel acceleration lane, a lane line should be extended from the end of the channelizing line for a distance of one-half the length of the full-width acceleration lane as shown in Figure 3B-9.

Option:

For entrance ramps with a tapered acceleration lane, lane line markings may be placed to extend the channelizing line, but not beyond a point where the tapered lane meets the near side of the through traffic lane as shown in Figure 3B-9.

Lane drop markings as shown in Figure 3B-10 may be used in advance of lane drops at exit ramps to distinguish a lane drop from a normal exit ramp or from an auxiliary lane. The lane drop marking may consist of a wide, white dotted line with line segments 0.9 m (3 ft) in length separated by 2.7 m (9 ft) gaps.

When ramps are two lanes wide, a study may be useful to determine the most desirable pavement marking plan.

Guidance:

If used, lane drop markings should begin 800 m (0.5 mi) in advance of the theoretical gore point.

Option:

Where lane changes might cause conflicts, a wide solid white channelizing line may extend upstream from the theoretical gore point.

### **Section 3B.06 Edge Line Pavement Markings**

**Standard:**

**If used, edge line pavement markings shall delineate the right or left edges of a roadway.**

**Except for dotted edge line extensions (see Section 3B.08), edge line markings shall not be continued through intersections or major driveways.**

**If used on the roadways of divided highways or one-way streets, or on any ramp in the direction of travel, left edge line pavement markings shall consist of a normal solid yellow line to delineate the left edge of a roadway or to indicate driving or passing restrictions left of these markings.**

**If used, the right edge line pavement markings shall consist of a normal solid white line to delineate the right edge of the roadway.**

Guidance:

Edge line markings should not be broken for minor driveways.


Support:

Edge line markings have unique value as visual references to guide road users during adverse weather and visibility conditions.

Option:


Wide solid edge line markings may be used for greater emphasis.

**Figure 3B-8. Examples of Channelizing Line Applications for Exit Ramp Markings (Sheet 1 of 2)**




**Figure 3B-8. Examples of Channelizing Line Applications for Exit Ramp Markings (Sheet 2 of 2)**


c - Auxiliary lane, such as at cloverleaf interchange



**Figure 3B-9. Examples of Channelizing Line Applications for Entrance Ramp Markings**



**Figure 3B-10. Example of Lane Drop Markings at Exit Ramps**



### **Section 3B.07 Warrants for Use of Edge Lines**

#### **Standard:**

**Edge line markings shall be placed on paved streets or highways with the following characteristics:**

- A. Freeways;**
- B. Expressways; and**
- C. Rural arterials with a traveled way of 6.1 m (20 ft) or more in width and an ADT of 6,000 vehicles per day or greater.**

#### **Guidance:**

Edge line markings should be placed on paved streets or highways with the following characteristics:

- A. Rural arterials and collectors with a traveled way of 6.1 m (20 ft) or more in width and an ADT of 3,000 vehicles per day or greater.
- B. At other paved streets and highways where an engineering study indicates a need for edge line markings.

Edge line markings should not be placed where an engineering study or engineering judgment indicates that providing them is likely to decrease safety.

#### **Option:**

Edge line markings may be placed on streets and highways with or without centerline markings.

Edge line markings may be excluded, based on engineering judgment, for reasons such as if the traveled way edges are delineated by curbs, parking, bicycle lanes, or other markings.

Edge line markings may be used where edge delineation is desirable to minimize unnecessary driving on paved shoulders or on refuge areas that have lesser structural pavement strength than the adjacent roadway.

### **Section 3B.08 Extensions Through Intersections or Interchanges**

#### **Standard:**

**Pavement markings extended into or continued through an intersection or interchange area shall be the same color and at least the same width as the line markings they extend (see Figure 3B-11).**

#### **Option:**

A normal line may be used to extend a wide line through an intersection.

#### **Guidance:**


Where highway design or reduced visibility conditions make it desirable to provide control or to guide vehicles through an intersection or interchange, such as at offset, skewed, complex, or multilegged intersections, on curved roadways, or where multiple turn lanes are used, dotted line markings should be used to extend longitudinal line markings through an intersection or interchange area.

#### **Option:**


Dotted edge line extensions may be placed through intersections or major driveways.

### Figure 3B-11. Examples of Extensions through Intersections (Sheet 1 of 2)

a - Typical pavement markings with offset lane lines continued through the intersection and optional crosswalk lines and stop lines




b - Typical pavement markings with optional double-turn lane lines, lane-use turn arrows, crosswalk lines, and stop lines




### Figure 3B-11. Examples of Extensions through Intersections (Sheet 2 of 2)

c - Typical dotted line markings to extend longitudinal lane line markings



d - Typical dotted line markings to extend longitudinal centerline markings



**Guidance:**

Where greater restriction is required, solid lane lines or channelizing lines should be extended into or continued through intersections or major driveways. However, edge lines should not be extended into or continued through intersections or major driveways as solid lines.

A single line of equal width to one of the lines of the double line should be used to extend a double line through an intersection.

To the extent possible, pavement marking extensions through intersections should be designed in a manner that minimizes potential confusion for drivers in adjacent or opposing lanes.

**Section 3B.09 Lane Reduction Transition Markings****Standard:**

**Where pavement markings are used, lane reduction transition markings shall be used to guide traffic through transition areas where the number of through lanes is reduced, as shown in Figure 3B-12. On two-way roadways, no-passing zone markings shall be used to prohibit passing in the direction of the convergence, and shall continue through the transition area.**

**Guidance:**

For roadways having a posted or statutory speed limit of 70 km/h (45 mph) or greater, the transition taper length for a lane reduction should be computed by the formula  $L = 0.62 WS$  for speeds in km/h ( $L = WS$  for speeds in mph). For roadways where the posted or statutory speed limit is less than 70 km/h (45 mph), the formula  $L = WS^2/155$  for speeds in km/h ( $L = WS^2/60$  for speeds in mph) should be used to compute taper length. Under both formulas, L equals the taper length in meters (feet), W equals the width of the offset distance in meters (feet), and S equals the 85th-percentile speed or the posted or statutory speed limit, whichever is higher.

Where observed speeds exceed posted or statutory speed limits, longer tapers should be used.

**Option:**

On new construction, where no posted or statutory speed limit is established, the design speed may be used in the transition taper length formula.

**Guidance:**

Lane line markings should be discontinued one-quarter of the distance between the Lane Ends sign (see Section 2C.33) and the point where the transition taper begins.

Edge line markings should be installed from the location of the warning sign to beyond the beginning of the narrower roadway.

**Support:**

Pavement markings at lane reduction transitions supplement the standard signs.

**Section 3B.10 Approach Markings for Obstructions****Standard:**

**Pavement markings shall be used to guide traffic away from fixed obstructions within a paved roadway. Approach markings for bridge supports, refuge islands, median islands, and raised channelization islands shall consist of a tapered line or lines extending from the centerline or the lane line to a point 0.3 to 0.6 m (1 to 2 ft) to the right side, or to both sides, of the approach end of the obstruction (see Figure 3B-13).**

**Guidance:**

For roadways having a posted or statutory speed limit of 70 km/h (45 mph) or greater, the taper length of the tapered line markings should be computed by the formula  $L = 0.62 WS$  for speeds in km/h ( $L = WS$  for

speeds in mph). For roadways where the posted or statutory speed limit is less than 70 km/h (45 mph), the formula  $L = WS^2/155$  for speeds in km/h ( $L = WS^2/60$  for speeds in mph) should be used to compute taper length. Under both formulas, L equals the taper length in meters (feet), W equals the width of the offset distance in meters (feet), and S equals the 85th-percentile speed or the posted or statutory speed limit, whichever is higher.

**Standard:**

**The minimum taper length shall be 30 m (100 ft) in urban areas and 60 m (200 ft) in rural areas.**

Support:

Examples of approach markings for obstructions in the roadway are shown in Figure 3B-13.

Option:

Where observed speeds exceed posted or statutory speed limits, longer tapers may be used.

**Standard:**

**If traffic is required to pass only to the right of the obstruction, the markings shall consist of a two-direction no-passing zone marking at least twice the length of the diagonal portion as determined by the appropriate taper formula (see Figure 3B-13).**

Option:

If traffic is required to pass only to the right of the obstruction, yellow diagonal approach markings may be placed in the neutral area between the no-passing zone markings as shown in Figure 3B-13. Other markings, such as yellow delineators, raised pavement markers, and white crosswalk pavement markings, may also be placed in the neutral area.

**Standard:**

**If traffic can pass either to the right or left of the obstruction, the markings shall consist of two channelizing lines diverging from the lane line, one to each side of the obstruction. In advance of the point of divergence, a solid wide white line or solid double normal white line shall be extended in place of the broken lane line for a distance equal to the length of the diverging lines (see Figure 3B-13).**

Option:

If traffic can pass either to the right or left of the obstruction, additional white markings may be placed in the neutral area between the channelizing lines as shown in Figure 3B-13.

**Section 3B.11 Raised Pavement Markers**

**Standard:**

**A raised pavement marker shall be a device with a height of at least 10 mm (0.4 in) mounted on or in a road surface that is intended to be used as a positioning guide or to supplement or substitute for pavement markings or to mark the position of a fire hydrant..**

**The color of raised pavement markers under both daylight and nighttime conditions shall conform to the color of the marking for which they serve as a positioning guide, or for which they supplement or substitute.**


Option:

Blue raised pavement markers may be used to mark the position of fire hydrants.

Support:

Retroreflective and internally illuminated raised pavement markers are available in monodirectional and bidirectional configurations. The bidirectional marker is capable of displaying the applicable color for each direction of travel.

**Figure 3B-12. Examples of Lane Reduction Markings**




L = Length in meters (feet)  
 S = Posted, 85th-percentile, or statutory speed in km/h (mph)  
 W = Offset in meters (feet)  
 d = Advance warning distance (see Section 2C.05)  
 See Section 3D.04 for delineator spacing.

For speeds 70 km/h (45 mph) or more:  
 $L = 0.62 WS$  ( $L=WS$ )

For speeds less than 70 km/h (45 mph):  
 $L = \frac{WS^2}{155}$  ( $L = \frac{WS^2}{60}$ )

**Figure 3B-13. Examples of Markings for Obstructions in the Roadway**  
(Sheet 1 of 2)



For speeds 70 km/h (45 mph) or more  $L = 0.62 WS$  ( $L = WS$ )  
 For speeds less than 70 km/h (45 mph)  $L = WS^2/155$  ( $L = WS^2/60$ )  
 S = Posted, 85th-percentile, or statutory speed in km/h (mph)  
 W = Offset distance in meters (ft)

Minimum length of : L = 30 m (100 ft) in urban areas  
 L = 60 m (200 ft) in rural areas


Length "L" should be extended as required by sight distance conditions

**Legend**

- Direction of travel
- ⊠ Obstruction

**Figure 3B-13. Examples of Markings for Obstructions in the Roadway**  
(Sheet 2 of 2)

**c - Traffic passing both sides of obstruction**



For speeds 70 km/h (45 mph) or more  $L = 0.62 WS$  ( $L = WS$ )  
 For speeds less than 70 km/h (45 mph)  $L = WS^2/155$  ( $L = WS^2/60$ )  
 S = Posted, 85th-percentile, or statutory speed in km/h (mph)  
 W = Offset distance in meters (ft)

Minimum length of : L = 30 m (100 ft) in urban areas  
 L = 60 m (200 ft) in rural areas

Length "L" should be extended as required by sight distance conditions

**Guidance:**

Nonretroreflective raised pavement markers should not be used alone, without supplemental retroreflective or internally illuminated markers, as a substitute for other types of pavement markings.

Directional configurations should be used to maximize correct information and to minimize confusing information provided to the road user. Directional configurations also should be used to avoid confusion resulting from visibility of markers that do not apply to the road user.

The spacing of raised pavement markers used to supplement or substitute for other types of longitudinal markings should correspond with the pattern of broken lines for which the markers supplement or substitute.

**Standard:**

**The value of N for the spacing of raised pavement markers for a broken or dotted line shall equal the length of one line segment plus one gap. The value of N referenced for solid lines shall equal the N for the broken or dotted lines that might be adjacent to or might extend the solid lines (see Sections 3B.13 and 3B.14).**

**Support:**

Figures 9-20 through 9-22 in the “Traffic Control Devices Handbook” (see Section 1A.11) contain additional information regarding the spacing of raised pavement markers on longitudinal markings.

### **Section 3B.12 Raised Pavement Markers as Vehicle Positioning Guides with Other Longitudinal Markings**

**Option:**

Raised pavement markers may be used as positioning guides with longitudinal line markings without necessarily conveying information to the road user about passing or lane-use restrictions. In such applications, markers may be positioned between the two lines of a one-way or two-way no-passing zone marking or positioned in line with or immediately adjacent to single solid or broken centerline or lane line markings.

**Support:**

A typical spacing for such applications is  $2N$ , where  $N$  equals the length of one line segment plus one gap (see Section 3B.11).

**Option:**

Where it is desired to alert the road user to changes in the travel path, such as on sharp curves or on transitions that reduce the number of lanes or that shift traffic laterally, the spacing may be reduced to  $N$  or less.

On freeways and expressways, a spacing of  $3N$  may be used for relatively straight and level roadway segments where engineering judgment indicates that such spacing will provide adequate delineation under wet night conditions.

### **Section 3B.13 Raised Pavement Markers Supplementing Other Markings**

**Guidance:**

The use of raised pavement markers for supplementing longitudinal line markings should conform to the following:

A. Lateral Positioning

1. When supplementing double line markings, pairs of raised pavement markers placed laterally in line with or immediately outside of the two lines should be used.
2. When supplementing wide line markings, pairs of raised pavement markers placed laterally adjacent to each other should be used.

### B. Longitudinal Spacing

1. When supplementing solid line markings, raised pavement markers at a spacing no greater than  $N$  (see Section 3B.11) should be used, except when supplementing left edge line markings, a spacing of no greater than  $N/2$  should be used. Raised markers should not supplement right edge line markings.
2. When supplementing broken line markings, a spacing no greater than  $3N$  should be used. However, when supplementing broken line markings identifying reversible lanes, a spacing of no greater than  $N$  should be used.
3. When supplementing dotted line markings, a spacing appropriate for the application should be used.
4. When supplementing longitudinal line markings through at-grade intersections, one raised pavement marker for each short line segment should be used.
5. When supplementing edge line extensions through freeway interchanges, a spacing of no greater than  $N$  should be used.

#### Option:

Raised pavement markers also may be used to supplement other markings for channelizing islands or approaches to obstructions.

### **Section 3B.14 Raised Pavement Markers Substituting for Pavement Markings**

#### Option:

Retroreflective or internally illuminated raised pavement markers, or nonretroreflective raised pavement markers supplemented by retroreflective or internally illuminated markers, may be substituted for markings of other types.

#### Guidance:

If used, the pattern and color of the raised pavement markers should simulate the pattern and color of the markings for which they substitute.

The normal spacing of raised pavement markers, when substituting for other markings, should be determined in terms of the standard length of the broken line segment.

#### Option:

The side of a raised pavement marker that is visible to traffic proceeding in the wrong direction may be red.

#### **Standard:**

**If raised pavement markers are used to substitute for broken line markings, a group of three to five markers equally spaced at a distance no greater than  $N/8$  (see Section 3B.11) shall be used. If  $N$  is other than 12 m (40 ft), the markers shall be equally spaced over the line segment length (at  $1/2$  points for 3 markers, at  $1/3$  points for 4 markers, and at  $1/4$  points for 5 markers). At least one retroreflective or internally illuminated marker per group shall be used or a retroreflective or internally illuminated marker shall be installed midway in each gap between successive groups of nonretroreflective markers.**

**When raised pavement markers substitute for solid lane line markings, the markers shall be equally spaced at no greater than  $N/4$  with retroreflective or internally illuminated units at a spacing no greater than  $N/2$ .**

#### Guidance:

Raised pavement markers should not substitute for right edge line markings.

**Standard:**

**When raised pavement markers substitute for dotted lines, they shall be spaced at no greater than  $N/4$ , with not less than one raised pavement marker per dotted line. At least one raised marker every  $N$  shall be retroreflective or internally illuminated.**

**Option:**

When substituting for wide lines, raised pavement markers may be placed laterally adjacent to each other to simulate the width of the line.

**Section 3B.15 Transverse Markings****Standard:**

**Transverse markings, which include shoulder markings, word and symbol markings, stop lines, yield lines, crosswalk lines, speed measurement markings, speed hump markings, parking space markings, and others, shall be white unless otherwise specified herein.**

**Transverse lines used within painted islands and gore areas shall be the same color as the outline markings they supplement.**

**Guidance:**

Because of the low approach angle at which pavement markings are viewed, transverse lines should be proportioned to provide visibility equal to that of longitudinal lines.

**Standard:**

**Pavement marking letters, numerals, and symbols shall be installed in accordance with the Pavement Markings information in the “Sign Design Manual” (SDM) (see Section 1A.11).**

**Section 3B.16 Stop and Yield Lines****Standard:**

**If used, stop lines shall consist of solid white lines extending across approach lanes to indicate the point at which the stop is intended or required to be made.**

**If used, yield lines (see Figure 3B-14) shall consist of a row of solid white isosceles triangles pointing toward approaching vehicles extending across approach lanes to indicate the point at which the yield is intended or required to be made.**

**Guidance:**

Stop lines should be 300 to 600 mm (12 to 24 in) wide.

Stop lines should be used to indicate the point behind which vehicles are required to stop, in compliance with a STOP (R1-1) sign, traffic control signal, or some other traffic control device, except YIELD signs

The individual triangles comprising the yield line should have a base of 300 to 600 mm (12 to 24 in) wide and a height equal to 1.5 times the base. The space between the triangles should be 75 to 300 mm (3 to 12 in).



**Option:**

Yield lines may be used to indicate the point behind which vehicles are required to yield in compliance with a YIELD (R1-2) sign or a Yield Here to Pedestrians (R1-5) sign.



**Guidance:**

If used, stop and yield lines should be placed a minimum of 1.2 m (4 ft) in advance of the nearest crosswalk line at controlled intersections, except for yield lines at roundabout intersections as provided for in Section 3B.24 and at midblock crosswalks. In the absence of a marked crosswalk, the stop line or yield line should be placed at the desired stopping or yielding point, but should be placed no more than 9 m (30 ft)

**Figure 3B-14. Example of Yield Line Layouts**



**(a) Minimum Dimensions**



**(b) Maximum Dimensions**

Notes:  
 Triangle height is equal to 1.5 times the base dimension.  
 Yield lines may be smaller than suggested when installed on much narrower, slow-speed facilities such as shared-use paths.

nor less than 1.2 m (4 ft) from the nearest edge of the intersecting traveled way. Stop lines should be placed to allow sufficient sight distance to all other approaches to an intersection.


If used at an unsignalized midblock crosswalk, yield lines should be placed adjacent to the Yield Here to Pedestrians sign located 6.1 to 15 m (20 to 50 ft) in advance of the nearest crosswalk line, and parking should be prohibited in the area between the yield line and the crosswalk (see Figure 3B-15).

Stop lines at midblock signalized locations should be placed at least 12 m (40 ft) in advance of the nearest signal indication (see Section 4D.15).

**Support:**

Drivers who yield too close to crosswalks on multi-lane approaches place pedestrians at risk by blocking other drivers' views of pedestrians.

**Figure 3B-15. Examples of Yield Lines at Unsignalized Midblock Crosswalks**



### Section 3B.17 Crosswalk Markings

#### Support:

Crosswalk markings provide guidance for pedestrians who are crossing roadways by defining and delineating paths on approaches to and within signalized intersections, and on approaches to other intersections where traffic stops.

Crosswalk markings also serve to alert road users of a pedestrian crossing point across roadways not controlled by highway traffic signals or STOP signs.

At nonintersection locations, crosswalk markings legally establish the crosswalk.

#### Standard:

**When crosswalk lines are used, they shall consist of solid white lines that mark the crosswalk. They shall be not less than 150 mm (6 in) nor greater than 600 mm (24 in) in width.**

**Guidance:**

If transverse lines are used to mark a crosswalk, the gap between the lines should not be less than 1.8 m (6 ft). If diagonal or longitudinal lines are used without transverse lines to mark a crosswalk, the crosswalk should be not less than 1.8 m (6 ft) wide.

Crosswalk lines, if used on both sides of the crosswalk, should extend across the full width of pavement or to the edge of the intersecting crosswalk to discourage diagonal walking between crosswalks (see Figures 3B-15 and 3B-16).

Crosswalks should be marked at all intersections where there is substantial conflict between vehicular and pedestrian movements.

Marked crosswalks also should be provided at other appropriate points of pedestrian concentration, such as at loading islands, midblock pedestrian crossings, or where pedestrians could not otherwise recognize the proper place to cross.

Crosswalk lines should not be used indiscriminately. An engineering study should be performed before they are installed at locations away from highway traffic signals or STOP signs.

Because nonintersection pedestrian crossings are generally unexpected by the road user, warning signs (see Section 2C.41) should be installed and adequate visibility should be provided by parking prohibitions.

**Support:**

Section 3B.16 contains information regarding placement of stop line markings near crosswalk markings.

**Option:**

For added visibility, the area of the crosswalk may be marked with white diagonal lines at a 45-degree angle to the line of the crosswalk or with white longitudinal lines parallel to traffic flow as shown in Figure 3B-16.

When diagonal or longitudinal lines are used to mark a crosswalk, the transverse crosswalk lines may be omitted. This type of marking may be used at locations where substantial numbers of pedestrians cross without any other traffic control device, at locations where physical conditions are such that added visibility of the crosswalk is desired, or at places where a pedestrian crosswalk might not be expected.

**Guidance:**

If used, the diagonal or longitudinal lines should be 300 to 600 mm (12 to 24 in) wide and spaced 300 to 1500 mm (12 to 60 in) apart. The marking design should avoid the wheel paths, and the spacing should not exceed 2.5 times the line width.

**Option:**

When an exclusive pedestrian phase that permits diagonal crossing is provided at a traffic control signal, a marking as shown in Figure 3B-16 may be used for the crosswalk.


**Section 3B.18 Parking Space Markings****Support:**

Marking of parking space boundaries encourages more orderly and efficient use of parking spaces where parking turnover is substantial. Parking space markings tend to prevent encroachment into fire hydrant zones, bus stops, loading zones, approaches to intersections, curb ramps, and clearance spaces for islands and other zones where parking is restricted. Examples of parking space markings are shown in Figure 3B-18


**Standard:**

**Parking space markings shall be white and not less than 100 mm (4 in) nor more than 150 mm (6 in) wide.**


**Figure 3B-16. Examples of Crosswalk Markings**




**Figure 3B-17. Example of Crosswalk Markings for Exclusive Pedestrian Phase That Permits Diagonal Crossing**



**Figure 3B-18. Examples of Parking Space Markings**




**Figure 3B-19. International Symbol of Accessibility Parking Space Marking with Blue Background and White Border Options**



**Figure 3B-20. Example of Elongated Letters for Word Pavement Markings**



**Figure 3B-21. Examples of Standard Arrows for Pavement Markings**



Typical sizes for normal installation; sizes may be reduced approximately one-third for low-speed urban conditions; larger sizes may be needed for freeways, above average speeds, and other critical locations. A narrow elongated arrow design is optional. For proper proportion, see the Pavement Markings information in the "Sign Design Manual" (ODOT) (see Section 1A.11).

**Where angle parking is permitted under Section 4511.69 of the Ohio Revised Code (see Appendix B2), the stalls shall be marked with a series of solid lines spaced not less than 2.6 m (8.5 ft) apart and placed at the desired angle to the curb.**

Option:

Blue lines may supplement white parking space markings of each parking space designated for use only by persons with disabilities.

Support:

Additional parking space markings for the purpose of designating spaces for use only by persons with disabilities are discussed in Section 3B.19 and illustrated in Figure 3B-19.

### **Section 3B.19 Pavement Word and Symbol Markings**

Support:

Word and symbol markings on the pavement are used for the purpose of guiding, warning, or regulating traffic. Symbol messages are preferable to word messages. Examples of standard word and arrow pavement markings are shown in Figures 3B-20 and 3B-21.

**Standard:**

**Word and symbol markings shall be white, except as otherwise noted in this Section.**

Guidance:

Letters and numerals should be 1.8 m (6 ft) or more in height.

Word and symbol markings should not exceed three lines of information.

If a pavement marking word message consists of more than one line of information, it should read in the direction of travel. The first word of the message should be nearest to the road user.

Except for the two opposing arrows of a two-way left-turn lane marking (see Figure 3B-7), the longitudinal space between word or symbol message markings, including arrow markings, should be at least four times the height of the characters for low-speed roads, but not more than ten times the height of the characters under any conditions.

The number of different word and symbol markings used should be minimized to provide effective guidance and avoid misunderstanding.

Except as noted in the Option, pavement word and symbol markings should be no more than one lane in width.

Option:

The SCHOOL word marking may extend to the width of two approach lanes (see Section 7C.06).

Guidance:

When the SCHOOL word marking is extended to the width of two approach lanes, the characters should be 3 m (10 ft) or more in height (see Section 7C.06).


Pavement word and symbol markings should be proportionally scaled to fit within the width of the facility upon which they are applied.

Option:


On narrow, low-speed shared-use paths, the pavement words and symbols may be smaller than suggested, but to the relative scale.

The International Symbol of Accessibility parking space markings may be placed in each parking space designated for use by persons with disabilities. A blue background with white border may supplement the wheelchair symbol as shown in Figure 3B-19.


**Figure 3B-22. Examples of Lane Use Control Word and Symbol Markings**



**Figure 3B-23. Examples of Arrow Markings at Exit Ramp Terminals**




**Figure 3B-24. Examples of Arrow Markings at Entrance Ramp Terminals**




### Figure 3B-25. Yield Ahead Triangle Symbols

a - Posted or Statutory Speed Limit 70 km/h (45 mph) or greater



b - Posted or Statutory Speed Limit less than 70 km/h (45 mph)



**Standard:**

**Where through traffic lanes approaching an intersection become mandatory turn lanes, lane-use arrow markings (see Figure 3B-21) shall be used and shall be accompanied by standard signs.**

**Lane use, lane reduction, and wrong-way arrow markings shall be designed as shown in Figure 3B-21.**

## Guidance:

Where through lanes become mandatory turn lanes, signs or markings should be repeated as necessary to prevent entrapment and to help the road user select the appropriate lane in advance of reaching a queue of waiting vehicles.

## Option:

Lane-use arrow markings (see Figure 3B-21) may be used to convey either guidance or mandatory messages.

The ONLY word marking (see Figure 3B-20) may be used to supplement lane-use arrow markings (see Figure 3B-22).

In situations where a lane reduction transition occurs, the lane reduction arrow markings shown in Figure 3B-21 may be used.

## Guidance:

Where crossroad channelization or ramp geometrics do not make wrong-way movements difficult, a lane-use arrow should be placed in each lane of an exit ramp near the crossroad terminal where it will be clearly visible to a potential wrong-way road user (see Figure 3B-23).

## Option:

The wrong-way arrow markings shown in Figure 3B-21 may be placed near the downstream terminus of a ramp as shown in Figures 3B-23 and 3B-24 to indicate the correct direction of traffic flow and to discourage drivers from traveling in the wrong direction.

A yield-ahead triangle symbol or YIELD AHEAD word pavement marking may be used on approaches to intersections where the approaching traffic will encounter a YIELD sign at the intersection (see Figure 3B-25).

## Support:

Lane-use arrow markings are often used to provide guidance in turn bays (see Figure 3B-22), where turns may or may not be mandatory, and in two-way left-turn lanes (see Figure 3B-7).

## Option:

Word and symbol markings may include, but are not limited to, the following. Other words or symbols may also be used under certain conditions.

- A. Regulatory:
  - 1. STOP
  - 2. RIGHT (LEFT) TURN ONLY
  - 3. 25 MPH
  - 4. Arrow Symbols
- B. Warning:
  - 1. STOP AHEAD
  - 2. YIELD AHEAD
  - 3. YIELD AHEAD Triangle Symbol
  - 4. SCHOOL XING
  - 5. SIGNAL AHEAD
  - 6. PED XING

7. SCHOOL
  8. R X R
  9. BUMP
  10. HUMP
- C. Guide:
1. US 40
  2. STATE 135
  3. ROUTE 40

**Standard:**

**Except at the ends of aisles in parking lots, the word STOP shall not be used on the pavement unless accompanied by a stop line (see Section 3B.16) and STOP sign (see Section 2B.04). At the ends of aisles in parking lots, the word STOP shall not be used on the pavement unless accompanied by a stop line.**

**The word STOP shall not be placed on the pavement in advance of a stop line, unless every vehicle is required to stop at all times.**

**The yield-ahead triangle symbol or YIELD AHEAD word pavement marking shall not be used unless a YIELD sign (see Section 2B.08) is in place at the intersection. The yield-ahead symbol marking shall be as shown in Figure 3B-25.**

**Section 3B.20 Speed Measurement Markings****Support:**

A speed measurement marking is a transverse marking placed on the roadway to assist the enforcement of speed regulations.

**Standard:**

**Speed measurement markings, if used, shall be white, and shall not be greater than 600 mm (24 in) in width.**

**Option:**

Speed measurement markings may extend 600 mm (24 in) on either side of the centerline or 600 mm (24 in) on either side of edge line markings at 400 m (0.25 mi) intervals over a 1.6 km (1 mi) length of roadway. When paved shoulders of sufficient width are available, the speed measurements markings may be placed entirely on these shoulders. Advisory signs may be used in conjunction with these markings (see Figure 3B-10).

**Section 3B.21 Curb Markings****Support:**

Curb markings are most often used to indicate parking regulations or to delineate the curb.

**Standard:**

**Signs shall be used with curb markings in those areas where curb markings are frequently obliterated by snow and ice accumulation unless the no parking zone is controlled by statute or local ordinance.**

**Where curbs are marked, the colors shall conform to the general principles of markings (see Section 3A.04).**

**Guidance:**

Except as noted in the Option, when curb markings are used without signs to convey parking regulations, a legible word marking regarding the regulation (such as “No Parking” or “No Standing”) should be placed on the curb.

**Option:**

Curb markings without word markings or signs may be used to convey a general prohibition by statute of parking within a specified distance of a STOP sign, driveway, fire hydrant, or crosswalk.

**Guidance:**

Retroreflective solid yellow markings should be placed on the noses of raised medians and curbs of islands that are located in the line of traffic flow where the curb serves to channel traffic to the right of the obstruction.

Retroreflective solid white markings should be used when traffic may pass on either side of the island.

**Option:**

Local highway agencies may prescribe special colors for curb markings to supplement standard signs for parking regulation.

**Support:**

Since yellow and white curb markings are frequently used for curb delineation and visibility, it is advisable to establish parking regulations through the installation of standard signs (see Sections 2B.39 through 2B.41).

Where the curbs of the islands become parallel to the direction of traffic flow, it is not necessary to mark the curbs unless an engineering study indicates the need for this type of delineation.

Curbs at openings in a continuous median island need not be marked unless an engineering study indicates the need for this type of marking.

**Section 3B.22 Preferential Lane Word and Symbol Markings****Standard:**

**When a lane is assigned full or part time to a particular class or classes of vehicles, preferential lane markings shall be used.**

**Signs or signals shall be used with preferential lane word or symbol markings.**

**All preferential lane word and symbol markings shall be white.**

**All preferential lane word and symbol markings shall be positioned laterally in the center of the preferred-use lane.**

**Support:**

Preferential lanes identify a wide variety of special uses, including, but not limited to, high-occupancy vehicle (HOV) lanes, bicycle lanes, bus only lanes, taxi only lanes, and light rail transit only lanes.

**Standard:**

**Where a preferential lane use is established, the preferential lane shall be marked with one or more of the following symbol or word markings for the preferential lane use specified:**

- A. HOV lane—the preferential lane use marking for high-occupancy vehicle lanes shall consist of white lines formed in a diamond shape symbol or the word message HOV. The diamond shall be at least 0.75 m (2.5 ft) wide and 3.7 m (12 ft) in length. The lines shall be at least 150 mm (6 in) in width.**
- B. Bicycle lane—the preferential lane use marking for a bicycle lane shall consist of a bicycle symbol or the word marking BIKE LANE (see Chapter 9C and Figures 9C-1 and 9C-3 through 9C-6).**
- C. Bus only lane—the preferential lane use marking for a bus only lane shall consist of the word marking BUS ONLY.**
- D. Taxi only lane—the preferential lane use marking for a taxi only lane shall consist of the word marking TAXI ONLY.**

**E. Light rail transit lane**—the preferential lane use marking for a light rail transit lane shall consist of the letter T.

**F. Other preferential lane use markings shall be identified in accordance with Section 3B.23.**

**If two or more preferential lane uses are permitted in a single lane, the symbol or word marking for each preferential lane use shall be installed.**

Guidance:

Engineering judgment should determine the need for supplemental devices such as tubular markers, traffic cones, or flashing lights.

Support:

The spacing of the markings is an engineering judgment that is based on the prevailing speed, block lengths, distance from intersections, and other factors that affect clear communication to the road user. Markings spaced as close as 24 m (80 ft) apart might be appropriate on City streets, while markings spaced 300 m (1,000 ft) might be appropriate for freeways.

Option:

The vehicle occupancy requirements established for a high-occupancy vehicle lane may be included in sequence after the diamond symbol or HOV word message

### **Section 3B.23 Preferential Lane Longitudinal Markings for Motor Vehicles**

**Standard:**

**Preferential lane longitudinal markings for motor vehicles shall be marked with the appropriate word or symbol pavement markings in accordance with Section 3B.22.**

Support:

Preferential lanes can take many forms depending on the level of usage and the design of the facility. They might be physically separated from the other travel lanes by a barrier, median, or painted neutral area, or they might be concurrent with other travel lanes and be separated only by longitudinal pavement markings. Further, physically separated preferential lanes might operate in the same direction or be reversible.

Option:

Preferential lanes may be operated either full-time (24 hours per day on all days), for extended periods of the day, or part-time (restricted usage during specific hours on specified days).

**Standard:**

**The following four items are presented in tabular form in Table 3B-2:**

- A. Physically separated, nonreversible preferential lane**—the longitudinal pavement markings for preferential lanes that are physically separated from the other travel lanes by a barrier, median, or painted neutral area shall consist of a single normal solid yellow line at the left edge of the travel lane(s), a single normal solid white line at the right edge of the travel lane(s), and if there are two or more preferential lanes, the preferential travel lanes shall be separated with a normal broken white line (see Figure 3B-26a).
- B. Physically separated, reversible preferential lane**—the longitudinal pavement markings for reversible preferential lanes that are physically separated from the other travel lanes by a barrier, median, or painted neutral area shall consist of a single normal solid white line at both edges of the travel lane(s), and if there are two or more preferential lanes, the preferential travel lanes shall be separated with a normal broken white line (see Figure 3B-26a).


**Table 3B-2. Standard Edge Line Lane Markings for Preferential Lanes**

Type of Preferential Lane	Left Edge Line	Right Edge Line
<b>Physically Separated, Nonreversible</b>	A single normal solid yellow line	A single normal solid white line
<b>Physically Separated, Reversible</b>	A single normal solid white line	A single normal solid white line
<b>Concurrent Flow-Left Side</b>	A single normal solid yellow line	<p>A double solid wide white line where crossing is prohibited (see Figure 3B-26b)</p> <p>A single solid wide white line where crossing is discouraged (see Figure 2B-26c)</p> <p>A single broken wide white line where crossing is permitted (see Figure 3B-26d)</p>
<b>Concurrent Flow-Right Side</b>	<p>A double solid wide white line where crossing is prohibited (see Figure 3B-26e)</p> <p>A single solid wide white line where crossing is discouraged (see Figure 3B-26e)</p> <p>A single broken wide white line where crossing is permitted (see Figure 3B-26e)</p> <p>A single dotted normal white line where crossing is permitted for any vehicle to perform a right-turn maneuver (see Figure 3B-26e)</p>	A single normal solid white line


Notes: If there are two or more preferential lanes, they shall be separated with a normal broken white line.  
 The standard lane markings listed in this table are provided in a tabular format for reference.  
 This information is also described in the second Standard in Section 3B.23.

**Figure 3B-26. Examples of Markings for Preferential Lanes**  
(Sheet 1 of 2)


**a - Physically separated permanent lane(s)**



**b - Full-time concurrent lane(s) where enter/exit movements are PROHIBITED**



**c - Concurrent lane(s) where enter/exit movements are DISCOURAGED**



Note: Double yellow if centerline of 2-way roadway

Legend


→ Direction of travel

\*\* Applicable symbol or word

**Figure 3B-26. Examples of Markings for Preferential Lanes**  
(Sheet 2 of 2)

**d - Full-time concurrent lane(s)  
where enter/exit movements  
are PERMITTED**

**e - Right Side Concurrent Lane(s)**



Note: Double yellow if centerline of 2-way roadway

Legend

- Direction of travel
- \*\* Applicable symbol or word

**C. Concurrent flow (left side) preferential lane**—the longitudinal pavement markings for a full-time or part-time preferential lane on the left side of the other traveled lanes shall consist of a single normal solid yellow line at the left edge of the preferential travel lane(s) and one of the following at the right edge of the preferential travel lane(s):

1. A double solid wide white line where crossing is prohibited (see Figure 3B-26b).
2. A single solid wide white line where crossing is discouraged (see Figure 3B-26c).
3. A single broken wide white line where crossing is permitted (see Figure 3B-26d).

If there are two or more preferential lanes, the preferential travel lanes shall be separated with a normal broken white line.

**D. Concurrent flow (right side) preferential lane**—the longitudinal pavement markings for a full-time or part-time preferential lane on the right of the other travel lanes shall consist of a single normal solid white line at the right edge of the preferential travel lane(s) if warranted and one of the following at the left edge of the preferential travel lane(s):

1. A double solid wide white line where crossing is prohibited (see Figure 3B-26b).
2. A single solid wide white line where crossing is discouraged (see Figure 3B-26c).
3. A single broken wide white line where crossing is permitted (see Figure 3B-26d).
4. A single dotted normal white line where crossing is permitted for any vehicle to perform a right turn maneuver (see Figure 3B-26e).

If there are two or more preferential lanes, the preferential travel lanes shall be separated with a normal broken white line.

Guidance:

When concurrent flow preferential lanes and other travel lanes are separated by more than 1.2 m (4 ft), chevron markings should be placed in the neutral area. The chevron spacing should be 30 m (100 ft) or greater.

Option:

For full-time or part-time concurrent flow preferential lanes, the spacing or skip pattern of the single broken wide white line may be reduced. The width of the single broken wide white line may be increased.

### **Section 3B.24 Markings for Roundabout Intersections**

Support:

Roundabout intersections are distinctive circular roadways that have the following three critical characteristics:

- A. A requirement to yield at entry which gives a vehicle on the circular roadway the right-of-way;
- B. A deflection of the approaching vehicle around the central island; and
- C. A flare or widening of the approach to allow for proper operation as needed.

Examples of markings for roundabout intersections are shown in Figures 3B-27 and 3B-28.

Option:

A yellow edge line may be placed around the inner (left) edge of the circular roadway.

Guidance:

A white line should be used on the outer (right) side of the circular roadway as follows: a solid line along the splitter island and a dotted line across the lane(s) entering the roundabout intersection.

Edge line extensions should not be placed across the exits from the circular roadway.

Where crosswalk markings are used, these markings should be located a minimum of 7.6 m (25 ft) upstream from the yield line, or, if none, from the dotted white line.

Option:

Lane lines may be used on the circular roadway if there is more than one lane.

A yield line (see Section 3B.16) may be used to indicate the point behind which vehicles are required to yield at the entrance to a roundabout intersection.

**Standard:**

**Bicycle lane markings shall not be provided on the circular roadway of a roundabout intersection.**

**Section 3B.25 Markings for Other Circular Intersections**

Support:

Other circular intersections include but are not limited to rotaries, traffic circles, and residential traffic calming designs.

Option:

The markings shown in Figures 3B-27 and 3B-28 may be used at other circular intersections when engineering judgment indicates that their presence will benefit drivers or pedestrians.

**Section 3B.26 Speed Hump Markings**

**Standard:**

**If used, speed hump markings shall be a series of white markings placed on a speed hump to identify its location.**

Option:

Speed humps, except those used for crosswalks, may be marked in accordance with Figure 3B-29. The markings shown in Figure 3B-30 may be used where the speed hump also functions as a crosswalk or speed table.

**Section 3B.27 Advance Speed Hump Markings**

**Standard:**

**If used, advance speed hump markings shall be a special white marking placed in advance of speed humps or other engineered vertical roadway deflections such as dips.**

Option:

Advance speed hump markings may be used in advance of an engineered vertical roadway deflection where added visibility is desired or where such deflection is not expected (see Figure 3B-31).


Advance pavement wording such as BUMP or HUMP (see Section 3B.19) may be used on the approach to a speed hump either alone or in conjunction with advance speed hump markings. Appropriate advance warning signs may be used in conformance with Section 2C. 24.

Guidance:


If used, advance speed hump markings should be installed in each approach lane.




**Figure 3B-28. Examples of Markings for Roundabout Intersections with Two-Lane Approaches**




**Figure 3B-29. Examples of Pavement Markings for Speed Humps Without Crosswalks**



**Figure 3B-30. Examples of Pavement Markings for Speed Tables or Speed Humps with Crosswalks**



**Figure 3B-31. Examples of Advance Warning Markings for Speed Humps**



**DETAIL—SPEED HUMP ADVANCE WARNING MARKINGS**

## CHAPTER 3C. OBJECT MARKERS AND END-OF-ROADWAY MARKERS

### Section 3C.01 Object Marker Design and Placement Height

#### Support:

Object markers are used to mark obstructions within or adjacent to the roadway.

#### Standard:

When used, object markers (see Figure 3C-1) shall consist of an arrangement of one or more of the following types:

**Type 1**—either a marker consisting of nine yellow retroreflectors, each with a minimum diameter of 75 mm (3 in), mounted symmetrically on a yellow (OM1-1) or black (OM1-2) diamond panel 450 mm (18 in) or more on a side; or on an all-yellow retroreflective diamond panel (OM1-3) of the same size.

**Type 2**—either a marker (OM2-1V or OM2-1H) consisting of three yellow retroreflectors, each with a minimum diameter of 75 mm (3 in), arranged either horizontally or vertically on a white panel measuring at least 150 x 300 mm (6 x 12 in); or on an all-yellow horizontal or vertical retroreflective panel (OM2-2V or OM2-2H), measuring at least 150 x 300 mm (6 x 12 in),.

**Type 3**—a striped marker, 300 x 900 mm (12 x 36 in), consisting of a vertical rectangle with alternating black and retroreflective yellow stripes sloping downward at an angle of 45 degrees toward the side of the obstruction on which traffic is to pass. The designs for the two styles of Type 3 object markers (see Figure 3C-1) shall be as provided in the Sign Design Manual (SDM) (see Section 1A.11).

#### Support:

A better appearance can be achieved if the black stripes are wider than the yellow stripes.

Type 3 object markers with stripes that begin at the upper right side and slope downward to the lower left side are designated as right object markers (OM-3R, OM-H3R). Object markers with stripes that begin at the upper left side and slope downward to the lower right side are designated as left object markers (OM-3L, OM-H3L).

#### Guidance:

When used for marking objects in the roadway or objects that are 2.4 m (8 ft) or less from the shoulder or curb, the mounting height to the bottom of the object marker should be at least 1.2 m (4 ft) above the surface of the nearest traffic lane.

When used to mark objects more than 2.4 m (8 ft) from the shoulder or curb, the mounting height to the bottom of the object marker should be at least 1.2 m (4 ft) above the ground.

#### Option:

When object markers or markings are applied to an object that by its nature requires a lower or higher mounting, the vertical mounting height may vary according to need.

### Section 3C.02 Markings for Objects in the Roadway

#### Standard:

Obstructions within the roadway shall be marked with a Type 1 or Type 3 object marker. In addition to markers on the face of the obstruction, warning of approach to the obstruction shall be given by appropriate pavement markings (see Section 3B.10).

#### Option:

To provide additional emphasis, large surfaces such as bridge piers may be painted with diagonal stripes, 300 mm (12 in) or greater in width, similar in design to the Type 3 object marker.

**Standard:**

**The alternating black and retroreflective yellow stripes (OM-3L OM-H3L, OM-3R, OM-H3R) shall be sloped down at an angle of 45 degrees toward the side on which traffic is to pass the obstruction. If traffic can pass to either side of the obstruction, the alternating black and retroreflective yellow stripes (OM-3C, OM-H3C) shall form chevrons that point upwards.**

**Option:**

Appropriate signs (see Sections 2B.33 and 2C.20) directing traffic to one or both sides of the obstruction may be used instead of the object marker.

**Section 3C.03 Markings for Objects Adjacent to the Roadway****Support:**

Objects not actually in the roadway are sometimes so close to the edge of the road that they need a marker. These include underpass piers, bridge abutments, handrails, and culvert headwalls. In other cases there might not be a physical object involved, but other roadside conditions exist, such as narrow shoulders, drop-offs, gores, small islands, and abrupt changes in the roadway alignment, that might make it undesirable for a road user to leave the roadway, and therefore would create a need for a marker.

**Option:**

Type 2 or Type 3 object markers may be used at locations such as those described in the preceding Support paragraph.

**Standard:**

**If used, the inside edge of the marker shall be in line with the inner edge of the obstruction.**

**Guidance:**

Standard warning signs (see Chapter 2C) should also be used where applicable.

**Section 3C.04 End-of-Roadway Markers****Support:**

The end-of-roadway marker is used to warn and alert road users of the end of a roadway in other than construction or maintenance areas.

**Standard:**

**The end-of-roadway marker (see Figure 3C-1) shall be one of the following: a marker consisting of nine red retroreflectors, each with a minimum diameter of 75 mm (3 in), mounted symmetrically on a red (OM4-1) or black (OM4-2) diamond panel 450 mm (18 in) or more on a side; or a retroreflective red diamond panel (OM4-3) 450 mm (18 in) or more on a side.**

**Option:**

The end-of-roadway marker may be used in instances where there are no alternate vehicular paths.

Where conditions warrant, more than one marker, or a larger marker with or without a Type III barricade (see Section 3F.01), may be used at the end of the roadway.

**Standard:**


**The minimum mounting height to the bottom of an end-of-roadway marker shall be 1.2 m (4 ft) above the edge of the pavement.**

**Guidance:**


Appropriate advance warning signs (see Chapter 2C) should be used.

**Figure 3C-1. Object Markers and End-of-Roadway Markers**


**Type 1 Object Markers**



OM1-1



OM1-2



OM1-3

**Type 2 Object Markers**



OM2-1V



OM2-2V



OM2-1H



OM2-2H

**Type 3 Object Markers**



OM-3L



OM-3C



OM-3R



OM-H3L




OM-H3C




OM-H3R


**End-of-Roadway Markers**



OM4-1



OM4-2



OM4-3

Intentionally blank.

## CHAPTER 3D. DELINEATORS

### Section 3D.01 Delineators

#### Support:

Delineators are particularly beneficial at locations where the alignment might be confusing or unexpected, such as at lane reduction transitions and curves. Delineators are effective guidance devices at night and during adverse weather. An important advantage of delineators in certain locations is that they remain visible when the roadway is wet or snow covered.

Delineators are considered guidance devices rather than warning devices.

#### Option:

Delineators may be used on long continuous sections of highway or through short stretches where there are changes in horizontal alignment.

### Section 3D.02 Delineator Design

#### Standard:

**Delineators shall be retroreflective devices mounted above the roadway surface and along the side of the roadway in a series to indicate the alignment of the roadway. Delineators shall consist of retroreflector units that are capable of clearly retroreflecting light under normal atmospheric conditions from a distance of 300 m (1,000 ft) when illuminated by the high beams of standard automobile lights.**

**Retroreflective elements for delineators shall have a minimum dimension of 75 mm (3 in).**

#### Option:

Elongated retroreflective units of appropriate size may be used in place of two retroreflectors mounted as a unit.

### Section 3D.03 Delineator Application

#### Standard:

**The color of delineators shall conform to the color of edge lines stipulated in Section 3B.06.**

**Single delineators shall be provided on the right side of freeways and expressways and on at least one side of interchange ramps, except in the following cases:**

- A. On tangent sections of freeways and expressways when all of the following conditions are met:**
  - 1. Raised pavement markers are used continuously on lane lines throughout all curves and on all tangents to supplement pavement markings.**
  - 2. Where whole routes or substantial portions of routes have large sections of tangent alignment.**
  - 3. Roadside delineators are used to lead into all curves.**
- B. On sections of roadways where continuous lighting is in operation between interchanges.**

#### Option:

Delineators may be provided on other classes of roads. Single delineators may be provided on the left side of roadways.

#### Guidance:

Single delineators should be provided on the outside of curves on interchange ramps.

Where median crossovers are provided for official or emergency use on divided highways and where these crossovers are to be marked, a double yellow delineator should be placed on the left side of the through roadway on the far side of the crossover for each roadway.

Double or vertically elongated delineators should be installed at 30 m (100 ft) intervals along acceleration and deceleration lanes.

**Option:**

Red delineators may be used on the reverse side of any delineator where it would be viewed by a road user traveling in the wrong direction on that particular ramp or roadway.

Delineators of the appropriate color may be used to indicate a lane reduction transition where either an outside or inside lane merges into an adjacent lane.

**Guidance:**

For lane reduction transitions, the delineators should be used adjacent to the lane or lanes reduced for the full length of the transition and should be so placed and spaced to show the reduction (see Figure 3B-12).

**Support:**

Delineators are not necessary for traffic moving in the direction of a wider pavement or on the side of the roadway where the alignment is not affected by the lane reduction transition.

**Guidance:**

On a highway with continuous delineation on either or both sides, delineators should be carried through transitions.

**Option:**

On a highway with continuous delineation on either or both sides, the spacing between a series of delineators may be closer.

**Standard:**

**When used on a truck escape ramp, delineators shall be red.**

**Guidance:**

Red delineators should be placed on both sides of truck escape ramps. The delineators should be spaced at 15 m (50 ft) intervals for a distance sufficient to identify the ramp entrance. Delineator spacing beyond the ramp entrance should be adequate for guidance according to the length and design of the escape ramp.

### **Section 3D.04 Delineator Placement and Spacing**

**Guidance:**

Delineators should be mounted on suitable supports so that the top of the highest retroreflector is 1.2 m (4 ft) above the near roadway edge. They should be placed 0.6 to 2.4 m (2 to 8 ft) outside the outer edge of the shoulder, or if appropriate, in line with the roadside barrier that is 2.4 m (8 ft) or less outside the outer edge of the shoulder.

Delineators should be placed at a constant distance from the edge of the roadway, except that where an obstruction intrudes into the space between the pavement edge and the extension of the line of the delineators, the delineators should be transitioned to be in line with or inside the innermost edge of the obstruction. If the obstruction is a guardrail, the delineators should be transitioned to be either just behind, directly above (in line with), or on the innermost edge of the guardrail.

Delineators should be spaced 60 to 160 m (200 to 530 ft) apart on mainline tangent sections. Delineators should be spaced 30 m (100 ft) apart on ramp tangent sections.

**Support:**

Examples of delineator installations are shown in Figure 3D-1.

Option:

When uniform spacing is interrupted by such features as driveways and intersections, delineators which would ordinarily be located within the features may be relocated in either direction for a distance not exceeding one quarter of the uniform spacing. Delineators still falling within such features may be eliminated.

Delineators may be transitioned in advance of a lane transition or obstruction as a guide for oncoming traffic.

Guidance:

The spacing of delineators should be adjusted on approaches to and throughout horizontal curves so that several delineators are always simultaneously visible to the road user. The approximate spacing shown in Table 3D-1 should be used.

**Table 3D-1. Approximate Spacing for Delineators on Horizontal Curves**

Radius (R) of Curve (meters)	Approximate Spacing (S) on Curve (meters)	Radius (R) of Curve (feet)	Approximate Spacing (S) on Curve (feet)
15	6	50	20
35	8	115	25
55	11	180	35
75	13	250	40
95	15	300	50
125	18	400	55
155	20	500	65
185	22	600	70
215	24	700	75
245	26	800	80
275	27	900	85
305	29	1,000	90


**Distances in feet were rounded to the nearest 5 feet.**

Spacing for specific radii may be interpolated from table. The minimum spacing should be 6.1 m (20 ft). The spacing on curves should not exceed 90 m (300 ft). In advance of or beyond a curve, and proceeding away from the end of the curve, the spacing of the first delineator is 2S, the second 3S, and the third 6S but not to exceed 90 m (300 ft). S refers to the delineator spacing for specific radii computed from the formula  $S=1.7\sqrt{R-15}$  for metric units and  $S=3\sqrt{R-50}$  for English units.

**Figure 3D-1. Examples of Delineator Placement**

**NOTE:**

Delineators should be placed at a constant distance from the roadway edge, except that when an obstruction exists near the pavement edge, the line of delineators should make a smooth transition to the inside of the obstruction.



## CHAPTER 3E. COLORED PAVEMENTS

### Section 3E.01 General

#### Support:

When used for guidance or regulation of traffic, colored pavements are traffic control devices. Colored pavements also are sometimes used to supplement other traffic control devices.

Colored pavement located between crosswalk lines to emphasize the presence of the crosswalk is not considered to be a traffic control device.

#### Guidance:

Colored pavements used as traffic control devices should be used only where they contrast significantly with adjoining paved areas.

Colors that degrade the contrast of white crosswalk lines, or that might be mistaken by road users as a traffic control application, should not be used for colored pavement located between crosswalk lines.

#### Standard:

**Colored pavements shall not be used as a traffic control device, unless the device is applicable at all times.**

**Colored pavements used as traffic control devices shall be limited to the following colors and applications:**

- A. Yellow shall be used only for flush or raised median islands separating traffic flows in opposite directions.**
- B. White shall be used for delineation on shoulders, and for flushed or raised channelizing islands where traffic passes on both sides in the same general direction.**

Intentionally blank.

## CHAPTER 3F. BARRICADES AND CHANNELIZING DEVICES

### Section 3F.01 Barricades

#### Standard:

**When used to warn and alert road users of the terminus of a roadway in other than temporary traffic control zones, barricades shall meet the design criteria of Section 6F.63 for a Type III barricade, except that the colors of the stripes shall be retroreflective white and retroreflective red.**

#### Option:

An end-of-roadway marker or markers may be used as described in Section 3C.04. Barricades may be used to mark any of the following conditions:

- A. A roadway ends;
- B. A ramp or lane closed for operational purposes; or
- C. The permanent or semipermanent closure or termination of a roadway.

#### Guidance:

Appropriate advance warning signs (see Chapter 2C) should be used.

### Section 3F.02 Channelizing Devices

#### Option:

Channelizing devices, such as traffic cones and tubular markers, may be used for general traffic control purposes such as adding emphasis to reversible lane delineation, channelizing lines, or islands.

#### Standard:

**Channelizing devices shall conform to Section 6F.58 and shall be a minimum of 450 mm (18 in) in height.**

**The minimum height of cones shall be 700 mm (28 in) for use on freeways and other high-speed roadways, and on all facilities when used during hours of darkness or whenever more conspicuous guidance is needed.**

**The color of channelizing devices used outside of temporary traffic control zones shall be either orange or the same color as the pavement marking that they supplement, or for which they are substituted.**

**For nighttime use, channelizing devices shall be retroreflective.**

**Retroreflective material shall have a smooth, sealed outer surface that will display a similar color during both day and night.**

**Retroreflection of cones and tubular markers shall be as described in Sections 6F.59 and 6F.60.**

#### Guidance:

Channelizing devices should be kept clean and bright to maximize target value.

Intentionally blank.

## CHAPTER 3G. ISLANDS

### Section 3G.01 General

Support:

Chapter 3G addresses the characteristics of islands as traffic-control devices. Criteria for the design of islands are set forth in “A Policy on Geometric Design of Highways and Streets” (see Section 1A.11).

**Standard:**

**An island for traffic control purposes shall be the defined area between traffic lanes for control of vehicular movements or for pedestrian refuge. Within an intersection area, a median or an outer separation shall be an island.**

Option:

An island may be designated by pavement markings, channelizing devices, curbs, pavement edges, or other devices.

### Section 3G.02 Approach-End Treatment

Guidance:

The ends of islands first approached by traffic should be preceded by a gradually diverging marking on the roadway surface, to guide vehicles into desired paths of travel along the island edge.

Option:

Approach-end markings that can be readily crossed even at considerable speed may contain slightly raised (usually less than 25 mm (1 in) high) sections of coarse aggregate or other suitable materials to create rumble sections that provide increased visibility of the marked areas and that produce an audible warning to road users traveling across them.

**Standard:**

**Rumble strips or other devices, when used in advance of islands having raised curbs, shall not be placed in such a manner as to constitute an unexpected obstacle.**

Guidance:

Bars or buttons should not project more than 25 to 75 mm (1 to 3 in) above the pavement surface and should be designed so that any wheel encroachment within the area will be obvious to the vehicle operator, but will not result in loss of control of the vehicle.

Option:

Bars or buttons may be preceded by rumble sections, or their height may be gradually increased as approached by traffic.

Pavement markings may be used with raised bars to better designate the island area.

### Section 3G.03 Island Marking Application

**Standard:**

**Markings, as related to islands, shall consist only of pavement and curb markings, object markers, and delineators.**

**On the approach to islands, the triangular neutral area in advance of the end of the island shall include pavement markings as described in Section 3B.10.**

**Option:**

As indicated in Section 3G.02, rumble sections, or other similar traffic control designs which contrast with the pavement surface, may also be applied in the triangular neutral area in advance of the end of an island.

**Guidance:**

When raised bars or buttons are used in these neutral areas, they should be marked with white or yellow retroreflective materials, as determined by the direction or directions of travel they separate.

**Section 3G.04 Island Marking Colors****Guidance:**

Islands outlined by curbs or pavement markings should be marked with retroreflective white or yellow material as determined by the direction or directions of travel they separate (see Section 3A.04).

The retroreflective area should be of sufficient length to denote the general alignment of the edge of the island along which vehicles travel, including the approach nose, when viewed from the approach to the island.

**Option:**

On long islands, curb retroreflection may be discontinued such that it does not extend for the entire length of the curb, especially if the island is illuminated or marked with delineators or edge lines.

**Section 3G.05 Island Object Markers****Option:**

Object markers may be installed alone or in combination with signs (such as KEEP RIGHT, KEEP LEFT, double arrows, or guide signs) located within the island.

**Section 3G.06 Island Delineators****Standard:**

**Delineators installed on islands shall be the same colors as the related edge lines except that, when facing wrong-way traffic, they shall be red (see Section 3D.03).**

**Each roadway through an intersection shall be considered separately in positioning delineators to assure maximum effectiveness.**

## PART 4. HIGHWAY TRAFFIC SIGNALS

### TABLE OF CONTENTS

		<u>Page</u>
<b>CHAPTER 4A.</b>	<b>GENERAL</b>	
Section 4A.01	Types.....	4A-1
Section 4A.02	Definitions Relating to Highway Traffic Signals .....	4A-1
<b>CHAPTER 4B.</b>	<b>TRAFFIC CONTROL SIGNALS—GENERAL</b>	
Section 4B.01	General.....	4B-1
Section 4B.02	Basis of Installation or Removal of Traffic Control Signals .....	4B-1
Section 4B.03	Advantages and Disadvantages of Traffic Control Signals .....	4B-2
Section 4B.04	Alternatives to Traffic Control Signals .....	4B-2
Section 4B.05	Adequate Roadway Capacity.....	4B-3
Section 4B.06	Traffic Signals on State Highway Extensions in Villages .....	4B-3
<b>CHAPTER 4C.</b>	<b>TRAFFIC CONTROL SIGNAL NEEDS STUDIES</b>	
Section 4C.01	Studies and Factors for Justifying Traffic Control Signals .....	4C-1
Section 4C.02	Warrant 1, Eight-Hour Vehicular Volume .....	4C-3
Section 4C.03	Warrant 2, Four-Hour Vehicular Volume.....	4C-4
Section 4C.04	Warrant 3, Peak Hour .....	4C-5
Section 4C.05	Warrant 4, Pedestrian Volume.....	4C-6
Section 4C.06	Warrant 5, School Crossing.....	4C-6
Section 4C.07	Warrant 6, Coordinated Signal System.....	4C-9
Section 4C.08	Warrant 7, Crash Experience.....	4C-9
Section 4C.09	Warrant 8, Roadway Network .....	4C-10
<b>CHAPTER 4D.</b>	<b>TRAFFIC CONTROL SIGNAL FEATURES</b>	
Section 4D.01	General.....	4D-1
Section 4D.02	Responsibility for Operation and Maintenance .....	4D-1
Section 4D.03	Provisions for Pedestrians.....	4D-2
Section 4D.04	Meaning of Vehicular Signal Indications .....	4D-2
Section 4D.05	Application of Steady Signal Indications .....	4D-4
Section 4D.06	Application of Steady Signal Indications for Left Turns.....	4D-5
Section 4D.07	Application of Steady Signal Indications for Right Turns .....	4D-8
Section 4D.08	Prohibited Steady Signal Indications.....	4D-9
Section 4D.09	Unexpected Conflicts During Green or Yellow Intervals .....	4D-9
Section 4D.10	Yellow Change and Red Clearance Intervals .....	4D-10
Section 4D.11	Application of Flashing Signal Indications .....	4D-10
Section 4D.12	Flashing Operation of Traffic Control Signals .....	4D-11
Section 4D.13	Preemption and Priority Control of Traffic Control Signals .....	4D-12
Section 4D.14	Coordination of Traffic Control Signals.....	4D-13
Section 4D.15	Size, Number, and Location of Signal Faces by Approach .....	4D-14
Section 4D.16	Number and Arrangement of Signal Sections in Vehicular Traffic Control Signal Faces .....	4D-16
Section 4D.17	Visibility, Shielding, and Positioning of Signal Faces .....	4D-20
Section 4D.18	Design, Illumination, and Color of Signal Sections .....	4D-21
Section 4D.19	Lateral Placement of Signal Supports and Cabinets.....	4D-23
Section 4D.20	Temporary Traffic Control Signals .....	4D-23
Section 4D.21	Traffic Signal Signs, Auxiliary.....	4D-24

<b>CHAPTER 4E.</b>	<b>PEDESTRIAN CONTROL FEATURES</b>	
Section 4E.01	Pedestrian Signal Heads .....	4E-1
Section 4E.02	Meaning of Pedestrian Signal Head Indications.....	4E-1
Section 4E.03	Application of Pedestrian Signal Heads .....	4E-1
Section 4E.04	Size, Design, and Illumination of Pedestrian Signal Head Indications .....	4E-2
Section 4E.05	Location and Height of Pedestrian Signal Heads .....	4E-4
Section 4E.06	Accessible Pedestrian Signals .....	4E-4
Section 4E.07	Countdown Pedestrian Signals .....	4E-6
Section 4E.08	Pedestrian Detectors .....	4E-7
Section 4E.09	Accessible Pedestrian Signal Detectors.....	4E-7
Section 4E.10	Pedestrian Intervals and Signal Phases.....	4E-8
<b>CHAPTER 4F.</b>	<b>TRAFFIC CONTROL SIGNALS FOR EMERGENCY VEHICLE ACCESS</b>	
Section 4F.01	Applications of Emergency-Vehicle Traffic Control Signals .....	4F-1
Section 4F.02	Design of Emergency-Vehicle Traffic Control Signals.....	4F-1
Section 4F.03	Operation of Emergency-Vehicle Traffic Control Signals.....	4F-2
<b>CHAPTER 4G.</b>	<b>TRAFFIC CONTROL SIGNALS FOR ONE-LANE, TWO-WAY FACILITIES</b>	
Section 4G.01	Application of Traffic Control Signals for One-Lane, Two-Way Facilities .....	4G-1
Section 4G.02	Design of Traffic Control Signals for One-Lane, Two-Way Facilities.....	4G-1
Section 4G.03	Operation of Traffic Control Signals for One-Lane, Two-Way Facilities .....	4G-1
<b>CHAPTER 4H.</b>	<b>TRAFFIC CONTROL SIGNALS FOR FREEWAY ENTRANCE RAMPS</b>	
Section 4H.01	Application of Freeway Entrance Ramp Control Signals.....	4H-1
Section 4H.02	Design of Freeway Entrance Ramp Control Signals .....	4H-1
<b>CHAPTER 4I.</b>	<b>TRAFFIC CONTROL FOR MOVABLE BRIDGES</b>	
Section 4I.01	Application of Traffic Control for Movable Bridges .....	4I-1
Section 4I.02	Design and Location of Movable Bridge Signals and Gates.....	4I-1
Section 4I.03	Operation of Movable Bridge Signals and Gates .....	4I-3
<b>CHAPTER 4J.</b>	<b>LANE-USE CONTROL SIGNALS</b>	
Section 4J.01	Application of Lane-Use Control Signals.....	4J-1
Section 4J.02	Meaning of Lane-Use Control Signal Indications .....	4J-1
Section 4J.03	Design of Lane-Use Control Signals .....	4J-2
Section 4J.04	Operation of Lane-Use Control Signals .....	4J-3
<b>CHAPTER 4K.</b>	<b>FLASHING BEACONS</b>	
Section 4K.01	General Design and Operation of Flashing Beacons.....	4K-1
Section 4K.02	Intersection Control Beacon .....	4K-1
Section 4K.03	Warning Beacon .....	4K-2
Section 4K.04	Speed Limit Sign Beacon .....	4K-2
Section 4K.05	Stop Beacon .....	4K-3
<b>CHAPTER 4L.</b>	<b>IN-ROADWAY LIGHTS</b>	
Section 4L.01	Application of In-Roadway Lights .....	4L-1
Section 4L.02	In-Roadway Warning Lights at Crosswalks .....	4L-1

**FIGURES**

<b>CHAPTER 4C.</b>	<b>TRAFFIC CONTROL SIGNAL NEEDS STUDIES</b>	
Figure 4C-1	Warrant 2, Four-Hour Vehicular Volume.....	4C-7
Figure 4C-2	Warrant 2, Four-Hour Vehicular Volume (70% Factor) .....	4C-7
Figure 4C-3	Warrant 3, Peak Hour .....	4C-8
Figure 4C-4	Warrant 3, Peak Hour (70% Factor) .....	4C-8
<b>CHAPTER 4D.</b>	<b>TRAFFIC CONTROL SIGNAL FEATURES</b>	
Figure 4D-1	Maximum Mounting Height of Signal Faces Located Between 12 Meters (40 Feet) and 16 Meters (53 Feet) from Stop Line .....	4D-17
Figure 4D-2	Horizontal Location of Signal Faces .....	4D-18
Figure 4D-3	Typical Arrangements of Signal Lenses in Signal Faces .....	4D-22
<b>CHAPTER 4E.</b>	<b>PEDESTRIAN CONTROL FEATURES</b>	
Figure 4E-1	Typical Pedestrian Signal Indications .....	4E-3
Figure 4E-2	Recommended Pushbutton Locations for Accessible Pedestrian Signals .....	4E-10
<b>CHAPTER 4J.</b>	<b>LANE-USE CONTROL SIGNALS</b>	
Figure 4J-1	Left-Turn Lane-Use Control Signals .....	4J-2

**TABLES**

<b>CHAPTER 4C.</b>	<b>TRAFFIC CONTROL SIGNAL NEEDS STUDIES</b>	
Table 4C-1	Warrant 1, Eight-Hour Vehicular Volume .....	4C-4
<b>CHAPTER 4D.</b>	<b>TRAFFIC CONTROL SIGNAL FEATURES</b>	
Table 4D-1	Minimum Sight Distance .....	4D-16

Intentionally blank.

## CHAPTER 4A. GENERAL

### Section 4A.01 Types

Support:

The following types and uses of highway traffic signals are discussed in Part 4: traffic control signals; pedestrian signals; emergency-vehicle traffic control signals; traffic control signals for one-lane, two-way facilities; traffic control signals for freeway entrance ramps; traffic control signals for movable bridges; lane-use control signals; flashing beacons; and in-roadway lights.

### Section 4A.02 Definitions Relating to Highway Traffic Signals

Standard:

The following technical terms, when used in Part 4, shall be defined as follows:

1. **Accessible Pedestrian Signal**—a device that communicates information about pedestrian timing in nonvisual format such as audible tones, verbal messages, and/or vibrating surfaces.
2. **Active Grade Crossing Warning System**—the flashing-light signals, with or without warning gates, together with the necessary control equipment used to inform road users of the approach or presence of trains at highway-rail grade crossings or highway-light rail transit grade crossings.
3. **Actuated Operation**—a type of traffic control signal operation in which some or all signal phases are operated on the basis of actuation.
4. **Actuation**—initiation of a change in or extension of a traffic signal phase through the operation of any type of detector.
5. **Approach**—all lanes of traffic moving towards an intersection or a midblock location from one direction, including any adjacent parking lane(s).
6. **Average Day**—a day representing traffic volumes normally and repeatedly found at a location, typically a weekday when volumes are influenced by employment or a weekend day when volumes are influenced by entertainment or recreation.
7. **Backplate**— see Signal Backplate.
8. **Beacon**—a highway traffic signal with one or more signal sections that operates in a flashing mode.
9. **Conflict Monitor**—a device used to detect and respond to improper or conflicting signal indications and improper operating voltages in a traffic controller assembly.
10. **Controller Assembly**—a complete electrical device mounted in a cabinet for controlling the operation of a highway traffic signal.
11. **Controller Unit**—that part of a controller assembly that is devoted to the selection and timing of the display of signal indications.
12. **Crosswalk**—*means: (1) That part of a roadway at intersections ordinarily included within the real or projected prolongation of property lines and curb lines or, in the absence of curbs, the edges of the traversable roadway; (2) Any portion of a roadway at an intersection or elsewhere, distinctly indicated for pedestrian crossing by lines or other markings on the surface; (3) Notwithstanding divisions (LL)(1) and (2) of this section, there shall not be a crosswalk where local authorities have placed signs indicating no crossing.*  
[4511.01(LL),O.R.C.]
13. **Cycle Length**—the time required for one complete sequence of signal indications.
14. **Dark Mode**—the lack of all signal indications at a signalized location. (The dark mode is most commonly associated with power failures, ramp meters, beacons, and some movable bridge signals.)
15. **Detector**—a device used for determining the presence or passage of vehicles or pedestrians.
16. **Dual-Arrow Signal Section**—a type of signal section designed to include both a yellow arrow and a green arrow.
17. **Emergency Vehicle Traffic Control Signal**—a special traffic control signal that assigns the right-of-way to an authorized emergency vehicle.

18. **Flasher**—a device used to turn highway traffic signal indications on and off at a repetitive rate of approximately once per second.
19. **Flashing**—an operation in which a highway traffic signal indication is turned on and off repetitively.
20. **Flashing Mode**—a mode of operation in which at least one traffic signal indication in each vehicular signal face of a highway traffic signal is turned on and off repetitively.
21. **Full-Actuated Operation**—a type of traffic control signal operation in which all signal phases function on the basis of actuation.
22. **Highway Traffic Signal**—a power-operated traffic control device by which traffic is warned or directed to take some specific action. These devices do not include signals at toll plazas, power-operated signs, illuminated pavement markers, warning lights (see Section 6F.78), or steady-burning electric lamps.
23. **In-Roadway Lights**—a special type of highway traffic signal installed in the roadway surface to warn road users that they are approaching a condition on or adjacent to the roadway that might not be readily apparent and might require the road users to slow down and/or come to a stop.
24. **Intersection**—*means: (1) The area embraced within the prolongation or connection of the lateral curb lines, or, if none, then the lateral boundary lines of the roadways of two highways which join one another at, or approximately at, right angles, or the area within which vehicles traveling upon different highways joining at any other angle may come into conflict; (2) Where a highway includes two roadways thirty feet or more apart, then every crossing of each roadway of such divided highway by an intersecting highway shall be regarded as a separate intersection. If an intersecting highway also includes two roadways thirty feet or more apart, then every crossing of two roadways of such highways shall be regarded as a separate intersection; (3) The junction of an alley with a street or highway, or with another alley, shall not constitute an intersection. [4511.01(KK), O.R.C.]*
25. **Intersection Control Beacon**—a beacon used only at an intersection to control two or more directions of travel.
26. **Interval**—the part of a signal cycle during which signal indications do not change.
27. **Interval Sequence**—the order of appearance of signal indications during successive intervals of a signal cycle.
28. **Lane-Use Control Signal**—a signal face displaying signal indications to permit or prohibit the use of specific lanes of a roadway or to indicate the impending prohibition of such use.
29. **Lens**—see Signal Lens.
30. **Louver**—see Signal Louver.
31. **Major Street**—the street normally carrying the higher volume of vehicular traffic.
32. **Malfunction Management Unit**—same as Conflict Monitor.
33. **Minor Street**—the street normally carrying the lower volume of vehicular traffic.
34. **Movable Bridge Resistance Gate**—a type of traffic gate, which is located downstream of the movable bridge warning gate, that provides a physical deterrent to vehicle and/or pedestrian traffic when placed in the appropriate position.
35. **Movable Bridge Signal**—a highway traffic signal installed at a movable bridge to notify traffic to stop during periods when the roadway is closed to allow the bridge to open.
36. **Movable Bridge Warning Gate**—a type of traffic gate designed to warn, but not primarily to block, vehicle and/or pedestrian traffic when placed in the appropriate position.
37. **Pedestrian Change Interval**—an interval during which the flashing UPRAISED HAND (symbolizing DONT WALK) signal indication is displayed. When a verbal message is provided at an accessible pedestrian signal, the verbal message is “wait.”
38. **Pedestrian Clearance Time**—the time provided for a pedestrian crossing in a crosswalk, after leaving the curb or shoulder, to travel to the far side of the traveled way or to a median.
39. **Pedestrian Signal Head**—a signal head, which contains the symbols WALKING PERSON (symbolizing WALK) and UPRAISED HAND (symbolizing DONT WALK), that is installed to direct pedestrian traffic at a traffic control signal.

40. **Permissive Mode**—a mode of traffic control signal operation in which, when a CIRCULAR GREEN signal indication is displayed, left or right turns are permitted to be made after yielding to pedestrians and/or oncoming traffic.
41. **Platoon**—a group of vehicles or pedestrians traveling together as a group, either voluntarily or involuntarily, because of traffic signal controls, geometrics, or other factors.
42. **Preemption Control**—the transfer of normal operation of a traffic control signal to a special control mode of operation.
43. **Pretimed Operation**—a type of traffic control signal operation in which none of the signal phases function on the basis of actuation.
44. **Priority Control**—a means by which the assignment of right-of-way is obtained or modified.
45. **Protected Mode**—a mode of traffic control signal operation in which left or right turns are permitted to be made when a left or right GREEN ARROW signal indication is displayed.
46. **Pushbutton**—a button to activate pedestrian timing.
47. **Pushbutton Locator Tone**—a repeating sound that informs approaching pedestrians that they are required to push a button to actuate pedestrian timing and that enables pedestrians who have visual disabilities to locate the pushbutton.
48. **Ramp Control Signal**—a highway traffic signal installed to control the flow of traffic onto a freeway at an entrance ramp or at a freeway-to-freeway ramp connection.
49. **Ramp Meter**—see Ramp Control Signal.
50. **Red Clearance Interval**—an optional interval that follows a yellow change interval and precedes the next conflicting green interval.
51. **Right-of-Way**—*means either of the following, as the context requires: (1) The right of a vehicle, streetcar, trackless trolley, or pedestrian to proceed uninterrupted in a lawful manner in the direction in which it or the individual is moving in preference to another vehicle, streetcar, trackless trolley, or pedestrian approaching from a different direction into its or the individual's path; (2) A general term denoting land, property, or interest therein, usually in the configuration of a strip, acquired for or devoted to transportation purposes. When used in this context, right-of-way includes the roadway, shoulders or berm, ditch, and slopes extending to the right-of-way limits under the control of the state or local authority. [4511.01(UU), O.R.C.]*
52. **Roadway Network**—a geographical arrangement of intersecting roadways.
53. **Semiactuated Operation**—a type of traffic control signal operation in which at least one, but not all, signal phases function on the basis of actuation.
54. **Separate Left-Turn Signal Face**—a signal face for controlling a left-turn movement that sometimes displays a different color of circular signal indication than the adjacent through signal faces display.
55. **Shared Left-Turn Signal Face**—a signal face, for controlling both a left turn movement and the adjacent through movement, that always displays the same color of circular signal indication that the adjacent through signal face or faces display.
56. **Signal Backplate**—a thin strip of material that extends outward from and parallel to a signal face on all sides of a signal housing to provide a background for improved visibility of the signal indications.
57. **Signal Coordination**—the establishment of timed relationships between adjacent traffic control signals.
58. **Signal Face**—that part of a traffic control signal provided for controlling one or more traffic movements on a single approach.
59. **Signal Head**—an assembly of one or more signal sections.
60. **Signal Housing**—that part of a signal section that protects the light source and other required components.
61. **Signal Indication**—the illumination of a signal lens or equivalent device.
62. **Signal Lens**—that part of the signal section that redirects the light coming directly from the light source and its reflector, if any.

63. **Signal Louver**—a device that can be mounted inside a signal visor to restrict visibility of a signal indication from the side or to limit the visibility of the signal indication to a certain lane or lanes, or to a certain distance from the stop line.
64. **Signal Phase**—the right-of-way, yellow change, and red clearance intervals in a cycle that are assigned to an independent traffic movement or combination of movements.
65. **Signal Section**—the assembly of a signal housing, signal lens, and light source with necessary components to be used for providing one signal indication.
66. **Signal System**—two or more traffic control signals operating in signal coordination.
67. **Signal Timing**—the amount of time allocated for the display of a signal indication.
68. **Signal Visor**—that part of a signal section that directs the signal indication specifically to approaching traffic and reduces the effect of direct external light entering the signal lens.
69. **Signal Warrant**—a threshold condition that, if found to be satisfied as part of an engineering study, shall result in analysis of other traffic conditions or factors to determine whether a traffic control signal or other improvement is justified.
70. **Speed Limit Sign Beacon**—a beacon used to supplement a SPEED LIMIT sign.
71. **Steady (Steady Mode)**—the continuous illumination of a signal indication for the duration of an interval, signal phase, or consecutive signal phases.
72. **Stop Beacon**—a beacon used to supplement a STOP sign, a DO NOT ENTER sign, or a WRONG WAY sign.
73. **Traffic Control Signal**—*means any device whether, manually, electrically, or mechanically operated, by which traffic is alternately directed to stop, to proceed, to change direction, or not to change direction. [4511.01(RR), O.R.C.]*
74. **Vibrotactile Pedestrian Device**—a device that communicates, by touch, information about pedestrian timing using a vibrating surface.
75. **Visibility-Limited Signal Face or Signal Section**—a type of signal face or signal section designed (or shielded, hooded, or louvered) to restrict the visibility of a signal indication from the side, to a certain lane or lanes, or to a certain distance from the stop line.
76. **Walk Interval**—an interval during which the WALKING PERSON (symbolizing WALK) signal indication is displayed. When a verbal message is provided at an accessible pedestrian signal, the verbal message is “walk sign.”
76. **Warning Beacon**—a beacon used only to supplement an appropriate warning or regulatory sign or marker.
78. **Yellow Change Interval**—the first interval following the green interval during which the yellow signal indication is displayed.

## CHAPTER 4B. TRAFFIC CONTROL SIGNALS—GENERAL

### Section 4B.01 General

#### Standard:

A traffic control signal (or traffic signal) shall be defined (see Sections 1A.13 ad 4A.02) as: “*any device, whether manually, electrically or mechanically operated, by which traffic is alternately directed to stop, to proceed, to change direction or not to change direction*” (4511.01 (RR), O.R.C.).

Traffic shall be defined (see Section 1A.13) as: “*Pedestrians, ridden or herded animals, vehicles, streetcars, trackless trolleys, and other devices, either singularly or together, while using any highway for purposes of travel*” (4511.01(TT), O.R.C.).

#### Support:

Words such as pedestrians and bicyclists are used redundantly in selected sections of Part 4 to encourage sensitivity to these elements of “traffic.”

Standards for traffic control signals are important because traffic control signals need to attract the attention of a variety of road users, including those who are older, those with impaired vision, as well as those who are fatigued or distracted, or who are not expecting to encounter a signal at a particular location.

### Section 4B.02 Basis of Installation or Removal of Traffic Control Signals

#### Guidance:

The selection and use of traffic control signals should be based on an engineering study of roadway, traffic, and other conditions.

#### Support:

A careful analysis of traffic operations, pedestrian and bicyclist needs, and other factors at a large number of signalized and unsignalized locations, coupled with engineering judgment, has provided a series of signal warrants, described in Chapter 4C, that define the minimum conditions under which installing traffic control signals might be justified.

#### Guidance:

Engineering judgment should be applied in the review of operating traffic control signals to determine whether the type of installation and the timing program meet the current requirements of all forms of traffic

If changes in traffic patterns eliminate the need for a traffic control signal, consideration should be given to removing it and replacing it with appropriate alternative traffic control devices, if any are needed.

#### Option:

If the engineering study indicates that the traffic control signal is no longer justified, removal may be accomplished using the following steps:

- A. Determine the appropriate traffic control to be used after removal of the signal.
- B. Remove any sight-distance restrictions as necessary.
- C. Inform the public of the removal study, for example by installing an informational sign (or signs) such as the SIGNAL UNDER STUDY FOR REMOVAL (W3-H12) sign at the signalized location in a position where it is visible to all road users.
- D. Flash or cover the signal heads for a minimum of 90 days, and install the appropriate stop control or other traffic control devices.
- E. Remove the signal if the engineering data collected during the removal study period confirms that the signal is no longer needed. Instead of total removal of the traffic control signal, the poles and cables may remain in place after removal of the signal heads for continued analysis.

### **Section 4B.03 Advantages and Disadvantages of Traffic Control Signals**

Support:

When properly used, traffic control signals are valuable devices for the control of vehicular and pedestrian traffic. They assign the right-of-way to the various traffic movements and thereby profoundly influence traffic flow.

Traffic control signals that are properly designed, located, operated, and maintained will have one or more of the following advantages:

- A. They provide for the orderly movement of traffic.
- B. They increase the traffic-handling capacity of the intersection if:
  1. Proper physical layouts and control measures are used, and
  2. The signal operational parameters are reviewed and updated (if needed) on a regular basis (as engineering judgment determines that significant traffic flow and/or land use changes have occurred) to maximize the ability of the traffic control signal to satisfy current traffic demands.
- C. They reduce the frequency and severity of certain types of crashes, especially right-angle collisions.
- D. They are coordinated to provide for continuous or nearly continuous movement of traffic at a definite speed along a given route under favorable conditions.
- E. They are used to interrupt heavy traffic at intervals to permit other traffic, vehicular or pedestrian, to cross.

Traffic control signals are often considered a panacea for all traffic problems at intersections. This belief has led to traffic control signals being installed at many locations where they are not needed, adversely affecting the safety and efficiency of vehicular, bicycle, and pedestrian traffic.

Traffic control signals, even when justified by traffic and roadway conditions, can be ill-designed, ineffectively placed, improperly operated, or poorly maintained. Improper or unjustified traffic control signals can result in one or more of the following disadvantages:

- A. Excessive delay;
- B. Excessive disobedience of the signal indications;
- C. Increased use of less adequate routes as road users attempt to avoid the traffic control signals; and
- D. Significant increases in the frequency of collisions (especially rear-end collisions).

### **Section 4B.04 Alternatives to Traffic Control Signals**

Guidance:

Since vehicular delay and the frequency of some types of crashes are sometimes greater under traffic signal control than under STOP sign control, consideration should be given to providing alternatives to traffic control signals even if one or more of the signal warrants has been satisfied.

Option:

These alternatives may include, but are not limited to, the following:

- A. Installing signs along the major street to warn road users approaching the intersection;
- B. Relocating the stop line(s) and making other changes to improve the sight distance at the intersection;
- C. Installing measures designed to reduce speeds on the approaches;
- D. Installing a flashing beacon at the intersection to supplement STOP sign control;
- E. Installing flashing beacons on warning signs in advance of a STOP sign controlled intersection on major-and/or minor-street approaches;
- F. Adding one or more lanes on a minor-street approach to reduce the number of vehicles per lane on the approach;
- G. Revising the geometrics at the intersection to channelize vehicular movements and reduce the time required for a vehicle to complete a movement, which could also assist pedestrians;
- H. Installing roadway lighting if a disproportionate number of crashes occur at night;

- I. Restricting one or more turning movements, perhaps on a time-of-day basis, if alternate routes are available;
- J. If the warrant is satisfied, installing multiway STOP sign control;
- K. Installing a roundabout intersection; and
- L. Employing other alternatives, depending on conditions at the intersection.

#### **Section 4B.05 Adequate Roadway Capacity**

##### Support:

The delays inherent in the alternating assignment of right-of-way at intersections controlled by traffic control signals can frequently be reduced by widening the major roadway, the minor roadway, or both roadways. Widening the minor roadway often benefits the operations on the major roadway, because it reduces the green time that must be assigned to minor-roadway traffic. In urban areas, the effect of widening can be achieved by eliminating parking on intersection approaches. It is desirable to have at least two lanes for moving traffic on each approach to a signalized location. Additional width on the departure side of the intersection, as well as on the approach side, will sometimes be needed to clear traffic through the intersection effectively.

##### Guidance:

Adequate roadway capacity should be provided at a signalized location. Before an intersection is widened, the additional green time pedestrians need to cross the widened roadways should be considered to determine if it will exceed the green time saved through improved vehicular flow.

#### **Section 4B.06 Traffic Signals on State Highway Extensions in Villages**

##### Standard:

**As noted in Section 4511.11(C) of the Ohio Revised Code (O.R.C.) (see Appendix B2): “No village shall place or maintain any traffic control signal upon an extension of the state highway system within the village without first obtaining the permission of the director.”**

##### Support:

Section 4511.11(C) of the O.R.C. also states that “the director may revoke the permission and may require to be removed any traffic control signal that has been erected without the director’s permission on an extension of a state highway within a village, or that, if erected under a permit granted by the director, does not conform to the state manual and specifications, or that is not operated in accordance with the terms of the permit.”

##### Guidance:

Requests from village authorities for permission to install and operate traffic control signals on state highway extensions within villages (village signal permits) should be submitted to the ODOT District Deputy Director in accordance with the procedures, and using the forms, in Part 4 of the ODOT Traffic Engineering Manual (TEM) (see Section 1A.11).

##### Support:

The instructions and forms for submitting village signal permit requests are also available from each ODOT District Office.

Traffic control signal needs studies are discussed in Chapter 4C of this Manual. Additional information about preparing traffic studies is available in various traffic engineering publications, including the ODOT TEM (see Section 1A.11).

Intentionally blank.

## CHAPTER 4C. TRAFFIC CONTROL SIGNAL NEEDS STUDIES

### Section 4C.01 Studies and Factors for Justifying Traffic Control Signals

#### Standard:

**An engineering study of traffic conditions, pedestrian characteristics, and physical characteristics of the location shall be performed to determine whether installation of a traffic control signal is justified at a particular location.**

**The investigation of the need for a traffic control signal shall include an analysis of the applicable factors contained in the following traffic signal warrants and other factors related to existing operation and safety at the study location:**

**Warrant 1, Eight-Hour Vehicular Volume.**

**Warrant 2, Four-Hour Vehicular Volume.**

**Warrant 3, Peak Hour.**

**Warrant 4, Pedestrian Volume.**

**Warrant 5, School Crossing.**

**Warrant 6, Coordinated Signal System.**

**Warrant 7, Crash Experience.**

**Warrant 8, Roadway Network.**

**The satisfaction of a traffic signal warrant or warrants shall not in itself require the installation of a traffic control signal.**

#### Support:

Sections 8D.07 and 10D.05 contain information regarding the use of traffic control signals instead of gates and/or flashing light signals at highway-railroad grade crossings and highway-light rail transit grade crossings, respectively.

#### Guidance:

A traffic control signal should not be installed unless one or more of the factors described in this Chapter are met.

A traffic control signal should not be installed unless an engineering study indicates that installing a traffic control signal will improve the overall safety and/or operation of the intersection.

A traffic control signal should not be installed if it will seriously disrupt progressive traffic flow.

The study should consider the effects of the right-turn vehicles from the minor-street approaches. Engineering judgment should be used to determine what, if any, portion of the right-turn traffic is subtracted from the minor-street traffic count when evaluating the count against the above signal warrants.

Engineering judgment should also be used in applying various traffic signal warrants to cases where approaches consist of one lane plus one left-turn or right-turn lane. The site-specific traffic characteristics dictate whether an approach should be considered as one lane or two lanes. For example, for an approach with one lane for through and right-turning traffic plus a left-turn lane, engineering judgment could indicate that it should be considered a one-lane approach if the traffic using the left-turn lane is minor. In such a case, the total traffic volume approaching the intersection should be applied against the signal warrants as a one-lane approach. The approach should be considered two lanes if approximately half of the traffic on the approach turns left and the left-turn lane is of sufficient length to accommodate all left-turn vehicles.

Similar engineering judgment and rationale should be applied to a street approach with one lane plus a right-turn lane. In this case, the degree of conflict of minor-street right-turn traffic with traffic on the major street should be considered. Thus, right-turn traffic should not be included in the minor-street volume if the movement enters the major street with minimal conflict. The approach should be evaluated as a one-lane approach with only the traffic volume in the through/left-turn lane considered.

At a location that is under development or construction and where it is not possible to obtain a traffic count that would represent future traffic conditions, hourly volumes should be estimated as part of an engineering study for comparison with traffic signal warrants. Except for locations where the engineering study uses the satisfaction of Warrant 8 to justify a signal, a traffic control signal installed under projected conditions should have an engineering study done within 1 year of putting the signal into stop-and-go operation to determine if the signal is justified. If not justified, the signal should be taken out of stop-and-go operation or removed.

For signal warrant analysis, a location with a wide median, even if the median width is greater than 9 m (30 ft), should be considered as one intersection.

Option:

At an intersection with a high volume of left-turn traffic from the major street, the signal warrant analysis may be performed in a manner that considers the higher of the major-street left-turn volumes as the “minor-street” volume and the corresponding single direction of opposing traffic on the major street as the “major-street” volume.

For signal warrant analysis, bicyclists may be counted as either vehicles or pedestrians.

Support:

When performing a signal warrant analysis, bicyclists riding in the street with other vehicular traffic are usually counted as vehicles and bicyclists who are clearly using pedestrian facilities are usually counted as pedestrians.

Option:

Engineering study data may include the following:

- A. The number of vehicles entering the intersection in each hour from each approach during 12 hours of an average day. It is desirable that the hours selected contain the greatest percentage of the 24-hour traffic volume.
- B. Vehicular volumes for each traffic movement from each approach, classified by vehicle type (heavy trucks, passenger cars and light trucks, public-transit vehicles, and, in some locations, bicycles), during each 15-minute period of the 2 hours in the morning and 2 hours in the afternoon during which total traffic entering the intersection is greatest.
- C. Pedestrian volume counts on each crosswalk during the same periods as the vehicular counts in Item B above and during hours of highest pedestrian volume. Where young, elderly, and/or persons with physical or visual disabilities need special consideration, the pedestrians and their crossing times may be classified by general observation.
- D. Information about nearby facilities and activity centers that serve the young, elderly, and/or persons with disabilities, including requests from persons with disabilities for accessible crossing improvements at the location under study. These persons might not be adequately reflected in the pedestrian volume count if the absence of a signal restrains their mobility.
- E. The posted or statutory speed limit or the 85th-percentile speed on the uncontrolled approaches to the location.
- F. A condition diagram showing details of the physical layout, including such features as intersection geometrics, channelization, grades, sight-distance restrictions, transit stops and routes, parking conditions, pavement markings, roadway lighting, driveways, nearby railroad crossings, distance to nearest traffic control signals, utility poles and fixtures, and adjacent land use.
- G. A collision diagram showing crash experience by type, location, direction of movement, severity, weather, time of day, date, and day of week for at least 1 year.

The following data, which are desirable for a more precise understanding of the operation of the intersection, may be obtained during the periods specified in Item B of the preceding paragraph:

- A. Vehicle-hours of stopped time delay determined separately for each approach.
- B. The number and distribution of acceptable gaps in vehicular traffic on the major street for entrance from the minor street.

- C. The posted or statutory speed limit or the 85th-percentile speed on controlled approaches at a point near to the intersection but unaffected by the control.
- D. Pedestrian delay time for at least two 30-minute peak pedestrian delay periods of an average weekday or like periods of a Saturday or Sunday.
- E. Queue length on stop-controlled approaches.

### **Section 4C.02 Warrant 1, Eight-Hour Vehicular Volume**

#### **Support:**

The Minimum Vehicular Volume, Condition A, is intended for application at locations where a large volume of intersecting traffic is the principal reason to consider installing a traffic control signal.

The Interruption of Continuous Traffic, Condition B, is intended for application at locations where Condition A is not satisfied and where the traffic volume on a major street is so heavy that traffic on a minor intersecting street suffers excessive delay or conflict in entering or crossing the major street.

It is intended that Warrant 1 be treated as a single warrant. If Condition A is satisfied, then the criteria for Warrant 1 is satisfied and Condition B and the combination of Conditions A and B are not needed. Similarly, if Condition B is satisfied, then the criteria for Warrant 1 is satisfied and the combination of Conditions A and B is not needed.

#### **Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that one of the following conditions exist for each of any 8 hours of an average day:**

- A. The vehicles per hour given in both of the 100 percent columns of Condition A in Table 4C-1 exist on the major-street and the higher-volume minor-street approaches, respectively, to the intersection; or**
- B. The vehicles per hour given in both of the 100 percent columns of Condition B in Table 4C-1 exist on the major-street and the higher-volume minor-street approaches, respectively, to the intersection.**

**In applying each condition the major-street and minor-street volumes shall be for the same 8 hours. On the minor street, the higher volume shall not be required to be on the same approach during each of these 8 hours.**

#### **Option:**

If the posted or statutory speed limit or the 85th-percentile speed on the major street exceeds 70 km/h or exceeds 40 mph, or if the intersection lies within the built-up area of an isolated community having a population of less than 10,000, the traffic volumes in the 70 percent columns in Table 4C-1 may be used in place of the 100 percent columns.

#### **Guidance:**

The combination of Conditions A and B is intended for application at locations where Condition A is not satisfied and Condition B is not satisfied, and should be applied only after an adequate trial of other alternatives that could cause less delay and inconvenience to traffic has failed to solve the traffic problems.

#### **Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that both of the following conditions exist for each of any 8 hours of an average day:**

- A. The vehicles per hour given in both of the 80 percent columns of Condition A in Table 4C-1 exist on the major-street and the higher-volume minor-street approaches, respectively, to the intersection; and**
- B. The vehicles per hour given in both of the 80 percent columns of Condition B in Table 4C-1 exist on the major-street and the higher-volume minor-street approaches, respectively, to the intersection.**

**Table 4C-1. Warrant 1, Eight-Hour Vehicular Volume**

Condition A—Minimum Vehicular Volume									
Number of lanes for moving traffic on each approach		Vehicles per hour on major street (total of both approaches)				Vehicles per hour on higher-volume minor-street approach (one direction only)			
Major Street	Minor Street	100% <sup>a</sup>	80% <sup>b</sup>	70% <sup>c</sup>	56% <sup>d</sup>	100% <sup>a</sup>	80% <sup>b</sup>	70% <sup>c</sup>	56% <sup>d</sup>
1 .....	1 .....	500	400	350	280	150	120	105	84
2 or more	1 .....	600	480	420	336	150	120	105	84
2 or more	2 or more	600	480	420	336	200	160	140	112
1 .....	2 or more	500	400	350	280	200	160	140	112

Condition B—Interruption of Continuous Traffic									
Number of lanes for moving traffic on each approach		Vehicles per hour on major street (total of both approaches)				Vehicles per hour on higher-volume minor-street approach (one direction only)			
Major Street	Minor Street	100% <sup>a</sup>	80% <sup>b</sup>	70% <sup>c</sup>	56% <sup>d</sup>	100% <sup>a</sup>	80% <sup>b</sup>	70% <sup>c</sup>	56% <sup>d</sup>
1 .....	1 .....	750	600	525	420	75	60	53	42
2 or more	1 .....	900	720	630	504	75	60	53	42
2 or more	2 or more	900	720	630	504	100	80	70	56
1 .....	2 or more	750	600	525	420	100	80	70	56

- <sup>a</sup> Basic minimum hourly volume.
- <sup>b</sup> Used for combination of Conditions A and B after adequate trial of other remedial measures.
- <sup>c</sup> May be used when the major-street speed exceeds 70 km/h or exceeds 40 mph or in an isolated community with a population of less than 10,000.
- <sup>d</sup> May be used for combination of Conditions A and B after adequate trial of other remedial measures when the major-street speed exceeds 70 km/h or exceeds 40 mph or in an isolated community with a population of less than 10,000.

**These major-street and minor-street volumes shall be for the same 8 hours for each condition; however, the 8 hours satisfied in Condition A shall not be required to be the same 8 hours satisfied in Condition B. On the minor street, the higher volume shall not be required to be on the same approach during each of the 8 hours.**

Option:

If the posted or statutory speed limit or the 85th-percentile speed on the major street exceeds 70 km/h or exceeds 40 mph, or if the intersection lies within the built-up area of an isolated community having a population of less than 10,000, the traffic volumes in the 56 percent columns in Table 4C-1 may be used in place of the 80 percent columns.

**Section 4C.03 Warrant 2, Four-Hour Vehicular Volume**

Support:

The Four-Hour Vehicular Volume signal warrant conditions are intended to be applied where the volume of intersecting traffic is the principal reason to consider installing a traffic control signal.

**Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that, for each of any 4 hours of an average day, the plotted points representing the vehicles per hour on the major street (total of both approaches) and the corresponding vehicles per hour on the higher-volume minor-street approach (one direction only) all fall above the applicable curve in Figure 4C-1 for the existing combination of approach lanes. On the minor street, the higher volume shall not be required to be on the same approach during each of these 4 hours.**

## Option:

If the posted or statutory speed limit or the 85th-percentile speed on the major street exceeds 70 km/h or exceeds 40 mph, or if the intersection lies within the built-up area of an isolated community having a population of less than 10,000, Figure 4C-2 may be used in place of Figure 4C-1.

**Section 4C.04 Warrant 3, Peak Hour**

## Support:

The Peak Hour signal warrant is intended for use at a location where traffic conditions are such that for a minimum of 1 hour of an average day, the minor-street traffic suffers undue delay when entering or crossing the major street.

## Guidance:

A signal installed under the Peak Hour warrant should be traffic actuated. Consideration should be given to operating the signal in the flashing mode during off-peak periods.

**Standard:**

**This signal warrant shall be applied only in unusual cases, such as office complexes, manufacturing plants, industrial complexes, or high-occupancy vehicle facilities that attract or discharge large numbers of vehicles over a short time.**

**The need for a traffic control signal shall be considered if an engineering study finds that the criteria in either of the following two categories are met:**

- A. If all three of the following conditions exist for the same 1 hour (any four consecutive 15-minute periods) of an average day:**
  - 1. The total stopped time delay experienced by the traffic on one minor-street approach (one direction only) controlled by a STOP sign equals or exceeds: 4 vehicle-hours for a one-lane approach; or 5 vehicle-hours for a two-lane approach, and**
  - 2. The volume on the same minor-street approach (one direction only) equals or exceeds 100 vehicles per hour for one moving lane of traffic or 150 vehicles per hour for two moving lanes, and**
  - 3. The total entering volume serviced during the hour equals or exceeds 650 vehicles per hour for intersections with three approaches or 800 vehicles per hour for intersections with four or more approaches.**
- B. The plotted point representing the vehicles per hour on the major street (total of both approaches) and the corresponding vehicles per hour on the higher-volume minor-street approach (one direction only) for 1 hour (any four consecutive 15-minute periods) of an average day falls above the applicable curve in Figure 4C-3 for the existing combination of approach lanes.**

## Option:

If the posted or statutory speed limit or the 85th-percentile speed on the major street exceeds 70 km/h or exceeds 40 mph, or if the intersection lies within the built-up area of an isolated community having a population of less than 10,000, Figure 4C-4 may be used in place of Figure 4C-3 to satisfy the criteria in the second category of the Standard.

**Section 4C.05 Warrant 4, Pedestrian Volume****Support:**

The Pedestrian Volume signal warrant is intended for application where the traffic volume on a major street is so heavy that pedestrians experience excessive delay in crossing the major street.

**Standard:**

**The need for a traffic control signal at an intersection or midblock crossing shall be considered if an engineering study finds that both of the following criteria are met:**

- A. The pedestrian volume crossing the major street at an intersection or midblock location during an average day is 100 or more for each of any 4 hours or 190 or more during any 1 hour; and**
- B. There are fewer than 60 gaps per hour in the traffic stream of adequate length to allow pedestrians to cross during the same period when the pedestrian volume criterion is satisfied. Where there is a divided street having a median of sufficient width for pedestrians to wait, the requirement applies separately to each direction of vehicular traffic.**

**The Pedestrian Volume signal warrant shall not be applied at locations where the distance to the nearest traffic control signal along the major street is less than 90 m (300 ft), unless the proposed traffic control signal will not restrict the progressive movement of traffic.**

**If this warrant is met and a traffic control signal is justified by an engineering study, the traffic control signal shall be equipped with pedestrian signal heads conforming to requirements set forth in Chapter 4E.**

**Guidance:**

If this warrant is met and a traffic control signal is justified by an engineering study, then:

- A. If at an intersection, the traffic control signal should be traffic-actuated and should include pedestrian detectors.
- B. If at a nonintersection crossing, the traffic control signal should be pedestrian-actuated, parking and other sight obstructions should be prohibited for at least 30 m (100 ft) in advance of and at least 6.1 m (20 ft) beyond the crosswalk, and the installation should include suitable standard signs and pavement markings.
- C. Furthermore, if installed within a signal system, the traffic control signal should be coordinated.

**Option:**

The criterion for the pedestrian volume crossing the major roadway may be reduced as much as 50 percent if the average crossing speed of pedestrians is less than 1.2 m/sec (4 ft/sec).

A traffic control signal may not be needed at the study location if adjacent coordinated traffic control signals consistently provide gaps of adequate length for pedestrians to cross the street, even if the rate of gap occurrence is less than one per minute.


**Section 4C.06 Warrant 5, School Crossing****Support:**

The School Crossing signal warrant is intended for application where the fact that school children cross the major street is the principal reason to consider installing a traffic control signal.

**Standard:**


**The need for a traffic control signal shall be considered when an engineering study of the frequency and adequacy of gaps in the vehicular traffic stream as related to the number and size of groups of school children at an established school crossing across the major street shows that the number of adequate gaps in the traffic stream during the period when the children are using the**

**Figure 4C-1. Warrant 2, Four-Hour Vehicular Volume**




\*Note: 115 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 80 vph applies as the lower threshold volume for a minor-street approach with one lane.

**Figure 4C-2. Warrant 2, Four-Hour Vehicular Volume (70% Factor)**  
(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h OR ABOVE 40 mph ON MAJOR STREET)



\*Note: 80 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 60 vph applies as the lower threshold volume for a minor-street approach with one lane.


**Figure 4C-3. Warrant 3, Peak Hour**



\*Note: 150 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 100 vph applies as the lower threshold volume for a minor-street approach with one lane.

**Figure 4C-4. Warrant 3, Peak Hour (70% Factor)**

(COMMUNITY LESS THAN 10,000 POPULATION OR ABOVE 70 km/h OR ABOVE 40 mph ON MAJOR STREET)



\*Note: 100 vph applies as the lower threshold volume for a minor-street approach with two or more lanes and 75 vph applies as the lower threshold volume for a minor-street approach with one lane.

crossing is less than the number of minutes in the same period (see Section 7A.03) and there are a minimum of 20 students during the highest crossing hour.

Before a decision is made to install a traffic control signal, consideration shall be given to the implementation of other remedial measures, such as warning signs and flashers, school speed zones, school crossing guards, or a grade-separated crossing.

The School Crossing signal warrant shall not be applied at locations where the distance to the nearest traffic control signal along the major street is less than 90 m (300 ft), unless the proposed traffic control signal will not restrict the progressive movement of traffic.

Guidance:

If this warrant is met and a traffic control signal is justified by an engineering study, then:

- A. If at an intersection, the traffic control signal should be traffic-actuated and should include pedestrian detectors.
- B. If at a nonintersection crossing, the traffic control signal should be pedestrian-actuated, parking and other sight obstructions should be prohibited for at least 30 m (100 ft) in advance of and at least 6.1 m (20 ft) beyond the crosswalk, and the installation should include suitable standard signs and pavement markings.
- C. Furthermore, if installed within a signal system, the traffic control signal should be coordinated.

#### **Section 4C.07 Warrant 6, Coordinated Signal System**

Support:

Progressive movement in a coordinated signal system sometimes necessitates installing traffic control signals at intersections where they would not otherwise be needed in order to maintain proper platooning of vehicles.

**Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that one of the following criteria is met:**

- A. **On a one-way street or a street that has traffic predominantly in one direction, the adjacent traffic control signals are so far apart that they do not provide the necessary degree of vehicular platooning.**
- B. **On a two-way street, adjacent traffic control signals do not provide the necessary degree of platooning and the proposed and adjacent traffic control signals will collectively provide a progressive operation.**

Guidance:

The Coordinated Signal System signal warrant should not be applied where the resultant spacing of traffic control signals would be less than 300 m (1,000 ft).

#### **Section 4C.08 Warrant 7, Crash Experience**

Support:

The Crash Experience signal warrant conditions are intended for application where the severity and frequency of crashes are the principal reasons to consider installing a traffic control signal.

**Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that all of the following criteria are met:**

- A. **Adequate trial of alternatives with satisfactory observance and enforcement has failed to reduce the crash frequency; and**

- B. Five or more reported crashes, of types susceptible to correction by a traffic control signal, have occurred within a 12-month period, each crash involving personal injury or property damage apparently exceeding the applicable requirements for a reportable crash; and**
- C. For each of any 8 hours of an average day, the vehicles per hour (vph) given in both of the 80 percent columns of Condition A in Table 4C-1 (see Section 4C.02), or the vph in both of the 80 percent columns of Condition B in Table 4C-1 exists on the major-street and the higher-volume minor-street approach, respectively, to the intersection, or the volume of pedestrian traffic is not less than 80 percent of the requirements specified in the Pedestrian Volume warrant. These major-street and minor-street volumes shall be for the same 8 hours. On the minor street, the higher volume shall not be required to be on the same approach during each of the 8 hours.**

**Option:**

If the posted or statutory speed limit or the 85th-percentile speed on the major street exceeds 70 km/h or exceeds 40 mph, or if the intersection lies within the built-up area of an isolated community having a population of less than 10,000, the traffic volumes in the 56 percent columns in Table 4C-1 may be used in place of the 80 percent columns.

**Section 4C.09 Warrant 8, Roadway Network**

**Support:**

Installing a traffic control signal at some intersections might be justified to encourage concentration and organization of traffic flow on a roadway network.

**Standard:**

**The need for a traffic control signal shall be considered if an engineering study finds that the common intersection of two or more major routes meets one or both of the following criteria:**

- A. The intersection has a total existing, or immediately projected, entering volume of at least 1,000 vehicles per hour during the peak hour of a typical weekday and has 5-year projected traffic volumes, based on an engineering study, that meet one or more of Warrants 1, 2, and 3 during an average weekday; or**
- B. The intersection has a total existing or immediately projected entering volume of at least 1,000 vehicles per hour for each of any 5 hours of a nonnormal business day (Saturday or Sunday).**

**A major route as used in this signal warrant shall have one or more of the following characteristics:**

- A. It is part of the street or highway system that serves as the principal roadway network for through traffic flow; or**
- B. It includes rural or suburban highways outside, entering, or traversing a City; or**
- C. It appears as a major route on an official plan, such as a major street plan in an urban area traffic and transportation study.**

## CHAPTER 4D. TRAFFIC CONTROL SIGNAL FEATURES

### Section 4D.01 General

Support:

The features of traffic control signals of interest to road users are the location, design, and meaning of the signal indications. Uniformity in the design features that affect the traffic to be controlled, as set forth in this Manual, is especially important for reasonably safe and efficient traffic operations.

Pavement markings (see Part 3) that clearly communicate the operational plan of an intersection to road users play an important role in the effective operation of traffic control signals. By designating the number of lanes, the use of each lane, the length of additional lanes on the approach to an intersection, and the proper stopping points, the engineer can design the signal phasing and timing to best match the goals of the operational plan.

**Standard:**

**A traffic control signal shall control traffic only at the intersection or midblock location where the signal faces are placed.**

**STOP signs shall not be used in conjunction with any traffic control signal operation, except in either of the following cases:**

- A. If the signal indication for an approach is a flashing red at all times; or**
- B. If a minor street or driveway is located within or adjacent to the area controlled by the traffic control signal, but does not require separate traffic signal control because an extremely low potential for conflict exists.**

**When a traffic control signal is not in operation, such as before it is placed in service, during seasonal shutdowns, or when it is not desirable to operate the traffic control signal, the signal faces shall be covered, turned, or taken down to clearly indicate that the traffic control signal is not in operation.**

**Midblock crosswalks shall not be signalized if they are located within 90 m (300 ft) from the nearest traffic control signal, unless the proposed traffic control signal will not restrict the progressive movement of traffic.**

Guidance:

Midblock crosswalks should not be signalized if they are located within 30 m (100 ft) from side streets or driveways that are controlled by STOP signs or YIELD signs.

Pavement markings should be used at traffic control signal locations as provided in Part 3. If the road surface will not retain pavement markings, signs should be installed to provide the needed road user information.

Engineering judgment should be used to determine the proper phasing and timing for a traffic control signal. Since traffic flows and patterns change, phasing and timing should be reevaluated regularly and updated if needed.

### Section 4D.02 Responsibility for Operation and Maintenance

Guidance:

Prior to installing any traffic control signal, the responsibility for the maintenance of the signal and all of the appurtenances, hardware, software, and the timing plan(s) should be clearly established. The responsible agency should provide for the maintenance of the traffic control signal and all of its appurtenances in a competent manner.

To this end the agency should:

- A. Keep every controller assembly in effective operation in accordance with its predetermined timing schedule; check the operation of the controller assembly frequently enough to verify that it is operating in accordance with the predetermined timing schedule; and establish a policy to maintain a record of all timing changes and that only authorized persons are permitted to make timing changes;
- B. Clean the optical system of the signal sections and replace the light sources as frequently as experience proves necessary;
- C. Clean and service equipment and other appurtenances as frequently as experience proves necessary;
- D. Provide for alternate operation of the traffic control signal during a period of failure, using flashing mode or manual control, or manual traffic direction by proper authorities as might be required by traffic volumes or congestion, or by erecting other traffic control devices;
- E. Have properly skilled maintenance personnel available without undue delay for all emergency and lamp failure calls;
- F. Provide spare equipment to minimize the interruption of traffic control signal operation as a result of equipment failure;
- G. Provide for the availability of properly skilled maintenance personnel for the repair of all components; and
- H. Maintain the appearance of the signal displays and equipment.

### **Section 4D.03 Provisions for Pedestrians**

Support:

Chapter 4E contains additional information regarding pedestrian signals.

**Standard:**

**The design and operation of traffic control signals shall take into consideration the needs of pedestrian as well as vehicular traffic.**

**If engineering judgment indicates the need for provisions for a given pedestrian movement, signal faces conveniently visible to pedestrians shall be provided by pedestrian signal heads or a signal face for an adjacent vehicular movement.**

Guidance:

Safety considerations should include the installation, where appropriate, of accessible pedestrian signals (see Sections 4E.06 and 4E.09) that provide information in nonvisual format (such as audible tones, verbal messages, and/or vibrating surfaces).

Where pedestrian movements regularly occur, pedestrians should be provided with sufficient time to cross the roadway by adjusting the traffic control signal operation and timing to provide sufficient crossing time every cycle or by providing pedestrian detectors.

Option:

If it is desirable to prohibit certain pedestrian movements at a traffic control signal, a PEDESTRIANS PROHIBITED (R9-3) or No Pedestrian Crossing (R9-3a) sign may be used (see Section 2B.44).

### **Section 4D.04 Meaning of Vehicular Signal Indications**

Support:

The "Ohio Revised Code" is the primary source for the standards for the meaning of vehicular signal indications to both vehicle operators and pedestrians as set forth below, and the standards for the meaning of separate pedestrian signal indications as set forth in Section 4E.02.

**Standard:**

**As specified in 4511.13 and 4511.15 of the Ohio Revised Code, the following meanings shall be given to highway traffic signal indications, except those for Pedestrian Signals (see Section 4E.01) and Lane-Use Control Signals (see Section 4J.02):**

[from O.R.C. Section 4511.13]

**(A) Green indication:**

- (1) Vehicular traffic, streetcars, and trackless trolleys facing a circular green signal may proceed straight through or turn right or left unless a sign at such place prohibits either such turn. But vehicular traffic, streetcars, and trackless trolleys, including vehicles, streetcars, and trackless trolleys turning right or left, shall yield the right-of-way to other vehicles, streetcars, trackless trolleys, and pedestrians lawfully within the intersection or an adjacent crosswalk at the time such signal is exhibited.**
- (2) Vehicular traffic, streetcars, and trackless trolleys facing a green arrow signal, shown alone or in combination with another indication, may cautiously enter the intersection only to make the movement indicated by such arrow, or such other movement as is permitted by other indications shown at the same time. Such vehicular traffic, streetcars, and trackless trolleys shall yield the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.**
- (3) Unless otherwise directed by a pedestrian-control signal, as provided in section 4511.14 of the Revised Code, pedestrians facing any green signal, except when the sole green signal indication is a turn arrow, may proceed across the roadway within any marked or unmarked crosswalk.**

**(B) Steady yellow indication:**

- (1) Vehicular traffic, streetcars, and trackless trolleys facing a steady circular yellow or yellow arrow signal indication are thereby warned that the related green movement is being terminated or that a red indication will be exhibited immediately thereafter when vehicular traffic, streetcars, and trackless trolleys shall not enter the intersection.**
- (2) Pedestrians facing a steady circular yellow or yellow arrow signal, unless otherwise directed by a pedestrian-control signal as provided in section 4511.14 of the Revised Code, are thereby advised that there is insufficient time to cross the roadway before a red indication is shown and no pedestrian shall then start to cross the roadway.**

**(C) Steady red indication:**

- (1) Vehicular traffic, streetcars, and trackless trolleys facing a steady red signal alone shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or if none, then before entering the intersection and shall remain standing until an indication to proceed is shown, except as provided in divisions (C)(2) and (3) of this section.**
- (2) Unless a sign is in place prohibiting a right turn as provided in division (C)(5) of this section, vehicular traffic, streetcars, and trackless trolleys facing a steady red signal may cautiously enter the intersection to make a right turn after stopping as required by division (C)(1) of this section. Such vehicular traffic, streetcars, and trackless trolleys shall yield the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.**
- (3) Unless a sign is in place prohibiting a left turn as provided in division (C)(5) of this section, vehicular traffic, streetcars, and trackless trolleys facing a steady red signal on a one-way street that intersects another one-way street on which traffic moves to the left may cautiously enter the intersection to make a left turn into the one-way street after stopping as required by division (C)(1) of this section, and yielding the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.**
- (4) Unless otherwise directed by a pedestrian-control signal as provided in section 4511.14 of the Revised Code, pedestrians facing a steady red signal alone shall not enter the roadway.**
- (5) Local authorities may by ordinance, or the director of transportation on state highways may, prohibit a right or a left turn against a steady red signal at any intersection, which shall be effective when signs giving notice thereof are posted at the intersection. (See Section 2B.45 for further information.)**

- (D) In the event an official traffic control signal is erected and maintained at a place other than an intersection, the provisions of this section shall be applicable except as to those provisions which by their nature can have no application. Any stop required shall be made at a sign or marking on the pavement indicating where the stop shall be made, but in the absence of any such sign or marking the stop shall be made at the signal.**

[from O.R.C. Section 4511.15]

**(A) Flashing red stop signal:**

*Operators of vehicles, trackless trolleys, and streetcars shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or if none, then at the point nearest the intersecting roadway where the driver has a view of approaching traffic on the intersecting roadway before entering it, and the right to proceed shall be subject to the rules applicable after making a stop at a stop sign.*

**(B) Flashing yellow caution signal:**

*Operators of vehicles, trackless trolleys, and streetcars may proceed through the intersection or past such signal only with caution.*

**Section 4D.05 Application of Steady Signal Indications**

**Standard:**

When a traffic control signal is being operated in a steady (stop-and-go) mode, at least one lens in each signal face shall be illuminated at any given time.

A signal face(s) that controls a particular vehicular movement during any interval of a cycle shall control that same movement during all intervals of the cycle.

Steady signal indications shall be applied as follows:

**A. A steady CIRCULAR RED signal indication:**

1. Shall be displayed when it is intended to prohibit traffic, except pedestrians directed by a pedestrian signal head, from entering the intersection or other controlled area. Turning after stopping is permitted as stated in Item C.1 of Section 4D.04.
2. Shall be displayed with the appropriate GREEN ARROW signal indications when it is intended to permit traffic to make a specified turn or turns, and to prohibit traffic from proceeding straight ahead through the intersection or other controlled area, except in protected only mode turn signal faces, or in protected/permissive mode left-turn operation with separate left-turn signal faces (see Section 4D.06).

**B. A steady CIRCULAR YELLOW signal indication:**

1. Shall be displayed following a CIRCULAR GREEN or straight-through GREEN ARROW signal indication in the same signal face.
2. Shall not be displayed in conjunction with the change from the CIRCULAR RED signal indication to the CIRCULAR GREEN signal indication.
3. Shall be followed by a CIRCULAR RED signal indication except that, when entering preemption operation, the return to the previous CIRCULAR GREEN signal indication shall be permitted following a CIRCULAR YELLOW signal indication (see Section 4D.13).
4. Shall not be displayed to an approach from which drivers are turning left permissively unless one of the following conditions exists:
  - (a) A steady CIRCULAR YELLOW signal indication is also being shown simultaneously to the opposing approach;
  - (b) A separate left-turn signal face is provided and operated as described in Section 4D.06;
  - (c) An engineering study has determined that, because of unique intersection conditions, the conditions described in items (a) and (b) above cannot reasonably be implemented without causing significant operational or safety problems and that the volume of impacted left-turning traffic is relatively low, and those left-turning drivers are advised that the opposing traffic is not simultaneously being shown a CIRCULAR YELLOW signal indication if this operation occurs continuously by the installation near the left-most signal head of a W25-1 sign (see Section 2C.39) with the legend ONCOMING TRAFFIC HAS EXTENDED GREEN; or
  - (d) Drivers are advised of the operation if it occurs only occasionally, such as during a preemption sequence or because of the skipping of actuated phases, by the installation

near the left-most signal head of a W25-2 sign (see Section 2C.39) with the legend  
**ONCOMING TRAFFIC MAY HAVE EXTENDED GREEN.**

- C. A steady **CIRCULAR GREEN** signal indication shall be displayed only when it is intended to permit traffic to proceed in any direction that is lawful and practical.
- D. A steady **YELLOW ARROW** signal indication:
  - 1. Shall be displayed in the same direction as a **GREEN ARROW** signal indication following a **GREEN ARROW** signal indication in the same signal face, unless:
    - (a) The **GREEN ARROW** signal indication and a **CIRCULAR GREEN** (or straight-through **GREEN ARROW**) signal indication terminate simultaneously in the same signal face, or
    - (b) The green arrow is a straight-through **GREEN ARROW**.
  - 2. Shall not be displayed when any conflicting vehicular movement has a green or yellow signal indication or any conflicting pedestrian movement has a **WALKING PERSON** (symbolizing **WALK**) or flashing **UPRAISED HAND** (symbolizing **DONT WALK**) signal indication (see Section 4D.09).
  - 3. Shall be terminated by a **CIRCULAR RED** signal indication except:
    - (a) When entering preemption operation, the return to the previous **GREEN ARROW** signal indication shall be permitted following a **YELLOW ARROW** signal indication.
    - (b) When the movement controlled by the arrow is to continue on a permissive mode basis during an immediately following **CIRCULAR GREEN** signal indication.
- E. A steady **GREEN ARROW** signal indication:
  - 1. Shall be displayed only to allow vehicular movements, in the direction indicated, that are not in conflict with other vehicles moving on a green or yellow signal indication or with pedestrians crossing in conformance with a **WALKING PERSON** (symbolizing **WALK**) or flashing **UPRAISED HAND** (symbolizing **DONT WALK**) signal indication (see Section 4D.09).
  - 2. Shall be displayed on a signal face that controls a left-turn movement when said movement is not in conflict with other vehicles moving on a green or yellow signal indication or with pedestrians crossing in conformance with a **WALKING PERSON** (symbolizing **WALK**) or flashing **UPRAISED HAND** (symbolizing **DONT WALK**) signal indication (see Section 4D.09).
  - 3. Shall not be required on the stem of T-intersections or for turns from one-way streets.

Option:

Steady **YELLOW ARROW** and **GREEN ARROW** signal indications, if not otherwise prohibited, may be used instead of the corresponding circular signal indications at the following locations:

- A. On an approach intersecting a one-way street;
- B. Where certain movements are prohibited; and
- C. Where certain movements are physically impossible.

If U-turns are permitted from the approach and if drivers making a right turn from the conflicting approach to the left are simultaneously being shown a right-turn **GREEN ARROW** signal indication, drivers making a U-turn may be advised of the operation by the installation near the left-turn signal face of a **U-TURN YIELD TO RIGHT TURN (R10-16)** sign (see Section 2B.45).

#### **Section 4D.06 Application of Steady Signal Indications for Left Turns**

Support:

Left-turning traffic is controlled by one of four modes as follows:

- A. Permissive Only Mode—turns made on the **CIRCULAR GREEN** signal indication after yielding to oncoming traffic and pedestrians;
- B. Protected Only Mode—turns made only when the left-turn **GREEN ARROW** signal indication is displayed;
- C. Protected/Permissive Mode—both modes occur on an approach during the same cycle; or

- D. Variable Left-Turn Mode—the operating mode changes among the protected only mode and/or the protected/permissive mode and/or the permissive only mode during different periods of the day.

Option:

In areas having a high percentage of elderly drivers, special consideration may be given to the use of protected only mode left-turn phasing, when appropriate.

**Standard:**

The required left-turn signal faces and operation for an approach shall be determined by the selected mode of left-turn operation, as follows:

- A. **Permissive Only Mode**—The signal indications for permissive only mode left turns shall be provided by the signal faces controlling the through movement, or by a permissive-only left-turn signal face that is either a shared signal face or a separate signal face. A permissive-only shared signal face, regardless of where the permissive-only left-turn signal face is positioned and regardless of how many adjacent through signal faces are provided, shall always simultaneously display the same color of circular indication that the adjacent through signal face or faces display. A separate permissive-only left-turn signal face sometimes displays a different color of circular signal indication than the adjacent through signal faces display.
- If a separate left-turn signal face is provided for permissive only left turns, it shall meet the following requirements:
1. During the permissive left-turn movement, the left-turn signal face shall display a CIRCULAR GREEN signal indication.
  2. If the CIRCULAR GREEN and CIRCULAR YELLOW signal indications in the left-turn signal face are visibility-limited from the adjacent through movement, the left-turn signal face shall not be required to simultaneously display the same color of circular signal indication as the signal faces for the adjacent through movement.
  3. If the CIRCULAR GREEN and CIRCULAR YELLOW signal indications in the left-turn signal face are visibility-limited from the adjacent through movement, the display of a CIRCULAR GREEN signal indication for a permissive left-turn movement while the signal faces for the adjacent through movement display CIRCULAR RED signal indications and the opposing left-turn signal faces display left-turn GREEN ARROW signal indications for a protected left-turn movement shall be permitted.
  4. If the left-turn signal face does not simultaneously display the same color of circular signal indication as the signal faces for the adjacent through movement, a LEFT TURN YIELD ON GREEN (symbolic green ball) (R10-12) sign or a LEFT TURN SIGNAL—YIELD ON GREEN (symbolic green ball) (R10-21) sign (see Figure 2B-19) shall be used.
- B. **Protected Only Mode**—The left-turn signal face shall be capable of displaying one of the following sets of signal indications:
1. CIRCULAR RED, left-turn YELLOW ARROW, and left-turn GREEN ARROW signal indications. At least one left-turn signal face shall be provided in addition to the two approach signal faces required in Section 4D.15 for the major movement. Only one of the three colors shall be illuminated at any given time. Unless the CIRCULAR RED signal indication is shielded, hooded, louvered, positioned, or designed such that it is not readily visible to drivers in the through lane(s), a LEFT TURN SIGNAL sign (R10-10L) shall be used.
  2. CIRCULAR RED, CIRCULAR YELLOW, CIRCULAR GREEN, and left-turn GREEN ARROW signal indications. This four-section signal face shall be used only when the CIRCULAR GREEN and left-turn GREEN ARROW signal indications begin and terminate together. During each interval, the circular signal indication shall be the same color as the signal indication on the signal face(s) for the adjacent through traffic.
- C. **Protected/Permissive Mode**—The signal indications for protected/permissive mode left turns shall be provided in either a shared signal face or a separate signal face. Any protected/permissive left-turn signal face that always simultaneously displays the same color

of circular signal indication that the adjacent through signal faces display shall be considered to be a shared signal face, regardless of where the left-turn signal face is positioned and regardless of how many adjacent through signal faces are provided. Any protected/permissive left-turn signal face that sometimes displays a different color of circular signal indication than the adjacent through signal faces display shall be considered to be a separate signal face. The requirements for each type of signal face are as follows:

1. If a shared signal face is provided, it shall be considered an approach signal face, and shall meet the following requirements:
    - (a) During the protected left-turn movement, the signal face shall simultaneously display a left-turn GREEN ARROW signal indication and a circular signal indication that is the same color as the signal indication for the adjacent through lane on the same approach as the protected left turn.  
During the protected left-turn movement, the signal faces for through traffic on the opposing approach shall simultaneously display CIRCULAR RED signal indications.
    - (b) During the permissive left-turn movement, all signal faces on the approach shall display CIRCULAR GREEN signal indications.
    - (c) All signal faces on the approach shall simultaneously display the same color of circular signal indications to both through and left-turn road users.
    - (d) A supplementary sign shall not be required. If used, it shall be a LEFT TURN YIELD ON GREEN (symbolic green ball) (R10-12) sign (see Figure 2B-19).
  2. If a separate signal face is provided, it shall be considered a left-turn signal face, and shall meet the following requirements:
    - (a) During the protected left-turn movement, the left-turn signal face shall display a left-turn GREEN ARROW signal indication.  
During the protected left-turn movement, the signal faces for through traffic on the opposing approach shall simultaneously display CIRCULAR RED signal indications.
    - (b) During the permissive left-turn movement, the left-turn signal face shall display a CIRCULAR GREEN signal indication.
    - (c) If the CIRCULAR GREEN and CIRCULAR YELLOW signal indications in the left-turn signal face are visibility-limited from the adjacent through movement, the left-turn signal face shall not be required to simultaneously display the same color of circular signal indication as the signal faces for the adjacent through movement.
    - (d) If the CIRCULAR GREEN and CIRCULAR YELLOW signal indications in the left-turn signal face are visibility-limited from the adjacent through movement, the display of a CIRCULAR GREEN signal indication for a permissive left-turn movement while the signal faces for the adjacent through movement display CIRCULAR RED signal indications and the opposing left-turn signal face displays a left-turn GREEN ARROW for a protected left-turn movement shall be permitted.
    - (e) If the left-turn signal face does not simultaneously display the same color of circular signal indication as the signal faces for the adjacent through movement, a LEFT TURN SIGNAL—YIELD ON GREEN (symbolic green ball) (R10-21) sign (see Figure 2B-19) shall be used.
- D. Variable Left-Turn Mode—If the protected only mode occurs during one or more periods of the day, and the permissive only mode or the combined protected/permissive mode occurs during other periods of the day, the requirements of Items A, B, and C in this Standard that are appropriate to that mode of operation shall be met, subject to the following:
1. The CIRCULAR GREEN and CIRCULAR YELLOW signal indications shall not be displayed when operating in the protected only mode.
  2. The left-turn GREEN ARROW and left-turn YELLOW ARROW signal indications shall not be displayed when operating in the permissive only mode.

**Option:**

Additional appropriate signal indications or changeable message signs may be used to meet the requirements for the variable left-turn mode.

**Section 4D.07 Application of Steady Signal Indications for Right Turns****Support:**

Right-turning traffic is controlled by one of four modes as follows:

- A. Permissive Only Mode—turns made on the CIRCULAR GREEN signal indication after yielding to pedestrians.
- B. Protected Only Mode—turns made only when the right-turn GREEN ARROW signal indication is displayed.
- C. Protected/Permissive Mode—both modes occur on an approach during the same cycle.
- D. Variable Right-Turn Mode—the operating mode changes among the protected only mode and/or the protected/permissive mode and/or the permissive only mode during different periods of the day.

**Standard:**

The required right-turn signal faces and operation for an approach shall be determined by the selected mode of right-turn operation, as follows:

- A. **Permissive Only Mode**—A separate signal indication or signal face for right turns shall not be required. The signal indication for permissive only mode right turns shall be the same color as the signal indication for adjacent through traffic.
- B. **Protected Only Mode**—The right-turn signal face shall be capable of displaying one of the following sets of signal indications:
  1. CIRCULAR RED, right-turn YELLOW ARROW, and right-turn GREEN ARROW signal indications. At least one right-turn signal face shall be provided in addition to the two approach signal faces required in Section 4D.15 for the major movement. Only one of three colors shall be illuminated at any given time. Unless the CIRCULAR RED signal indication is shielded, hooded, louvered, positioned, or designed such that it is not readily visible to drivers in the through lane(s), a RIGHT TURN SIGNAL sign (R10-10R) shall be used.
  2. CIRCULAR RED, CIRCULAR YELLOW, CIRCULAR GREEN, and right-turn GREEN ARROW signal indications. This four-section signal face shall be used only when the CIRCULAR GREEN and right-turn GREEN ARROW signal indications begin and terminate together. During each interval, the circular signal indication shall be the same color as the signal indication on the signal faces for the adjacent through traffic.
- C. **Protected/Permissive Mode**—A separate signal face is not required for the right turn, but, if provided, it shall be considered an approach signal face, and shall meet the following requirements:
  1. During the protected right-turn movement, the signal face shall simultaneously display:
    - (a) A right-turn GREEN ARROW signal indication, and
    - (b) A circular signal indication that is the same color as the signal indication for the adjacent through lane on the same approach as the protected right turn.
  2. During the permissive right-turn movement, all signal faces on the approach shall display a CIRCULAR GREEN signal indication.
  3. All signal faces on the approach shall simultaneously display the same color of circular signal indications to both through and right-turn road users.
- D. **Variable Right-Turn Mode**—If the protected only mode occurs during one or more periods of the day, and the permissive only mode or the combined protected/permissive mode occurs during other periods of the day, the requirements of Items A, B, and C in this Standard that are appropriate to that mode of operation shall be met subject to the following:

1. The **CIRCULAR GREEN** and **CIRCULAR YELLOW** signal indications shall not be displayed when operating in the protected only mode.
2. The **right-turn GREEN ARROW** and **right-turn YELLOW ARROW** signal indications shall not be displayed when operating in the permissive only mode.

Option:

Additional appropriate signal indications or changeable message signs may be used to meet the requirements for the variable right-turn mode.

#### **Section 4D.08 Prohibited Steady Signal Indications**

**Standard:**

The following combinations of signal indications shall not be simultaneously displayed on any one signal face:

- A. **CIRCULAR GREEN** with **CIRCULAR YELLOW**.
- B. **CIRCULAR RED** with **CIRCULAR YELLOW**.
- C. **CIRCULAR GREEN** with **CIRCULAR RED**.
- D. **Straight-through GREEN ARROW** with **CIRCULAR RED**.

The above combinations shall not be simultaneously displayed in different signal faces on any one approach unless one of the following conditions exists:

- A. One of the signal faces is a turn signal controlling a protected only mode turn, and a **LEFT (RIGHT) TURN SIGNAL** sign (R10-10) (see Sections 4D.06 and 4D.07) is mounted adjacent to each such signal face, or
- B. The signal faces are shielded, hooded, louvered, positioned, or designed so that the combination is not confusing to approaching road users.

A **RED ARROW** signal indication or a straight-through **YELLOW ARROW** signal indication shall not be displayed on any signal face, either alone or in combination with any other signal indication.

#### **Section 4D.09 Unexpected Conflicts During Green or Yellow Intervals**

**Standard:**

A steady **GREEN ARROW** or **YELLOW ARROW** signal indication shall not be displayed to vehicular movements that are in conflict with the following:

- A. Other vehicles moving on a green or yellow signal indication, except for the situation regarding U-turns described in Section 4D.05. Vehicles departing in the same direction shall not be considered in conflict if, for each turn lane with moving traffic, there is a separate departing lane, and pavement markings or raised channelization clearly indicate which departure lane to use.
- B. Pedestrians crossing in conformance with a **WALKING PERSON** (symbolizing **WALK**) or flashing **UPRAISED HAND** (symbolizing **DONT WALK**) signal indication.

Guidance:

No movement that creates an unexpected crossing of pathways of moving vehicles or pedestrians should be allowed during any green or yellow interval, except when all three of the following conditions are met:

- A. The movement involves only slight conflict, and
- B. Serious traffic delays are substantially reduced by permitting the conflicting movement, and
- C. Drivers and pedestrians subjected to the unexpected conflict are effectively warned thereof by a sign.

## **Section 4D.10 Yellow Change and Red Clearance Intervals**

### **Standard:**

A yellow signal indication shall be displayed following every CIRCULAR GREEN or GREEN ARROW signal indication.

The exclusive function of the yellow change interval shall be to warn traffic of an impending change in the right-of-way assignment.

The duration of a yellow change interval shall be predetermined.

### Guidance:

A yellow change interval should have a duration of approximately 3 to 6 seconds. The longer intervals should be reserved for use on approaches with higher speeds.

### Option:

The yellow change interval may be followed by a red clearance interval to provide additional time before conflicting traffic movements, including pedestrians, are released.

### **Standard:**

The duration of a red clearance interval shall be predetermined.

### Guidance:

A red clearance interval should have a duration not exceeding 6 seconds.

## **Section 4D.11 Application of Flashing Signal Indications**

### **Standard:**

The light source of a flashing signal indication shall be flashed continuously at a rate of not less than 50 nor more than 60 times per minute. The illuminated period of each flash shall be not less than half and not more than two-thirds of the total flash cycle.

Flashing signal indications shall comply with the requirements of other Sections of this Manual regarding shielding or positioning of conflicting signal indications, except that flashing yellow signal indications for through traffic shall not be required to be shielded or positioned to prevent visual conflict for road users in separately controlled turn lanes.

The following applications shall apply whenever a traffic control signal is operated in the flashing mode:

- A. Each approach or protected only mode turn movement that is controlled during steady mode (stop-and-go) operation shall display a signal indication during flashing operation.
- B. All signal faces that are flashed on an approach shall flash the same color, either yellow or red, except that separate signal faces for protected only mode turn movements and separate signal faces for protected/permissive left-turn movements shall be permitted to flash a CIRCULAR RED signal indication when the through signal indications are flashed yellow. Shared signal faces for protected/permissive left-turn movements shall not be permitted to flash a CIRCULAR RED signal indication when the through signal indications are flashed yellow.
- C. If a signal face includes both circular and arrow signal lenses of the color that is to be flashed, only the circular signal indication shall be flashed.

### Guidance:

When a traffic control signal is operated in the flashing mode, a flashing yellow signal indication should be used for the major street and a flashing red signal indication should be used for the other approaches unless flashing red signal indications are used on all approaches.

## **Section 4D.12 Flashing Operation of Traffic Control Signals**

### **Standard:**

Each traffic control signal shall be provided with an independent flasher mechanism that operates in compliance with Section 4D.11. The flashing operation shall not be terminated by removal or turn off of the controller unit or of the conflict monitor (malfunction management unit) or both.

When a traffic control signal is operated in the flashing mode:

- A. Flashing yellow signal indications shall not be displayed for approaches with conflicting traffic movements, except for permissive left-turn movements.
- B. At least one signal indication in each signal face on an approach shall be flashed except in the following circumstance:

A single-section signal face consisting of a continuously-illuminated GREEN ARROW signal lens that is used alone to indicate a continuous movement in the steady (stop-and-go) mode shall remain continuously illuminated when the traffic control signal is operated in the flashing mode.

A manual switch, a conflict monitor (malfunction management unit) circuit, and, if appropriate, automatic means shall be provided to initiate the flashing mode.

The transition from steady (stop-and-go) mode to flashing mode, if initiated by a conflict monitor (malfunction management unit) or by a manual switch, shall be permitted to be made at any time.

Programmed changes from steady (stop-and-go) mode to flashing mode shall be made under either of the following circumstances:

- A. At the end of the common major-street red interval (such as just prior to the start of the green in both directions on the major street), or
- B. Directly from a steady CIRCULAR GREEN or GREEN ARROW signal indication to a flashing CIRCULAR YELLOW or YELLOW ARROW signal indication, respectively.

During programmed changes, no steady green signal indication or flashing yellow signal indication shall be terminated and immediately followed by a steady red or flashing red signal indication without first displaying the steady yellow signal indication.

Changes from flashing mode to steady (stop-and-go) mode shall be made under one of the following procedures:

- A. **Yellow-red flashing mode:** Changes from flashing mode to steady (stop-and-go) mode shall be made at the beginning of the major-street green interval (when a green signal indication is shown to through traffic in both directions on the major street), or if there is no common major-street green interval, at the beginning of the green interval for the major traffic movement on the major street.
- B. **Red-red flashing mode:** Changes from flashing mode to steady (stop-and-go) mode shall be made by changing the flashing red indications to steady red indications followed by appropriate green indications to begin the steady mode cycle. These green indications shall be the beginning of the major-street green interval (when a green signal indication is shown to through traffic in both directions on the major street) or if there is no common major-street green interval, at the beginning of the green interval for the major traffic movement on the major street.

### **Guidance:**

When changing from the yellow-red flashing mode to steady (stop-and-go) mode, if there is no common major-street green interval, the provision of a steady red clearance interval for the other approaches before changing from a flashing yellow or a flashing red signal indication to a green signal indication on the major approach should be considered.

The steady red clearance interval provided during the change from red-red flashing mode to steady (stop-and-go) mode should have a duration of 6 seconds.

Support:

Section 4E.09 contains information regarding the operation of accessible pedestrian signal detector pushbutton locator tones during flashing operation.

### **Section 4D.13 Preemption and Priority Control of Traffic Control Signals**

Option:

Traffic control signals may be designed and operated to respond to certain classes of approaching vehicles by altering the normal signal timing and phasing plan(s) during the approach and passage of those vehicles. The alternative plan(s) may be as simple as extending a currently displayed green interval or as complex as replacing the entire set of signal phases and timing.

Support:

Preemption control (see definition in Section 4A.02) is typically given to trains, boats, emergency vehicles and light rail transit.

Examples of preemption control include the following:

- A. The prompt displaying of green signal indications at signalized locations ahead of fire vehicles, law enforcement vehicles, ambulances, and other official emergency vehicles;
- B. A special sequence of signal phases and timing to provide additional clearance time for vehicles to clear the tracks prior to the arrival of a train; and
- C. A special sequence of signal phases to display a red indication to prohibit turning movements towards the tracks during the approach or passage of a train or transit vehicle.

Priority control (see definition in Section 4A.02) is typically given to certain nonemergency vehicles such as buses and light-rail vehicles.

Examples of priority control include the following:

- A. The displaying of early or extended green signal indications at an intersection to assist public transit vehicles in remaining on schedule; and
- B. Special phasing to assist public transit vehicles in entering the travel stream ahead of the platoon of traffic.

Some types or classes of vehicles supersede others when a traffic control signal responds to more than one type or class. In general, a vehicle that is more difficult to control supersedes a vehicle that is easier to control. Typically, the order of priority is: train, boat, heavy vehicle (fire vehicle, emergency medical service), light vehicle (law enforcement), light rail transit, rubber-tired transit.

**Standard:**

**During the transition into preemption control:**

- A. **The yellow change interval, and any red clearance interval that follows, shall not be shortened or omitted.**
- B. **The shortening or omission of any pedestrian walk interval and/or pedestrian change interval shall be permitted.**
- C. **The return to the previous steady green signal indication shall be permitted following a steady yellow signal indication in the same signal face, omitting the red clearance interval, if any.**

**During preemption control and during the transition out of preemption control:**

- A. **The shortening or omission of any yellow change interval, and of any red clearance interval that follows, shall not be permitted.**
- B. **A signal indication sequence from a steady yellow signal indication to a steady green signal indication shall not be permitted.**

**During priority control and during the transition into or out of priority control:**

- A. The shortening or omission of any yellow change interval, and of any red clearance interval that follows, shall not be permitted.**
- B. The shortening of any pedestrian walk interval below that time described in Section 4E.10 shall not be permitted.**
- C. The omission of a pedestrian walk interval and its associated change interval shall not be permitted unless the associated vehicular phase is also omitted or the pedestrian phase is exclusive.**
- D. The shortening or omission of any pedestrian change interval shall not be permitted.**
- E. A signal indication sequence from a steady yellow signal indication to a steady green signal indication shall not be permitted.**

**Guidance:**

When a traffic control signal that is returning to a steady mode from a dark mode (typically upon restoration from a power failure) receives a preemption or priority request, care should be exercised to minimize the possibility of vehicles or pedestrians being misdirected into a conflict with the vehicle making the request.

If a traffic control signal is installed near or within a highway-railroad grade crossing or if a highway-railroad grade crossing with active traffic control devices is within or near a signalized highway intersection, Chapter 8D should be consulted.

Traffic control signals operating under preemption control or under priority control should be operated in a manner designed to keep traffic moving.

Traffic control signals that are designed to respond under preemption or priority control to more than one type or class of vehicle should be designed to respond in the relative order of importance or difficulty in stopping the type or class of vehicle.

**Option:**

During the change from a dark mode to a steady mode under a preemption or priority request, the display of signal indications that could misdirect road users may be prevented by the following:

- A. Having the traffic control signal remain in the dark mode;
- B. Having the traffic control signal remain in the flashing mode;
- C. Altering the flashing mode;
- D. Executing the normal start-up routine before responding; and
- E. Responding directly to initial or dwell period.

A distinctive indication may be provided at the intersection to show that an emergency vehicle has been given control of the traffic control signal.

Preemption or priority control of traffic control signals may also be a means of assigning priority right-of-way to specified classes of vehicles at certain nonintersection locations such as on approaches to one-lane bridges and tunnels, movable bridges, highway maintenance and construction activities, metered freeway entrance ramps, and transit operations.

**Section 4D.14 Coordination of Traffic Control Signals****Guidance:**

Traffic control signals within 800 m (0.5 mi) of one another along a major route or in a network of intersecting major routes should be coordinated, preferably with interconnected controller units. However, signal coordination need not be maintained across boundaries between signal systems that operate on different cycle lengths.

**Support:**

For coordination with railroad-highway grade crossing signals, see Sections 4D.13 and 8D.07.

### **Section 4D.15 Size, Number, and Location of Signal Faces by Approach**

#### **Support:**

Sections 4D.05, and 4D.16 through 4D.18 contain additional information regarding the design of signal faces.

#### **Standard:**

**There shall be two nominal diameter sizes for vehicular signal lenses: 200 mm (8 in) and 300 mm (12 in).**

**Three-hundred millimeter (12 in) signal lenses shall be used:**

- A. For signal indications for approaches (see definition in Section 4A.02) where road users view both traffic control and lane-use control signal heads simultaneously;**
- B. If the nearest signal face is between 35 m (120 ft) and 45 m (150 ft) beyond the stop line, unless a supplemental near-side signal face is provided;**
- C. For signal faces located more than 45 m (150 ft) from the stop line;**
- D. For approaches to all signalized locations for which the minimum sight distance in Table 4D-1 cannot be met; and**
- E. For arrow signal indications.**

**A 200 mm (8 in) signal lens for a CIRCULAR RED signal indication shall not be used in combination with a 300 mm (12 in) signal lens for a CIRCULAR GREEN signal indication or a 300 mm (12 in) signal lens for a CIRCULAR YELLOW signal indication.**

#### **Option:**

Different sizes of signal lenses may be used in the same signal face or signal head, except for the prohibitions listed in the Standards in this Section.

#### **Guidance:**

Three-hundred millimeter (12 in) signal lenses should be used for all signal indications for the following:

- A. Approaches with 85th-percentile approach speeds exceeding 60 km/h (40 mph);
- B. Approaches where a traffic control signal might be unexpected;
- C. All approaches without curbs and gutters where only post-mounted signal heads are used; and
- D. Locations where there is a significant percentage of elderly drivers.

#### **Standard:**

**The signal faces for each approach to an intersection or a midblock location shall be provided as follows:**

- A. A minimum of two signal faces shall be provided for the major movement on the approach, even if the major movement is a turning movement.**
- B. See Section 4D.06 for left-turn signal faces.**
- C. See Section 4D.07 for right-turn signal faces.**
- D. Except where the width of an intersecting roadway or other conditions make it physically impractical:**
  - 1. A signal face installed to satisfy the requirements for left-turn signal faces (see Section 4D.06) and right-turn signal faces (see Section 4D.07), and at least one and preferably both of the two signal faces required for the major movement on the approach shall be located:**
    - (a) Not less than 12 m (40 ft) beyond the stop line.**
    - (b) Not more than 55 m (180 ft) beyond the stop line unless a supplemental near side signal face is provided.**
    - (c) As near as practical to the line of the driver's normal view, if mounted over the roadway.**

2. Where the nearest signal face is located between 45 and 55 m (150 and 180 ft) beyond the stop line, engineering judgment of the conditions, including the worst-case visibility conditions, shall be used to determine if the provision of a supplemental near side signal face would be beneficial.
  3. A signal face installed to satisfy the requirements for left-turn signal faces (see Section 4D.06) and right-turn signal faces (see Section 4D.07), and at least one and preferably both of the two signal faces required for the major movement on the approach shall be located no higher than at a maximum height to the top of the signal housing mounted over a roadway of 7.8 m (25.6 ft) above the pavement (see Section 4D.17). For viewing distances between 12 m (40 ft) and 16 m (53 ft) from the stop line, the maximum mounting height to the top of the signal housing shall be as shown on Figure 4D-1. (See Section 4D.17 for additional information regarding mounting heights.)
  4. At least one and preferably both of the signal faces required by Item A in this Standard shall be located between two lines intersecting with the center of the approach at a point 3 m (10 ft) behind the stop line, one making an angle of approximately 20 degrees to the right of the center of the approach extended, and the other making an angle of approximately 20 degrees to the left of the center of the approach extended (see Figure 4D-2)
  5. If both of the signal faces required by Item A in this Standard are post-mounted, they shall both be on the far side of the intersection, one on the right and one on the left of the approach lane(s).
- E. If the minimum sight distance in Table 4D-1 cannot be met, a sign shall be installed to warn approaching traffic of the traffic control signal.
- F. Required signal faces for through traffic on any one approach shall be located not less than 2.4 m (8 ft) apart measured horizontally perpendicular to the approach between the centers of the signal faces.
- G. If more than one turn signal face is provided for a protected-mode turn and if one or both of the signal faces are located over the roadway, the signal faces shall be located not less than 2.4 m (8 ft) apart measured horizontally perpendicular to the approach between the centers of the signal faces.
- H. If supplemental signal faces are used, the following limitations shall apply:
1. Left-turn arrows shall not be used in near-right signal faces.
  2. Right-turn arrows shall not be used in far-left signal faces. A far-side median-mounted signal face shall be considered a far-left signal for this application.

Guidance:

The two signal faces required for each approach should be continuously visible to traffic approaching the traffic control signal, from a point at least the minimum sight distance indicated in Table 4D-1 in advance of and measured to the stop line. This range of continuous visibility should be provided unless precluded by a physical obstruction or unless another signalized location is within this range.

If two or more left-turn lanes are provided for a separately controlled protected only mode left-turn movement, or if a left-turn movement represents the major movement from an approach, two left-turn signal faces should be provided.

If two or more right-turn lanes are provided for a separately controlled right-turn movement, or if a right-turn movement represents the major movement from an approach, two right-turn signal faces should be provided.

Near-side signal faces should be located as near as practical to the stop line.

If a signal face controls a specific lane or lanes of an approach, its position should make it readily visible to road users making that movement.

Supplemental signal faces should be used if engineering judgment has shown that they are needed to achieve intersection visibility both in advance and immediately before the signalized location. If

**Table 4D-1. Minimum Sight Distance**

85th-Percentile Speed (km/h)	Minimum Sight Distance (meters)	85th-Percentile Speed (mph)	Minimum Sight Distance (feet)
30	50	20	175
40	65	25	215
50	85	30	270
60	110	35	325
70	140	40	390
80	165	45	460
90	195	50	540
100	220	55	625
		60	715

supplemental signal faces are used, they should be located to provide optimum visibility for the movement to be controlled.

At signalized midblock crosswalks, at least one of the signal faces should be over the traveled way for each approach.

Option:

If a sign is installed to warn approaching road users of the traffic control signal, the sign may be supplemented by a Warning Beacon (see Section 4K.03).

A Warning Beacon used in this manner may be interconnected with the traffic signal controller assembly in such a manner as to flash yellow during the period when road users passing this beacon at the legal speed for the roadway might encounter a red signal indication (or a queue resulting from the display of the red signal indication) upon arrival at the signalized location.

#### **Section 4D.16 Number and Arrangement of Signal Sections in Vehicular Traffic Control Signal Faces**

**Standard:**

**Each signal face at a signalized location shall have three, four, or five signal sections.**



**A single-section signal face shall be permitted at a traffic control signal if it consists of a continuously illuminated GREEN ARROW signal lens that is being used to indicate a continuous movement.**

**Arrows shall be pointed:**


- A. Vertically upward to indicate a straight-through movement;**
- B. Horizontally in the direction of the turn to indicate a turn at approximately or greater than a right angle; and**
- C. Upward with a slope at an angle approximately equal to that of the turn if the angle of the turn is substantially less than a right angle.**

**The signal lenses in a signal face shall be arranged in a vertical or horizontal straight line, except that in a vertical array, signal lenses of the same color may be arranged horizontally adjacent to each**

**Figure 4D-1. Maximum Mounting Height of Signal Faces Located Between 12 Meters (40 Feet) and 16 Meters (53 Feet) from Stop Line**



**Figure 4D-2. Horizontal Location of Signal Faces**



other at right angles to the basic straight line arrangement. Such clusters shall be limited to two identical signal lenses or to two or three different signal lenses of the same color.

In each signal face, all red signal lenses in vertically arranged signal faces shall be located above, and in horizontally arranged signal faces shall be located to the left, of all yellow and green signal lenses.

If a CIRCULAR YELLOW signal lens is used, it shall be located between the red signal lens or lenses and all other signal lenses.

In vertically arranged signal faces, each YELLOW ARROW signal lens shall be located immediately above the GREEN ARROW signal lens to which it applies. If a dual-arrow signal section (capable of alternating between the display of a GREEN ARROW and a YELLOW ARROW signal indication) is used, the lenses shall be in the same position relative to other lenses as are the GREEN ARROW signal lenses in a vertically arranged signal face.

In horizontally arranged signal faces, the YELLOW ARROW signal lens shall be located immediately to the left of the GREEN ARROW signal lens. If a dual-arrow signal section (capable of alternating between the display of a GREEN ARROW and a YELLOW ARROW signal indication) is used, the dual left-turn arrow signal lens shall be located immediately to the right of the CIRCULAR YELLOW signal lens, the straight-through GREEN ARROW signal lens shall be located immediately to the right of the CIRCULAR GREEN signal lens, and the dual right-turn arrow signal lens shall be located to the right of all other signal lenses.

The relative positions of signal lenses within the signal face shall be as follows:

- A. In a vertically arranged signal face from top to bottom:
  - CIRCULAR RED
  - CIRCULAR YELLOW
  - CIRCULAR GREEN
  - Straight-through GREEN ARROW
  - Left-turn YELLOW ARROW
  - Left-turn GREEN ARROW
  - Right-turn YELLOW ARROW
  - Right-turn GREEN ARROW
- B. In a horizontally arranged signal face from left to right:
  - CIRCULAR RED
  - CIRCULAR YELLOW
  - Left-turn YELLOW ARROW
  - Left-turn GREEN ARROW
  - CIRCULAR GREEN
  - Straight-through GREEN ARROW
  - Right-turn YELLOW ARROW
  - Right-turn GREEN ARROW
- C. If adjacent signal indications in a signal face are not identical, their arrangement shall follow Items A or B above, as applicable.

Option:

In a vertically arranged signal face, identical signal indications may be repeated in adjacent horizontal locations within the same signal face.

Horizontally arranged and vertically arranged signal faces may be used on the same approach provided they are separated to meet the lateral separation spacing required in Section 4D.15.

Support:

Figure 4D-3 illustrates some of the possible arrangements of signal lenses in signal faces.

## **Section 4D.17 Visibility, Shielding, and Positioning of Signal Faces**

### **Standard:**

The primary consideration in signal face placement, aiming, and adjustment shall be to optimize the visibility of signal indications to approaching traffic. Road users approaching a signalized intersection or other signalized area, such as a midblock crosswalk, shall be given a clear and unmistakable indication of their right-of-way assignment.

Section 4511.16 of the Ohio Revised Code (see Appendix B2) prohibits the display of and authorizes removal of any unauthorized sign, signal, marking or device which interferes with the effectiveness of any traffic control device.

The geometry of each intersection to be signalized, including vertical grades, horizontal curves, and obstructions as well as the lateral and vertical angles of sight toward a signal face, as determined by typical driver-eye position, shall be considered in determining the vertical, longitudinal, and lateral position of the signal face.

In cases where irregular street design necessitates placing signal faces for different street approaches with a comparatively small angle between their respective signal lenses, each signal lens shall, to the extent practical, be shielded or directed by signal visors, signal louvers, or other means so that an approaching road user can see only the signal lens(es) controlling the movements on the road user's approach.

The bottom of the signal housing and any related attachments to a vehicular signal face located over a roadway shall be at least 4.6 m (15 ft) above the pavement. The top of the signal housing of a vehicular signal face located over a roadway shall not be more than 7.8 m (25.6 ft) above the pavement.

Signal visors exceeding 300 mm (12 in) in length shall not be used on free-swinging signal heads.

The bottom of the signal housing (including brackets) of a vehicular signal face that is vertically arranged and not located over a roadway:

- A. Shall be at least 2.4 m (8 ft) but not more than 5.8 m (19 ft) above the sidewalk or, if there is no sidewalk, above the pavement grade at the center of the roadway.
- B. Shall be at least 1.4 m (4.5 ft) but not more than 5.8 m (19 ft) above the median island grade of a center median island if located on the near side of the intersection.

The bottom of the signal housing (including brackets) of a vehicular signal face that is horizontally arranged and not located over a roadway:

- A. Shall be at least 2.4 m (8 ft) but not more than 6.7 m (22 ft) above the sidewalk or, if there is no sidewalk, above the pavement grade at the center of the roadway.
- B. Shall be at least 1.4 m (4.5 ft) but not more than 6.7 m (22 ft) above the median island grade of a center median island if located on the near side of the intersection.

Signal heads mounted at less than 4.6 meters (15 feet) from the bottom of the housing and any related attachments at the side of a roadway with curbs shall have a horizontal clearance of not less than 0.6 m (2 ft) from the face of a vertical curb. If there is no curb, signal heads shall have a horizontal clearance of not less than 0.6 m (2 ft) from the edge of a shoulder.

### **Guidance:**

Signal visors should be used on signal faces to aid in directing the signal indication specifically to approaching traffic, as well as to reduce "sun phantom," which can result when external light enters the lens.

The use of signal visors, or the use of signal faces or devices that direct the light without a reduction in intensity, should be considered as an alternative to signal louvers because of the reduction in light output caused by signal louvers.

The use of a signal backplate for target value enhancement should be considered on signal faces viewed against a bright sky or bright or confusing backgrounds.

**Support:**

The use of backplates enhances the contrast between the traffic signal indications and their surroundings for both day and night conditions, which is also helpful to elderly drivers.

**Option:**

Special signal faces, such as visibility-limited signal faces, may be used such that the road user does not see signal indications intended for other approaches before seeing the signal indications for their own approach, if simultaneous viewing of both signal indications could cause the road user to be misdirected.

If the sight distance to the signal heads facing the approach is limited by horizontal or vertical alignment, supplemental signal faces aimed at a point on the approach at which the signal indications first become visible may be used.

**Section 4D.18 Design, Illumination, and Color of Signal Sections****Standard:**

**Each signal indication, except those used for pedestrian signal heads and lane-use control signals, shall be circular or arrow.**

**Letters or numbers shall not be displayed as part of a vehicular signal indication.**

**Each signal indication shall be independently illuminated.**

**Each circular signal indication shall emit a single color: red, yellow, or green.**

**Each arrow signal indication shall emit a single color: yellow or green except that the alternate display (dual-arrow signal section) of a GREEN ARROW and a YELLOW ARROW signal indication, both pointing in the same direction, shall be permitted, provided that they are not displayed simultaneously.**

**The arrow, which shall show only one direction, shall be the only illuminated part of an arrow signal indication.**

**Except for the requirements of this section, the requirements of the “Standards for Vehicle Traffic Control Signal Heads” (see Section 1A.11) shall be met.**

**References to signal lenses in this section shall not be used to limit signal optical units to incandescent lamps within optical assemblies that include lenses.**

**Support:**

Research has resulted in signal optical units that are not lenses, such as, but not limited to, light-emitting diode (LED) traffic signal modules. Some units are practical for all signal indications, and some are practical for specific types such as visibility-limited signal indications.

**Guidance:**


The intensity and distribution of light from each illuminated signal lens should conform to the current “Standards for Vehicle Traffic Control Signal Heads” and “Traffic Signal Lamps” (see Section 1A.11).

If a signal indication is operated in the flashing mode for nighttime operation and the signal indication is so bright as to cause excessive glare, some form of automatic dimming should be used to reduce the brilliance of the signal indication.

**Standard:**

**The inside of signal visors (hoods), the entire surface of louvers and fins, and the front surface of backplates shall have a dull black finish to minimize light reflection and to increase contrast between the signal indication and its background.**

**Figure 4D-3. Typical Arrangements of Signal Lenses in Signal Faces**



### **Section 4D.19 Lateral Placement of Signal Supports and Cabinets**

#### **Guidance:**

The following items should be considered when placing signal supports and cabinets:

- A. Reference should be made to the American Association of State Highway and Transportation Officials (AASHTO) "Roadside Design Guide" (see Section 1A.11) and to the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" (see Section 1A.11).
- B. Signal supports should be placed as far as practical from the edge of the traveled way without adversely affecting the visibility of the signal indications.  
Where supports cannot be located based on the recommended AASHTO clearances, consideration should be given to the use of appropriate safety devices.  
No part of a concrete base for a signal support should extend more than 100 mm (4 in) above the ground level at any point. This limitation does not apply to the concrete base for a rigid support.
- C. In order to minimize hindrance to the passage of persons with physical disabilities, a signal support or controller cabinet should not obstruct the sidewalk, or access from the sidewalk to the crosswalk.
- D. Controller cabinets should be located as far as practical from the edge of the roadway.
- E. On medians, the above minimum clearances for signal supports should be obtained if practical.

### **Section 4D.20 Temporary Traffic Control Signals**

#### **Standard:**

**A temporary traffic control signal shall be defined as a traffic control signal that is installed for a limited time period. A portable traffic control signal shall be defined as a temporary traffic control signal that is designed so that it can be easily transported and reused at different locations.**

#### **Support:**

A temporary traffic control signal is generally installed using methods that minimize the costs of installation, relocation, and/or removal. Typical temporary traffic control signals are for specific purposes, such as for one-lane, two-way facilities in temporary traffic control zones (see Chapter 4G), for a haul-road intersection, or for access to a site that will have a permanent access point developed at another location in the near future.

#### **Standard:**

**Advance signing shall be used when employing a temporary traffic control signal.**

**A temporary traffic control signal shall:**

- A. **Meet the physical display and operational requirements of a conventional traffic control signal.**
- B. **Be removed when no longer needed.**
- C. **Be placed in the flashing mode when not being used if it will be operated in the steady mode within 5 working days; otherwise, it shall be removed.**
- D. **Be placed in the flashing mode during periods when it is not desirable to operate the signal, or the signal heads shall be covered, turned, or taken down to indicate that the signal is not in operation.**

#### **Guidance:**

A temporary traffic control signal should be used only if engineering judgment indicates that installing the signal will improve the overall safety and/or operation of the location. The use of temporary traffic control signals by a work crew on a regular basis in their work area should be subject to the approval of the jurisdiction having authority over the roadway.

A temporary traffic control signal should not operate longer than 30 days unless associated with a longer-term temporary traffic control zone project.

For use of temporary traffic control signals in temporary traffic control zones, reference should be made to Section 6F.80.

#### **Section 4D.21 Traffic Signal Signs, Auxiliary**

Support:

Traffic signal signs are sometimes used at highway traffic signal locations to instruct or guide pedestrians, bicyclists, or motorists.

**Standard:**

**The minimum vertical and horizontal clearance of the total assembly of traffic signal signs (see Section 2B.45) shall conform to the provisions of Section 4D.17.**

**If used, illuminated traffic signal signs shall be designed and mounted in such a manner as to avoid glare and reflections that seriously detract from the signal indications. Traffic control signal faces shall be given dominant position and brightness to maximize their priority in the overall display.**

Guidance:

Traffic signal signs should be located adjacent to the signal face to which they apply.

## CHAPTER 4E. PEDESTRIAN CONTROL FEATURES

### Section 4E.01 Pedestrian Signal Heads

Support:

Pedestrian signal heads provide special types of traffic signal indications exclusively intended for controlling pedestrian traffic. These signal indications consist of the illuminated symbols of a WALKING PERSON (symbolizing WALK) and an UPRAISED HAND (symbolizing DONT WALK).

Guidance:

Engineering judgment should determine the need for separate pedestrian signal heads (see Section 4D.03) and accessible pedestrian signals (see Section 4E.06).

### Section 4E.02 Meaning of Pedestrian Signal Head Indications

Standard:

Divisions (A) and (B) of Section 4511.14 of the Ohio Revised code (O.R.C.) (Appendix B2) prescribe the meanings of Pedestrian Signal Indications as follows:

*Whenever special pedestrian control signals exhibiting the words “walk” or “don’t walk,” or the symbol of a walking person or an upraised palm are in place, such signals shall indicate the following instructions:*

- A. *“Walk” or the symbol of a walking person: Pedestrians facing such signal may proceed across the roadway in the direction of the signal and shall be given the right of way by the operators of all vehicles, streetcars, and trackless trolleys.*
- B. *“Don’t Walk” or the symbol of an upraised palm: No pedestrian shall start to cross the roadway in the direction of the signal.*

In addition to the meaning prescribed in the O.R.C. for a DON’T WALK indication, a flashing DON’T WALK or UPRAISED PALM symbol signal indication means that a pedestrian shall not start to cross the roadway in the direction of the signal indication, but that any pedestrian who has already started to cross on a steady WALK or WALKING PERSON symbol signal indication shall proceed out of the traveled way.

A flashing WALK or WALKING PERSON symbol signal indication has no meaning and shall not be used.

### Section 4E.03 Application of Pedestrian Signal Heads

Standard:

Pedestrian signal heads shall be used in conjunction with vehicular traffic control signals under any of the following conditions:

- A. If a traffic control signal is justified by an engineering study and meets either Warrant 4, Pedestrian Volume or Warrant 5, School Crossing (see Chapter 4C);
- B. If an exclusive signal phase is provided or made available for pedestrian movements in one or more directions, with all conflicting vehicular movements being stopped;
- C. At an established school crossing at any signalized location; and/or
- D. Where engineering judgment determines that multiphase signal indications (as with split-phase timing) would tend to confuse or cause conflicts with pedestrians using a crosswalk guided only by vehicular signal indications.

Guidance:

Pedestrian signal heads should be used under any of the following conditions:

- A. If it is necessary to assist pedestrians in making a reasonably safe crossing or if engineering judgment determines that pedestrian signal heads are justified to minimize vehicle-pedestrian conflicts;

- B. If pedestrians are permitted to cross a portion of a street, such as to or from a median of sufficient width for pedestrians to wait, during a particular interval but are not permitted to cross the remainder of the street during any part of the same interval; and/or
- C. If no vehicular signal indications are visible to pedestrians, or if the vehicular signal indications that are visible to pedestrians starting or continuing a crossing provide insufficient guidance for them to decide when it is reasonably safe to cross, such as on one-way streets, at T-intersections, or at multiphase signal operations.

#### **Section 4E.04 Size, Design, and Illumination of Pedestrian Signal Head Indications**

##### **Standard:**

All new pedestrian signal head indications shall be displayed within a rectangular background and shall consist of symbolized messages (see Figure 4E-1), except that existing pedestrian signal head indications with lettered or outline style symbol messages may be retained for the remainder of their useful service life. The symbol designs that are set forth in the “Sign Design Manual” (SDM) (see Section 1A.11) shall be used. Each pedestrian signal head indication shall be independently illuminated and emit a single color.

The UPRaised HAND (symbolizing DONT WALK) signal section shall be mounted directly above or integral with the WALKING PERSON (symbolizing WALK) signal section.

The WALKING PERSON (symbolizing WALK) signal indication shall be white, conforming to the publication entitled “Pedestrian Traffic Control Signal Indications” (see Section 1A.11), with all except the symbol obscured by an opaque material.

The UPRaised HAND (symbolizing DONT WALK) signal indication shall be Portland orange, conforming to the publication entitled “Pedestrian Traffic Control Signal Indications” (see Section 1A.11), with all except the symbol obscured by an opaque material.

When not illuminated, the WALKING PERSON (symbolizing WALK) and UPRaised HAND (symbolizing DONT WALK) symbols shall not be readily visible to pedestrians at the far end of the crosswalk that the pedestrian signal head indications control.

For pedestrian signal head indications, the symbols shall be at least 150 mm (6 in) high.

The light source of a flashing UPRaised HAND (symbolizing DONT WALK) signal indication shall be flashed continuously at a rate of not less than 50 nor more than 60 times per minute. The illuminated period of each flash shall be not less than half and not more than two-thirds of the total flash cycle.

##### **Guidance:**

Pedestrian signal head indications should be conspicuous and recognizable to pedestrians at all distances from the beginning of the controlled crosswalk to a point 3 m (10 ft) from the end of the controlled crosswalk during both day and night.

For crosswalks where the pedestrian enters the crosswalk more than 30 m (100 ft) from the pedestrian signal head indications, the symbols should be at least 225 mm (9 in) high.

##### **Option:**

An animated eyes symbol may be added to a pedestrian signal head in order to prompt pedestrians to look for vehicles in the intersection during the time that the WALK signal indication is displayed.



##### **Standard:**

If used, the animated eyes symbol shall consist of an outline of a pair of white steadily-illuminated eyes with white eyeballs that scan from side to side at a rate of approximately once per second. The animated eyes symbol shall be at least 300 mm (12 in) wide with each eye having a width of at least 125 mm (5 in) and a height of at least 62 mm (2.5 in). The animated eyes symbol shall be illuminated at the start of the walk interval and shall terminate at the end of the walk interval.

**Figure 4E-1. Typical Pedestrian Signal Indications**



**One Section**



**Two Section**

## **Section 4E.05 Location and Height of Pedestrian Signal Heads**

### **Standard:**

**Pedestrian signal heads shall be mounted with the bottom of the signal housing including brackets not less than 2.1 m (7 ft) nor more than 3 m (10 ft) above sidewalk level, and shall be positioned and adjusted to provide maximum visibility at the beginning of the controlled crosswalk.**

**If pedestrian signal heads are mounted on the same support as vehicular signal heads, there shall be a physical separation between them.**

## **Section 4E.06 Accessible Pedestrian Signals**

### **Support:**

The primary technique that pedestrians who have visual disabilities use to cross streets at signalized locations is to initiate their crossing when they hear the traffic in front of them stop and the traffic alongside them begin to move, corresponding to the onset of the green interval. This technique is effective at many signalized locations. The existing environment is often sufficient to provide the information that pedestrians who have visual disabilities need to operate reasonably safely at a signalized location. Therefore, many signalized locations will not require any accessible pedestrian signals.

### **Guidance:**

If a particular signalized location presents difficulties for pedestrians who have visual disabilities to cross reasonably safely and effectively, an engineering study should be conducted that considers the safety and effectiveness for pedestrians in general, as well as the information needs of pedestrians with visual disabilities.

### **Support:**

The factors that might make crossing at a signalized intersection difficult for pedestrians who have visual disabilities include: increasingly quiet cars, right turn on red (which masks the beginning of the through phase), continuous right-turn movements, complex signal operations, traffic circles, and wide streets. Further, low traffic volumes might make it difficult for pedestrians who have visual disabilities to discern signal phase changes.

Local organizations, providing support services to pedestrians who have visual and/or hearing disabilities, can often act as important advisors to the traffic engineer when consideration is being given to the installation of devices to assist such pedestrians. Additionally, orientation and mobility specialists or similar staff also might be able to provide a wide range of advice. The U.S. Access Board's Document A-37, "Accessible Pedestrian Signals," provides various techniques for making pedestrian signal information available to persons with visual disabilities (see Preface of this Manual for the address for the U.S. Access Board).

Accessible pedestrian signals provide information in nonvisual format (such as audible tones, verbal messages, and/or vibrating surfaces).

Information regarding detectors for accessible pedestrian signals is found in Section 4E.09.

### **Standard:**

**When used, accessible pedestrian signals shall be used in combination with pedestrian signal timing. The information provided by an accessible pedestrian signal shall clearly indicate which pedestrian crossing is served by each device.**

**Under stop-and-go operation, accessible pedestrian signals shall not be limited in operation by the time of day or day of week.**

### **Guidance:**

The installation of accessible pedestrian signals at signalized locations should be based on an engineering study, which should consider the following factors:

- A. Potential demand for accessible pedestrian signals;
- B. A request for accessible pedestrian signals;
- C. Traffic volumes during times when pedestrians might be present, including periods of low traffic volumes or high turn-on-red volumes;
- D. The complexity of traffic signal phasing; and
- E. The complexity of intersection geometry.

Support:

Technology that provides different sounds for each nonconcurrent signal phase has frequently been found to provide ambiguous information.

**Standard:**

**When choosing audible tones, possible extraneous sources of sounds (such as wind, rain, vehicle back-up warnings, or birds) shall be considered in order to eliminate potential confusion to pedestrians who have visual disabilities.**

Guidance:

Audible pedestrian tones should be carefully selected to avoid misleading pedestrians who have visual disabilities when the following conditions exist:

- A. Where there is an island that allows unsignalized right turns across a crosswalk between the island and the sidewalk.
- B. Where multileg approaches or complex signal phasing require more than two pedestrian phases, such that it might be unclear which crosswalk is served by each audible tone.
- C. At intersections where a diagonal pedestrian crossing is allowed, or where one street receives a WALKING PERSON (symbolizing WALK) signal indication simultaneously with another street.

**Standard:**

**When accessible pedestrian signals have an audible tone(s), they shall have a tone for the walk interval. The audible tone(s) shall be audible from the beginning of the associated crosswalk. If the tone for the walk interval is similar to the pushbutton locator tone, the walk interval tone shall have a faster repetition rate than the associated pushbutton locator tone.**

Support:

A pushbutton locator tone is a repeating sound that informs approaching pedestrians that they are required to push a button to actuate pedestrian timing, and that enables visually impaired pedestrians to locate the pushbutton (see Section 4E.09).

Guidance:

The accessible walk signal tone should be no louder than the locator tone, except when there is optional activation to provide a louder signal tone for a single pedestrian phase.

Automatic volume adjustment in response to ambient traffic sound level should be provided up to a maximum volume of 89 dBA. Where automatic volume adjustment is used, tones should be no more than 5 dBA louder than ambient sound. The A-weighted sound pressure level should conform to the requirements of "ISO 1996-1:1982" and "ISO 1996-2:1987" (see the Preface of this Manual for the address for the International Organization for Standards).

**Standard:**

**When verbal messages are used to communicate the pedestrian interval, they shall provide a clear message that the walk interval is in effect, as well as to which crossing it applies.**

**The verbal message that is provided at regular intervals throughout the timing of the walk interval shall be the term "walk sign," which may be followed by the name of the street to be crossed.**

**A verbal message is not required at times when the walk interval is not timing, but, if provided:**

- A. It shall be the term "wait."

**B. It need not be repeated for the entire time that the walk interval is not timing.**

Option:

Accessible pedestrian signals that provide verbal messages may provide similar messages in languages other than English, if needed, except for the terms “walk sign” and “wait.”

Support:

A vibrotactile pedestrian device communicates information about pedestrian timing through a vibrating surface by touch.

**Standard:**

**Vibrotactile pedestrian devices, where used, shall indicate that the walk interval is in effect, and for which direction it applies, through the use of a vibrating directional arrow or some other means.**

Guidance:

When provided, vibrotactile pedestrian devices should be located next to, and on the same pole as, the pedestrian pushbutton, if any, and adjacent to the intended crosswalk.

**Section 4E.07 Countdown Pedestrian Signals**

Option:

A pedestrian interval countdown display may be added to a pedestrian signal head in order to inform pedestrians of the number of seconds remaining in the pedestrian change interval.

**Standard:**

**If used, countdown pedestrian signals shall consist of Portland orange numbers that are at least 150 mm (6 in) in height on a black opaque background. The countdown pedestrian signal shall be located immediately adjacent to the associated UPRAISED HAND (symbolizing DONT WALK) pedestrian signal head indication.**

**If used, the display of the number of remaining seconds shall begin only at the beginning of the pedestrian change interval. After the countdown displays zero, the display shall remain dark until the beginning of the next countdown.**

**If used, the countdown pedestrian signal shall display the number of seconds remaining until the termination of the pedestrian change interval. Countdown displays shall not be used during the walk interval nor during the yellow change interval of a concurrent vehicular phase.**

Guidance:

If used with a pedestrian signal head that does not have a concurrent vehicular phase, the pedestrian change interval (flashing UPRAISED HAND) should be set to be approximately 4 seconds less than the required pedestrian crossing time (see Section 4E.10) and an additional clearance interval (during which steady UPRAISED HAND is displayed) should be provided prior to the start of the conflicting vehicular phase. In this case, the countdown display of the number of remaining seconds should be displayed only during the display of the flashing UPRAISED HAND, should display zero at the time when the flashing UPRAISED HAND changes to steady UPRAISED HAND, and should be dark during the additional clearance interval prior to the conflicting vehicular phase.

For crosswalks where the pedestrian enters the crosswalk more than 30 m (100 ft) from the countdown pedestrian signal display, the numbers should be at least 225 mm (9 in) in height.

Because some technology includes the countdown pedestrian signal logic in a separate timing device that is independent of the timing in the traffic signal controller, care should be exercised by the engineer when timing changes are made to pedestrian change intervals.

If the pedestrian change interval is interrupted or shortened as a part of a transition into a preemption sequence (see Section 4E.10), the countdown pedestrian signal display should be discontinued and go dark immediately upon activation of the preemption transition.

#### **Section 4E.08 Pedestrian Detectors**

Guidance:

When pedestrian actuation is used, pedestrian pushbutton detectors should be capable of easy activation and conveniently located near each end of the crosswalks.

**Standard:**

**Signs (see Section 2B.44) shall be mounted adjacent to or integral with pedestrian pushbutton detectors, explaining their purpose and use.**

Option:

At certain locations, a sign in a more visible location may be used to call attention to the pedestrian detector.

Guidance:

If two crosswalks, oriented in different directions, end at or near the same location, the positioning of pedestrian detectors and/or the legends on the pedestrian detector signs should clearly indicate which crosswalk signal is actuated by each pedestrian detector.

**Standard:**

**If the pedestrian clearance time is sufficient only to cross from the curb or shoulder to a median of sufficient width for pedestrians to wait and the signals are pedestrian actuated, an additional pedestrian detector shall be provided in the median.**

Guidance:

The use of additional pedestrian detectors on islands or medians where a pedestrian might become stranded should be considered.

A mounting height of approximately 1.1 m (3.5 ft) above the sidewalk should be used for pedestrian pushbutton detectors.

If used, special purpose pushbuttons (to be operated only by authorized persons) should include a housing capable of being locked to prevent access by the general public and do not need an instructional sign.

**Standard:**

**If used, a pilot light or other means of indication installed with a pedestrian pushbutton shall not be illuminated until actuation. Once it is actuated, it shall remain illuminated until the pedestrian's green or WALKING PERSON (symbolizing WALK) signal indication is displayed.**

Option:

At signalized locations with a demonstrated need and subject to equipment capabilities, pedestrians with special needs may be provided with additional crossing time by means of an extended pushbutton press.

#### **Section 4E.09 Accessible Pedestrian Signal Detectors**

**Standard:**

**An accessible pedestrian signal detector shall be defined as a device designated to assist the pedestrian who has visual or physical disabilities in activating the pedestrian phase.**

**At accessible pedestrian signal locations with pedestrian actuation, each pushbutton shall activate both the walk interval and the accessible pedestrian signals.**

**Option:**

Accessible pedestrian signal detectors may be pushbuttons or passive detection devices.

Pushbutton locator tones may be used with accessible pedestrian signals.

**Guidance:**

At accessible pedestrian signal locations, pushbuttons should clearly indicate which crosswalk signal is actuated by each pushbutton. Pushbuttons and tactile arrows should have high visual contrast as described in the “Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)” (see Section 1A.11). Tactile arrows should point in the same direction as the associated crosswalk. At corners of signalized locations with accessible pedestrian signals where two pedestrian pushbuttons are provided, the pushbuttons should be separated by a distance of at least 3 m (10 ft). This enables pedestrians who have visual disabilities to distinguish and locate the appropriate pushbutton.

Pushbuttons for accessible pedestrian signals should be located (see Figure 4E-2) as follows:

- A. Adjacent to a level all-weather surface to provide access from a wheelchair, and where there is an all-weather surface, wheelchair accessible route to the ramp;
- B. Within 1.5 m (5 ft) of the crosswalk extended;
- C. Within 3 m (10 ft) of the edge of the curb, shoulder, or pavement; and
- D. Parallel to the crosswalk to be used.

If the pedestrian clearance time is sufficient only to cross from the curb or shoulder to a median of sufficient width for pedestrians to wait and accessible pedestrian detectors are used, an additional accessible pedestrian detector should be provided in the median.

**Standard:**

**When used, pushbutton locator tones shall be easily locatable, shall have a duration of 0.15 seconds or less, and shall repeat at 1-second intervals.**

**Guidance:**

Pushbuttons should be audibly locatable. Pushbutton locator tones should be intensity responsive to ambient sound, and be audible 1.8 to 3.7 m (6 to 12 ft) from the pushbutton, or to the building line, whichever is less. Pushbutton locator tones should be no more than 5 dBA louder than ambient sound.

Pushbutton locator tones should be deactivated during flashing operation of the traffic control signal.

**Option:**

At locations with pretimed traffic control signals or nonactuated approaches, pedestrian pushbuttons may be used to activate the accessible pedestrian signals.

The audible tone(s) may be made louder (up to a maximum of 89 dBA) by holding down the pushbutton for a minimum of 3 seconds. The louder audible tone(s) may also alternate back and forth across the crosswalk, thus providing optimal directional information.

The name of the street to be crossed may also be provided in accessible format, such as Braille or raised print.

**Section 4E.10 Pedestrian Intervals and Signal Phases****Standard:**

**When pedestrian signal heads are used, a WALKING PERSON (symbolizing WALK) signal indication shall be displayed only when pedestrians are permitted to leave the curb or shoulder.**

**A pedestrian clearance time shall begin immediately following the WALKING PERSON (symbolizing WALK) signal indication. The first portion of the pedestrian clearance time shall consist of a pedestrian change interval during which a flashing UPRAISED HAND (symbolizing DONT WALK) signal indication shall be displayed. The remaining portions shall consist of the yellow change**

**interval and any red clearance interval (prior to a conflicting green being displayed), during which a flashing or steady UPRAISED HAND (symbolizing DONT WALK) signal indication shall be displayed.**

**If countdown pedestrian signals are used, a steady UPRAISED HAND (symbolizing DONT WALK) signal indication shall be displayed during the yellow change interval and any red clearance interval (prior to a conflicting green being displayed) (see Section 4E.07).**

**At intersections equipped with pedestrian signal heads, the pedestrian signal indications shall be displayed except when the vehicular traffic control signal is being operated in the flashing mode. At those times, the pedestrian signal lenses shall not be illuminated.**

Guidance:

Except as noted in the Option, the walk interval should be at least 7 seconds in length so that pedestrians will have adequate opportunity to leave the curb or shoulder before the pedestrian clearance time begins.

Option:

If pedestrian volumes and characteristics do not require a 7-second walk interval, walk intervals as short as 4 seconds may be used.

Support:

The walk interval itself need not equal or exceed the pedestrian clearance time calculated for the roadway width, because many pedestrians will complete their crossing during the pedestrian clearance time.

Guidance:

The pedestrian clearance time should be sufficient to allow a pedestrian crossing in the crosswalk who left the curb or shoulder during the WALKING PERSON (symbolizing WALK) signal indication to travel at a walking speed of 1.2 m (4 ft) per second, to at least the far side of the traveled way or to a median of sufficient width for pedestrians to wait. Where pedestrians who walk slower than 1.2 m (4 ft) per second, or pedestrians who use wheelchairs, routinely use the crosswalk, a walking speed of less than 1.2 m (4 ft) per second should be considered in determining the pedestrian clearance time.

Option:

Passive pedestrian detection equipment, which can detect pedestrians who need more time to complete their crossing and can extend the length of the pedestrian clearance time for that particular cycle, may be used in order to avoid using a lower walking speed to determine the pedestrian clearance time.

Guidance:

Where the pedestrian clearance time is sufficient only for crossing from the curb or shoulder to a median of sufficient width for pedestrians to wait, additional measures should be considered, such as median-mounted pedestrian signals or additional signing.



Option:

The pedestrian clearance time may be entirely contained within the vehicular green interval, or may be entirely contained within the vehicular green and yellow change intervals.

On a street with a median of sufficient width for pedestrians to wait, a pedestrian clearance time that allows the pedestrian to cross only from the curb or shoulder to the median may be provided.

During the transition into preemption, the walk interval and the pedestrian change interval may be shortened or omitted as described in Section 4D.13.

**Figure 4E-2. Recommended Pushbutton Locations for Accessible Pedestrian Signals**



## CHAPTER 4F. TRAFFIC CONTROL SIGNALS FOR EMERGENCY VEHICLE ACCESS

### Section 4F.01 Applications of Emergency-Vehicle Traffic Control Signals

#### Support:

An emergency-vehicle traffic control signal is a special traffic control signal that assigns the right-of-way to an authorized emergency vehicle.

#### Option:

An emergency-vehicle traffic control signal may be installed at a location that does not meet other traffic signal warrants such as at an intersection or other location to permit direct access from a building housing the emergency vehicle.

#### Guidance:

If a traffic control signal is not justified under the signal warrants of Chapter 4C and if gaps in traffic are not adequate to permit reasonably safe entrance of emergency vehicles, or the stopping sight distance for vehicles approaching on the major street is insufficient to permit reasonably safe entrance of emergency vehicles, installing an emergency-vehicle traffic control signal should be considered. If one of the signal warrants of Chapter 4C is met and a traffic control signal is justified by an engineering study, and if a decision is made to install a traffic control signal, it should be based upon the provisions of Chapter 4D.

The sight distance determination should be based on the location of the visibility obstruction for the critical approach lane for each street or drive and the posted or statutory speed limit or 85th-percentile speed on the major street, whichever is higher.

### Section 4F.02 Design of Emergency-Vehicle Traffic Control Signals

#### Standard:

**Except as specified in this Section, an emergency-vehicle traffic control signal shall meet the requirements of this Manual.**

**An Emergency Vehicle (W11-8) sign (see Section 2C.40) with an EMERGENCY SIGNAL AHEAD (W11-12p) supplemental plaque shall be placed in advance of all emergency-vehicle traffic control signals. If a warning beacon is installed to supplement the W11-8 sign, the design and location of the beacon shall conform to the Standards specified in Sections 4K.01 and 4K.03.**

#### Guidance:

At least one of the two required signal faces for each approach on the major street should be located over the roadway.

The following size signal lenses should be used for emergency-vehicle traffic control signals: 300 mm (12 in) diameter for red and steady yellow signal indications, and 200 mm (8 in) diameter for flashing yellow or steady green signal indications.

#### Standard:

**An EMERGENCY SIGNAL (R10-13) sign shall be mounted adjacent to a signal face on each major street approach (see Section 2B.45). If an overhead signal face is provided, the EMERGENCY SIGNAL sign shall be mounted adjacent to the overhead signal face.**

#### Option:

An approach that only serves emergency vehicles may be provided with only one signal face consisting of one or more signal sections.

Besides using a 200 mm (8 in) diameter signal indication, other appropriate means to reduce the flashing yellow light output may be used.

### **Section 4F.03 Operation of Emergency-Vehicle Traffic Control Signals**

#### **Standard:**

**Right-of-way for emergency vehicles at signalized locations operating in the steady (stop-and-go) mode shall be obtained as specified in Section 4D.13.**

**As a minimum, the signal indications, sequence, and manner of operation of an emergency-vehicle traffic control signal installed at a midblock location shall be as follows:**

- A. The signal indication, between emergency-vehicle actuations, shall be either steady green or flashing yellow. If the flashing yellow signal indication is used instead of the steady green signal indication, it shall be displayed in the normal position of the steady green signal indication, while the red and steady yellow signal indications shall be displayed in their normal positions.**
- B. When an emergency vehicle actuation occurs, a steady yellow change interval followed by a steady red interval shall be displayed to traffic on the major street.**
- C. A yellow change interval is not required following the green interval for the emergency-vehicle driveway.**

**Emergency-vehicle traffic control signals located at intersections shall either be operated in the flashing mode between emergency-vehicle actuations (see Section 4D.12) or be fully or semi-traffic-actuated, to accommodate normal vehicular and pedestrian traffic on the streets.**

**Warning beacons, if used with an emergency-vehicle traffic control signal, shall be flashed only:**

- A. For an appropriate time in advance of and during the steady yellow change interval for the major street; and**
- B. During the steady red interval for the major street.**

#### **Guidance:**

The duration of the red interval for traffic on the major street should be determined by on-site test-run time studies, but should not exceed 1.5 times the time required for the emergency vehicle to clear the path of conflicting vehicles.

#### **Option:**

An emergency-vehicle traffic control signal sequence may be initiated manually from a local control point such as a fire station or law enforcement headquarters or from an emergency vehicle equipped for remote operation of the signal.

## **CHAPTER 4G. TRAFFIC CONTROL SIGNALS FOR ONE-LANE, TWO-WAY FACILITIES**

### **Section 4G.01 Application of Traffic Control Signals for One-Lane, Two-Way Facilities**

**Support:**

A traffic control signal at a narrow bridge, tunnel, or roadway section is a special signal that assigns the right-of-way for vehicles passing over a bridge or through a tunnel or roadway section that is not of sufficient width for two opposing vehicles to pass reasonably safely.

Temporary traffic control signals (see Sections 4D.20 and 6F.80) are the most frequent application of one-lane, two-way facilities.

**Guidance:**

Sight distance across or through the one-lane, two-way facility should be considered as well as the approach speed and sight distance approaching the facility when determining whether traffic control signals should be installed.

**Option:**

At a narrow bridge, tunnel, or roadway section where a traffic control signal is not justified under the conditions of Chapter 4C, a traffic control signal may be used if gaps in opposing traffic do not permit the reasonably safe flow of traffic through the one-lane section of roadway.

### **Section 4G.02 Design of Traffic Control Signals for One-Lane, Two-Way Facilities**

**Standard:**

**The provisions of Chapter 4D shall apply to traffic control signals for one-lane, two-way facilities, except that:**

- A. Durations of red clearance intervals shall be adequate to clear the one-lane section of conflicting vehicles.**
- B. Adequate means, such as interconnection, shall be provided to prevent conflicting signal indications, such as green and green, at opposite ends of the section.**

### **Section 4G.03 Operation of Traffic Control Signals for One-Lane, Two-Way Facilities**

**Standard:**

**Traffic control signals at one-lane, two-way facilities shall operate in a manner consistent with traffic requirements.**

**When in the flashing mode, the signal indications shall flash red.**

**Guidance:**

Adequate time should be provided to allow traffic to clear the narrow facility before opposing traffic is allowed to move. Engineering judgment should be used to determine the proper timing for the signal.

Intentionally blank.

## CHAPTER 4H. TRAFFIC CONTROL SIGNALS FOR FREEWAY ENTRANCE RAMP

### Section 4H.01 Application of Freeway Entrance Ramp Control Signals

#### Support:

Ramp control signals are traffic control signals that control the flow of traffic entering the freeway facility.

Freeway entrance ramp control signals are sometimes used if controlling traffic entering the freeway could reduce the total expected delay to traffic in the freeway corridor, including freeway ramps and local streets, and if at least one of the following conditions is present:

- A. Congestion recurs on the freeway because traffic demand is in excess of the capacity, or congestion recurs or a high frequency of crashes exists at the freeway entrance because of inadequate ramp merging area. A good indicator of recurring freeway congestion is freeway operating speeds less than 80 km/h (50 mph) occurring regularly for at least a half-hour period. Freeway operating speeds less than 50 km/h (30 mph) for a half-hour period or more would indicate severe congestion.
- B. Controlling traffic entering a freeway assists in meeting local transportation system management objectives identified for freeway traffic flow, such as the following:
  - 1 Maintenance of a specific freeway level of service.
  2. Priority treatments with higher levels of service for mass transit and carpools.
  3. Redistribution of freeway access demand to other on-ramps.
- C. Predictable, sporadic congestion occurs on isolated sections of freeway because of short-period peak traffic loads from special events or from severe peak loads of recreational traffic.

#### Guidance:

The installation of ramp control signals should be preceded by an engineering study of the physical and traffic conditions on the highway facilities likely to be affected. The study should include the ramps and ramp connections and the surface streets that would be affected by the ramp control, as well as the freeway section concerned. Types of traffic data that should be obtained include, but are not limited to, traffic volumes, traffic crashes, freeway operating speeds, and travel time and delay on the freeway, approaches, ramps, and alternate surface routes.

Capacities and demand/capacity relationships should be determined for each freeway section. The locations and causes of capacity restrictions and those sections where demand exceeds capacity should be identified. From these and other data, estimates should be made of desirable metering rates, probable reductions in the delay of freeway traffic, likely increases in delay to ramp traffic, and the potential impact on surface streets. The study should include an evaluation of the ramp's storage capacities for vehicles delayed at the signal, the impact of queued traffic on the local street intersection, and the availability of suitable alternate surface routes having adequate capacity to accommodate any additional traffic volume.

Before installing ramp control signals, consideration should be given to their potential acceptance by the public and the requirements for enforcing ramp control, as well as alternate means of increasing the capacity, reducing the demand, or improving the characteristics of the freeway.

### Section 4H.02 Design of Freeway Entrance Ramp Control Signals

#### Standard:

**Ramp control signals shall meet all of the standard design specifications for traffic control signals, except as noted herein:**

- A. **The signal face for freeway entrance ramp control signals shall be either a two-lens signal face containing red and green signal lenses or a three-lens signal face containing red, yellow, and green signal lenses.**
- B. **A minimum of two signal faces per ramp shall face entering traffic.**
- C. **Ramp control signal faces need not be illuminated when not in use.**

**Ramp control signals shall be located and designed to minimize their viewing by mainline freeway traffic.**

Option:

The required signal faces, if located at the side of the ramp roadway, may be mounted such that the height above the pavement grade at the center of the ramp roadway to the bottom of the signal housing of the lowest signal face is between 1.4 m (4.5 ft) and 1.8 m (6 ft).

## **CHAPTER 4I. TRAFFIC CONTROL FOR MOVABLE BRIDGES**

### **Section 4I.01 Application of Traffic Control for Movable Bridges**

Support:

Traffic control signals for movable bridges are a special type of highway traffic signal installed at movable bridges to notify road users to stop because of a road closure rather than alternately giving the right-of-way to conflicting traffic movements. The signals are operated in coordination with the opening and closing of the movable bridge, and with the operation of movable bridge warning and resistance gates, or other devices and features used to warn, control, and stop traffic.

Movable bridge warning gates installed at movable bridges decrease the likelihood of vehicles and pedestrians passing the stop line and entering an area where potential hazards exist because of bridge operations.

A movable bridge resistance gate is sometimes used at movable bridges and located downstream of the movable bridge warning gate. A movable bridge resistance gate provides a physical deterrent to road users when placed in the appropriate position. The movable bridge resistance gates are considered a design feature and not a traffic control device; requirements for them are contained in AASHTO's "Standard Specifications for Movable Highway Bridges" (see the Preface for AASHTO's address).

**Standard:**

**Traffic control at movable bridges shall include both signals and gates, except in the following cases:**

- A. Neither is required if other traffic control devices or measures considered appropriate are used under either of the following conditions:**
  - 1. On low-volume roads (roads of less than 400 vehicles average daily traffic); or**
  - 2. At manually operated bridges if electric power is not available.**
- B. Only signals are required in urban areas if intersecting streets or driveways make gates ineffective.**
- C. Only movable bridge warning gates are required if a traffic control signal that is controlled as part of the bridge operations exists within 150 m (500 ft) of the movable bridge resistance gates and no intervening traffic entrances exist.**

### **Section 4I.02 Design and Location of Movable Bridge Signals and Gates**

**Standard:**

**The signal heads and mountings of movable bridge signals shall follow the provisions of Chapter 4D except as noted in this Section.**

**Since movable bridge operations cover a variable range of time periods between openings, the signal faces shall be one of the following types:**

- A. Three-section signal faces with red, yellow, and green signal lenses; or**
- B. Two one-section signal faces with red signal lenses in a vertical array separated by a STOP HERE ON RED (R10-6) sign (see Section 45).**

**Regardless of which signal type is selected, two signal faces shall be provided for each approach to the movable span.**

Guidance:

If movable bridge operation is frequent, the use of three-section signal faces should be considered.

**Standard:**

**If physical conditions prevent a road user from having a continuous view of at least two signal indications for the distance specified in Table 4D-1, an auxiliary device (either a supplemental signal face or the mandatory DRAWBRIDGE AHEAD (W3-6) warning sign to which has been added a**

**warning beacon that is interconnected with the movable bridge controller unit) shall be provided in advance of movable bridge signals and gates.**

**A DRAWBRIDGE AHEAD warning (W3-6) sign (see Figure 2C-4) shall be used in advance of movable bridge signals and gates to give warning to road users, except in urban conditions where such signing would not be practical.**

**Movable bridge warning gates, if used, shall extend at least across the full width of the approach lanes if movable bridge resistance gates are used. On divided highways in which the roadways are separated by a barrier median, movable bridge warning gates, if used, shall extend across all roadway lanes approaching the span openings. Except where physical conditions make it impractical, movable bridge warning gates shall be located 30 m (100 ft) or more from the movable bridge resistance gates or, if movable bridge resistance gates are not used, 30 m (100 ft) or more from the movable span.**

**Movable bridge warning gates shall be at least standard railroad size, striped with 400 mm (16 in) alternate diagonal, fully reflectorized red and white stripes. Flashing red lights in accordance with the Standards for those on railroad gates (see Section 8D.04) shall be included on the gate arm and they shall only be operated if the gate is closed or in the process of being opened or closed. In the horizontal position, the top of the gate shall be approximately 1.2 m (4 ft) above the pavement.**

**If two sets of gates (both a warning and a resistance gate) are used for a single direction, highway traffic signals need not accompany the resistance gate nearest the span opening, but there shall be flashing red lights on the movable bridge warning gate.**

Guidance:

Signal faces with 300 mm (12 in) diameter signal lenses should be used for movable bridge signals.

Insofar as practical, the height and lateral placement of signal faces should conform to the requirements for other traffic control signals in accordance with Section 4D.15. They should be located not more than 15 m (50 ft) in advance of the movable bridge warning gate.

Movable bridge warning gates should be of lightweight construction. In its normal upright position, the gate arm should provide adequate lateral clearance. If the movable bridge is close to a highway-rail grade crossing and traffic might possibly be stopped on the crossing as a result of the bridge opening, a traffic control device should notify the road users to not stop on the railroad tracks.

If movable bridge resistance gates are not used on undivided highways, movable bridge warning gates, if used, should extend across the full width of the roadway.

On bridges or causeways that cross a long reach of water and that might be hit by large marine vessels, within the limits of practicality, traffic should not be halted on a section of the bridge or causeway that is subject to impact.

In cases where it is not practical to halt traffic on a span that is not subject to impact, traffic should be halted at least one span from the opening. If traffic is halted by signals and gates more than 100 m (330 ft) from the movable bridge warning gates (or from the span opening if movable bridge warning gates are not used), a second set of gates should be installed approximately 30 m (100 ft) from the gate or span opening.

Option:

Movable bridge signals may be supplemented with audible warning devices to provide additional warning to drivers and pedestrians.

If prevailing approach speeds are 40 km/h (25 mph) or less, signal heads with 200 mm (8 in) diameter lenses may be used.

The movable bridge resistance gates may be delineated, if practical, in a manner similar to the movable bridge warning gate.

The DRAWBRIDGE AHEAD sign may be supplemented by a Warning Beacon (see Section 4K.03).

A single full-width gate or two half-width gates may be used.

Support:

Highway traffic signals need not accompany the gates nearest the span opening.

The locations of movable bridge signals and gates are determined by the location of the movable bridge resistance gate (if used) rather than by the location of the movable spans. The movable bridge resistance gates for high-speed highways are preferably located 15 m (50 ft) or more from the span opening except for bascule and lift bridges, where they are often attached to, or are a part of, the structure.

### **Section 4I.03 Operation of Movable Bridge Signals and Gates**

**Standard:**

**Traffic control devices at movable bridges shall be coordinated with the movable spans, so that the signals, gates, and movable spans are controlled by the bridge tender through an interlocked control.**

**If the three-section type of signal face is used, the green signal indication shall be illuminated at all times between bridge openings, except that if the bridge is not expected to open during continuous periods in excess of 5 hours, a flashing yellow signal indication may be used. The signal shall display a steady red signal indication when traffic is required to stop. The duration of the yellow change interval between the display of the steady green and steady red signal indications, or flashing yellow and steady red signal indications, shall be predetermined.**

**If the vertical array of red signal lenses is the type of signal face selected, the red signal lenses shall flash alternately only when traffic is required to stop.**

Guidance:

The duration of the yellow change interval should have a range from 3 to 6 seconds.

Signals on adjacent streets and highways should be interconnected with the drawbridge control if indicated by engineering judgment.

Intentionally blank.

## CHAPTER 4J. LANE-USE CONTROL SIGNALS

### Section 4J.01 Application of Lane-Use Control Signals

#### Support:

Lane-use control signals are special overhead signals that permit or prohibit the use of specific lanes of a street or highway or that indicate the impending prohibition of their use. Lane-use control signals are distinguished by placement of special signal faces over a certain lane or lanes of the roadway and by their distinctive shapes and symbols. Supplementary signs are sometimes used to explain their meaning and intent.

Lane-use control signals are most commonly used for reversible-lane control, but are also used in nonreversible freeway lane applications.

#### Guidance:

An engineering study should be conducted to determine whether a reversible-lane operation can be controlled satisfactorily by static signs (see Section 2B.25) or whether lane-use control signals are necessary. Lane-use control signals should be used to control reversible-lane operations if any of the following conditions are present:

- A. More than one lane is reversed in direction;
- B. Two-way or one-way left turns are allowed during peak-period reversible operations, but those turns are from a different lane than used during off-peak periods;
- C. Other unusual or complex operations are included in the reversible-lane pattern;
- D. Demonstrated crash experience occurring with reversible-lane operation controlled by static signs that can be corrected by using lane-use control signals at the times of transition between peak and off-peak patterns; and/or
- E. An engineering study indicates that safer and more efficient operation of a reversible-lane system would be provided by lane-use control signals.

#### Option:

Lane-use control signals also may be used for reversible-lane operations at toll booths. They may also be used if there is no intent or need to reverse lanes, including:

- A. On a freeway, if it is desired to keep traffic out of certain lanes at certain hours to facilitate the merging of traffic from a ramp or other freeway;
- B. On a freeway, near its terminus, to indicate a lane that ends; and
- C. On a freeway or long bridge, to indicate that a lane may be temporarily blocked by a crash, breakdown, construction or maintenance activities, and so forth.

### Section 4J.02 Meaning of Lane-Use Control Signal Indications


#### Standard:

The meanings of certain lane-use control signal indications are established by Section 4511.131 of the Ohio Revised Code (O.R.C.) (see Appendix B2) as follows:


*When lane-use control signals are placed over individual lanes of a street or highway, said signals shall indicate and apply to drivers of vehicles and trackless trolleys as follows:*

- A. **A steady downward green arrow: Vehicular traffic and trackless trolleys may travel in any lane over which a green arrow signal is shown. [4511.131(A), O.R.C.]**
- B. **A steady yellow "X": Vehicular traffic and trackless are warned to vacate in a safe manner any lane over which such signal is shown to avoid occupying that lane when a steady red "X" signal is shown. [4511.131(B), O.R.C.]**
- C. **A steady WHITE TWO-WAY LEFT-TURN ARROW signal indication (see Figure 4J-1) shall mean that a road user is permitted to use a lane over which the signal indication is located for a left turn, but not for through travel, with the understanding that common use of the lane by oncoming road users for left turns is also permitted.**

### Figure 4J-1. Left-Turn Lane-Use Control Signals



Two-way left-turn arrow



One-way left-turn arrow

White arrows on opaque background  
750 x 750 mm  
(30 x 30 in)

- D. A steady WHITE ONE WAY LEFT-TURN ARROW signal indication (see Figure 4J-1) shall mean that a road user is permitted to use a lane over which the signal indication is located for a left turn (without opposing turns in the same lane), but not for through travel.
- E. A steady red "X": Vehicular traffic and trackless trolleys shall not enter or travel in any lane over which such signal is shown. [4511.131(D), O.R.C.]  
This signal indication shall modify accordingly the meaning of all other traffic controls present. The road user shall obey all other traffic controls and follow normal safe driving practices.

Pavement markings (see Section 3B.03) shall be used in conjunction with reversible-lane control signals.

#### Section 4J.03 Design of Lane-Use Control Signals

##### Standard:

All lane-use control signal indications shall be in units with rectangular signal faces and shall have opaque backgrounds. Nominal minimum height and width of each DOWNWARD GREEN ARROW, YELLOW X, and RED X signal face shall be 450 mm (18 in) for typical applications. The WHITE TWO-WAY LEFT-TURN ARROW and WHITE ONE WAY LEFT-TURN ARROW signal faces shall have a nominal minimum height and width of 750 mm (30 in).

Each lane to be reversed or closed shall have signal faces with a DOWNWARD GREEN ARROW and a RED X symbol.

Each reversible lane that also operates as a two-way or one-way left-turn lane during certain periods shall have signal faces that also include the applicable WHITE TWO-WAY LEFT-TURN ARROW or WHITE ONE WAY LEFT-TURN ARROW symbol.

Each nonreversible lane immediately adjacent to a reversible lane shall have signal indications that display a DOWNWARD GREEN ARROW to traffic traveling in the permitted direction and a RED X to traffic traveling in the opposite direction.

If in separate signal sections, the relative positions, from left to right, of the signal indications shall be **RED X, YELLOW X, DOWNWARD GREEN ARROW, WHITE TWO-WAY LEFT-TURN ARROW, WHITE ONE WAY LEFT-TURN ARROW.**

The color of lane-use control signal indications shall be clearly visible for 700 m (2,300 ft) at all times under normal atmospheric conditions, unless otherwise physically obstructed.

Lane-use control signal faces shall be located approximately over the center of the lane controlled.

If the area to be controlled is more than 700 m (2,300 ft) in length, or if the vertical or horizontal alignment is curved, intermediate lane-use control signal faces shall be located over each controlled lane at frequent intervals. This location shall be such that road users will at all times be able to see at least one signal indication and preferably two along the roadway, and will have a definite indication of the lanes specifically reserved for their use.

All lane-use control signal faces shall be located in a straight line across the roadway approximately at right angles to the roadway alignment.

The bottom of the signal housing of any lane-use control signal face shall be at least 4.6 m (15 ft) but not more than 5.8 m (19 ft) above the pavement grade.

On roadways having intersections controlled by traffic control signals, the lane-use control signal face shall be located sufficiently far in advance of or beyond such traffic control signals to prevent them from being misconstrued as traffic control signals.

Option:

In areas with minimal visual clutter and with speeds of less than 70 km/h or less than 45 mph, lane-use control signal faces with nominal height and width of 300 mm (12 in) may be used for the DOWNWARD GREEN ARROW, YELLOW X, and RED X signal faces, and lane-use control signal faces with nominal height and width of 450 mm (18 in) may be used for the WHITE TWO-WAY LEFT-TURN ARROW and WHITE ONE-WAY LEFT-TURN ARROW signal faces.

Other sizes of lane-use control signal faces larger than 450 mm (18 in) with message recognition distances appropriate to signal spacing may be used for the DOWNWARD GREEN ARROW, YELLOW X, and RED X signal faces.

Nonreversible lanes not immediately adjacent to a reversible lane on any street so controlled may also be provided with signal indications that display a DOWNWARD GREEN ARROW to traffic traveling in the permitted direction and a RED X to traffic traveling in the opposite direction.

The signal indications provided for each lane may be in separate signal sections or may be superimposed in the same signal section.

#### **Section 4J.04 Operation of Lane-Use Control Signals**

**Standard:**

All lane-use control signals shall be coordinated so that all the signal indications along the controlled section of roadway are operated uniformly and consistently. The lane-use control signal system shall be designed to reliably guard against showing any prohibited combination of signal indications to any traffic at any point in the controlled lanes.

For reversible-lane control signals, the following combination of signal indications shall not be shown simultaneously over the same lane to both directions of travel:

- A. DOWNWARD GREEN ARROW in both directions;
- B. YELLOW X in both directions;
- C. WHITE ONE WAY LEFT-TURN ARROW in both directions;
- D. DOWNWARD GREEN ARROW in one direction and YELLOW X in the other direction;
- E. WHITE TWO-WAY LEFT-TURN ARROW or WHITE ONE WAY LEFT-TURN ARROW in one direction and DOWNWARD GREEN ARROW in the other direction;

- F. **WHITE TWO-WAY LEFT-TURN ARROW** in one direction and **WHITE ONE WAY LEFT-TURN ARROW** in the other direction; and
- G. **WHITE ONE WAY LEFT-TURN ARROW** in one direction and **YELLOW X** in the other direction.

A moving condition in one direction shall be terminated either by the immediate display of a **RED X** signal indication or by a **YELLOW X** signal indication followed by a **RED X** signal indication. In either case, the duration of the **RED X** signal indication shall be sufficient to allow clearance of the lane before any moving condition is allowed in the opposing direction.

Whenever a **DOWNWARD GREEN ARROW** signal indication is changed to a **WHITE TWO-WAY LEFT-TURN ARROW** signal indication, the **RED X** signal indication shall continue to be displayed to the opposite direction of travel for an appropriate duration to allow traffic time to vacate the lane being converted to a two-way left-turn lane.

If an automatic control system is used, a manual control to override the automatic control shall be provided.

Guidance:

The type of control provided for reversible-lane operation should be such as to permit either automatic or manual operation of the lane-use control signals.

**Standard:**

If used, lane-use control signals shall be operated continuously, except that lane-use control signals that are used only for special events or other infrequent occurrences and lane-use control signals on nonreversible freeway lanes may be darkened when not in operation. The change from normal operation to nonoperation shall occur only when the lane-use control signals display signal indications that are appropriate for the lane use that applies when the signals are not operated. The lane-use control signals shall display signal indications that are appropriate for the existing lane use when changed from nonoperation to normal operations. Also, traffic control devices shall clearly indicate the proper lane use when the lane control signals are not in operation.

Support:

Section 2B.25 contains additional information concerning considerations involving left-turn prohibitions in conjunction with reversible-lane operations.

## CHAPTER 4K. FLASHING BEACONS

### Section 4K.01 General Design and Operation of Flashing Beacons

Support:

A Flashing Beacon is a highway traffic signal with one or more signal sections that operates in a flashing mode. It can provide traffic control when used as an intersection control beacon or warning in alternative uses.

**Standard:**

**Flashing Beacon units and their mountings shall follow the provisions of Chapter 4D, except as specified herein.**

**Beacons shall be flashed at a rate of not less than 50 nor more than 60 times per minute. The illuminated period of each flash shall not be less than one-half and not more than two-thirds of the total cycle.**

Guidance:

If used to supplement a warning or regulatory sign, the edge of the beacon signal housing should normally be located no closer than 300 mm (12 in) outside of the nearest edge of the sign.

Option:

An automatic dimming device may be used to reduce the brilliance of flashing yellow signal indications during night operation.

### Section 4K.02 Intersection Control Beacon

**Standard:**

**An Intersection Control Beacon shall consist of one or more signal faces directed toward each approach to an intersection. Each signal face shall consist of one or more signal sections of a standard traffic signal face, with flashing CIRCULAR YELLOW or CIRCULAR RED signal indications in each signal face. They shall be installed and used only at an intersection to control two or more directions of travel.**

**Application of Intersection Control Beacon signal indications shall be limited to the following:**

- A. Yellow on one route (normally the major street) and red for the remaining approaches; and**
- B. Red for all approaches (if the warrant for a multiway stop is satisfied).**

**Flashing yellow signal indications shall not face conflicting vehicular approaches.**

**A STOP sign shall be used on approaches to which a flashing red signal indication is shown on an Intersection Control Beacon (see Section 2B.04).**

Guidance:

An Intersection Control Beacon should not be mounted on a pedestal in the roadway unless the pedestal is within the confines of a traffic or pedestrian island.

Option:

Supplemental signal indications may be used on one or more approaches in order to provide adequate visibility to approaching road users.

Intersection Control Beacons may be used at intersections where traffic or physical conditions do not justify conventional traffic control signals but crash rates indicate the possibility of a special need.

An Intersection Control Beacon is generally located over the center of an intersection; however, it may be used at other suitable locations.

### **Section 4K.03 Warning Beacon**

Support:

Typical applications of Warning Beacons include the following:

- A. At obstructions in or immediately adjacent to the roadway;
- B. As supplemental emphasis to warning signs;
- C. As emphasis for midblock crosswalks;
- D. On approaches to intersections where additional warning is required, or where special conditions exist; and
- E. As supplemental emphasis to regulatory signs, except STOP, YIELD, DO NOT ENTER, and SPEED LIMIT signs.

**Standard:**

**A Warning Beacon shall consist of one or more signal sections of a standard traffic signal face with a flashing CIRCULAR YELLOW signal indication in each signal section.**

**A Warning Beacon shall be used only to supplement an appropriate warning or regulatory sign or marker. The beacon shall not be included within the border of the sign except for SCHOOL SPEED LIMIT sign beacons.**

**Warning Beacons, if used at intersections, shall not face conflicting vehicular approaches.**

**If a Warning Beacon is suspended over the roadway, the clearance above the pavement shall be at least 4.6 m (15 ft) but not more than 5.8 m (19 ft).**

Guidance:

The condition or regulation justifying Warning Beacons should largely govern their location with respect to the roadway.

If an obstruction is in or adjacent to the roadway, illumination of the lower portion or the beginning of the obstruction or a sign on or in front of the obstruction, in addition to the beacon, should be considered.

Warning Beacons should be operated only during those hours when the condition or regulation exists.

Option:

If Warning Beacons have more than one signal section, they may be flashed either alternately or simultaneously.

A flashing yellow beacon interconnected with a traffic signal controller assembly may be used with a traffic signal warning sign (see Section 2C.29).

### **Section 4K.04 Speed Limit Sign Beacon**

**Standard:**

**A Speed Limit Sign Beacon shall be used only to supplement a Speed Limit sign.**

**A Speed Limit Sign Beacon shall consist of one or more signal sections of a standard traffic control signal face, with a flashing CIRCULAR YELLOW signal indication in each signal section. The signal lenses shall have a nominal diameter of not less than 200 mm (8 in). If two lenses are used, they shall be vertically aligned, except that they may be horizontally aligned if the Speed Limit (R2-1) sign is longer horizontally than vertically. If two lenses are used, they shall be alternately flashed.**

Option:

A Speed Limit Sign Beacon may be used with a fixed or variable Speed Limit sign. If applicable, a flashing Speed Limit Sign Beacon (with an appropriate accompanying sign) may be used to indicate that the speed limit shown is in effect.

Support:

Section 7B.11 contains additional Options for the use of Speed Limit Sign Beacons with SCHOOL SPEED LIMIT signs.

#### **Section 4K.05 Stop Beacon**

**Standard:**

**A Stop Beacon shall consist of one or more signal sections of a standard traffic signal face with a flashing CIRCULAR RED signal indication in each signal section. If two horizontally aligned signal lenses are used, they shall be flashed simultaneously to avoid being confused with a highway-rail grade crossing flashing- light signals. If two vertically aligned signal lenses are used, they shall be flashed alternately.**

**The bottom of the signal housing of a Stop Beacon shall be not less than 300 mm (12 in) nor more than 600 mm (24 in) above the top of a STOP sign (see Section 2B.04).**

Intentionally blank.

## CHAPTER 4L. IN-ROADWAY LIGHTS

### Section 4L.01 Application of In-Roadway Lights

#### Support:

In-Roadway Lights are special types of highway traffic signals installed in the roadway surface to warn road users that they are approaching a condition on or adjacent to the roadway that might not be readily apparent and might require the road users to slow down and/or come to a stop. This includes, but is not necessarily limited to, situations warning of marked school crosswalks, marked midblock crosswalks, marked crosswalks on uncontrolled approaches, marked crosswalks in advance of roundabout intersections as described in Sections 3B.24 and 3B.25, and other roadway situations involving pedestrian crossings.

#### Standard:

**If used, In-Roadway Lights shall not exceed a height of 19 mm (0.75 in) above the roadway surface.**

#### Option:

The flash rate for In-Roadway Lights may be different from the flash rate of standard beacons.

### Section 4L.02 In-Roadway Warning Lights at Crosswalks

#### Standard:

**If used, In-Roadway Warning Lights at crosswalks shall be installed only at marked crosswalks with applicable warning signs. They shall not be used at crosswalks controlled by YIELD signs, STOP signs, or traffic control signals.**

**If used, In-Roadway Warning Lights at crosswalks shall be installed along both sides of the crosswalk and shall span its entire length.**

**If used, In-Roadway Warning Lights at crosswalks shall initiate operation based on pedestrian actuation and shall cease operation at a predetermined time after the pedestrian actuation or, with passive detection, after the pedestrian clears the crosswalk.**

**If used, In-Roadway Warning Lights at crosswalks shall display a flashing yellow signal indication when actuated. The flash rate for In-Roadway Warning Lights at crosswalks shall be at least 50, but not more than 60, flash periods per minute. The flash rate shall not be between 5 and 30 flashes per second to avoid frequencies that might cause seizures.**

**If used on one-lane, one-way roadways, a minimum of two In-Roadway Warning Lights shall be installed on the approach side of the crosswalk. If used on two-lane roadways, a minimum of three In-Roadway Warning Lights shall be installed along both sides of the crosswalk. If used on roadways with more than two lanes, a minimum of one In-Roadway Warning Light per lane shall be installed along both sides of the crosswalk.**

**If used, In-Roadway Warning Lights shall be installed in the area between the outside edge of the crosswalk line and 3 m (10 ft) from the outside edge of the crosswalk. In-Roadway Warning Lights shall face away from the crosswalk if unidirectional, or shall face away from and across the crosswalk if bidirectional.**

#### Guidance:

If used, the period of operation of the In-Roadway Warning Lights following each actuation should be sufficient to allow a pedestrian crossing in the crosswalk to leave the curb or shoulder and travel at a normal walking speed of 1.2 m (4 ft) per second to at least the far side of the traveled way or to a median of sufficient width for pedestrians to wait. Where pedestrians who walk slower than normal, or pedestrians who use wheelchairs, routinely use the crosswalk, a walking speed of less than 1.2 m (4 ft) per second should be considered in determining the period of operation. Where the period of operation is sufficient only for

crossing from a curb or shoulder to a median of sufficient width for pedestrians to wait, additional measures should be considered, such as median-mounted pedestrian actuators.

If used, In-Roadway Warning Lights should be installed in the center of each travel lane, at the centerline of the roadway, at each edge of the roadway or parking lanes, or at other suitable locations away from the normal tire track paths.

The location of the In-Roadway Warning Lights within the lanes should be based on engineering judgment.

Option:

In-Roadway Warning Lights at crosswalks may use pedestrian detectors to determine the duration of the operation instead of ceasing operation after a predetermined time.

On one-way streets, In-Roadway Warning Lights may be omitted on the departure side of the crosswalk.

Based on engineering judgment, the In-Roadway Warning Lights on the departure side of the crosswalk on the left side of a median may be omitted.

Unidirectional In-Roadway Warning Lights installed at crosswalk locations may have an optional, additional yellow light indication in each unit that is visible to pedestrians in the crosswalk to indicate to pedestrians in the crosswalk that the In-Roadway Warning Lights are in fact flashing as they cross the street. These lights may flash with and at the same flash rate as the light module in which each is installed.

## PART 5. TRAFFIC CONTROL DEVICES FOR LOW-VOLUME ROADS

### TABLE OF CONTENTS

		<u>Page</u>
<b>CHAPTER 5A.</b>	<b>GENERAL</b>	
Section 5A.01	Function .....	5A-1
Section 5A.02	Application.....	5A-1
Section 5A.03	Design .....	5A-1
Section 5A.04	Placement.....	5A-2
<b>CHAPTER 5B.</b>	<b>REGULATORY SIGNS</b>	
Section 5B.01	Introduction.....	5B-1
Section 5B.02	STOP and YIELD Signs (R1-1 and R1-2).....	5B-1
Section 5B.03	Speed Limit Signs (R2 Series).....	5B-1
Section 5B.04	Traffic Movement and Prohibition Signs (R3, R4, R5, R6, R9, R10, R11, R12, R13, and R14 Series) .....	5B-1
Section 5B.05	Parking Signs (R8 Series).....	5B-2
Section 5B.06	Other Regulatory Signs.....	5B-3
<b>CHAPTER 5C.</b>	<b>WARNING SIGNS</b>	
Section 5C.01	Introduction.....	5C-1
Section 5C.02	Horizontal Alignment Signs (W1-1 through W1-8) .....	5C-1
Section 5C.03	Intersection Warning Signs (W2-1 through W2-5) .....	5C-1
Section 5C.04	Stop Ahead and Yield Ahead Signs (W3-1, W3-2).....	5C-1
Section 5C.05	NARROW BRIDGE Sign (W5-2).....	5C-1
Section 5C.06	ONE LANE BRIDGE Sign (W5-3).....	5C-1
Section 5C.07	Hill Sign (W7-1) .....	5C-2
Section 5C.08	PAVEMENT ENDS Sign (W8-3) .....	5C-2
Section 5C.09	Vehicular Traffic and Nonvehicular Signs (W11 Series and W8-6).....	5C-2
Section 5C.10	Advisory Speed Plaque (W13-1) .....	5C-2
Section 5C.11	DEAD END or NO OUTLET Signs (W14-1, W14-1a, W14-2, W14-2a) .....	5C-3
Section 5C.12	NO TRAFFIC SIGNS Sign (W18-1).....	5C-3
Section 5C.13	Other Warning Signs .....	5C-3
<b>CHAPTER 5D.</b>	<b>GUIDE SIGNS</b>	
Section 5D.01	Introduction.....	5D-1
<b>CHAPTER 5E.</b>	<b>MARKINGS</b>	
Section 5E.01	Introduction.....	5E-1
Section 5E.02	Centerline Markings .....	5E-1
Section 5E.03	Edge Line Markings.....	5E-1
Section 5E.04	Delineators .....	5E-1
Section 5E.05	Object Markers .....	5E-1
Section 5E.06	Other Markings .....	5E-2
<b>CHAPTER 5F.</b>	<b>TRAFFIC CONTROL FOR HIGHWAY-RAIL GRADE CROSSINGS</b>	
Section 5F.01	Introduction.....	5F-1
Section 5F.02	Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1, R15-2).....	5F-1
Section 5F.03	Highway-Rail Grade Crossing Advance Warning Signs (W10 Series).....	5F-1
Section 5F.04	STOP and YIELD Signs (R1-1, R1-2).....	5F-1
Section 5F.05	Pavement Markings .....	5F-2

Section 5F.06 Other Traffic Control Devices .....5F-2

**CHAPTER 5G. TEMPORARY TRAFFIC CONTROL ZONES**

Section 5G.01 Introduction..... 5G-1  
 Section 5G.02 Applications..... 5G-1  
 Section 5G.03 Channelization Devices ..... 5G-1  
 Section 5G.04 Markings ..... 5G-2  
 Section 5G.05 Other Traffic Control Devices ..... 5G-3

**FIGURES**

**CHAPTER 5B. REGULATORY SIGNS**

Figure 5B-1 Regulatory Signs on Low-Volume Roads ..... 5B-2  
 Figure 5B-2 Parking Signs on Low-Volume Roads..... 5B-3

**CHAPTER 5C. WARNING SIGNS**

Figure 5C-1 Horizontal Alignment and Intersection Warning Signs on Low-Volume Roads . 5C-4  
 Figure 5C-2 Other Warning Signs on Low-Volume Roads ..... 5C-5

**CHAPTER 5F. TRAFFIC CONTROL FOR HIGHWAY-RAIL GRADE CROSSINGS**

Figure 5F-1 Highway-Rail Grade Crossing Signs for Low-Volume Roads .....5F-2

**CHAPTER 5G. TEMPORARY TRAFFIC CONTROL ZONES**

Figure 5G-1 Temporary Traffic Control Signs on Low-Volume Roads ..... 5G-2

**TABLES**

**CHAPTER 5A. GENERAL**

Table 5A-1 Minimum Sign Sizes on Low-Volume Roads ..... 5A-3

## CHAPTER 5A. GENERAL

### **Section 5A.01 Function**

Support:

At some locations on low-volume roads, the use of traffic control devices might be needed to provide the road user limited, but essential, information regarding regulation, guidance, and warning.

Other Parts of this Manual contain criteria applicable to all low-volume roads; however, Part 5 specifically supplements and references the criteria for traffic control devices commonly used on low-volume roads.

**Standard:**

**A low-volume road shall be defined for this Part of the Manual as follows:**

- A. A low-volume road shall be a facility lying outside of built-up areas of Cities, towns, and communities, and it shall have a traffic volume of less than 400 AADT.**
- B. A low-volume road shall not be a freeway, expressway, interchange ramp, freeway service road, or a road on a designated State highway system. In terms of highway classification, it shall be a variation of a conventional road or a special purpose road as defined in Section 2A.01.**
- C. A low-volume road shall be classified as either paved or unpaved.**

Support:

Low-volume roads typically include farm-to-market, recreational, resource management and development, and local roads.

Guidance:

The needs of unfamiliar road users for occasional, recreational, and commercial transportation purposes should be considered.

### **Section 5A.02 Application**

Support:

It is possible, in many cases, to provide essential information to road users on low-volume roads with a limited number of traffic control devices. The focus might be on devices that:

- A. Warn of conditions not normally encountered;
- B. Prohibit unsafe movements; or
- C. Provide minimal destination guidance.

As with other roads, the application of traffic control devices on low-volume roads is based on engineering judgment or studies.

**Standard:**

**The criteria contained in Part 5 shall not prohibit the installation nor the full application of traffic control devices on a low-volume road where conditions justify their use.**

Guidance:

Additional traffic control devices and criteria contained in other Parts of the Manual should be considered for use on low-volume roads.

### **Section 5A.03 Design**

**Standard:**

**Traffic control devices for use on low-volume roads shall be designed in accordance with the criteria contained in Part 5, and where required, in other applicable Parts of this Manual.**

The typical sizes for signs installed on low-volume roads shall be as shown in Table 5A-1. The Minimum sign sizes shall only be used on low-volume roads where the 85th-percentile speed or posted speed limit is less than 60 km/h (35 mph).

All signs shall be retroreflective or illuminated to show the same shape and similar color both day and night, unless specifically stated otherwise in other applicable Parts of this Manual. The requirements for sign illumination shall not be considered to be satisfied by street, highway, or strobe lighting.

All markings shall be visible at night and shall be retroreflective unless ambient illumination provides adequate visibility of the markings.

**Guidance:**

Oversized sign sizes should be used where engineering judgment indicates a need based on high vehicle operating speeds, driver expectancy, traffic operations, or roadway conditions.

**Section 5A.04 Placement**

**Standard:**

The traffic control devices used on low-volume roads shall be placed and positioned in accordance with the criteria contained in Part 5 and, where necessary, in accordance with the lateral, longitudinal, and vertical placement criteria contained in Part 2 and other applicable Sections of this Manual.

**Guidance:**

The placement of warning signs should conform to the guidance contained in Section 2C.05 and other applicable Sections of this Manual.

**Option:**

A lateral offset of not less than 0.6 m (2 ft) from the roadway edge to the roadside edge of a sign may be used where roadside features such as terrain, shrubbery, and/or trees prevent lateral placement in accordance with Section 2A.19.

**Standard:**

If located within a clear zone, ground-mounted sign supports shall be yielding, breakaway, or shielded with a longitudinal barrier or crash cushion as required in Section 2A.19.

**Table 5A-1. Minimum Sign Sizes on Low-Volume Roads (Sheet 1 of 2)**

Sign	Sign Code	Section	Sign Sizes		
			Typical	Minimum	Oversized
STOP	R1-1	5B.02	750 x 750 (30 x 30)	—	900 x 900 (36 x 36)
YIELD	R1-2	5B.02	750 x 750 x 750 (30 x 30 x 30)	—	900 x 900 x 900 (36 x 36 x 36)
Speed Limit	R2-1	5B.03	600 x 750 (24 x 30)	450 x 600 (18 x 24)	900 x 1200 (36 x 48)
DO NOT PASS	R4-1	5B.04	600 x 750 (24 x 30)	450 x 600 (18 x 24)	900 x 1200 (36 x 48)
PASS WITH CARE	R4-2	5B.04	600 x 750 (24 x 30)	450 x 600 (18 x 24)	900 x 1200 (36 x 48)
Keep Right	R4-7	5B.04	600 x 750 (24 x 30)	450 x 600 (18 x 24)	900 x 1200 (36 x 48)
DO NOT ENTER	R5-1	5B.04	750 x 750 (30 x 30)	—	900 x 900 (36 x 36)
No Trucks	R5-2	5B.04	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
One Way	R6-2	5B.04	450 x 600 (18 x 24)	—	600 x 750 (24 x 30)
No Parking	R8-3	5B.05	450 x 600 (18 x 24)	—	600 x 750 (24 x 30)
No Parking (symbol)	R8-3a	5B.05	600 x 600 (24 x 24)	450 x 450 (18 x 18)	750 x 750 (30 x 30)
NO PARKING (plaque)	R8-3c, 3d	5B.05	600 x 450 (24 x 18)	450 x 300 (18 x 12)	750 x 600 (30 x 24)
ROAD CLOSED	R11-2	5B.04	1200 x 750 (48 x 30)	—	—
Road Closed, Local Traffic Only	R11-3a	5B.04	1500 x 750 (60 x 30)	—	—
Bridge Out, Local Traffic Only	R11-3b	5B.04	1500 x 750 (60 x 30)	—	—
Weight Limit	R12-1	5B.04	600 x 750 (24 x 30)	—	900 x 1200 (36 x 48)
Railroad Crossbuck	R15-1	5F.02	1200 x 225 (48 x 9)	—	—
Number of Tracks	R15.2	5F.02	675 x 450 (27 x 18)	—	—
Horizontal Alignment	W1-1, 2, 3, 4, 5	5C.02	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
One-Direction Large Arrow	W1-6	5C.02	900 x 450 (36 x 18)	—	1200 x 600 (48 x 24)
Two-Direction Large Arrow	W1-7	5C.02	900 x 450 (36 x 18)	—	1200 x 600 (48 x 24)
Chevron Alignment	W1-8	5C.02	300 x 450 (12 x 18)	—	450 x 600 (18 x 24)
Intersection Warning	W2-1, 4, 5	5C.03	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
Stop Ahead	W3-1	5C.04	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
Yield Ahead	W3-2	5C.04	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
BE PREPARED TO STOP	W3-4	5G.05	900 x 900 (36 x 36)	750 x 750 (30 x 30)	1200 x 1200 (48 x 48)

**Table 5A-1. Minimum Sign Sizes on Low-Volume Roads (Sheet 2 of 2)**

Sign	Sign Code	Section	Sign Sizes		
			Typical	Minimum	Oversized
NARROW BRIDGE	W5-2	5C.05	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
ONE LANE BRIDGE	W5-3	5C.06	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
Hill	W7-1, 1a	5C.07	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
XX % GRADE	W7-3	5C.07	600 x 450 (24 x 18)	—	750 x 600 (30 x 24)
NEXT XX MILES	W7-3a	5C.09	600 x 450 (24 x 18)	—	750 x 600 (30 x 24)
PAVEMENT ENDS	W8-3	5C.08	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
LOOSE GRAVEL	W8-7	5G.05	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
Railroad Advance Warning	W10-1	5F.03	600 Dia. (24 Dia.)	450 Dia. (18 Dia.)	750 Dia. (30 Dia.)
Crossing Warning	W10-2, 3, 4	5F.03	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
Entering / Crossing	W11 series	5C.09	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
Advisory Speed (plaque)	W13-1	5C.10	450 x 450 (18 x 18)	—	600 x 600 (24 x 24)
DEAD END / NO OUTLET	W14-1, 2	5C.11	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
DEAD END / NO OUTLET	W14-1a, 2a	5C.11	900 x 225 (36 x 9)	600 x 150 (24 x 6)	—
NO PASSING ZONE (pennant)	W14-3	5G.05	750x1000x1000 (30 x 40 x 40)	600x 900x900 (24 x 36 x 36)	900x1200x1200 (36 x 48 x 48)
Supplemental Distance (plaque)	W16-2	5C.09	600 x 450 (24 x 18)	450 x 300 (18 x 12)	750 x 600 (30 x 24)
AHEAD (plaque)	W16-9p	5C.09	600 x 300 (24 x 12)	—	750 x 450 (30 x 18)
NO TRAFFIC SIGNS	W18-1	5C.12	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
ROAD WORK XX FEET	W20-1	5G.05	900 x 900 (36 x 36)	750 x 750 (30 x 30)	1200 x 1200 (48 x 48)
Flagger	W20-7a	5G.05	900 x 900 (36 x 36)	750 x 750 (30 x 30)	1200 x 1200 (48 x 48)
Workers	W21-1a	5G.05	900 x 900 (36 x 36)	750 x 750 (30 x 30)	1200 x 1200 (48 x 48)
FRESH OIL	W21-2	5G.05	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
ROAD MACHINERY AHEAD	W21-3	5G.05	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
SHOULDER WORK	W21-5	5G.05	600 x 600 (24 x 24)	—	750 x 750 (30 x 30)
SURVEY CREW	W21-6	5G.05	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)
Construction Arrow	W1-H11	6F.44.1	750 x 750 (30 x 30)	600 x 600 (24 x 24)	900 x 900 (36 x 36)

- Notes:
1. Larger signs may be used when appropriate.
  2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height.
  3. The Minimum sign sizes shall only be used on low-volume roads where the 85th-percentile speed or posted speed limit is less than 60 km/h (35 mph).

## CHAPTER 5B. REGULATORY SIGNS

### **Section 5B.01 Introduction**

Support:

The purpose of a regulatory sign is to inform highway users of traffic laws or regulations, and to indicate the applicability of legal requirements that would not otherwise be apparent.

The criteria for regulatory signs are contained in Chapter 2B and in other Sections of this Manual. Criteria for regulatory signs that are specific to low-volume roads are contained in this Chapter.

### **Section 5B.02 STOP and YIELD Signs (R1-1 and R1-2)**

Guidance:

STOP (R1-1) and YIELD (R1-2) signs (see Figure 5B-1) should be considered for use on low-volume roads where engineering judgment or a study, consistent with the provisions of Sections 2B.04 to 2B.10, indicates that either of the following conditions applies:

- A. An intersection of a less-important road with a main road where application of the normal right-of-way rule might not be readily apparent.
- B. An intersection that has restricted sight distance for the prevailing vehicle speeds.

### **Section 5B.03 Speed Limit Signs (R2 Series)**

Standard:

**If used, Speed Limit (R2 series) signs (see Figure 5B-1) shall display the speed limit established by law, ordinance, regulation, or as adopted by the authorized agency following an engineering study. The speed limits shown shall be in multiples of 5 miles per hour.**

Speed limits shall be established in accordance with Section 2B.13.

Speed Limit signs shall be used where statutory speed limits are changed by an authorized Speed Zone except that, when the authorized Speed Zone falls within the limits of a School Zone, there should be no Speed Limit signs (except School Speed Limit signs) erected or in place within the School Zone.

Option:

Speed limit signs may be used on low-volume roads that carry traffic from, onto, or adjacent to higher-volume roads that have posted speed limits.

### **Section 5B.04 Traffic Movement and Prohibition Signs (R3, R4, R5, R6, R9, R10, R11, R12, R13, and R14 Series)**

Support:

The regulatory signs (see Figure 5B-1) in these series inform road users of required, permitted, or prohibited traffic movements involving turn, alignment, exclusion, and pedestrians.

Standard:

**If used, signs for traffic prohibitions or restrictions shall be placed in advance of the prohibition or restriction so that traffic can use an alternate route or turn around.**

Guidance:

Signs should be used on low-volume roads to indicate traffic prohibitions and restrictions such as road closures and weight restrictions.

**Figure 5B-1. Regulatory Signs on Low-Volume Roads**

R1-1



R1-2



R2-1



R4-1



R4-2



R4-7



R5-1




R5-2




R6-2



R11-2



R11-3a



R11-3b



R12-1

Option:

These signs may be useful on a low-volume road near and at the intersections or the connections with a higher class of road, and where the regulatory message is essential for reasonably safe transition from the low-volume road to the higher-class facility and vice versa.

### **Section 5B.05 Parking Signs (R8 Series)**

Option:

Parking signs (see Figure 5B-2) may be installed selectively on low-volume roads with due consideration of enforcement.

**Section 5B.06 Other Regulatory Signs**

**Standard:**

**Other regulatory signs used on low-volume roads that are not discussed in Part 5 shall conform with the criteria contained in other Parts of this Manual.**

---

***Figure 5B-2. Parking Signs on Low-Volume Roads***



R8-3



R8-3a



R8-3c  
Supplemental  
Plaque



R8-3d  
Supplemental  
Plaque

Intentionally blank.

## CHAPTER 5C. WARNING SIGNS

### Section 5C.01 Introduction

Support:

The purpose of a warning sign is to provide advance warning to the road user of unexpected conditions on or adjacent to the roadway that might not be readily apparent.

The criteria for warning signs are contained in Chapter 2C and in other Sections of this Manual. Criteria for warning signs that are specific to low-volume roads are contained in this Chapter.

### Section 5C.02 Horizontal Alignment Signs (W1-1 through W1-8)

Support:

Horizontal Alignment signs (see Figure 5C-1) include turn, curve, reverse turn, reverse curve, winding road, large arrow, and chevron alignment signs.

Option:

Horizontal Alignment signs may be used where engineering judgment indicates a need to inform the road user of a change in the horizontal alignment of the roadway.

### Section 5C.03 Intersection Warning Signs (W2-1 through W2-5)

Support:

Intersection signs (see Figure 5C-1) include the crossroad, side road, T-symbol, and Y-symbol signs.

Option:

Intersection signs may be used where engineering judgment indicates a need to inform the road user in advance of an intersection.

### Section 5C.04 Stop Ahead and Yield Ahead Signs (W3-1, W3-2)

Standard:

**A Stop Ahead (W3-1) sign (see Figure 5C-2) shall be used where a STOP sign is not visible for a sufficient distance to permit the road user to bring the vehicle to a stop at the STOP sign.**

**A Yield Ahead (W3-2) sign (see Figure 5C-2) shall be used where a YIELD sign is not visible for a sufficient distance to permit the road user to bring the vehicle to a stop, if necessary, at the YIELD sign.**

Option:

Word message (W3-1a and W3-2a) signs may be used as alternates to symbol signs.

### Section 5C.05 NARROW BRIDGE Sign (W5-2)

Option:

The NARROW BRIDGE (W5-2) sign (see Figure 5C-2) may be used on an approach to a bridge or culvert that has a clear width less than that of the approach roadway.

### Section 5C.06 ONE LANE BRIDGE Sign (W5-3)

Guidance:

A ONE LANE BRIDGE (W5-3) sign (see Figure 5C-2) should be used on low-volume two-way roadways in advance of any bridge or culvert:

- A. Having a clear roadway width of less than 4.9 m (16 ft); or

- B. Having a clear roadway width of less than 5.5 m (18 ft) when commercial vehicles constitute a high proportion of the traffic; or
- C. Having a clear roadway width of 5.5 m (18 ft) or less where the approach sight distance is limited on the approach to the structure.

Option:

Roadway alignment and additional warning may be provided on the approach to a bridge or culvert by the use of object markers and/or delineators.

### **Section 5C.07 Hill Sign (W7-1)**

Option:

An engineering study of vehicles and road characteristics, such as percent grade and length of grade, may be conducted to determine hill signing requirements.

The use of the Hill (W7-1) sign (see Figure 5C-2) on low-volume roads may be confined to roads where commercial or recreational vehicles are anticipated.

Word messages (W7-1a) may be used as alternates to symbols.

### **Section 5C.08 PAVEMENT ENDS Sign (W8-3)**

Option:

A PAVEMENT ENDS (W8-3) sign (see Figure 5C-2) may be used to warn road users where a paved surface changes to a gravel or earth road surface.

### **Section 5C.09 Vehicular Traffic and Nonvehicular Signs (W11 Series and W8-6)**

Guidance:

Vehicular Traffic signs (see Figure 5C-2) should be used to alert road users to frequent unexpected entries into the roadway by trucks, bicyclists, farm vehicles, fire trucks, and other vehicles. Such signs should be used only at locations where the road user's sight distance is restricted or the activity would be unexpected.

Option:

Nonvehicular signs (see Figure 5C-2) may be used to alert the road user to frequent unexpected entries into the roadway by pedestrian, animal, and other crossing activities that may cause potential conflicts.

A W7-3a, W16-2, or W16-9p supplemental plaque (see Figure 5C-2) with the legend NEXT XX MILES, XX FEET, or AHEAD may be installed below a Vehicular Traffic or Nonvehicular sign (see Sections 2C.40 and 2C.41).

Guidance:

If the activity is seasonal or temporary, the sign should be removed or covered when the crossing activity does not exist.

### **Section 5C.10 Advisory Speed Plaque (W13-1)**

Option:

An Advisory Speed (W13-1) plaque (see Figure 5C-1) may be mounted below a warning sign when the condition requires a reduced speed.

**Section 5C.11 DEAD END or NO OUTLET Signs (W14-1, W14-1a, W14-2, W14-2a)****Option:**

The DEAD END (W14-1) and NO OUTLET (W14-2) signs (see Figure 5C-2) and the DEAD END (W14-1a) and NO OUTLET (W14-2a) signs (see Figure 2C-3) may be used to warn road users of a road that has no outlet or that terminates in a dead end or cul-de-sac.

**Guidance:**

If used, these signs should be placed at a location that gives drivers of large commercial or recreational vehicles an opportunity to select a different route or turn around.

**Section 5C.12 NO TRAFFIC SIGNS Sign (W18-1)****Option:**


A W18-1 warning sign (see Figure 5C-2) with the legend NO TRAFFIC SIGNS may be used only on unpaved, low-volume roads to advise users that no signs are installed along the distance of the road. If used, the sign may be installed at the point where road users would enter the low-volume road or where, based on engineering judgment, the road user may need this information.

A W7-3a, W16-2, or W16-9p supplemental plaque (see Figure 5C-2) with the legend NEXT XX MILES, XX FEET, or AHEAD may be installed below the W18-1 sign when appropriate.

**Section 5C.13 Other Warning Signs****Standard:**

**Other warning signs used on low-volume roads that are not discussed in Part 5, but are in this Manual, shall conform with the criteria contained in other Parts of this Manual. Warning signs that are not specified in this Manual shall conform to the criteria in Sections 2C.02 and 2C.03.**

**Figure 5C-1. Horizontal Alignment and Intersection Warning Signs on Low-Volume Roads**



**Figure 5C-2. Other Warning Signs on Low-Volume Roads**



W3-1



W3-2



W5-2



W5-3



W7-1



W7-3



W7-3a



W8-3



W8-6



W11-1



W11-2



W11-3



W11-4



W11-5



W11-8



W11-10



W14-1



W14-2



W16-2



W16-9p



W18-1

Intentionally blank.

## CHAPTER 5D. GUIDE SIGNS

### Section 5D.01 Introduction

#### Support:

The purpose of a guide sign is to inform road users regarding positions, directions, destinations, and routes.

The criteria for guide signs, in general, are contained in Chapters 2D through 2H and in other Sections of this Manual. Criteria for guide signs that are specific to low-volume roads are contained in this Chapter.

#### Guidance:

The familiarity of the road users with the road should be considered in determining the need for guide signs on low-volume roads.

#### Support:

Low-volume roads generally do not require guide signs to the extent that they are needed on higher classes of roads. Because guide signs are typically only beneficial as a navigational aid for road users who are unfamiliar with a low-volume road, guide signs might not be needed on low-volume roads that serve only local traffic.

#### Guidance:

If used, destination names should be as specific and descriptive as possible. Destinations such as campgrounds, ranger stations, recreational areas, and the like should be clearly indicated so that they are not interpreted to be communities or locations with road user services.

#### Option:

Guide signs may be used at intersections to provide information for road users returning to a higher class of roads.

Intentionally blank.

## CHAPTER 5E. MARKINGS

### Section 5E.01 Introduction

Support:

The purpose of markings on highways is to provide guidance and information for road users regarding roadway conditions and restrictions.

The criteria for markings, delineators, and object markers, in general, are contained in Part 3 and in other Sections of this Manual. Criteria for markings that are specific to low-volume roads are contained in this Chapter.

### Section 5E.02 Centerline Markings

Standard:

**Where centerline markings are installed, no-passing zone markings in conformance with Section 3B.02 shall also be installed.**

Guidance:

Centerline markings should be used on paved low-volume roads where engineering judgment or an engineering study indicates a need for them.

### Section 5E.03 Edge Line Markings

Support:

The purpose of edge line markings is to delineate the left or right edge of the roadway.

Guidance:

Edge line markings should be considered for use on paved low-volume roads based on engineering judgment or an engineering study.

Option:

Edge line markings may be placed on highways with or without centerline markings.

Edge line markings may be placed on paved low-volume roads for roadway features such as horizontal curves, narrow bridges, pavement width transitions, curvilinear alignment, and at other locations based on engineering judgment or an engineering study.

### Section 5E.04 Delineators

Support:

The purpose of delineators is to enhance driver safety where it is desirable to call attention to a changed or changing condition such as abrupt roadway narrowing or curvature.

Option:

Delineators may be used on low-volume roads based on engineering judgment, such as for curves, T-intersections, and abrupt changes in the roadway width. In addition, they may be used to mark the location of driveways or other minor roads entering the low-volume road.

### Section 5E.05 Object Markers

Support:

The purpose of object markers is to mark obstructions located within or adjacent to the roadway, such as bridge abutments, drainage structures, and other physical objects.

**Guidance:**

The end of a low-volume road should be marked with an end-of-roadway marker in conformance with Section 3C.04.

**Option:**

A Type III barricade may be used where engineering studies or judgment indicates a need for a more visible end-of-roadway treatment (see Section 3F.01).

**Section 5E.06 Other Markings****Standard:**

**Other markings, such as stop lines, crosswalks, pavement legends, barricades, channelizing devices, and islands, used on low-volume roads shall conform with the criteria contained in this Manual.**

## CHAPTER 5F. TRAFFIC CONTROL FOR HIGHWAY-RAIL GRADE CROSSINGS

### Section 5F.01 Introduction

Support:

The criteria for highway-rail grade crossing traffic control devices are contained in Part 8 and in other Sections of this Manual.

Traffic control for highway-rail grade crossings includes all signs, signals, markings, illumination, and other warning devices and their supports along roadways either approaching or at highway-rail grade crossings. The function of this traffic control is to permit reasonably safe and efficient operation of both rail and road traffic at highway-rail grade crossings.

### Section 5F.02 Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1, R15-2)

Standard:

**The Highway-Rail Grade Crossing (Crossbuck) (R15-1) sign (see Figure 5F-1) shall be used at all highway-rail grade crossings. For all low-volume roads, Crossbuck signs shall be used on the right side of each approach. If there are two or more tracks, the supplemental Number of Tracks (R15-2) sign (see Figure 5F-1) shall display the number of tracks and shall be installed below the Crossbuck sign.**

A strip of retroreflective white material not less than 50 mm (2 in) in width shall be used on the back of each blade of each Crossbuck sign for the length of each blade, at all highway-rail grade crossings, except those where Crossbuck signs have been installed back-to-back.

A strip of retroreflective white material, not less than 50 mm (2 in) in width, shall be used on each support at passive highway-rail grade crossings for the full length of the front and back of the support from the Crossbuck sign or Number of Tracks sign to within 0.6 m (2 ft) above the edge of the roadway, except on the side of those supports where a STOP (R1-1) or YIELD (R1-2) sign or flashing lights have been installed or on the back side of supports for Crossbuck signs installed on one-way streets.

### Section 5F.03 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series)

Standard:

**Except as noted in the Option, a Highway-Rail Grade Crossing Advance Warning (W10-1) sign (see Figure 5F-1) shall be used on all low-volume roads in advance of every highway-rail grade crossing.**

Option:

The Highway-Rail Grade Crossing Advance Warning sign may be omitted for highway-rail grade crossings that are flagged by train crews.

The W10-2, W10-3, and W10-4 signs (see Figure 5F-1) may be used on low-volume roads that run parallel to railroad tracks to warn road users making a turn that they will encounter a highway-rail grade crossing soon after making the turn.

### Section 5F.04 STOP and YIELD Signs (R1-1, R1-2)

Option:

STOP (R1-1) or YIELD (R1-2) signs may be used at low-volume highway-rail grade crossings, at the discretion of the responsible jurisdiction, for crossings without automatic traffic control devices, consistent with the provisions of Sections 2B.04 to 2B.10.

**Standard:**

A Stop Ahead (W3-1) sign or Yield Ahead (W3-2) sign shall be used in advance of a STOP or YIELD sign at a highway-rail grade crossing if the STOP or YIELD sign is not visible for a distance that enables the road user to bring the vehicle to a reasonably safe stop at the highway-rail grade crossing.

Use of STOP signs at highway-rail grade crossing shall be in accordance with Section 4511.61 of the Ohio Revised Code (see Appendix B2).


**Section 5F.05 Pavement Markings****Guidance:**

Pavement markings at highway-rail grade crossings should be used on paved low-volume roads, particularly if they are already deployed at most other highway-rail grade crossings within the immediate vicinity, or when the roadway has centerline markings.

**Section 5F.06 Other Traffic Control Devices****Standard:**

Other traffic control devices that are used at highway-rail grade crossings on low-volume roads, such as other signs, signals, and illumination that are not in this Chapter, shall conform with the criteria contained in Part 8 and other applicable Parts of this Manual.

**Figure 5F-1. Highway-Rail Grade Crossing Signs for Low-Volume Roads**



## CHAPTER 5G. TEMPORARY TRAFFIC CONTROL ZONES

### Section 5G.01 Introduction

#### Guidance:

The safety of road users, including pedestrians and bicyclists, as well as personnel in work zones, should be an integral and high priority element of every project in the planning, design, maintenance, and construction phases. Part 6 should be reviewed for additional criteria, specific details, and more complex temporary traffic control zone requirements. The following principles should be applied to temporary traffic control zones:

- A. Traffic movement should be disrupted as little as possible.
- B. Road users should be guided in a clear and positive manner while approaching and within construction, maintenance, and utility work areas.
- C. Routine inspection and maintenance of traffic control elements should be performed both day and night.
- D. Both the contracting agency and the contractor should assign at least one person on each project to have day-to-day responsibility for assuring that the traffic control elements are operating effectively and any needed operational changes are brought to the attention of their supervisors.

Traffic control in temporary traffic control zones should be designed on the assumption that road users will only reduce their speeds if they clearly perceive a need to do so, and then only in small increments of speed. Temporary traffic control zones should not present a surprise to the road user. Frequent and/or abrupt changes in geometrics and other features should be avoided. Transitions should be well delineated and long enough to accommodate driving conditions at the speeds vehicles are realistically expected to travel.

A Traffic Control Plan (see Section 6C.01) should be used for a temporary traffic control zone on a low-volume road to specify particular traffic control devices and features, or to reference typical drawings such as those contained in Part 6.

#### Support:

Applications of speed reduction countermeasures and enforcement can be effective in reducing traffic speeds in temporary traffic control zones.

### Section 5G.02 Applications

#### Guidance:

Planned work phasing and sequencing should be the basis for the use of traffic control devices for temporary traffic control zones. Part 6 should be consulted for specific traffic control requirements and examples where construction or maintenance work is planned.

#### Option:

Maintenance activities may not require extensive temporary traffic control if the traffic volumes and speeds are low. The traffic applications shown in Figures 6H-1, 6H-11, 6H-15, and 6H-16 of Part 6 are among those that may be used on low-volume roads.


For temporary traffic control zones on low-volume roads that require flaggers, a single flagger may be adequate if the flagger is visible to approaching traffic from all appropriate directions.

### Section 5G.03 Channelization Devices

#### Standard:

**Channelization devices for nighttime use shall have the same retroreflective requirements as specified for higher-volume roadways.**

**Figure 5G-1. Temporary Traffic Control Signs on Low-Volume Roads**



Option:

To alert, guide, and direct road users reasonably safely through temporary traffic control zones on low-volume roads, tapers may be used to move a road user out of the traffic lane and around the work space using the spacing of devices that is described in Section 6F.58.

**Section 5G.04 Markings**

Guidance:

Pavement markings should be considered for temporary traffic control zones on paved low-volume roads, especially roads that had existing pavement markings or that have a surfaced detour or temporary roadway.

Option:

Interim pavement markings in a temporary traffic control zone may not be needed based on the criteria for these markings in Section 6F. 72.

## **Section 5G.05 Other Traffic Control Devices**

### **Standard:**

**Other traffic control devices, such as other signs, signals, and illumination that are used on low-volume roads in temporary traffic control zones, but are not described in Part 5, shall conform with the criteria contained in other Parts of this Manual.**

### **Support:**

Some of the signs that might be applicable in a temporary traffic control zone on a low-volume road are shown in Figure 5G-1.

Intentionally blank.

## PART 6. TEMPORARY TRAFFIC CONTROL

### TABLE OF CONTENTS

		<u>Page</u>
<b>CHAPTER 6A.</b>	<b>GENERAL</b>	
Section 6A.01	General.....	6A-1
<b>CHAPTER 6B.</b>	<b>FUNDAMENTAL PRINCIPLES</b>	
Section 6B.01	Fundamental Principles of Temporary Traffic Control.....	6B-1
<b>CHAPTER 6C.</b>	<b>TEMPORARY TRAFFIC CONTROL ELEMENTS</b>	
Section 6C.01	Temporary Traffic Control Plans.....	6C-1
Section 6C.02	Temporary Traffic Control Zones.....	6C-2
Section 6C.03	Components of Temporary Traffic Control Zones.....	6C-2
Section 6C.04	Advance Warning Area.....	6C-4
Section 6C.05	Transition Area.....	6C-5
Section 6C.06	Activity Area.....	6C-5
Section 6C.07	Termination Area.....	6C-6
Section 6C.08	Tapers.....	6C-6
Section 6C.09	Detours and Diversions.....	6C-10
Section 6C.10	One-Lane, Two-Way Traffic Control.....	6C-10
Section 6C.11	Flagger Method of One-Lane, Two-Way Traffic Control.....	6C-10
Section 6C.12	Flag Transfer Method of One-Lane, Two-Way Traffic Control.....	6C-11
Section 6C.13	Pilot Car Method of One-Lane, Two-Way Traffic Control.....	6C-11
Section 6C.14	Temporary Traffic Control Signal Method of One-Lane, Two-Way Traffic Control.....	6C-11
Section 6C.15	Stop or Yield Control Method of One-Lane, Two-Way Traffic Control.....	6C-11
<b>CHAPTER 6D.</b>	<b>PEDESTRIAN AND WORKER SAFETY</b>	
Section 6D.01	Pedestrian Considerations.....	6D-1
Section 6D.02	Accessibility Considerations.....	6D-4
Section 6D.03	Worker Safety Considerations.....	6D-5
<b>CHAPTER 6E.</b>	<b>FLAGGER CONTROL</b>	
Section 6E.01	Qualifications for Flaggers.....	6E-1
Section 6E.02	High-Visibility Safety Apparel.....	6E-1
Section 6E.03	Hand-Signaling Devices.....	6E-1
Section 6E.04	Flagger Procedures.....	6E-2
Section 6E.05	Flagger Stations.....	6E-4
<b>CHAPTER 6F.</b>	<b>TEMPORARY TRAFFIC CONTROL ZONE DEVICES</b>	
Section 6F.01	Types of Devices.....	6F-1
Section 6F.02	General Characteristics of Signs.....	6F-1
Section 6F.03	Sign Placement.....	6F-3
Section 6F.04	Sign Maintenance.....	6F-11
Section 6F.05	Regulatory Sign Authority.....	6F-11
Section 6F.06	Regulatory Sign Design.....	6F-11
Section 6F.07	Regulatory Sign Applications.....	6F-13
Section 6F.08	ROAD (STREET) CLOSED Sign (R11-2).....	6F-13
Section 6F.09	Local Traffic Only Signs (R11-3a, R11-3b, R11-4, R11-H5).....	6F-14
Section 6F.10	Weight Limit Signs (R12-1, R12-2, R12-5).....	6F-14

Section 6F.11	STAY IN LANE Sign (R4-9) .....	6F-14
Section 6F.12	PEDESTRIAN CROSSWALK Sign (R9-8).....	6F-14
Section 6F.13	SIDEWALK CLOSED Signs (R9-9, R9-10, R9-11, R9-11a) .....	6F-15
Section 6F.14	Special Regulatory Signs .....	6F-15
Section 6F.14.1	Work Zone Increased Penalties Sign (R11-H5a) .....	6F-15
Section 6F.15	Warning Sign Function, Design, and Application.....	6F-16
Section 6F.16	Position of Advance Warning Signs.....	6F-17
Section 6F.17	ROAD (STREET) WORK Sign (W20-1) .....	6F-17
Section 6F.18	DETOUR Sign (W20-2) .....	6F-21
Section 6F.19	ROAD (STREET) CLOSED Sign (W20-3) .....	6F-21
Section 6F.20	ONE LANE ROAD Sign (W20-4) .....	6F-22
Section 6F.21	Lane(s) Closed Signs (W20-5, W20-5a).....	6F-22
Section 6F.22	CENTER LANE CLOSED AHEAD Signs (W9-3, W9-3a) .....	6F-22
Section 6F.23	THRU TRAFFIC MERGE LEFT (RIGHT) Sign (W4-7).....	6F-22
Section 6F.24	Lane Ends Sign (W4-2) .....	6F-22
Section 6F.25	ON RAMP Plaque (W13-4).....	6F-22
Section 6F.26	RAMP NARROWS Sign (W5-4).....	6F-22
Section 6F.27	SLOW TRAFFIC AHEAD Sign (W23-1).....	6F-23
Section 6F.28	EXIT OPEN, EXIT CLOSED (AHEAD), EXIT ONLY Signs (E5-2, E5-2a, E5-H2b, E5-H2c, E5-3) .....	6F-23
Section 6F.29	Flagger Sign (W20-7a, W20-7) .....	6F-23
Section 6F.30	Two-Way Traffic Sign (W6-3).....	6F-23
Section 6F.31	Workers Sign (W21-1, W21-1a).....	6F-23
Section 6F.32	FRESH OIL (TAR) Sign (W21-2).....	6F-24
Section 6F.33	ROAD MACHINERY AHEAD Sign (W21-3) .....	6F-24
Section 6F.34	Motorized Traffic Signs (W8-6, W11-10).....	6F-24
Section 6F.35	Shoulder Work Signs (W21-5, W21-5a, W21-5b) .....	6F-25
Section 6F.36	SURVEY CREW Sign (W21-6).....	6F-25
Section 6F.37	UTILITY WORK Sign (W21-7) .....	6F-25
Section 6F.38	Signs for Blasting Areas .....	6F-25
Section 6F.39	BLASTING ZONE AHEAD Sign (W22-1) .....	6F-26
Section 6F.40	TURN OFF 2-WAY RADIO AND CELL PHONE Sign (W22-2) .....	6F-26
Section 6F.41	END BLASTING ZONE Sign (W22-3).....	6F-26
Section 6F.42	SHOULDER Signs (W8-4, W8-9, W8-9a).....	6F-26
Section 6F.43	UNEVEN LANES Sign (W8-11) .....	6F-26
Section 6F.44	NO CENTER LINE and NO EDGE LINE Signs (W8-H12, W8-H12a).....	6F-26
Section 6F.45	Double Reverse Curve Signs (W24 Series).....	6F-27
Section 6F.46	Other Warning Signs .....	6F-27
Section 6F.46.1	Construction Arrow Sign (W1-H11).....	6F-27
Section 6F.47	Special Warning Signs.....	6F-27
Section 6F.48	Advisory Speed Plaque (W13-1) .....	6F-27
Section 6F.49	Supplementary Distance Plaque (W7-3a).....	6F-28
Section 6F.50	Guide Signs.....	6F-28
Section 6F.51	ROAD WORK NEXT XX MILES Sign (G20-1) .....	6F-29
Section 6F.52	END ROAD WORK Sign (G20-2).....	6F-29
Section 6F.53	Detour Signs (M4-8, M4-8a, M4-8b, M4-9, M4-9a, M4-9b, M4-9c, and M4-10) .....	6F-29
Section 6F.54	PILOT CAR FOLLOW ME Sign (G20-4) .....	6F-30
Section 6F.55	Portable Changeable Message Signs .....	6F-30
Section 6F.56	Arrow Panels .....	6F-32
Section 6F.57	High-Level Warning Devices (Flag Trees) .....	6F-34
Section 6F.58	Channelizing Devices .....	6F-34
Section 6F.59	Cones .....	6F-36
Section 6F.60	Tubular Markers .....	6F-37

Section 6F.61	Vertical Panels .....	6F-39
Section 6F.62	Drums.....	6F-40
Section 6F.63	Type I, II, or III Barricades .....	6F-40
Section 6F.64	Direction Indicator Barricades.....	6F-42
Section 6F.65	Temporary Traffic Barriers as Channelizing Devices .....	6F-43
Section 6F.66	Longitudinal Channelizing Barricades .....	6F-43
Section 6F.67	Other Channelizing Devices .....	6F-44
Section 6F.68	Detectable Edging for Pedestrians.....	6F-44
Section 6F.69	Temporary Raised Islands.....	6F-45
Section 6F.70	Opposing Traffic Lane Divider.....	6F-45
Section 6F.71	Pavement Markings .....	6F-46
Section 6F.72	Temporary Pavement Markings.....	6F-46
Section 6F.73	Raised Pavement Markers.....	6F-47
Section 6F.74	Delineators .....	6F-47
Section 6F.75	Lighting Devices.....	6F-48
Section 6F.76	Floodlights .....	6F-48
Section 6F.77	Flashing Warning Beacons .....	6F-49
Section 6F.78	Warning Lights .....	6F-49
Section 6F.79	Steady-Burn Electric Lamps .....	6F-50
Section 6F.80	Temporary Traffic Control Signals .....	6F-50
Section 6F.81	Temporary Traffic Barriers.....	6F-52
Section 6F.82	Crash Cushions .....	6F-52
Section 6F.83	Vehicle-Arresting Systems .....	6F-53
Section 6F.84	Rumble Strips .....	6F-54
Section 6F.85	Screens .....	6F-54
Section 6F.86	Future and Experimental Devices.....	6F-55

**CHAPTER 6G.****TYPE OF TEMPORARY TRAFFIC CONTROL ZONE ACTIVITIES**

Section 6G.01	Typical Applications.....	6G-1
Section 6G.02	Work Duration .....	6G-1
Section 6G.03	Location of Work.....	6G-3
Section 6G.04	Modifications To Fulfill Special Needs.....	6G-4
Section 6G.05	Work Affecting Pedestrian and Bicycle Facilities.....	6G-5
Section 6G.06	Work Outside of Shoulder .....	6G-6
Section 6G.07	Work on the Shoulder with No Encroachment.....	6G-6
Section 6G.08	Work on the Shoulder with Minor Encroachment.....	6G-7
Section 6G.09	Work Within the Median .....	6G-7
Section 6G.10	Work Within the Traveled Way of Two-Lane Highways .....	6G-8
Section 6G.11	Work Within the Traveled Way of Urban Streets .....	6G-8
Section 6G.12	Work Within the Traveled Way of Multi-lane, Nonaccess Controlled Highways .....	6G-9
Section 6G.13	Work Within the Traveled Way at an Intersection.....	6G-11
Section 6G.14	Work Within the Traveled Way of Freeways and Expressways .....	6G-12
Section 6G.15	Two-Lane, Two-Way Traffic on One Roadway of a Normally Divided Highway .....	6G-13
Section 6G.16	Crossovers.....	6G-13
Section 6G.17	Interchanges .....	6G-13
Section 6G.18	Movable Barriers .....	6G-14
Section 6G.19	Work in the Vicinity of Highway-Rail Grade Crossings.....	6G-14
Section 6G.20	Temporary Traffic Control During Nighttime Hours .....	6G-14

**CHAPTER 6H.****TYPICAL APPLICATIONS**

Section 6H.01	Typical Applications.....	6H-1
---------------	---------------------------	------

## **CHAPTER 6I. CONTROL OF TRAFFIC THROUGH TRAFFIC INCIDENT MANAGEMENT AREAS**

Section 6I.01	General.....	6I-1
Section 6I.02	Major Traffic Incidents.....	6I-2
Section 6I.03	Intermediate Traffic Incidents .....	6I-3
Section 6I.04	Minor Traffic Incidents .....	6I-4
Section 6I.05	Use of Emergency-Vehicle Lighting .....	6I-4

## **FIGURES**

### **CHAPTER 6C. TEMPORARY TRAFFIC CONTROL ELEMENTS**

Figure 6C-1	Component Parts of a Temporary Traffic Control Zone .....	6C-3
Figure 6C-2	Types of Tapers and Buffer Spaces.....	6C-7
Figure 6C-3	Example of a One-Lane, Two-Way Traffic Taper .....	6C-12

### **CHAPTER 6E. FLAGGER CONTROL**

Figure 6E-1	Use of Hand-Signaling Devices by Flaggers.....	6E-3
-------------	--	------

### **CHAPTER 6F. TEMPORARY TRAFFIC CONTROL ZONE DEVICES**

Figure 6F-1	Height and Lateral Location of Signs—Typical Installations.....	6F-9
Figure 6F-2	Methods of Mounting Signs Other Than on Posts .....	6F-10
Figure 6F-3	Regulatory Signs in Temporary Traffic Control Zones.....	6F-12
Figure 6F-4	Warning Signs in Temporary Traffic Control Zones .....	6F-18
Figure 6F-5	Exit Open and Closed and Detour Signs .....	6F-24
Figure 6F-6	Advance Warning Arrow Display Specifications.....	6F-35
Figure 6F-7	Channelizing Devices .....	6F-38

### **CHAPTER 6H. TYPICAL APPLICATIONS**

Figure 6H-1	Work Beyond the Shoulder (TA-1) .....	6H-7
Figure 6H-2	Blasting Zone (TA-2).....	6H-9
Figure 6H-3	Work on Shoulders (TA-3).....	6H-11
Figure 6H-4	Short-Duration or Mobile Operation on Shoulder (TA-4) .....	6H-13
Figure 6H-5	Shoulder Closure on Freeway (TA-5) .....	6H-15
Figure 6H-6	Shoulder Work with Minor Encroachment (TA-6) .....	6H-17
Figure 6H-7	Road Closure with Diversion (TA-7) .....	6H-19
Figure 6H-8	Road Closure with Off-Site Detour (TA-8).....	6H-21
Figure 6H-9	Overlapping Routes with Detour (TA-9).....	6H-23
Figure 6H-10	Lane Closure on Two-Lane Road Using Flaggers (TA-10) .....	6H-25
Figure 6H-11	Lane Closure on Two-Lane Road with Low Traffic Volumes (TA-11) .....	6H-27
Figure 6H-12	Lane Closure on Two-Lane Road Using Traffic Control Signals (TA-12).....	6H-29
Figure 6H-13	Temporary Road Closure (TA-13) .....	6H-31
Figure 6H-14	Haul Road Crossing (TA-14).....	6H-33
Figure 6H-15	Work in Center of Road with Low Traffic Volumes (TA-15) .....	6H-35
Figure 6H-16	Surveying Along Centerline of Road with Low Traffic Volumes (TA-16) .....	6H-37
Figure 6H-17	Mobile Operations on Two-Lane Road (TA-17).....	6H-39
Figure 6H-18	Lane Closure on Minor Street (TA-18) .....	6H-41
Figure 6H-19	Detour for One Travel Direction (TA-19).....	6H-43
Figure 6H-20	Detour for Closed Street (TA-20).....	6H-45
Figure 6H-21	Lane Closure on Near Side of Intersection (TA-21) .....	6H-47
Figure 6H-22	Right Lane Closure on Far Side of Intersection (TA-22).....	6H-49
Figure 6H-23	Left Lane Closure on Far Side of Intersection (TA-23) .....	6H-51
Figure 6H-24	Half Road Closure on Far Side of Intersection (TA-24) .....	6H-53

OMUTCD - English units are preferred.

Figure 6H-25	Multiple Lane Closures at Intersection (TA-25) .....	6H-55
Figure 6H-26	Closure in Center of Intersection (TA-26).....	6H-57
Figure 6H-27	Closure at Side of Intersection (TA-27) .....	6H-59
Figure 6H-28	Sidewalk Detour or Diversion (TA-28).....	6H-61
Figure 6H-29	Crosswalk Closures and Pedestrian Detours (TA-29).....	6H-63
Figure 6H-30	Interior Lane Closure on Multi-lane Street (TA-30) .....	6H-65
Figure 6H-31	Lane Closures on Street with Uneven Directional Volumes (TA-31).....	6H-67
Figure 6H-32	Half Road Closure on Multi-lane, High-Speed Highway (TA-32).....	6H-69
Figure 6H-33	Stationary Lane Closure on Divided Highway (TA-33).....	6H-71
Figure 6H-34	Lane Closure with Temporary Traffic Barrier (TA-34) .....	6H-73
Figure 6H-35	Mobile Operation on Multi-lane Road (TA-35) .....	6H-75
Figure 6H-36	Lane Shift on Freeway (TA-36).....	6H-77
Figure 6H-37	Double Lane Closure on Freeway (TA-37) .....	6H-79
Figure 6H-38	Interior Lane Closure on Freeway (TA-38) .....	6H-81
Figure 6H-39	Median Crossover on Freeway (TA-39).....	6H-83
Figure 6H-40	Median Crossover for Entrance Ramp (TA-40) .....	6H-85
Figure 6H-41	Median Crossover for Exit Ramp (TA-41).....	6H-87
Figure 6H-42	Work in Vicinity of Exit Ramp (TA-42) .....	6H-89
Figure 6H-43	Partial Exit Ramp Closure (TA-43).....	6H-91
Figure 6H-44	Work in Vicinity of Entrance Ramp (TA-44).....	6H-93
Figure 6H-45	Movable Barriers (TA-45) .....	6H-95
Figure 6H-46	Work in Vicinity of Highway-Rail Grade Crossing (TA-46).....	6H-97

**CHAPTER 6I. CONTROL OF TRAFFIC THROUGH TRAFFIC INCIDENT MANAGEMENT AREAS**

Figure 6I-1	Examples of Traffic Incident Management Area Signs.....	6I-2
-------------	---	------

**TABLES**

**CHAPTER 6C. TEMPORARY TRAFFIC CONTROL ELEMENTS**

Table 6C-1	Suggested Advance Warning Sign Spacing.....	6C-4
Table 6C-2	Stopping Sight Distance as a Function of Speed .....	6C-8
Table 6C-3	Taper Length Criteria for Temporary Traffic Control Zones.....	6C-9
Table 6C-4	Formulas for Determining Taper Lengths .....	6C-9

**CHAPTER 6E. FLAGGER CONTROL**

Table 6E-1	Stopping Sight Distance as a Function of Speed.....	6E-5
------------	---	------

**CHAPTER 6F. TEMPORARY TRAFFIC CONTROL ZONE DEVICES**

Table 6F-1	Sizes of Temporary Traffic Control Signs.....	6F-4
------------	---	------

**CHAPTER 6H. TYPICAL APPLICATIONS**

Table 6H-1	Index to Typical Applications.....	6H-2
Table 6H-2	Meaning of Symbols on Typical Application Diagrams .....	6H-4
Table 6H-3	Meaning of Letter Codes on Typical Application Diagrams.....	6H-5
Table 6H-4	Formulas for Determining Taper Lengths .....	6H-5

Intentionally blank.

## CHAPTER 6A. GENERAL

### Section 6A.01 General

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

When the normal function of the roadway is suspended, TTC planning provides for continuity of the movement of motor vehicle, bicycle, and pedestrian traffic (including accessible passage); transit operations; and access (and accessibility) to property and utilities.

The primary function of TTC is to provide for the reasonably safe and efficient movement of road users through or around TTC zones while reasonably protecting workers, responders to traffic incidents, and equipment.

Of equal importance to the public traveling through the TTC zone is the safety of workers performing the many varied tasks within the work space. TTC zones present constantly changing conditions that are unexpected by the road user. This creates an even higher degree of vulnerability for the workers and incident management responders on or near the roadway (see Section 6D.03). At the same time, the TTC zone provides for the efficient completion of whatever activity interrupted the normal use of the roadway.

Consideration for road user safety, worker and responder safety, and the efficiency of road user flow is an integral element of every TTC zone, from planning through completion. A concurrent objective of the TTC is the efficient construction and maintenance of the highway and the efficient resolution of traffic incidents.

No one set of TTC devices can satisfy all conditions for a given project or incident. At the same time, defining details that would be adequate to cover all applications is not practical. Instead, Part 6 displays typical applications that depict common applications of TTC devices. The TTC selected for each situation depends on type of highway, road user conditions, duration of operation, physical constraints, and the nearness of the work space or incident management activity to road users.

Improved road user performance might be realized through a well-prepared public relations effort that covers the nature of the work, the time and duration of its execution, the anticipated effects upon road users, and possible alternate routes and modes of travel. Such programs have been found to result in a significant reduction in the number of road users traveling through the TTC zone, which reduces the possible number of conflicts.

**Standard:**

**TTC plans and devices shall be the responsibility of the authority of a public body or official having jurisdiction for guiding road users. There shall be adequate statutory authority for the implementation and enforcement of needed road user regulations, parking controls, speed zoning, and the management of traffic incidents. Such statutes shall provide sufficient flexibility in the application of TTC to meet the needs of changing conditions in the TTC zone.**

Support:

Temporary facilities, including reasonably safe pedestrian routes around work sites, are also covered by the accessibility requirements of the Americans with Disabilities Act of 1990 (ADA) (Public Law 101-336, 104 Stat. 327, July 26, 1990. 42 USC 12101-12213 (as amended)).

**Guidance:**

The TTC plan should start in the planning phase and continue through the design, construction, and restoration phases. The TTC plans and devices should follow the principles set forth in Part 6. The management of traffic incidents should follow the principles set forth in Chapter 6I.

**Option:**

TTC plans may deviate from the typical applications described in Chapter 6H to allow for conditions and requirements of a particular site or jurisdiction.

**Support:**

The criteria of Part 6 apply to both rural and urban areas. A rural highway is normally characterized by lower volumes, higher speeds, fewer turning conflicts, and less conflict with pedestrians. An urban street is typically characterized by relatively low speeds, wide ranges of road user volumes, narrower roadway lanes, frequent intersections and driveways, significant pedestrian activity, and more businesses and houses.

## CHAPTER 6B. FUNDAMENTAL PRINCIPLES

### Section 6B.01 Fundamental Principles of Temporary Traffic Control

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

Construction, maintenance, utility, and incident zones can all benefit from TTC to compensate for the unexpected or unusual situations faced by road users. When planning for TTC in these zones, it can be assumed that it is appropriate for road users to exercise caution. Even though road users are assumed to be using caution, special care is still needed in applying TTC techniques.

Special plans preparation and coordination with transit, other highway agencies, law enforcement and other emergency units, utilities, schools, and railroad companies might be needed to reduce unexpected and unusual road user operation situations.

During TTC activities, commercial vehicles might need to follow a different route from passenger vehicles because of bridge, weight, clearance, or geometric restrictions. Also, vehicles carrying hazardous materials might need to follow a different route from other vehicles. The Truck Route and Hazardous Materials signs are included in Sections 2B.51 and 2B.52, respectively.

Experience has shown that following the fundamental principles of Part 6 will assist road users and help protect workers in the vicinity of TTC zones.

Guidance:

Road user and worker safety and accessibility in TTC zones should be an integral and high-priority element of every project from planning through design and construction. Similarly, maintenance and utility work should be planned and conducted with the safety and accessibility of all motorists, bicyclists, pedestrians (including those with disabilities), and workers being considered at all times. If the TTC zone includes a highway-rail grade crossing, early coordination with the railroad company should take place.

Support:

Formulating specific plans for TTC at traffic incidents is difficult because of the variety of situations that can arise.

Guidance:

General plans or guidelines should be developed to provide safety for motorists, bicyclists, pedestrians, workers, enforcement/emergency officials, and equipment, with the following factors being considered:

- A. The basic safety principles governing the design of permanent roadways and roadsides should also govern the design of TTC zones. The goal should be to route road users through such zones using roadway geometrics, roadside features, and TTC devices as nearly as possible comparable to those for normal highway situations.
- B. A TTC plan, in detail appropriate to the complexity of the work project or incident, should be prepared and understood by all responsible parties before the site is occupied. Any changes in the TTC plan should be approved by an official knowledgeable (for example, trained and/or certified) in proper TTC practices.

Road user movement should be inhibited as little as practical, based on the following considerations:

- A. TTC at work and incident sites should be designed on the assumption that drivers will only reduce their speeds if they clearly perceive a need to do so (see Section 6C.01).
- B. Frequent and abrupt changes in geometrics such as lane narrowing, dropped lanes, or main roadway transitions that require rapid maneuvers, should be avoided.
- C. Provisions should be made for the reasonably safe operation of work, particularly on high-speed, high-volume roadways.
- D. Road users should be encouraged to use alternative routes that do not include TTC zones.
- E. Bicyclists and pedestrians, including those with disabilities, should be provided with access and reasonably safe passage through the TTC zone.
- F. Roadway occupancy should be scheduled during off-peak hours and, if necessary, night work should be considered.
- G. Early coordination with officials having jurisdiction over the affected cross streets and providing emergency services should occur before roadway or ramp closings.
- H. Roadway occupancy and work completion time should be minimized to reduce exposure to potential hazards.

Motorists, bicyclists, and pedestrians should be guided in a clear and positive manner while approaching and traversing TTC zones and incident sites. The following principles should be applied:

- A. Adequate warning, delineation, and channelization should be provided to assist in guiding road users in advance of and through the TTC zone or incident site by using proper pavement marking, signing, or other devices that are effective under varying conditions. Providing information that is in usable formats by pedestrians with visual disabilities should also be considered.
- B. TTC devices inconsistent with intended travel paths through TTC zones should be removed or covered. However, in intermediate-term stationary, short-term, and mobile operations, where visible permanent devices are inconsistent with intended travel paths, devices that highlight or emphasize the appropriate path should be used. Providing traffic control devices that are accessible to and usable by pedestrians with disabilities should be considered.
- C. Flagging procedures, when used, should provide positive guidance to road users traversing the TTC zone.

To provide acceptable levels of operations, routine day and night inspections of TTC elements should be performed as follows:

- A. Individuals who are knowledgeable (for example, trained and/or certified) in the principles of proper TTC should be assigned responsibility for safety in TTC zones. The most important duty of these individuals should be to check that all TTC devices on the project are reasonably consistent with the TTC plan and are effective in providing reasonably safe conditions for motorists, bicyclists, pedestrians, and workers.
- B. As the work progresses, temporary traffic controls and/or working conditions should be modified in order to provide reasonably safe and efficient road user movement and to provide worker safety. The individual responsible for TTC should have the authority to halt work until applicable or remedial safety measures are taken.
- C. TTC zones should be carefully monitored under varying conditions of road user volumes, light, and weather to check that applicable TTC devices are effective, clearly visible, clean, and in compliance with the TTC plan.
- D. When warranted, an engineering study should be made (in cooperation with law enforcement officials) of reported crashes occurring within the TTC zone. Crash records in TTC zones should be monitored to identify the need for changes in the TTC zone.

Attention should be given to the maintenance of roadside safety during the life of the TTC zone by applying the following principles:

- A. To accommodate run-off-the-road incidents, disabled vehicles, or emergency situations, unencumbered roadside recovery areas or clear zones should be provided where practical.
- B. Channelization of road users should be accomplished by the use of pavement markings, signing, and crashworthy, detectable channelizing devices.

- C. Work equipment, workers' private vehicles, materials, and debris should be stored in such a manner to reduce the probability of being impacted by run-off-the-road vehicles.

Each person whose actions affect TTC zone safety, from the upper-level management through the field workers, should receive training appropriate to the job decisions each individual is required to make. Only those individuals who are trained in proper TTC practices and have a basic understanding of the principles (established by applicable standards and guidelines, including those of this Manual) should supervise the selection, placement, and maintenance of TTC devices used for TTC zones and for incident management.

Good public relations should be maintained by applying the following principles:

- A. The needs of all road users should be assessed such that appropriate advance notice is given and clearly defined alternative paths are provided.
- B. The cooperation of the various news media should be sought in publicizing the existence of and reasons for TTC zones because news releases can assist in keeping the road users well informed.
- C. The needs of abutting property owners, residents, and businesses should be assessed and appropriate accommodations made.
- D. The needs of emergency service providers (law enforcement, fire, and medical) should be assessed and appropriate coordination and accommodations made.
- E. The needs of railroads and transit should be assessed and appropriate coordination and accommodations made.
- F. The needs of operators of commercial vehicles such as buses and large trucks should be assessed and appropriate accommodations made.

**Standard:**

**Before any new detour or temporary route is opened to traffic, all necessary signs shall be in place.**

**All TTC devices shall be removed as soon as practical when they are no longer needed. When work is suspended for short periods of time, TTC devices that are no longer appropriate shall be removed or covered.**

Intentionally blank.

## CHAPTER 6C. TEMPORARY TRAFFIC CONTROL ELEMENTS

### Section 6C.01 Temporary Traffic Control Plans

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

A TTC plan describes TTC measures to be used for facilitating road users through a work zone or an incident area. TTC plans play a vital role in providing continuity of reasonably safe and efficient road user flow when a work zone, incident, or other event temporarily disrupts normal road user flow. Important auxiliary provisions that cannot conveniently be specified on project plans can easily be incorporated into Special Provisions within the TTC plan.

TTC plans range in scope from being very detailed to simply referencing typical drawings contained in this Manual, standard approved highway agency drawings and manuals, or specific drawings contained in the contract documents. The degree of detail in the TTC plan depends entirely on the nature and complexity of the situation.

Guidance:

TTC plans should be prepared by persons knowledgeable (for example, trained and/or certified) about the fundamental principles of TTC and work activities to be performed. The design, selection and placement of TTC devices for a TTC plan should be based on engineering judgment.

Coordination should be made between adjacent or overlapping projects to check that duplicate signing is not used and to check compatibility of traffic control between adjacent or overlapping projects.

Traffic control planning should be completed for all highway construction, utility work, maintenance operations, and incident management including minor maintenance and utility projects prior to occupying the TTC zone. Planning for all road users should be included in the process.

Provisions for effective continuity of accessible circulation paths for pedestrians should be incorporated into the TTC process. Where existing pedestrian routes are blocked or detoured, information should be provided about alternative routes that are usable by pedestrians with disabilities, particularly those who have visual disabilities. Access to temporary bus stops, reasonably safe travel across intersections with accessible pedestrian signals (see Section 4E.06), and other routing issues should be considered where temporary pedestrian routes are channelized. Barriers and channelizing devices that are detectable by people with visual disabilities should be provided.

Option:

Provisions may be incorporated into the project bid documents that enable contractors to develop an alternate TTC plan.

Modifications of TTC plans may be necessary because of changed conditions or a determination of better methods of safely and efficiently handling road users.

Guidance:

This alternate or modified plan should have the approval of the responsible highway agency prior to implementation.

Provisions for effective continuity of transit service should be incorporated into the TTC planning process because often public transit buses cannot efficiently be detoured in the same manner as other vehicles (particularly for short-term maintenance projects). Where applicable, the TTC plan should provide for features such as accessible temporary bus stops, pull-outs, and satisfactory waiting areas for transit patrons, including persons with disabilities, if applicable (see Section 10A.05 for additional light rail transit issues to consider for TTC).

Provisions for effective continuity of railroad service and acceptable access to abutting property owners and businesses should also be incorporated into the TTC planning process.

Reduced speed limits should be used only in the specific portion of the TTC zone where conditions or restrictive features are present. However, frequent changes in the speed limit should be avoided. A TTC plan should be designed so that vehicles can reasonably safely travel through the TTC zone with a speed limit reduction of no more than 16 km/h (10 mph).

A reduction of more than 16 km/h (10 mph) in the speed limit should be used only when required by restrictive features in the TTC zone. Where restrictive features justify a speed reduction of more than 16 km/h (10 mph), additional driver notification should be provided. The speed limit should be stepped down in advance of the location requiring the lowest speed, and additional TTC warning devices should be used.

Reduced speed zoning (lowering the regulatory speed limit) should be avoided as much as practical because drivers will reduce their speeds only if they clearly perceive a need to do so.

Support:

Research has demonstrated that large reductions in the speed limit, such as a 50 km/h (30 mph) reduction, increase speed variance and the potential for crashes. Smaller reductions in the speed limit of up to 16 km/h (10 mph) cause smaller changes in speed variance and lessen the potential for increased crashes. A reduction in the regulatory speed limit of only up to 16 km/h (10 mph) from the normal speed limit has been shown to be more effective.

Section 4511.21 of the Ohio Revised Code establishes how speed limits may be reduced and Part 6 of the ODOT "Traffic Engineering Manual" (see Section 1A.11) provides additional information on speeds in TTC zones.

### **Section 6C.02 Temporary Traffic Control Zones**

Support:

A TTC zone is an area of a highway where road user conditions are changed because of a work zone or an incident through the use of TTC devices, uniformed law enforcement officers, or other authorized personnel.

A work zone is an area of a highway with construction, maintenance, or utility work activities. A work zone is typically marked by signs, channelizing devices, barriers, pavement markings, and/or work vehicles. It extends from the first warning sign or high-intensity rotating, flashing, oscillating, or strobe lights on a vehicle to the END ROAD WORK sign or the last TTC device.


An incident area is an area of a highway where temporary traffic controls are imposed by authorized officials in response to a traffic incident (see Section 6I.01) or special event. It extends from the first warning device (such as a sign, light, or cone) to the last TTC device or to a point where road users return to the original lane alignment and are clear of the incident.

### **Section 6C.03 Components of Temporary Traffic Control Zones**

Support:

Most TTC zones are divided into four areas: the advance warning area, the transition area, the activity area, and the termination area. Figure 6C-1 illustrates these four areas. These four areas are described in Sections 6C.04 through 6C.07.

**Figure 6C-1. Component Parts of a Temporary Traffic Control Zone**



**Table 6C-1. Suggested Advance Warning Sign Spacing**

Road Type	Distance Between Signs **		
	A	B	C
Urban (low speed) *	30 (100)	30 (100)	30 (100)
Urban (high speed) *	100 (350)	100 (350)	100 (350)
Rural	150 (500)	150 (500)	150 (500)
Expressway/Freeway	300 (1,000)	450 (1,500)	800 (2,640)

\* Speed category to be determined by highway agency.

\*\* Distances are shown in meters (feet). The column headings A, B, and C are the dimensions shown in Figures 6H-1 through 6H-46. The A dimension is the distance from the transition or point of restriction to the first sign. The B dimension is the distance between the first and second signs. The C dimension is the distance between the second and third signs. (The third sign is the first one in a three-sign series encountered by a driver approaching a TTC zone.)

#### **Section 6C.04 Advance Warning Area**

##### Support:

The advance warning area is the section of highway where road users are informed about the upcoming work zone or incident area.

##### Option:

The advance warning area may vary from a single sign or high-intensity rotating, flashing, oscillating, or strobe lights on a vehicle to a series of signs in advance of the TTC zone activity area.

##### Guidance:

Typical distances for placement of advance warning signs on freeways and expressways should be longer because drivers are conditioned to uninterrupted flow. Therefore, the advance warning sign placement should extend on these facilities as far as 800 m (0.5 mi) or more.

On urban streets, the effective placement of the first warning sign in meters (feet) should range from 0.75 to 1.5 times the speed limit in km/h (4 to 8 times the speed limit in mph), with the high end of the range being used when speeds are relatively high. When a single advance warning sign is used (in cases such as low-speed residential streets), the advance warning area can be as short as 30 m (100 ft). When two or more advance warning signs are used on higher-speed streets, such as major arterials, the advance warning area should extend a greater distance (see Table 6C-1).

Since rural highways are normally characterized by higher speeds, the effective placement of the first warning sign in meters (feet) should be substantially longer—from 1.5 to 2.25 times the speed limit in km/h (8 to 12 times the speed limit in mph). Since two or more advance warning signs are normally used for these conditions, the advance warning area should extend 450 m (1,500 ft) or more for open highway conditions (see Table 6C-1).

##### Option:

Advance warning may be eliminated when the activity area is sufficiently removed from the road users' path so that it does not interfere with the normal flow.

### **Section 6C.05 Transition Area**

#### Support:

The transition area is that section of highway where road users are redirected out of their normal path. Transition areas usually involve strategic use of tapers, which because of their importance are discussed separately in detail.

#### Standard:

**When redirection of the road users' normal path is required, they shall be channelized from the normal path to a new path.**

#### Support:

In mobile operations, the transition area moves with the work space.

### **Section 6C.06 Activity Area**

#### Support:

The activity area is the section of the highway where the work activity takes place. It is comprised of the work space, the traffic space, and the buffer space.

The work space is that portion of the highway closed to road users and set aside for workers, equipment, and material, and a shadow vehicle if one is used upstream. Work spaces are usually delineated for road users by channelizing devices or, to exclude vehicles and pedestrians, by temporary barriers.

#### Option:

The work space may be stationary or may move as work progresses.

#### Guidance:

Since there might be several work spaces (some even separated by several kilometers or miles) within the project limits, each work space should be adequately signed to inform road users and reduce confusion.

#### Support:

The traffic space is the portion of the highway in which road users are routed through the activity area.

The buffer space is a lateral and/or longitudinal area that separates road user flow from the work space or an unsafe area, and might provide some recovery space for an errant vehicle.

#### Guidance:

Neither work activity nor storage of equipment, vehicles, or material should occur within a buffer space.

#### Option:

Buffer spaces may be positioned either longitudinally or laterally with respect to the direction of road user flow. The activity area may contain one or more lateral or longitudinal buffer spaces.

A longitudinal buffer space may be placed in advance of a work space.

The longitudinal buffer space may also be used to separate opposing road user flows that use portions of the same traffic lane, as shown in Figure 6C-2.

If a longitudinal buffer space is used, the values shown in Table 6C-2 may be used to determine the length of the longitudinal buffer space.

#### Support:

Typically, the buffer space is formed as a traffic island and defined by channelizing devices.

When a shadow vehicle, arrow panel, or changeable message sign is placed in a closed lane in advance of a work space, only the area upstream of the vehicle, arrow panel, or changeable message sign constitutes the buffer space.

Option:

The lateral buffer space may be used to separate the traffic space from the work space, as shown in Figures 6C-1 and 6C-2, or such areas as excavations or pavement-edge drop-offs. A lateral buffer space also may be used between two travel lanes, especially those carrying opposing flows.

Guidance:

The width of a lateral buffer space should be determined by engineering judgment.

Option:

When work occurs on a high-volume, highly congested facility, a vehicle storage or staging space may be provided for incident response and emergency vehicles (for example, tow trucks and fire apparatus) so that these vehicles can respond quickly to road user incidents.

Guidance:

If used, an incident response and emergency-vehicle storage area should not extend into any portion of the buffer space.

### **Section 6C.07 Termination Area**

**Standard:**

**The termination area shall be used to return road users to their normal path. The termination area shall extend from the downstream end of the work area to the last TTC device such as END ROAD WORK signs, if posted.**

Option:

An END ROAD WORK sign, a Speed Limit sign, or other signs may be used to inform road users that they can resume normal operations.

A longitudinal buffer space may be used between the work space and the beginning of the downstream taper.

### **Section 6C.08 Tapers**

Option:

Tapers may be used in both the transition and termination areas. Whenever tapers are to be used in close proximity to an interchange ramp, crossroads, curves, or other influencing factors, the length of the tapers may be adjusted.

Support:

Tapers are created by using a series of channelizing devices and/or pavement markings to move traffic out of or into the normal path. Types of tapers are shown in Figure 6C-2.

Longer tapers are not necessarily better than shorter tapers (particularly in urban areas with characteristics such as short block lengths or driveways) because extended tapers tend to encourage sluggish operation and to encourage drivers to delay lane changes unnecessarily. The test concerning adequate lengths of tapers involves observation of driver performance after TTC plans are put into effect.


Guidance:

The appropriate taper length (L) should be determined using the criteria shown in Tables 6C-3 and 6C-4.

The maximum distance in meters (feet) between devices in a taper should not exceed 0.2 times the speed limit in km/h (1.0 times the speed limit in mph).

OMUTCD - English units are preferred.

**Figure 6C-2. Types of Tapers and Buffer Spaces**



\* A shifting taper should be  $L$  when the speed is greater than or equal to 50 mph, and may be  $0.5L$  when the speed is less than 50 mph.

**Table 6C-2. Stopping Sight Distance as a Function of Speed**

Speed * (km/h)	Distance (m)
30	35
40	50
50	65
60	85
70	105
80	130
90	160
100	185
110	220
120	250

Speed * (mph)	Distance (ft)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\* Posted speed, off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed

**Support:**

A merging taper requires the longest distance because drivers are required to merge into common road space.

**Guidance:**

A merging taper should be long enough to enable merging drivers to have adequate advance warning and sufficient length to adjust their speeds and merge into a single lane before the end of the transition.

**Support:**

A shifting taper is used when a lateral shift is needed. When more space is available, a longer than minimum taper distance can be beneficial. Changes in alignment can also be accomplished by using horizontal curves designed for normal highway speeds.

**Guidance:**

Where speeds are 50 miles per hour or greater, a shifting taper should be approximately L in length.

**Option:**

Where speeds are less than 50 miles per hour, the shifting taper may be approximately 0.5L.

**Support:**

A shoulder taper may be beneficial on a high-speed roadway where shoulders are part of the activity area and are closed, or when improved shoulders might be mistaken as a driving lane. In these instances, the same type, but abbreviated, closure procedures used on a normal portion of the roadway can be used.

**Table 6C-3. Taper Length Criteria for Temporary Traffic Control Zones**

Type of Taper	Taper Length (L)
Merging Taper	at least L
Shifting Taper	0.5 L when speed is < 50 mph, and L when speed is ≥ 50 mph
Shoulder Taper	at least 0.33 L
One-Lane, Two-way Traffic Taper	300 m (100 ft) maximum
Downstream Taper	30 m (100 ft) per lane

**Table 6C-4. Formulas for Determining Taper Lengths**

Speed Limit (S)	Taper Length (L) Meters
60 km/h or less	$L = \frac{WS^2}{155}$
70 km/h or more	$L = \frac{WS}{1.6}$

Speed Limit (S)	Taper Length (L) Feet
40 mph or less	$L = \frac{WS^2}{60}$
45 mph or more	$L = WS$

Where: L = taper length in meters (feet)

W = width of offset in meters (feet)

S = posted speed limit, of off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in km/h (mph)

**Guidance:**

If used, shoulder tapers should have a length of approximately 0.33 L (see Tables 6C-3 and 6C-4). If a shoulder is used as a travel lane, either through practice or during a TTC activity, a normal merging or shifting taper should be used.

**Option:**

A downstream taper may be useful in termination areas to provide a visual cue to the driver that access is available back into the original lane or path that was closed.

**Guidance:**

When used, a downstream taper should have a length of approximately 30 m (100 ft) per lane with devices placed at a spacing of approximately 6.1 m (20 ft).

**Support:**

The one-lane, two-way taper is used in advance of an activity area that occupies part of a two-way roadway in such a way that a portion of the road is used alternately by traffic in each direction.

**Guidance:**

Traffic should be controlled by a flagger or temporary traffic control signal (if sight distance is limited), or a STOP or YIELD sign. A short taper having a maximum length of 30 m (100 ft) with channelizing devices at approximately 6.1 m (20 ft) spacings should be used to guide traffic into the one-way section.

**Support:**

An example of a one-lane, two-way traffic taper is shown in Figure 6C-3.

**Section 6C.09 Detours and Diversions****Support:**

A detour is a temporary rerouting of road users onto an existing highway in order to avoid a TTC zone.

**Guidance:**

Detours should be clearly signed over their entire length so that road users can easily use existing highways to return to the original highway.

**Support:**

A diversion is a temporary rerouting of road users onto a temporary highway or alignment placed around the work area.

**Section 6C.10 One-Lane, Two-Way Traffic Control****Standard:**

**When traffic in both directions must use a single lane for a limited distance, movements from each end shall be coordinated.**

**Guidance:**

Provisions should be made for alternate one-way movement through the constricted section via methods such as flagger control, a flag transfer, a pilot car, traffic control signals, or stop or yield control.

Control points at each end should be chosen to permit easy passing of opposing lanes of vehicles.

If traffic on the affected one-lane roadway is not visible from one end to the other, then flagging procedures, a pilot car with a flagger used as described in Section 6F.54, or a traffic control signal should be used to control opposing traffic flows.

**Support:**

At a spot constriction, such as an isolated pavement patch on highways with lower speeds and adequate sight distance, the movement of traffic through one-lane, two-way constrictions tends to be self-regulating.

**Section 6C.11 Flagger Method of One-Lane, Two-Way Traffic Control****Option:**

When a one-lane, two-way TTC zone is short enough to allow a flagger to see from one end of the zone to the other, traffic may be controlled by either a single flagger or by a flagger at each end of the section.

**Guidance:**

When a single flagger is used, the flagger should be stationed on the shoulder opposite the constriction or work space, or in a position where good visibility and traffic control can be maintained at all times. When good visibility and traffic control cannot be maintained by one flagger station, traffic should be controlled by a flagger at each end of the section. One of the flaggers should be designated as the coordinator. Flaggers should be able to communicate with each other orally, electronically, or with manual signals. These manual signals should not be mistaken for flagging signals.

**Section 6C.12 Flag Transfer Method of One-Lane, Two-Way Traffic Control****Support:**

The driver of the last vehicle proceeding into the one-lane section is given a red flag (or other token) and instructed to deliver it to the flagger at the other end. The opposite flagger, upon receipt of the flag, then knows that it is reasonably safe to allow traffic to move in the other direction. A variation of this method is to replace the use of a flag with an official pilot car that always follows the last road user vehicle proceeding through the section.

**Guidance:**

The flag transfer method should be employed only where the one-way traffic is confined to a relatively short length of a road, usually not more than 1.6 km (1 mi) in length.

**Section 6C.13 Pilot Car Method of One-Lane, Two-Way Traffic Control****Option:**

A pilot car may be used to guide a queue of vehicles through the TTC zone or detour.

**Guidance:**

The operation of the pilot vehicle should be coordinated with flagging operations or other controls at each end of the one-lane section. The pilot car should have the name of the contractor or contracting authority prominently displayed.

**Standard:**

**The PILOT CAR FOLLOW ME (G20-4) sign (see Figure 6F-4, Sheet 4 of 4) shall be mounted at a conspicuous location on the rear of the vehicle.**

**Section 6C.14 Temporary Traffic Control Signal Method of One-Lane, Two-Way Traffic Control****Option:**

Traffic control signals may be used to control vehicular traffic movements in one-lane, two-way TTC zones (see Figure 6H-12 and Chapter 4G).


**Section 6C.15 Stop or Yield Control Method of One-Lane, Two-Way Traffic Control****Option:**

STOP or YIELD signs may be used to control traffic on low-volume roads at a one-lane, two-way TTC zone when drivers are able to see the other end of the one-lane, two-way operation and have sufficient visibility of approaching vehicles.

**Guidance:**

If the STOP or YIELD sign is installed for only one direction, then the STOP or YIELD sign should face road users who are driving on the side of the roadway that is closed for the work activity area.

**Figure 6C-3. Example of a One-Lane, Two-Way Traffic Taper**



## CHAPTER 6D. PEDESTRIAN AND WORKER SAFETY

### Section 6D.01 Pedestrian Considerations

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

A wide range of pedestrians might be affected by TTC zones, including the young, elderly, and people with disabilities such as hearing, visual, or mobility. These pedestrians need a clearly delineated and usable travel path. Considerations for pedestrians with disabilities are addressed in Section 6D.02.

The most desirable way to provide information to pedestrians with visual disabilities that is equivalent to visual signage for notification of sidewalk closures is a speech message provided by an audible information device. Devices that provide speech messages in response to passive pedestrian actuation are the most desirable. Other devices that continuously emit a message, or that emit a message in response to use of a pushbutton, are also acceptable. Signage information can also be transmitted to personal receivers, but currently such receivers are not likely to be carried or used by pedestrians with visual disabilities in TTC zones. Audible information devices might not be needed if detectable channelizing devices make an alternate route of travel evident to pedestrians with visual disabilities.

Guidance:

If a pushbutton is used to provide equivalent TTC information to pedestrians with visual disabilities, the pushbutton should be equipped with a locator tone to notify pedestrians with visual disabilities that a special accommodation is available, and to help them locate the pushbutton.

**Standard:**

**The various TTC provisions for pedestrian and worker safety set forth in Part 6 shall be applied by knowledgeable (for example, trained and/or certified) persons after appropriate evaluation and engineering judgment.**

**Advance notification of sidewalk closures shall be provided to the maintaining agency. Where pedestrians with visual disabilities normally use the closed sidewalk, a barrier that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.**

Support:

It must be recognized that pedestrians are reluctant to retrace their steps to a prior intersection for a crossing or to add distance or out-of-the-way travel to a destination.

Guidance:

Adequate provisions should be made for persons with disabilities as determined by an engineering study or by engineering judgment. Because printed signs and surface delineation are not usable by pedestrians with visual disabilities, blocked routes, alternate crossings, and sign and signal information should be communicated to pedestrians with visual disabilities by providing audible information devices, accessible pedestrian signals, and barriers and channelizing devices that are detectable to pedestrians traveling with the aid of a long cane or who have low vision.

The following three items should be considered when planning for pedestrians in TTC zones:

- A. Pedestrians should not be led into conflicts with work site vehicles, equipment, and operations.

- B. Pedestrians should not be led into conflicts with vehicles moving through or around the work site.
- C. Pedestrians should be provided with a reasonably safe, convenient, and accessible path that replicates as nearly as practical the most desirable characteristics of the existing sidewalk(s) or footpath(s). Where pedestrians who have visual disabilities encounter work sites that require them to cross the roadway to find an accessible route, instructions should be provided using an audible information device. Accessible pedestrian signals (see Section 4E.06) with accessible pedestrian detectors (see Section 4E.09) might be needed to enable pedestrians with visual disabilities to cross wide or heavily traveled roadways.

A pedestrian route should not be severed and/or moved for nonconstruction activities such as parking for vehicles and equipment.

Consideration should be made to separate pedestrian movements from both work site activity and vehicular traffic. Unless a reasonably safe route that does not involve crossing the roadway can be provided, pedestrians should be appropriately directed with advance signing that encourages them to cross to the opposite side of the roadway. In urban and suburban areas with high vehicular traffic volumes, these signs should be placed at intersections (rather than midblock locations) so that pedestrians are not confronted with midblock work sites that will induce them to attempt skirting the work site or making a midblock crossing.

**Support:**

Figures 6H-28 and 6H-29 show typical TTC device usage and techniques for pedestrian movement through work zones.

**Guidance:**

When pedestrian movement through or around a work site is necessary, a separate usable footpath should be provided. If the previous pedestrian facility was accessible to pedestrians with disabilities, the footpath provided during temporary traffic control should also be accessible. There should not be any abrupt changes in grade or terrain that could cause a tripping hazard or could be a barrier to wheelchair use. Barriers and channelizing devices should be detectable to pedestrians who have visual disabilities (see Section 6F.68).

**Option:**

Whenever it is feasible, closing off the work site from pedestrian intrusion may be preferable to channelizing pedestrian traffic along the site with TTC devices.

**Support:**

Maintaining a detectable, channelized pedestrian route is much more useful to pedestrians who have visual disabilities than closing a walkway and providing audible directions to an alternate route involving additional crossings and a return to the original route. Braille is not useful in conveying such information because it is difficult to find. Audible instructions might be provided, but the extra distance and additional street crossings might add complexity to a trip.

**Guidance:**

Fencing should not create sight distance restrictions for road users. Fences should not be constructed of materials that would be hazardous if impacted by vehicles.

Wooden railing, fencing, and similar systems placed immediately adjacent to motor vehicle traffic should not be used as substitutes for crashworthy temporary traffic barriers.

**Standard:**

**TTC devices used to delineate a TTC zone pedestrian walkway shall be crashworthy and, when struck by vehicles, present a minimum threat to pedestrians, workers, and occupants of impacting vehicles.**

**Guidance:**

Ballast for TTC devices should be kept to the minimum amount needed and should be mounted low to prevent penetration of the vehicle windshield.

Movement by work vehicles and equipment across designated pedestrian paths should be minimized and, when necessary, should be controlled by flaggers or TTC. Staging or stopping of work vehicles or equipment along the side of pedestrian paths should be avoided, since it encourages movement of workers, equipment, and materials across the pedestrian path.

Access to the work space by workers and equipment across pedestrian walkways should be minimized because the access often creates unacceptable changes in grade, and rough or muddy terrain, and pedestrians will tend to avoid these areas by attempting nonintersection crossings where no curb ramps are available.

**Option:**

A canopied walkway may be used to protect pedestrians from falling debris, and to provide a covered passage for pedestrians.

**Guidance:**

Covered walkways should be sturdily constructed and adequately lighted for nighttime use.

When pedestrian and vehicle paths are rerouted to a closer proximity to each other, consideration should be given to separating them by a temporary traffic barrier.

If a temporary traffic barrier is used to shield pedestrians, it should be designed to accommodate site conditions.

**Support:**

Depending on the possible vehicular speed and angle of impact, temporary traffic barriers might deflect upon impact by an errant vehicle. Guidance for locating and designing temporary traffic barriers can be found in Chapter 9 of AASHTO's "Roadside Design Guide" (see Section 1A.11).

**Standard:**

**Short intermittent segments of temporary traffic barrier shall not be used because they nullify the containment and redirective capabilities of the temporary traffic barrier, increase the potential for serious injury both to vehicle occupants and pedestrians, and encourage the presence of blunt, leading ends. All upstream leading ends that are present shall be appropriately flared or protected with properly installed and maintained crashworthy cushions. Adjacent temporary traffic barrier segments shall be properly connected in order to provide the overall strength required for the temporary traffic barrier to perform properly.**

**Normal vertical curbing shall not be used as a substitute for temporary traffic barriers when temporary traffic barriers are clearly needed.**

**Option**

Temporary traffic barriers or longitudinal channelizing devices may be used to discourage pedestrians from unauthorized movements into the work space. They may also be used to inhibit conflicts with vehicular traffic by minimizing the possibility of midblock crossings.

**Support:**

A major concern for pedestrians is urban and suburban building construction encroaching onto the contiguous sidewalks, which forces pedestrians off the curb into direct conflict with moving vehicles.

**Guidance:**

If a significant potential exists for vehicle incursions into the pedestrian path, pedestrians should be rerouted or temporary traffic barriers should be installed.

**Support:**

TTC devices, portable concrete barriers, and wood or chainlink fencing with a continuous detectable edging can satisfactorily delineate a pedestrian path.

**Guidance:**

Tape, rope, or plastic chain strung between devices are not detectable, do not comply with the design standards in the “Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)” (see Section 1A.11), and should not be used as a control for pedestrian movements.

The extent of pedestrian needs should be determined through engineering judgment for each TTC zone situation. In general, pedestrian routes should be preserved in urban and commercial suburban areas. Alternative routing should be discouraged.

The highway agency in charge of the TTC zone should regularly inspect the activity area so that effective pedestrian TTC is maintained.

**Section 6D.02 Accessibility Considerations****Support:**

Additional information on the design and construction of accessible temporary facilities is found in publications listed in Section 1A.11 (see Documents 10 and 29 through 31).

**Guidance:**

The extent of pedestrian needs should be determined through engineering judgment or by the individual responsible for each TTC zone situation. This individual should be aware that the absence of a continuous pathway, including curb ramps and other accessible features, might preclude the use of the facility by pedestrians with disabilities.

**Standard:**

**When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and include accessibility features consistent with the features present in the existing pedestrian facility.**

**Guidance:**

To accommodate the needs of pedestrians, including those with disabilities, the following considerations should be addressed when temporary pedestrian pathways in TTC zones are designed or modified:

- A. Provisions for continuity of accessible paths for pedestrians should be incorporated into the TTC process. Pedestrians should be provided with a reasonably safe, convenient, and accessible path that replicates as much as practical the desirable characteristics of the existing pedestrian facilities.
- B. Access to temporary transit stops should be provided.
- C. Blocked routes, alternate crossings, and sign and signal information should be communicated to pedestrians with visual disabilities by providing devices such as audible information devices, accessible pedestrian signals, or barriers and channelizing devices that are detectable to the pedestrians traveling with the aid of a long cane or who have low vision. Where pedestrian traffic is detoured to a TTC signal, engineering judgment should be used to determine if pedestrian signals or accessible pedestrian signals should be considered for crossings along an alternate route.
- D. When channelization is used to delineate a pedestrian pathway, a continuous detectable edging should be provided throughout the length of the facility such that pedestrians using a long cane can follow it. These detectable edgings should adhere to the provisions of Section 6F.68.
- E. A smooth, continuous hard surface should be provided throughout the entire length of the temporary pedestrian facility. There should be no curbs or abrupt changes in grade or terrain that could cause tripping or be a barrier to wheelchair use. The geometry and alignment of the facility should meet the applicable requirements of the “Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)” (see Section 1A.11).

- F. The width of the existing pedestrian facility should be provided for the temporary facility if practical. Traffic control devices and other construction materials and features should not intrude into the usable width of the sidewalk, temporary pathway, or other pedestrian facility. When it is not possible to maintain a minimum width of 1500 mm (60 in) throughout the entire length of the pedestrian pathway, a 1500 x 1500 mm (60 x 60 in) passing space should be provided at least every 60 m (200 ft), to allow individuals in wheelchairs to pass.
- G. Signs and other devices mounted lower than 2.1 m (7 ft) above the temporary pedestrian pathway should not project more than 100 mm (4 in) into accessible pedestrian facilities.

### **Section 6D.03 Worker Safety Considerations**

#### **Support:**

Equally as important as the safety of road users traveling through the TTC zone is the safety of workers. TTC zones present temporary and constantly changing conditions that are unexpected by the road user. This creates an even higher degree of vulnerability for workers on or near the roadway.

Maintaining TTC zones with road user flow inhibited as little as possible, and using TTC devices that get the road user's attention and provide positive direction are of particular importance. Likewise, equipment and vehicles moving within the activity area create a risk to workers on foot. When possible, the separation of moving equipment and construction vehicles from workers on foot provides the operator of these vehicles with a greater separation clearance and improved sight lines to minimize exposure to the hazards of moving vehicles and equipment.

#### **Guidance:**

The following are the key elements of worker safety and TTC management that should be considered to improve worker safety:

- A. Training—all workers should be trained on how to work next to motor vehicle traffic in a way that minimizes their vulnerability. Workers having specific TTC responsibilities should be trained in TTC techniques, device usage, and placement.
- B. Worker Safety Apparel—all workers exposed to the risks of moving roadway traffic or construction equipment should wear high-visibility safety apparel meeting the requirements of ISEA “American National Standard for High-Visibility Safety Apparel” (see Section 1A.11), or equivalent revisions, and labeled as ANSI 107-1999 standard performance for Class 1, 2, or 3 risk exposure. A competent person designated by the employer to be responsible for the worker safety plan within the activity area of the job site should make the selection of the appropriate class of garment.
- C. Temporary Traffic Barriers—temporary traffic barriers should be placed along the work space depending on factors such as lateral clearance of workers from adjacent traffic, speed of traffic, duration and type of operations, time of day, and volume of traffic.
- D. Speed Reduction—reducing the speed of vehicular traffic, mainly through regulatory speed zoning, funneling, lane reduction, or the use of uniformed law enforcement officers or flaggers, should be considered.
- E. Activity Area—planning the internal work activity area to minimize backing-up maneuvers of construction vehicles should be considered to minimize the exposure to risk.
- F. Worker Safety Planning—a competent person designated by the employer should conduct a basic hazard assessment for the work site and job classifications required in the activity area. This safety professional should determine whether engineering, administrative, or personal protection measures should be implemented. This plan should be in accordance with the Occupational Safety and Health Act of 1970, as amended, “General Duty Clause” Section 5(a)(1) - Public Law 91-596, 84 Stat. 1590, December 29, 1970, as amended, and with the requirement to assess worker risk exposures for each job site and job classification, as per 29 CFR 1926.20 (b)(2) of “Occupational Safety and Health Administration Regulations, General Safety and Health Provisions ” (see Section 1A.11).

**Option:**

The following are additional elements of TTC management that may be considered to improve worker safety:

- A. **Shadow Vehicle**—in the case of mobile and constantly moving operations, such as pothole patching and striping operations, a shadow vehicle, equipped with appropriate lights and warning signs may be used to protect the workers from impacts by errant vehicles. The shadow vehicle may be equipped with a rear-mounted impact attenuator.
- B. **Road Closure**—if alternate routes are available to handle road users, the road may be closed temporarily. This may also facilitate project completion and thus further reduce worker vulnerability.
- C. **Law Enforcement Use**—in highly vulnerable work situations, particularly those of relatively short duration, law enforcement units may be stationed to heighten the awareness of passing vehicular traffic and to improve safety through the TTC zone.
- D. **Lighting**—for nighttime work, the TTC zone and approaches may be lighted.
- E. **Special Devices**—these include rumble strips, changeable message signs, hazard identification beacons, flags, and warning lights. Intrusion warning devices may be used to alert workers to the approach of errant vehicles.

**Support:**

Judicious use of the special devices described in Item E above might be helpful for certain difficult TTC situations, but misuse or overuse of special devices or techniques might lessen their effectiveness.

## CHAPTER 6E. FLAGGER CONTROL

### Section 6E.01 Qualifications for Flaggers

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**A flagger shall be a person who provides TTC.**

Guidance:

Because flaggers are responsible for public safety and make the greatest number of contacts with the public of all highway workers, they should be trained in safe traffic control practices and public contact techniques. Flaggers should be able to satisfactorily demonstrate the following abilities:

- A. Ability to receive and communicate specific instructions clearly, firmly, and courteously;
- B. Ability to move and maneuver quickly in order to avoid danger from errant vehicles;
- C. Ability to control signaling devices (such as paddles and flags) in order to provide clear and positive guidance to drivers approaching a TTC zone in frequently changing situations;
- D. Ability to understand and apply safe traffic control practices, sometimes in stressful or emergency situations; and
- E. Ability to recognize dangerous traffic situations and warn workers in sufficient time to avoid injury.

### Section 6E.02 High-Visibility Safety Apparel

**Standard:**

**For daytime and nighttime activity, flaggers shall wear safety apparel meeting the requirements of ISEA “American National Standard for High-Visibility Apparel” (see Section 1A.11) and labeled as meeting the ANSI107-1999 standard performance for Class 2 risk exposure. The apparel background (outer) material color shall be either fluorescent orange-red or fluorescent yellow-green as defined in the standard. The retroreflective material shall be either orange, yellow, white, silver, yellow-green, or a fluorescent version of these colors, and shall be visible at a minimum distance of 300 m (1,000 ft). The retroreflective safety apparel shall be designed to clearly identify the wearer as a person.**

Guidance:

For nighttime activity, safety apparel meeting the requirements of ISEA “American National Standard for High-Visibility Apparel” (see Section 1A.11) and labeled as meeting the ANSI 107-1999 standard performance for Class 3 risk exposure should be considered for flagger wear (instead of the Class 2 safety apparel in the Standard above).

When uniformed law enforcement officers are used, high-visibility safety apparel as described in this Section should be worn by the law enforcement officer.

### Section 6E.03 Hand-Signaling Devices

Support:

Hand-signaling devices, such as STOP/SLOW paddles, lights, and red flags, are used to control road users through TTC zones.

Guidance:

The STOP/SLOW paddle should be the primary and preferred hand-signaling device because the STOP/SLOW paddle gives road users more positive guidance than red flags. Use of flags should be limited to emergency situations, intersections and low-speed and/or low-volume locations which can best be controlled by a single flagger.

**Standard:**

The STOP/SLOW paddle shall have an octagonal shape on a rigid handle. STOP/SLOW paddles shall be at least 450 mm (18 in) wide with letters at least 150 mm (6 in) high and should be fabricated from light semirigid material. The background of the STOP face shall be red with white letters and border. The background of the SLOW face shall be orange with black letters and border. When used at night, the STOP/SLOW paddle shall be retroreflectorized.

**Option:**

The STOP/SLOW paddle may be modified to improve conspicuity by incorporating either white or red flashing lights on the STOP face, and either white or yellow flashing lights on the SLOW face. The flashing lights may be arranged in any of the following patterns:

- A. Two white or red lights, one centered vertically above and one centered vertically below the STOP legend; and/or two white or yellow lights, one centered vertically above and one centered vertically below the SLOW legend; or
- B. Two white or red lights, one centered horizontally on each side of the STOP legend; and/or two white or yellow lights, one centered horizontally on each side of the SLOW legend; or
- C. One white or red light centered below the STOP legend; and/or one white or yellow light centered below the SLOW legend; or
- D. A series of eight or more small white or red lights no larger than 6 mm (0.25 in) in diameter along the outer edge of the paddle, arranged in an octagonal pattern at the eight corners of the border of the STOP face; and/or a series of eight or more small white or yellow lights no larger than 6 mm (0.25 in) in diameter along the outer edge of the paddle, arranged in a diamond pattern along the border of the SLOW face.
- E. A series of white lights forming the shapes of the letters in the legend.

**Standard:**

If flashing lights are used on the STOP face of the paddle, their colors shall be all white or all red. If flashing lights are used on the SLOW face of the paddle, their colors shall be all white or all yellow.

If more than eight flashing lights are used, the lights shall be arranged such that they clearly convey the octagonal shape of the STOP face of the paddle and/or the diamond shape of the SLOW face of the paddle.

If flashing lights are used on the STOP/SLOW paddle, the flash rate shall be at least 50, but not more than 60, flashes per minute.

Flags, when used, shall be a minimum of 600 mm (24 in) square, made of a good grade of red material, and securely fastened to a staff that is approximately 900 mm (36 in) in length.

**Guidance:**

The free edge of a flag should be weighted so the flag will hang vertically, even in heavy winds.

**Standard:**

When used at nighttime, flags shall be retroreflectorized red.


**Section 6E.04 Flagger Procedures****Support:**

The use of paddles and flags by flaggers is illustrated in Figure 6E-1.

### Figure 6E-1. Use of Hand-Signaling Devices by Flaggers

**PREFERRED METHOD**  
**STOP/SLOW Paddle**

**EMERGENCY SITUATIONS ONLY**  
**Red Flag**



**TO STOP TRAFFIC**



**TO LET TRAFFIC PROCEED**



**TO ALERT AND SLOW TRAFFIC**

**Standard:**

**The following methods of signaling with paddles shall be used:**

- A. To stop road users, the flagger shall face road users and aim the STOP paddle face toward road users in a stationary position with the arm extended horizontally away from the body. The free arm shall be held with the palm of the hand above shoulder level toward approaching traffic.**
- B. To direct stopped road users to proceed, the flagger shall face road users with the SLOW paddle face aimed toward road users in a stationary position with the arm extended horizontally away from the body. The flagger shall motion with the free hand for road users to proceed.**
- C. To alert or slow traffic, the flagger shall face road users with the SLOW paddle face aimed toward road users in a stationary position with the arm extended horizontally away from the body.**

**Option:**

To further alert or slow traffic, the flagger holding the SLOW paddle face toward road users may motion up and down with the free hand, palm down.

**Standard:**

**The following methods of signaling with a flag shall be used:**

- A. To stop road users, the flagger shall face road users and extend the flag staff horizontally across the road users' lane in a stationary position so that the full area of the flag is visibly hanging below the staff. The free arm shall be held with the palm of the hand above the shoulder level toward approaching traffic.**
- B. To direct stopped road users to proceed, the flagger shall stand parallel to the road user movement and with flag and arm lowered from the view of the road users, and shall motion with the free hand for road users to proceed. Flags shall not be used to signal road users to proceed.**
- C. To alert or slow traffic, the flagger shall face road users and slowly wave the flag in a sweeping motion of the extended arm from shoulder level to straight down without raising the arm above a horizontal position. The flagger shall keep the free hand down.**

**Section 6E.05 Flagger Stations****Standard:**

**Flagger stations shall be located such that approaching road users will have sufficient distance to stop at an intended stopping point.**

**Option:**

The distances shown in Table 6E-1, which provides information regarding the stopping sight distance as a function of speed, may be used for the location of a flagger station. These distances may be increased for downgrades and other conditions that affect stopping distance.

**Guidance:**

Flagger stations should be located such that an errant vehicle has additional space to stop without entering the work space.

**Standard:**

**Except in emergency situations, flagger stations shall be preceded by an advance warning sign or signs. Except in emergency situations, flagger stations shall be illuminated at night.**

**Guidance:**

The flagger should stand either on the shoulder adjacent to the road user being controlled or in the closed lane prior to stopping road users. A flagger should only stand in the lane being used by moving road users after road users have stopped. The flagger should be clearly visible to the first approaching road user at all times. The flagger also should be visible to other road users. The flagger should be stationed sufficiently in advance of the workers to warn them (for example, with audible warning devices such as horns or whistles) of approaching danger by out-of-control vehicles. The flagger should stand alone, never permitting a group of workers to congregate around the flagger station.

**Option:**

At a spot constriction, the flagger may have to take a position on the shoulder opposite the closed section in order to operate effectively.

At spot lane closures where adequate sight distance is available for the reasonably safe handling of traffic, the use of one flagger may be sufficient.

**Table 6E-1. Stopping Sight Distance as a Function of Speed**

Speed * (km/h)	Distance (m)
30	35
40	50
50	65
60	85
70	105
80	130
90	160
100	185
110	220
120	250

Speed * (mph)	Distance (ft)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\* Posted speed, off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed

Intentionally blank.

## CHAPTER 6F. TEMPORARY TRAFFIC CONTROL ZONE DEVICES

### Section 6F.01 Types of Devices

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Guidance:

The design and application of TTC devices used in TTC zones should consider the needs of all road users (motorists, bicyclists, and pedestrians), including those with disabilities.

Support:

FHWA policy requires that all roadside appurtenances such as traffic barriers, barrier terminals and crash cushions, bridge railings, sign and light pole supports, and work zone hardware used on the National Highway System meet the crashworthy performance criteria contained in the National Cooperative Highway Research Program (NCHRP) Report 350, “Recommended Procedures for the Safety Performance Evaluation of Highway Features.” The NCHRP 350 safety criteria also applies to the use of such roadside appurtenances used on ODOT-maintained highways. The website maintained by FHWA at [http://safety.fhwa.dot.gov/programs/roadside\\_硬件.htm](http://safety.fhwa.dot.gov/programs/roadside硬件.htm) identifies all such hardware and includes copies of FHWA acceptance letters for each of them. In the case of proprietary items, links are provided to manufacturers' websites as a source of detailed information on specific devices. The website also contains an “Ask the Experts” section where questions on roadside design issues can be addressed. Local agencies might also have expanded the NCHRP Report 350 crashworthy criteria to apply to other highways in addition to the National Highway System.

Crashworthiness and crash testing information on devices described in Part 6 are found in AASHTO’s “Roadside Design Guide” (see Section 1A.11).

As stated in Definition 17 in Section 1A.13, “crashworthy” is a characteristic of a roadside appurtenance that has been successfully crash tested in accordance with a national standard such as the National Cooperative Highway Research Program Report 350, “Recommended Procedures for the Safety Performance Evaluation of Highway Features.”

**Standard:**

**As noted in the Preface and Section 1A.13, traffic control devices shall be defined as all flaggers, signs, signals, markings, and devices placed or erected by authority of a public body or official having jurisdiction, for the purpose of regulating, warning, or guiding traffic, including signs denoting names of streets and highways (see Section 1A.13).**

**All traffic control devices used on street and highway construction, maintenance, utility, or incident management operations shall conform to the applicable provisions of this Manual.**

### Section 6F.02 General Characteristics of Signs

Support:

TTC zone signs convey both general and specific messages by means of words or symbols and have the same three categories as all road user signs: regulatory, warning, and guide.

See Part 2 for more information regarding sign uniformity.

**Standard:**

**The colors for regulatory signs shall follow the Standards for regulatory signs in Table 2A-5 and Chapter 2B. Warning signs in TTC zones shall have a black legend and border on an orange background, except for the Highway-Rail Grade Crossing Advance Warning (W10-1) sign which shall have a black legend and border on a yellow background, and except for signs that are permitted in Part 2 or 7 to have fluorescent yellow-green backgrounds. Colors for guide signs shall follow the Standards in Table 2A-5 and Chapter 2D, except for guide signs as noted in Section 6F. 50.**

**Option:**

Where the color orange is required, fluorescent red-orange or fluorescent yellow-orange colors may also be used.

**Support:**

The fluorescent versions of orange provide higher conspicuity than standard orange, especially during twilight.

Warning and guide signs used for TTC incident management situations (see Chapter 6I) may have a black legend and border on a fluorescent pink background.

Existing warning signs that are still applicable may remain in place.

In order to maintain the systematic use of yellow or fluorescent yellow-green backgrounds for pedestrian, bicycle, and school warning signs in a jurisdiction, the yellow or fluorescent yellow-green background for pedestrian, bicycle, and school warning signs may be used in TTC zones.

Standard orange flags or flashing warning lights may be used in conjunction with signs.

**Standard:**

**When standard orange flags or flashing warning lights are used in conjunction with signs, they shall not block the sign face.**

**The sizes for TTC signs shall be as shown in Table 6F-1.**

**Option:**

The dimensions of signs shown in Table 6F-1 may be increased wherever necessary for greater legibility or emphasis, such as on freeways and expressways.

**Standard:**

**Deviations from standard sizes as prescribed herein shall be in 150 mm (6 in) increments.**

**Support:**

Sign design details are contained in the "Sign Design Manual" (SDM) (see Section 1A.11).

**Standard:**

**All signs used at night shall be either retroreflective with a material that has a smooth, sealed outer surface or illuminated to show the same shape and similar color both day and night.**

**The requirement for sign illumination shall not be considered to be satisfied by street, highway, or strobe lighting.**

**Option:**

Sign illumination may be either internal or external.

Signs may be made of rigid or flexible material.

### **Section 6F.03 Sign Placement**

#### Guidance:

Signs should be located on the right side of the roadway unless otherwise specified in this Manual.

#### Option:

Where special emphasis is needed, signs may be placed on both the left and right sides of the roadway. Signs mounted on portable supports may be placed within the roadway itself. Signs may also be mounted on or above barricades.

#### Support:

The Provisions of this section regarding mounting height apply unless specifically stated otherwise for a particular sign elsewhere in this Manual.

Guidelines for height and lateral clearance of temporary ground-mounted signs are shown in Figure 6F-1.

#### **Standard:**

**Ground-mounted signs installed at the side of the road in rural areas shall be mounted at a height at least 1.5 m (5 ft), measured from the bottom of the sign to the near edge of the pavement. In business, commercial, and residential districts where parking and/or bicycle or pedestrian movement is likely to occur, or where there are other obstructions to view, the distance between the bottom of the sign and the top of the near edge of the traveled way shall be at least 2.1 m (7 ft).**

**Signs mounted on barricades and barricade/sign combinations shall be crashworthy.**

**Where it has been determined that the accommodation of pedestrians with disabilities is necessary, signs shall be mounted and placed in accordance with Section 4.4 of the “Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)” (see Section 1A.11).**

#### Guidance:

Neither portable nor permanent sign supports should be located on sidewalks, bicycle facilities, or areas designated for pedestrian or bicycle traffic. Signs mounted lower than 2.1 m (7 ft) should not project more than 100 mm (4 in) into pedestrian facilities.

#### Option:

A 2.1 m (7 ft) mounting height may be used in rural areas for increased visibility.

The height to the bottom of a secondary sign mounted below another sign may be 0.3 m (1 ft) less than the appropriate height specified above.

#### Guidance:

Except as noted in the Option, signs mounted on portable supports should not be used for a duration of more than 3 days.

Regulatory or guide signs mounted on fixed or movable Type III barricades should be mounted so that the center of the sign is at or above the height of the top of the barricade. Other signs mounted on movable Type III barricades should be mounted below the top rail so that the top of the sign is in line with the top of the barricades. Guide signs, although ordinarily erected on posts, may also be mounted above barricades, but shall not interfere with the effectiveness of necessary regulatory and warning signs

#### Option:

The R9-8 through R9-11a series, R11 series, W1-6 through W1-8 series, M4-10, E5-1, or other similar type signs (see Figures 6F-3, 6F-4, and 6F-5) may be used on portable supports for longer than 3 days.

#### Support:

Methods of mounting signs other than on posts are illustrated in Figure 6F-2.

**Table 6F-1. Sizes of Temporary Traffic Control Signs (Sheet 1 of 5)**

Sign	Code No.	Conventional Road	Expressway	Freeway	Minimum	Oversized
STOP	R1-1	750 x 750 (30 x 30)	—	—	—	—
YIELD	R1-2	900x900x900 (36 x 36 x 36)	—	—	—	—
TO ONCOMING TRAFFIC	R1-2a	1200 X 600 (48 X 24)	—	—	—	—
Speed Limit	R2-1	600 x 750 (24 x 30)	—	—	—	—
VEHICLES OVER 4 TONS ...	R2-H2a	—	900 x 1200 (36 x 48)	1200 x 1500 (48 x 60)	—	—
SPEED LIMIT 65 VEHICLES OVER ...	R2-H2b	—	900 x 1800 (36 x 72)	1200 x 2400 (48 x 96)	—	—
Turn Prohibition	R3- 1, 2, 3, 4, 18	600 x 600 (24 x 24)	—	—	—	—
Mandatory Movement (1 lane)	R3-5	750 x 900 (30 x 36)	—	—	—	—
Optional Movement (1 lane)	R3-6	750 x 900 (30 x 36)	—	—	—	—
Mandatory Movement (text)	R3-7	750 x 750 (30 x 30)	—	—	—	—
Lane Use (2 lanes)	R3-8	750 x 750 (30 x 30)	—	—	—	—
DO NOT PASS	R4-1	600 x 750 (24 x 30)	—	—	—	—
PASS WITH CARE	R4-2	600 x 750 (24 x 30)	—	—	—	—
Keep Right	R4-7	600 x 750 (24 x 30)	—	—	—	—
STAY IN LANE	R4-9	600 x 750 (24 x 30)	—	—	—	—
DO NOT ENTER	R5-1	750 x 750 (30 x 30)	—	—	—	—
WRONG WAY	R5-1a	900 x 600 (36 x 24)	—	—	—	—
ONE WAY (inside arrow)	R6-1	900 x 300 (36 x 12)	—	—	—	—
ONE WAY (with arrow)	R6-2	450 x 600 (18 x 24)	—	—	—	—
No Parking (symbol)	R8-3a	600 x 600 (24 x 24)	—	—	—	—
Pedestrian Crosswalk	R9-8	900 x 450 (36 x 18)	—	—	—	—
SIDEWALK CLOSED	R9-9	600 x 300 (24 x 12)	—	—	—	—
SIDEWALK CLOSED USE OTHER SIDE	R9-10	600 x 300 (24 x 12)	—	—	—	—
SIDEWALK CLOSED AHEAD CROSS HERE	R9-11	600 x 300 (24 x 12)	—	—	—	—
SIDEWALK CLOSED CROSS HERE	R9-11a	600 x 300 (24 x 12)	—	—	—	—
ROAD CLOSED	R11-2	1200 x 750 (48 x 30)	—	—	—	—
ROAD CLOSED – LOCAL TRAFFIC ONLY	R11-3a, 4	1500 x 750 (60 x 30)	—	—	—	—

**Table 6F-1. Sizes of Temporary Traffic Control Signs (Sheet 2 of 5)**

Sign	Code No.	Conventional Road	Expressway	Freeway	Minimum	Oversized
Work Zone Increased Penalties	R11-H5a	600 x 1200 (24 x 48)	1200 X 2400 (48 x 96)	1200 X 2400 (48 x 96)	—	—
Weight Limit	R12-1, 2	600 x 750 (24 x 30)	—	—	—	—
Weight Limit (with symbols)	R12-5	750 x 1050 (30 x 42)	—	—	—	—
Turn and Curve Signs	W1-1, 2, 3, 4	750 x 750 (30 x 30)	—	—	—	—
Reverse Curve (2 or more lanes)	W1-4b, 4c	900 x 900 (36 x 36)	—	—	—	—
One-Direction Large Arrow	W1-6	1200 x 600 (48 x 24)	—	—	—	—
Chevron	W1-8	900 x 1200 (36 x 48)	—	—	—	—
Construction Arrow	W1-H11	750 x 750 (30 x 30)	—	—	—	—
Stop Ahead (symbol)	W3-1	900 x 900 (36 x 36)	—	—	—	—
Yield Ahead (symbol)	W3-2	900 x 900 (36 x 36)	—	—	—	—
Signal Ahead (symbol)	W3-3	900 x 900 (36 x 36)	—	—	—	—
BE PREPARED TO STOP	W3-4	900 x 900 (36 x 36)	—	—	—	—
Speed Limit XX Ahead (symbol)	W3-5	900 x 900 (36 x 36)	—	—	—	—
Reduced Speed Zone Ahead	W3-5a	900 x 900 (36 x 36)	—	—	—	—
Merging Traffic	W4-1, 5	900 x 900 (36 x 36)	—	—	—	—
Lane Ends (symbol)	W4-2	900 x 900 (36 x 36)	—	—	—	—
Added Lane	W4-3, 6	900 x 900 (36 x 36)	—	—	—	—
THRU TRAFFIC MERGE LEFT	W4-7	900 x 900 (36 x 36)	—	—	—	—
ROAD NARROWS	W5-1	900 x 900 (36 x 36)	—	—	—	—
NARROW BRIDGE	W5-2	900 x 900 (36 x 36)	—	—	—	—
ONE LANE BRIDGE	W5-3	900 x 900 (36 x 36)	—	—	—	—
RAMP NARROWS	W5-4	900 x 900 (36 x 36)	—	—	—	—
Divided Highway (symbol)	W6-1	900 x 900 (36 x 36)	—	—	—	—

**Table 6F-1. Sizes of Temporary Traffic Control Signs (Sheet 3 of 5)**

Sign	Code No.	Conventional Road	Expressway	Freeway	Minimum	Oversized
Divided Highway Ends (symbol)	W6-2	900 x 900 (36 x 36)	—	—	—	—
Two-Way Traffic	W6-3	750 x 750 (30 x 30)	—	—	—	—
TWO-WAY TRAFFIC (plaque)	W6-4	300 x 450 (12 x 18)	—	—	—	—
Hill (symbol)	W7-1	750 x 750 (30 x 30)	—	—	—	—
BUMP	W8-1	750 x 750 (30 x 30)	—	—	—	—
DIP	W8-2	750 x 750 (30 x 30)	—	—	—	—
PAVEMENT ENDS	W8-3	750 x 750 (30 x 30)	—	—	—	—
SOFT SHOULDER	W8-4	750 x 750 (30 x 30)	—	—	—	—
Slippery When Wet (symbol)	W8-5	750 x 750 (30 x 30)	—	—	—	—
TRUCK CROSSING	W8-6	750 x 750 (30 x 30)	—	—	—	—
LOOSE GRAVEL	W8-7	750 x 750 (30 x 30)	—	—	—	—
ROUGH ROAD	W8-8	750 x 750 (30 x 30)	—	—	—	—
LOW SHOULDER	W8-9	750 x 750 (30 x 30)	—	—	—	—
SHOULDER DROP-OFF	W8-9a	750 x 750 (30 x 30)	—	—	—	—
UNEVEN LANES	W8-11	900 x 900 (36 x 36)	—	—	—	—
NO CENTER LINE	W8-H12	900 x 900 (36 x 36)	—	—	—	—
NO EDGE LINE	W8-H12a	900 x 900 (36 x 36)	—	—	—	—
Lane Ends	W9-1, 2	900 x 900 (36 x 36)	—	—	—	—
LANE CLOSED AHEAD	W9-3	900 x 900 (36 x 36)	—	—	—	—
Center Lane Closed Ahead (symbol)	W9-3a	900 x 900 (36 x 36)	—	—	—	—
Railroad Advance Warning (circular)	W10-1	900 dia. (36 dia.)	—	—	—	—
Truck (symbol)	W11-10	750 x 750 (30 x 30)	—	—	—	—

**Table 6F-1. Sizes of Temporary Traffic Control Signs (Sheet 4 of 5)**

Sign	Code No.	Conventional Road	Expressway	Freeway	Minimum	Oversized
Two Arrow	W12-1	600 x 600 (24 x 24)	—	—	—	—
Low Clearance	W12-2	900 x 900 (36 x 36)	—	—	—	—
Advisory Speed (plaque)	W13-1	450 x 450 or 600 x 600 (18 x 18 or 24 x 24)	—	—	—	—
ON RAMP (plaque)	W13-4	900 x 900 (36 x 36)	—	—	—	—
NO PASSING ZONE (pennant)	W14-3	900x1200 x1200 (36 x 48 x 48)	—	—	—	—
XX FEET (plaque)	W16-2	600 x 450 (24 x 18)	—	—	—	—
Road Work (with distance)	W20-1	900 x 900 (36 x 36)	—	—	—	—
Detour (with distance)	W20-2	900 x 900 (36 x 36)	—	—	—	—
Road (Street) Closed (with distance)	W20-3	900 x 900 (36 x 36)	—	—	—	—
One Lane Road (with distance)	W20-4	900 x 900 (36 x 36)	—	—	—	—
Lane(s) Closed (with distance)	W20-5, 5a	900 x 900 (36 x 36)	—	—	—	—
Flagger (symbol)	W20-7a	900 x 900 (36 x 36)	—	—	—	—
WORKERS	W21-1	900 x 900 (36 x 36)	—	—	—	—
Workers (symbol)	W21-1a	900 x 900 (36 x 36)	—	—	—	—
FRESH OIL (TAR)	W21-2	750 x 750 (30 x 30)	—	—	—	—
ROAD MACHINERY AHEAD	W21-3	900 x 900 (36 x 36)	—	—	—	—
SHOULDER WORK	W21-5	750 x 750 (30 x 30)	—	—	—	—
SHOULDER CLOSED	W21-5a	750 x 750 (30 x 30)	—	—	—	—
SHOULDER CLOSED (with distance)	W21-5b	900 x 900 (36 x 36)	—	—	—	—
SURVEY CREW	W21-6	750 x 750 (30 x 30)	—	—	—	—
UTILITY WORK AHEAD	W21-7	900 x 900 (36 x 36)	—	—	—	—
BLASTING ZONE AHEAD	W22-1	1200 x 1200 (48 x 48)	—	—	—	—
TURN OFF 2-WAY RADIO AND CELL PHONE	W22-2	1050 x 900 (42 x 36)	—	—	—	—


**Table 6F-1. Sizes of Temporary Traffic Control Signs (Sheet 5 of 5)**

Sign	Code No.	Conventional Road	Expressway	Freeway	Minimum	Oversized
END BLASTING ZONE	W22-3	1050 x 900 (42 x 36)	—	—	—	—
SLOW TRAFFIC AHEAD	W23-1	1200 x 600 (48 x 24)	—	—	—	—
Double Reverse Curve (1 lane)	W24-1	900 x 900 (36 x 36)	—	—	—	—
Double Reverse Curve (2 lanes)	W24-1a	900 x 900 (36 x 36)	—	—	—	—
Double Reverse Curve (3 lanes)	W24-1b	900 x 900 (36 x 36)	—	—	—	—
ROAD WORK NEXT XX MILES	G20-1	900 x 450 (36 x 18)	—	—	—	—
END ROAD WORK	G20-2	900 x 450 (36 x 18)	—	—	—	—
PILOT CAR FOLLOW ME	G20-4	900 x 450 (36 x 18)	—	—	—	—
EXIT OPEN	E5-2	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	—	—
EXIT CLOSED	E5-2a	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	—	—
EXIT OPEN AHEAD	E5-H2b	1200 x 1200 (48 x 48)	1200 x 1200 (48 x 48)	1200 x 1200 (48 x 48)	—	—
EXIT CLOSED AHEAD	E5-H2c	1200 x 1200 (48 x 48)	1200 x 1200 (48 x 48)	1200 x 1200 (48 x 48)	—	—
EXIT ONLY	E5-3	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	1200 x 900 (48 x 36)	—	—
DETOUR (plaque)	M4-8	600 x 300 (24 x 12)	—	—	—	—
END DETOUR	M4-8a	600 x 450 (24 x 18)	—	—	—	—
END (plaque)	M4-8b	600 x 300 (24 x 12)	—	—	—	—
DETOUR (with arrow)	M4-9	750 x 600 (30 x 24)	—	—	—	—
Bike/Pedestrian Detour (with arrow)	M4-9a	750 x 600 (30 x 24)	—	—	—	—
PEDESTRIAN DETOUR (with arrow)	M4-9b	750 x 600 (30 x 24)	—	—	—	—
BIKE DETOUR (with arrow)	M4-9c	750 x 600 (30 x 24)	—	—	—	—
Detour (inside arrow)	M4-10	1200 x 450 (48 x 18)	—	—	—	—


## Notes:

1. Larger signs may be used wherever necessary for greater legibility or emphasis.
2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height.
3. For freeways and expressways, the size of diamond shaped TTC warning signs shall be a minimum of 1200 x 1200 mm (48 x 48 in).

**Figure 6F-1. Height and Lateral Location of Signs—Typical Installations**



**Figure 6F-2. Methods of Mounting Signs Other Than on Posts**



Note: Examples only, see NCHRP Report 350 regarding crashworthy designs.

**Guidance:**

Signs mounted on Type III barricades should not cover more than 50 percent of the top two rails or 33 percent of the total area of the three rails.

**Standard:**

**Sign supports shall be crashworthy. Large signs having an area exceeding 5 square meters (50 square feet) that are installed on multiple breakaway posts shall be mounted a minimum of 2.1 m (7 ft) above the ground.**

**Signs mounted on barricades, or other portable supports, shall be no less than 0.3 m (1 ft) above the traveled way.**

**Option:**

For mobile operations, a sign may be mounted on a work vehicle, a shadow vehicle, or a trailer stationed in advance of the TTC zone or moving along with it. The work vehicle, the shadow vehicle, and/or the trailer may or may not have an impact attenuator.

**Guidance:**

Unshielded sign posts placed in the clear zone should yield or breakaway upon impact to minimize obstructions to road users.

**Support:**

If alterations are made to specific traffic control device supports that have been successfully crash tested in accordance with NCHRP Report 350, the altered supports might not be considered to be crashworthy.

**Section 6F.04 Sign Maintenance****Standard:**

**Signs shall be properly maintained for cleanliness, visibility, and correct positioning.**

**Signs that have lost significant legibility shall be promptly replaced.**

**Section 6F.05 Regulatory Sign Authority****Support:**

Regulatory signs such as those shown in Figure 6F-3 and Appendix C inform road users of traffic laws or regulations and indicate the applicability of legal requirements that would not otherwise be apparent.

**Standard:**

**Regulatory signs shall be authorized by the public agency or official having jurisdiction and shall conform with Chapter 2B.**

**Section 6F.06 Regulatory Sign Design****Standard:**

**TTC regulatory signs shall conform to the Standards for regulatory signs presented in Part 2 and the "Sign Design Manual" (SDM) (see Section 1A.11).**

**Support:**

Regulatory signs are generally rectangular with a black legend and border on a white background. Exceptions include the STOP, YIELD, DO NOT ENTER, WRONG WAY, and ONE WAY signs.

**Option:**

The ONE WAY sign may be either a horizontal or vertical rectangular sign.

**Figure 6F-3. Regulatory Signs in Temporary Traffic Control Zones**  
(Sheet 1 of 2)



R1-1



R1-2



R1-2a



R2-1



R3-1



R3-2



R3-3



R3-4



R3-5



R3-6



R3-7



R3-8




R3-18



R4-1



R4-2



R4-7



R4-9



R5-1



R5-1a



R6-1



R6-2




R8-3a



R9-8

**Figure 6F-3. Regulatory Signs in Temporary Traffic Control Zones**  
(Sheet 2 of 2)



### Section 6F.07 Regulatory Sign Applications

#### Standard:

If a TTC zone requires regulatory measures different from those existing, the existing permanent regulatory devices shall be removed or covered and superseded by the appropriate temporary regulatory signs. This change shall be made in conformance with applicable ordinances or statutes of the jurisdiction.

### Section 6F.08 ROAD (STREET) CLOSED Sign (R11-2)

#### Guidance:

The ROAD (STREET) CLOSED (R11-2) sign (see Figure 6F-3, Sheet 2 of 2) should be used when the roadway is closed to all road users except contractors' equipment or officially authorized vehicles. The R11-2 sign should be accompanied by appropriate warning and detour signing.

#### Option:

The words BRIDGE OUT (or BRIDGE CLOSED) may be substituted for ROAD (STREET) CLOSED where applicable.

#### Guidance:

The ROAD (STREET) CLOSED sign should be installed at or near the center of the roadway on or above a Type III barricade that closes the roadway (see Section 6F.63).

**Standard:**

The ROAD (STREET) CLOSED sign shall not be used where road user flow is maintained or where the actual closure is some distance beyond the sign.

**Section 6F.09 Local Traffic Only Signs (R11-3a, R11-3b, R11-4, R11-H5)****Guidance:**

The Local Traffic Only signs (see Figure 6F-3, Sheet 2 of 2) should be used where road user flow detours to avoid a closure some distance beyond the sign, but where local road users can use the roadway to the point of closure. These signs should be accompanied by appropriate warning and detour signing.

In rural applications, the Local Traffic Only sign should have the legend ROAD CLOSED XX MILES AHEAD, LOCAL TRAFFIC ONLY (R11-3a).

The ROUTE CLOSED (R11-H5) sign should be used when the road on which it is used is not closed but the route, on another road, is closed. When used, the ROUTE CLOSED sign shall have attached to it a Route Marker (M1) sign.

**Option:**

In urban areas, the legend ROAD (STREET) CLOSED TO THRU TRAFFIC (R11-4) or ROAD CLOSED, LOCAL TRAFFIC ONLY may be used.

The words BRIDGE OUT (or BRIDGE CLOSED) may be substituted for the words ROAD (STREET) CLOSED on the R11-3a or R11-4 sign where applicable (see R11-3b in Appendix C).

**Section 6F.10 Weight Limit Signs (R12-1, R12-2, R12-5)****Standard:**

A Weight Limit sign (see Figure 6F-3, Sheet 2 of 2), which shows the gross weight or axle weight that is permitted on the roadway or bridge, shall be consistent with State or local regulations and shall not be installed without the approval of the authority having jurisdiction over the highway.

When weight restrictions are imposed because of the activity in a TTC zone, a marked detour shall be provided for vehicles weighing more than the posted limit.

**Section 6F.11 STAY IN LANE Sign (R4-9)****Option:**

A STAY IN LANE (R4-9) sign (see Figure 6F-3, Sheet 1 of 2) may be used where a multi-lane shift has been incorporated as part of the TTC on a highway to direct road users around road work that occupies part of the roadway on a multi-lane highway.

**Section 6F.12 PEDESTRIAN CROSSWALK Sign (R9-8)****Option:**

The PEDESTRIAN CROSSWALK (R9-8) sign (see Figure 6F-3, Sheet 1 of 2) may be used to indicate where a temporary crosswalk has been established.

**Standard:**

If a temporary crosswalk is established, it shall be accessible to pedestrians with disabilities in accordance with Section 6D.02.

### **Section 6F.13 SIDEWALK CLOSED Signs (R9-9, R9-10, R9-11, R9-11a)**

#### Guidance:

SIDEWALK CLOSED signs (see Figure 6F-3, Sheet 2 of 2) should be used where pedestrian flow is restricted. Bicycle/Pedestrian Detour (M4-9a) signs or Pedestrian Detour (M4-9b) signs should be used where pedestrian flow is rerouted (see Section 6F.53).

The SIDEWALK CLOSED (R9-9) sign should be installed at the beginning of the closed sidewalk, at the intersections preceding the closed sidewalk, and elsewhere along the closed sidewalk as needed.

The SIDEWALK CLOSED, (ARROW) USE OTHER SIDE (R9-10) sign should be installed at the beginning of the restricted sidewalk when a parallel sidewalk exists on the other side of the roadway.

The SIDEWALK CLOSED AHEAD, (ARROW) CROSS HERE (R9-11) sign should be used to indicate to pedestrians that sidewalks beyond the sign are closed and to direct them to open crosswalks, sidewalks, or other travel paths.

The SIDEWALK CLOSED, (ARROW) CROSS HERE (R9-11a) sign should be installed just beyond the point to which pedestrians are being redirected.

#### Support:

These signs are typically mounted on a detectable barricade to encourage compliance and to communicate with pedestrians that the sidewalk is closed. Printed signs are not useful to many pedestrians with visual disabilities. A barrier or barricade detectable by a person with a visual disability is sufficient to indicate that a sidewalk is closed. If the barrier is continuous with detectable channelizing devices for an alternate route, accessible signage might not be necessary. An audible information device is needed when the detectable barricade or barrier for an alternate channelized route is not continuous.

### **Section 6F.14 Special Regulatory Signs**

#### Option:

Special regulatory signs may be used based on engineering judgment consistent with regulatory requirements.

#### Guidance:

Special regulatory signs should conform to the general requirements of color, shape, and alphabet size and series. The sign message should be brief, legible, and clear.

#### **Section 6F.14.1 Work Zone Increased Penalties Sign (R11-H5a)**

#### Support:

O.R.C. Section 5501.27(A)(1) requires that the Director of Transportation “adopt rules governing the posting of signs advising motorists that increased penalties apply for certain traffic violations on streets or highways in a construction zone.” Also, O.R.C. Section 5501.27(A)(2) requires that the Director adopt “rules governing the posting of signs to be used pursuant to section 2903.081 of the Revised Code giving notice to motorists of the prohibitions set forth in sections 2903.06 and 2903.08 of the Revised Code regarding the death of or injury to any person in a construction zone as a proximate result of a reckless operation offense or speeding offense.”

#### Standard:

**In accordance with O.R.C. Section 4511.98, the “director of transportation, board of county commissioners, or board of township trustees shall cause signs to be erected advising motorists that increased penalties apply for certain traffic violations occurring on streets or highways in a construction zone. The increased penalties shall be effective only when signs are erected in accordance with the guidelines and design specifications established by the director under section 5501.27 of the Revised Code, and when a violation occurs during hours of actual work within the construction zone.”**

**The Work Zone Increased Penalties (R11-H5a) sign (see Appendix C) shall be used for this purpose.**

Support:

The guidelines established by the Director are in Part 6 of the ODOT "Traffic Engineering Manual" (TEM) (see Section 1A.11) and in Chapter 5501:2-10 of the Ohio Administrative Code (OAC). Administrative Code Section 5501:2-10-02 also requires that each agency adopt procedures pertaining to requiring a contractor, work crew, or utility to erect, maintain, and remove signs, in conformance with these guidelines.

### **Section 6F.15 Warning Sign Function, Design, and Application**

Support:

TTC zone warning signs (see Figure 6F-4 and Appendix C) notify road users of specific situations or conditions on or adjacent to a roadway that might not otherwise be apparent.

**Standard:**

**TTC warning signs shall conform to the Standards for warning signs presented in Part 2 and in the "Sign Design Manual" (SDM) (see Section 1A.11). Except as noted in the Option below, TTC warning signs shall be diamond-shaped with a black legend and border on an orange background, except for the W10-1 sign which shall have a black legend and border on a yellow background, and except for signs that are permitted in Part 2 or 7 to have fluorescent yellow-green backgrounds.**

Option:

Warning signs used for TTC incident management situations may have a black legend and border on a fluorescent pink background.

Mounting or space considerations may justify a change from the standard diamond shape.

In emergencies, available warning signs having yellow backgrounds may be used if signs with orange or fluorescent pink backgrounds are not at hand.

Guidance:

Where roadway or road user conditions require greater emphasis, larger than standard size warning signs should be used, with the legend enlarged approximately in proportion to the outside dimensions.

Where any part of the roadway is obstructed or closed by work activities or incidents, advance warning signs should be installed to alert road users well in advance of these obstructions or restrictions.

Where road users include pedestrians, the provision of supplemental audible information or detectable barriers or barricades should be considered for people with visual disabilities.

Support:

Detectable barriers or barricades communicate very clearly to pedestrians who have visual disabilities that they can no longer proceed in the direction that they are traveling.

Option:

Advance warning signs may be used singly or in combination.

**Standard:**

**Because of their importance, advance warning signs for higher-speed locations shall have a size of 1200 x 1200 mm (48 x 48 in) (see Part 2).**

**For freeways and expressways, the size of diamond shaped TTC warning signs shall be a minimum of 1200 x 1200 mm (48 x 48 in).**

**Option:**

Where speeds and volumes are moderately low, a minimum size of 900 x 900 mm (36 x 36 in) may be used for advance warning signs.

On secondary roads or City streets where speeds are very low, signs smaller than the standard size, but not less than 600 x 600 mm (24 x 24 in), may be used for warning signs having short word messages or clear symbols.

Advance warning signs larger than the minimum standards may be used for additional emphasis of the TTC zone (see Part 2).

Where distances are not shown on warning signs as part of the message, a supplemental plaque with the distance legend may be mounted immediately below the sign on the same support.

**Section 6F.16 Position of Advance Warning Signs****Guidance:**

As shown in Figure 6C-1, where highway conditions permit, warning signs in TTC zones should be placed in advance of the transition area at varying distances depending on roadway type, condition, and posted speed. Table 6C-1 contains information regarding the spacing of advance warning signs. Where a series of two or more advance warning signs is used, the closest sign to the transition area should be placed approximately 30 m (100 ft) for low-speed urban streets to 300 m (1,000 ft) or more for freeways and expressways.

**Support:**

Various conditions, such as limited sight distance or obstructions that might require a driver to reduce speed or stop, might require additional advance warning signs.

**Option:**

As an alternative to a specific distance on advance warning signs, the word AHEAD may be used.

**Support:**

At TTC zones on lightly-traveled roads, all of the advance warning signs prescribed for major construction might not be needed.

**Option:**

Utility work, maintenance, or minor construction can occur within the TTC zone limits of a major construction project, and additional warning signs may be needed.

**Guidance:**

Utility, maintenance, and minor construction signing and TTC should be coordinated with appropriate authorities so that road users are not confused or misled by the additional TTC devices.

**Section 6F.17 ROAD (STREET) WORK Sign (W20-1)****Guidance:**

The ROAD (STREET) WORK (W20-1) sign (see Figure 6F-4, Sheet 3 of 4), which serves as a general warning of obstructions or restrictions, should be located in advance of the work space or any detour, on the road where the work is taking place.

Where traffic can enter a TTC zone from a crossroad or a major (high-volume) driveway, an advance warning sign should be used on the crossroad or major driveway.

**Standard:**

**The ROAD (STREET) WORK (W20-1) sign shall have the legend ROAD (STREET) WORK, XX FT, XX MILES, or AHEAD.**

**Figure 6F-4. Warning Signs in Temporary Traffic Control Zones**  
(Sheet 1 of 4)



**Figure 6F-4. Warning Signs in Temporary Traffic Control Zones**  
(Sheet 2 of 4)



W6-3



W6-4



W7-1



W8-1



W8-2



W8-3



W8-4



W8-5



W8-6



W8-7



W8-8



W8-9



W8-9a



W8-11



W8-H12



W9-1



W9-2



W9-3



W9-3a



W10-1



W11-10



W12-1




W12-2




W13-1

**Figure 6F-4. Warning Signs in Temporary Traffic Control Zones**  
(Sheet 3 of 4)



\* These signs are shown in Appendix C and in the "Sign Design Manual" (SDM) with the optional AHEAD legend for the last line of the message. Also, an optional STREET CLOSED word message sign is shown in the SDM for the W20-3.

**Figure 6F-4. Warning Signs in Temporary Traffic Control Zones**  
(Sheet 4 of 4)



**Section 6F.18 DETOUR Sign (W20-2)**

Guidance:

The DETOUR (W20-2) sign (see Figure 6F-4, Sheet 3 of 4) should be used in advance of a road user detour over a different roadway or route.

**Standard:**

The DETOUR sign shall have the legend DETOUR, XX FT, XX MILES, or AHEAD.

**Section 6F.19 ROAD (STREET) CLOSED Sign (W20-3)**

Guidance:

The ROAD (STREET) CLOSED (W20-3) sign (see Figure 6F-4, Sheet 3 of 4) should be used in advance of the point where a highway is closed to all road users, or to all but local road users.

**Standard:**

The ROAD (STREET) CLOSED sign shall have the legend ROAD (STREET) CLOSED, XX FT, XX MILES, or AHEAD.

**Section 6F.20 ONE LANE ROAD Sign (W20-4)****Standard:**

The ONE LANE ROAD (W20-4) sign (see Figure 6F-4, Sheet 3 of 4) shall be used only in advance of that point where vehicular traffic in both directions must use a common single lane (see Section 6C.10). It shall have the legend ONE LANE ROAD, XX FT, XX MILES, or AHEAD.

**Section 6F.21 Lane(s) Closed Signs (W20-5, W20-5a)****Standard:**

The Lane(s) Closed sign (see Figure 6F-4, Sheet 3 of 4) shall be used in advance of that point where one or more through lanes of a multi-lane roadway are closed.

For a single lane closure, the Lane Closed (W20-5) sign (see Figure 6F-4, Sheet 3 of 4) shall have the legend RIGHT (LEFT) LANE CLOSED, XX FT, XX MILES, or AHEAD. Where two adjacent lanes are closed, the W20-5a sign (see Figure 6F-4, Sheet 3 of 4) shall have the legend RIGHT (LEFT) TWO LANES CLOSED, XX FT, XX MILES, or AHEAD.

**Section 6F.22 CENTER LANE CLOSED AHEAD Signs (W9-3, W9-3a)****Guidance:**

The CENTER LANE CLOSED AHEAD (W9-3) sign (see Figure 6F-4, Sheet 2 of 4) should be used in advance of that point where work occupies the center lane(s) and approaching vehicular traffic is directed to the right or left of the work zone in the center lane.

**Option:**

The Center Lane Closed Ahead (W9-3a) symbol sign (see Figure 6H-38) may be substituted for the CENTER LANE CLOSED AHEAD (W9-3) word message sign.

**Section 6F.23 THRU TRAFFIC MERGE LEFT (RIGHT) Sign (W4-7)****Guidance:**

The THRU TRAFFIC MERGE LEFT (RIGHT) (W4-7) sign (see Figure 6F-4, Sheet 1 of 4) should be used in advance of an intersection where one or more lane closures on the far side of a multi-lane intersection require through vehicular traffic on the approach to the intersection to use the left (right) lane to proceed through the intersection.

**Section 6F.24 Lane Ends Sign (W4-2)****Option:**

The Lane Ends (W4-2) symbol sign (see Figure 6F-4, Sheet 1 of 4) may be used to warn drivers of the reduction in the number of lanes for moving vehicular traffic in the direction of travel on a multi-lane roadway.

**Section 6F.25 ON RAMP Plaque (W13-4)****Guidance:**

When work is being done on a ramp, but the ramp remains open, the ON RAMP (W13-4) plaque (see Figure 6F-4, Sheet 3 of 4) should be used to supplement the advance ROAD WORK sign.

**Section 6F.26 RAMP NARROWS Sign (W5-4)****Guidance:**

The RAMP NARROWS (W5-4) sign (see Figure 6F-4, Sheet 1 of 4) should be used in advance of the point where work on a ramp reduces the normal width of the ramp along a part or all of the ramp.

**Section 6F.27 SLOW TRAFFIC AHEAD Sign (W23-1)**

Option:

The SLOW TRAFFIC AHEAD (W23-1) sign (see Figure 6F-4, Sheet 4 of 4) may be used on a shadow vehicle, usually mounted on the rear of the most upstream shadow vehicle, along with other appropriate signs for mobile operations to warn of slow moving work vehicles. A ROAD WORK (W20-1) sign may also be used with the SLOW TRAFFIC AHEAD sign.

**Section 6F.28 EXIT OPEN, EXIT CLOSED (AHEAD), EXIT ONLY Signs (E5-2, E5-2a, E5-H2b, E5-H2c, E5-3)**

Option:

An EXIT OPEN (E5-2), EXIT CLOSED (E5-2a), or EXIT ONLY (E5-3) sign (see Figure 6F-5) may be used to supplement other warning signs where work is being conducted in the vicinity of an exit ramp and where the exit maneuver for vehicular traffic using the ramp is different from the normal condition. The EXIT OPEN AHEAD (E5-H2b) and the EXIT CLOSED AHEAD (E5-H2c) signs may also be used (see Appendix C).

Guidance:

When an exit ramp is closed, an EXIT CLOSED panel with a black legend and border on an orange background should be placed diagonally across the interchange/intersection guide signs.

**Section 6F.29 Flagger Sign (W20-7a , W20-7)**

Guidance:

The Flagger (20-7a) symbol sign (see Figure 6F-4, Sheet 3 of 4) should be used in advance of any point where a flagger is stationed to control road users.

Option:

A distance legend may be displayed on a supplemental plaque below the Flagger sign. The sign may be used with appropriate legends or in conjunction with other warning signs, such as the BE PREPARED TO STOP (W3-4) sign (see Figure 6F-4, Sheet 1 of 4).

The FLAGGER (W20-7) word message sign with distance legends may be substituted for the Flagger (W20-7a) symbol sign.

**Standard:**

**The Flagger sign shall be removed, covered, or turned away from road users when the flagging operations are not occurring.**

**Section 6F.30 Two-Way Traffic Sign (W6-3)**


Guidance:

When one roadway of a normally divided highway is closed, with two-way vehicular traffic maintained on the other roadway, the Two-Way Traffic (W6-3) sign (see Figure 6F-4, Sheet 2 of 4) should be used at the beginning of the two-way vehicular traffic section and at intervals to remind road users of opposing vehicular traffic.

**Section 6F.31 Workers Sign (W21-1, W21-1a)**

Option:

A Workers (W21-1a) symbol sign (see Figure 6F-4, Sheet 3 of 4) may be used to alert road users of workers in or near the roadway.

**Figure 6F-5. Exit Open and Closed and Detour Signs****Guidance:**

In the absence of other warning devices, a Workers symbol sign should be used when workers are in the roadway.

**Option:**

The WORKERS (W21-1) word message sign may be used as an alternate to the Workers (W21-1a) symbol sign.

**Section 6F.32 FRESH OIL (TAR) Sign (W21-2)****Guidance:**

The FRESH OIL (TAR) (W21-2) sign (see Figure 6F-4, Sheet 3 of 4) should be used to warn road users of the surface treatment.

**Section 6F.33 ROAD MACHINERY AHEAD Sign (W21-3)****Option:**

The ROAD MACHINERY AHEAD (W21-3) sign (see Figure 6F-4, Sheet 3 of 4) may be used to warn of machinery operating in or adjacent to the roadway.

**Section 6F.34 Motorized Traffic Signs (W8-6, W11-10)****Option:**

Motorized Traffic (W8-6, W11-10) signs may be used to alert road users to locations where unexpected travel on the roadway or entries into or departures from the roadway by construction vehicles might occur. The TRUCK CROSSING (W8-6) word message sign may be used as an alternate to the Truck Crossing symbol (W11-10) sign (see Figure 6F-4, Sheet 2 of 4) where there is an established construction vehicle crossing of the roadway.

**Support:**

These locations might be relatively confined or might occur randomly over a segment of roadway.

**Section 6F.35 Shoulder Work Signs (W21-5, W21-5a, W21-5b)****Support:**

Shoulder Work signs (see Figure 6F-4, Sheets 3 and 4 of 4) warn of maintenance, reconstruction, or utility operations on the highway shoulder where the roadway is unobstructed.

**Standard:**

**The Shoulder Work sign shall have the legend SHOULDER WORK (W21-5), RIGHT (LEFT) SHOULDER CLOSED (W21-5a), or RIGHT (LEFT) SHOULDER CLOSED XXX FT or AHEAD (W21-5b).**

**Option:**

The Shoulder Work sign may be used in advance of the point on a nonlimited access highway where there is shoulder work. It may be used singly or in combination with a ROAD WORK NEXT MILES or ROAD WORK AHEAD sign.

**Guidance:**

On freeways and expressways, the RIGHT (LEFT) SHOULDER CLOSED XXX FT or AHEAD (W21-5b) sign followed by RIGHT (LEFT) SHOULDER CLOSED (W21-5a) sign should be used in advance of the point where the shoulder work occurs and should be preceded by a ROAD WORK AHEAD sign.

**Section 6F.36 SURVEY CREW Sign (W21-6)****Guidance:**

The SURVEY CREW (W21-6) sign (see Figure 6F-4, Sheet 4 of 4) should be used to warn of surveying crews working in or adjacent to the roadway.

**Section 6F.37 UTILITY WORK Sign (W21-7)****Option:**

The UTILITY WORK (W21-7) sign (see Figure 6F-4, Sheet 4 of 4) may be used as an alternate to the ROAD (STREET) WORK (W20-1) sign for utility operations on or adjacent to a highway.

**Support:**

Typical examples of where the UTILITY WORK sign is used appear in Figures 6H-4, 6H-6, 6H-10, 6H-15, 6H-18, 6H-21, 6H-22, 6H-26, and 6H-33.

**Standard:**

**The UTILITY WORK sign shall carry the legend UTILITY WORK, XX FT, XX MILES, or AHEAD.**

**Section 6F.38 Signs for Blasting Areas****Support:**

Radio-Frequency (RF) energy can cause the premature firing of electric detonators (blasting caps) used in TTC zones.

**Standard:**

**Road users shall be warned to turn off mobile radio transmitters and cellular telephones where blasting operations occur. A sequence of signs shall be prominently displayed to direct operators of mobile radio equipment, including cellular telephones, to turn off transmitters in a blasting area. These signs shall be covered or removed when there are no explosives in the area or the area is otherwise secured.**

**Section 6F.39 BLASTING ZONE AHEAD Sign (W22-1)****Standard:**

The BLASTING ZONE AHEAD (W22-1) sign (see Figure 6F-4, Sheet 4 of 4) shall be used in advance of any TTC zone where explosives are being used. The TURN OFF 2-WAY RADIO AND CELL PHONE and END BLASTING ZONE signs shall be used in sequence with this sign.

**Section 6F.40 TURN OFF 2-WAY RADIO AND CELL PHONE Sign (W22-2)****Standard:**

The TURN OFF 2-WAY RADIO AND CELL PHONE (W22-2) sign (see Figure 6F-4, Sheet 4 of 4) shall follow the BLASTING ZONE AHEAD sign and shall be placed at least 300 m (1,000 ft) before the beginning of the blasting zone.

**Section 6F.41 END BLASTING ZONE Sign (W22-3)****Standard:**

The END BLASTING ZONE (W22-3) sign (see Figure 6F-4, Sheet 4 of 4) shall be placed a minimum of 300 m (1,000 ft) past the blasting zone.

**Option:**

The END BLASTING ZONE sign may be placed either with or preceding the END ROAD WORK sign.

**Section 6F.42 Shoulder Signs (W8-4, W8-9, W8-9a)****Option:**

The SOFT SHOULDER (W8-4) sign (see Figure 6F-4, Sheet 2 of 4) may be used to warn of a soft shoulder condition.

The LOW SHOULDER (W8-9) sign (see Figure 6F-4, Sheet 2 of 4) may be used to warn of a shoulder condition where there is an elevation difference of less than 75 mm (3 in) between the shoulder and the travel lane.

**Guidance:**

The SHOULDER DROP OFF (W8-9a) sign (see Figure 6F-4, Sheet 2 of 4) should be used when a shoulder drop-off, adjacent to the travel lane, exceeds 75 mm (3 in) in depth for a continuous length along the roadway, based on engineering judgment.

**Section 6F.43 UNEVEN LANES Sign (W8-11)****Guidance:**

The UNEVEN LANES (W8-11) sign (see Figure 6F-4, Sheet 2 of 4) should be used during operations that create a difference in elevation between adjacent lanes that are open to travel.

**Section 6F.44 NO CENTER LINE and NO EDGE LINE Signs (W8-H12, W8-H12a)****Guidance:**

The NO CENTER LINE (W8-H12) sign (see Figure 6F-4, Sheet 2 of 4) or the NO EDGE LINE sign (W8-H12a) sign (see Appendix C) should be used as appropriate when the work obliterates the center or edge line pavement markings. The sign should be placed at the beginning of the TTC zone and repeated at 3.2 km (2 mi) intervals in long TTC zones.

**Support:**

See Section 6F.72 for information on temporary pavement markings.

**Section 6F.45 Double Reverse Curve Signs (W24 Series)**

Option:

The Double Reverse Curve (W24-1, W24-1a, or W24-1b) sign (see Figure 6F-4, Sheet 4 of 4) may be used when the tangent distance between two reverse curves is less than 180 m (600 ft), thus making it difficult for a second Reverse Curve (W1-4 Series) sign to be placed between the curves.

**Standard:**

**If a Double Reverse Curve sign is used, the number of lanes illustrated on the sign shall be the same as the number of through lanes available to road users, and the direction of the double reverse curve shall be appropriately illustrated.**

**Section 6F.46 Other Warning Signs**

Option:

Advance warning signs may be used by themselves or with other advance warning signs.

Besides the warning signs specifically related to TTC zones, several other warning signs in Part 2 may apply in TTC zones (see Appendix C).

**Standard:**

**Except as noted in Section 6F.02, other warning signs that are used in TTC zones shall have black legends and borders on an orange background.**

**Section 6F. 46.1 Construction Arrow Sign (W1-H11)**

Option:

This sign may be used to help guide traffic through TTC zones.

**Standard:**

**The Construction Arrow (W1-H11) sign (see Appendix C) shall not be used in place of the standard symbol warning signs. The sign shall be mounted so that the arrow indicates either an oblique left or right movement.**

Option:

The sign may be located on the left or right side of the traveled lane.

Support:

An example of a situation where this sign might be used would be a lane shift, such as those shown in Figures 6H-24, 6H-32 and 6H-36.

**Section 6F.47 Special Warning Signs**

Option:

Special warning signs may be used based on engineering judgment.

Guidance:

Special warning signs should conform to the general requirements of color, shape, and alphabet size and series. The sign message should be brief, legible, and clear.

**Section 6F.48 Advisory Speed Plaque (W13-1)**

Option:

In combination with a warning sign, an Advisory Speed (W13-1) plaque (see Figure 6F-4, Sheet 2 of 4) may be used to indicate a recommended safe speed through the TTC zone.

**Standard:**

The Advisory Speed plaque shall not be used in conjunction with any sign other than a warning sign, nor shall it be used alone. When used with orange TTC zone signs, this plaque shall have a black legend and border on an orange background. The sign shall be at least 600 x 600 mm (24 x 24 in) in size when used with a sign that is 900 x 900 mm (36 x 36 in) or larger. Except in emergencies, an Advisory Speed plaque shall not be mounted until the recommended speed is determined by the highway agency.

**Section 6F.49 Supplementary Distance Plaque (W7-3a)****Option:**

In combination with a warning sign, a Supplementary Distance (W7-3a) plaque with the legend NEXT XX MILE may be used to indicate the length of highway over which a work activity is being conducted, or over which a condition exists in the TTC zone.

In long TTC zones, Supplementary Distance plaques with the legend NEXT XX MILES may be placed in combination with warning signs at regular intervals within the zone to indicate the remaining length of highway over which the TTC work activity or condition exists.

**Standard:**

The Supplementary Distance plaque with the legend NEXT XX MILES shall not be used in conjunction with any sign other than a warning sign, nor shall it be used alone. When used with orange TTC zone signs, this plaque shall have a black legend and border on an orange background. The sign shall be at least 750 x 600 mm (30 x 24 in) in size when used with a sign that is 900 x 900 mm (36 x 36 in) or larger.

**Guidance:**

When used in TTC zones, the Supplementary Distance plaque with the legend NEXT XX MILES should be placed below the initial warning sign designating that, within the approaching zone, a temporary work activity or condition exists.

**Section 6F.50 Guide Signs****Support:**

Guide signs along highways provide road users with information to help them along their way through the TTC zone. The design of guide signs is presented in Part 2.

**Guidance:**

The following guide signs should be used in TTC zones as needed:

- A. Standard route markings, where temporary route changes are necessary;
- B. Directional signs and street name signs; and
- C. Special guide signs relating to the condition or work being done.

**Standard:**

If additional temporary guide signs are used in TTC zones, they shall have a black legend and border on an orange background.

**Option:**

Guide signs used in TTC incident management situations may have a black legend and border on a fluorescent pink background.

When directional signs and street name signs are used in conjunction with detour routing, these signs may have a black legend and border on an orange background.

When permanent directional signs or permanent street name signs are used in conjunction with detour signing, they may have a white legend on a green background.

### **Section 6F.51 ROAD WORK NEXT XX MILES Sign (G20-1)**

Guidance:

The ROAD WORK NEXT XX MILES (G20-1) sign (see Figure 6F-4, Sheet 3 of 4) should be installed in advance of TTC zones that are more than 3.2 km (2 mi) in length.

Option:

The ROAD WORK NEXT XX MILES sign may be mounted on a Type III barricade. The sign may also be used for TTC zones of shorter length.

**Standard:**

**The distance shown on the ROAD WORK NEXT XX MILES sign shall be stated to the nearest whole mile.**

### **Section 6F.52 END ROAD WORK Sign (G20-2)**

Guidance:

When used, the END ROAD WORK (G20-2) sign (see Figure 6F-4, Sheet 3 of 4) should be placed near the end of the termination area, as determined by engineering judgment..

Option:

The END ROAD WORK sign may be installed on the back of a warning sign facing the opposite direction of road users or on the back of a Type III barricade.

### **Section 6F.53 Detour Signs (M4-8, M4-8a, M4-8b, M4-9, M4-9a, M4-9b, M4-9c, M4-10)**

**Standard:**

**Each detour shall be adequately marked with standard temporary route signs and destination signs.**

Option:

Detour signs in TTC incident management situations may have a black legend and border on a fluorescent pink background.

The Detour Arrow (M4-10) sign (see Figure 6F-5) may be used where a detour route has been established.

The DETOUR (M4-8) sign (see Figure 6F-5) may be mounted at the top of a route sign assembly to mark a temporary route that detours from a highway, bypasses a section closed by a TTC zone, and rejoins the highway beyond the TTC zone.

Guidance:

The Detour Arrow (M4-10) sign should normally be mounted just below the ROAD CLOSED (R11-2, R11-3a, or R11-4) sign. The Detour Arrow sign should include a horizontal arrow pointed to the right or left as required.

The DETOUR (M4-9) sign (see Figure 6F-5) should be used for unnumbered highways, for emergency situations, for periods of short durations, or where, over relatively short distances, road users are guided along the detour and back to the desired highway without route signs.

A Street Name sign should be placed above, or the street name should be incorporated into, a DETOUR (M4-9) sign to indicate the name of the street being detoured.

**Option:**

The END DETOUR (M4-8a) or END (M4-8b) sign (see Figure 6F-5) may be used to indicate that the detour has ended.

**Guidance:**

When the END DETOUR sign is used on a numbered highway, the sign should be mounted above a sign after the end of the detour.

The Pedestrian/Bicycle Detour (M4-9a) sign (see Figure 6F-5) should be used where a pedestrian/bicycle detour route has been established because of the closing of a pedestrian/bicycle facility to through traffic.

**Standard:**

**If used, the Pedestrian/Bicycle Detour sign shall have an arrow pointing in the appropriate direction.**

**Option:**

The arrow on a Pedestrian/Bicycle Detour sign may be on the sign face or on a supplemental plaque.

The Pedestrian Detour (M4-9b) sign or Bicycle Detour (M4-9c) sign (see Figure 6F-5) may be used where a pedestrian or bicycle detour route (not both) has been established because of the closing of the pedestrian or bicycle facility to through traffic.

**Section 6F.54 PILOT CAR FOLLOW ME Sign (G20-4)****Standard:**

**The PILOT CAR FOLLOW ME (G20-4) sign (see Figure 6F-4, Sheet 4 of 4) shall be mounted in a conspicuous position on the rear of a vehicle used for guiding one-way vehicular traffic through or around a TTC zone. A flagger shall be stationed on the approach to the activity area to stop vehicular traffic until the pilot vehicle is available.**

**Section 6F.55 Portable Changeable Message Signs****Standard:**

**Portable Changeable Message signs shall be TTC devices with the flexibility to display a variety of messages. Each message shall consist of either one or two phases. A phase shall consist of up to three lines of eight characters per line. Each character module shall use at least a five wide and seven high pixel matrix.**

**Support:**

Portable Changeable Message signs are used most frequently on high-density urban freeways, but have applications on all types of highways where highway alignment, road user routing problems, or other pertinent conditions require advance warning and information.

Portable Changeable Message signs have a wide variety of applications in TTC zones including: roadway, lane, or ramp closures, crash or emergency incident management, width restriction information, speed control or reductions, advisories on work scheduling, road user management and diversion, warning of adverse conditions, or special events and other operational control.

The primary purpose of Portable Changeable Message signs in TTC zones is to advise the road user of unexpected situations. Some typical applications include the following:

- A. Where the speed of vehicular traffic is expected to drop substantially;
- B. Where significant queuing and delays are expected;
- C. Where adverse environmental conditions are present;
- D. Where there are changes in alignment or surface conditions;
- E. Where advance notice of ramp, lane, or roadway closures is needed;

- F. Where crash or incident management is needed; and/or
- G. Where changes in the road user pattern occur.

Guidance:

The components of a Portable Changeable Message sign should include: a message sign panel, control systems, a power source, and mounting and transporting equipment.

Portable Changeable Message signs should subscribe to the principles established in Section 2A.07 and other sections of this Manual and, to the extent practical, with the design (that is, color, letter size and shape, and borders) and applications prescribed in this Manual, except that the reverse colors for the letters and the background are considered acceptable.

The front face of the sign should be covered with a protective material. The color of the elements should be yellow or orange on a black background.

Portable Changeable Message signs should be visible from 800 m (0.5 mi) under both day and night conditions. For a trailer or large truck mounted sign, the letter height should be a minimum of 450 mm (18 in). For Changeable Message signs mounted on service patrol trucks, the letter height should be a minimum of 250 mm (10 in).

The message panel should have adjustable display rates (minimum of 3 seconds per phase), so that the entire message can be read at least twice at the posted speed, the off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed.

Messages should be designed taking into account the following factors:

- A. Each phase should convey a single thought.
- B. If the message can be displayed in one phase, the top line should present the problem, the center line should present the location or distance ahead, and the bottom line should present the recommended driver action.
- C. The message should be as brief as possible
- D. When a message is longer than two phases, additional Portable Changeable Message signs should be used
- E. When abbreviations are used, they should be easily understood (see Section 1A.14).

Option:

The message sign panel may vary in size.

Smaller letter sizes may be used on a Portable Changeable Message sign mounted on a trailer or large truck provided that the message is legible from at least 200 m (650 ft), or mounted on a service patrol truck provided that the message is legible from at least 100 m (330 ft).

Two Portable Changeable Message signs may be used for the purpose of allowing the entire message to be read twice at the posted speed.

**Standard:**

**Portable Changeable Message signs shall automatically adjust their brightness under varying light conditions, to maintain legibility.**

**The control system shall include a display screen upon which messages can be reviewed before being displayed on the message sign. The control system shall be capable of maintaining memory when power is unavailable.**

**Portable Changeable Message signs shall be equipped with a power source and a battery back-up to provide continuous operation when failure of the primary power source occurs.**

**The mounting of Portable Changeable Message signs on a trailer, a large truck, or a service patrol truck shall be such that the bottom of the message sign panel shall be a minimum of 2.1 m (7 ft) above**

**the roadway in urban areas and 1.5 m (5 ft) above the roadway in rural areas when it is in the operating mode.**

**The text of the messages shall not scroll or travel horizontally or vertically across the face of the sign.**

Guidance:

Portable Changeable Message signs should be used as a supplement to and not as a substitute for conventional signs and pavement markings.

When Portable Changeable Message signs are used for route diversion, they should be placed far enough in advance of the diversion to allow road users ample opportunity to perform necessary lane changes, to adjust their speed, or to exit the affected highway.

The Portable Changeable Message signs should be sited and aligned to provide maximum legibility. Multiple Portable Changeable Message signs should be placed on the same side of the roadway, separated from each other at distances based on Table 6C-1.

Portable Changeable Message signs should be placed on the shoulder of the roadway or, if practical, further from the traveled lane. They should be delineated with retroreflective TTC devices. When Portable Changeable Message signs are not being used, they should be removed; if not removed, they should be shielded; or if the previous two options are not feasible, they should be delineated with retroreflective TTC devices.

Portable Changeable Message sign trailers should be delineated on a permanent basis by affixing retroreflective material, known as conspicuity material, in a continuous line on the face of the trailer as seen by oncoming road users.

## **Section 6F.56 Arrow Panels**

**Standard:**

**An arrow panel shall be a sign with a matrix of elements capable of either flashing or sequential displays. This sign shall provide additional warning and directional information to assist in merging and controlling road users through or around a TTC zone.**

Guidance:

An arrow panel in the arrow or chevron mode should be used to advise approaching traffic of a lane closure along major multi-lane roadways in situations involving heavy traffic volumes, high speeds, and/or limited sight distances, or at other locations and under other conditions where road users are less likely to expect such lane closures.

If used, an arrow panel should be used in combination with appropriate signs, channelizing devices, or other TTC devices.

An arrow panel should be placed on the shoulder of the roadway or, if practical, further from the traveled lane. It should be delineated with retroreflective TTC devices. When an arrow panel is not being used, it should be removed; if not removed, it should be shielded; or if the previous two options are not feasible, it should be delineated with retroreflective TTC devices.

**Standard:**

**Arrow panels shall meet the minimum size, legibility distance, number of elements, and other specifications shown on Figure 6F-6.**

Support:

Type A arrow panels are appropriate for use on low-speed urban streets. Type B arrow panels are appropriate for intermediate-speed facilities and for maintenance or mobile operations on high-speed roadways. Type C arrow panels are intended to be used on high-speed, high-volume motor vehicle traffic control projects.

**Standard:**

**Arrow panels shall be rectangular, of solid appearance and shall be finished in nonreflective black.**

**The arrow panel shall be mounted on a vehicle, a trailer, or other suitable support.**

## Guidance:

The minimum mounting height of an arrow panel should be 2.1 m (7 ft) from the roadway to the bottom of the panel, except on vehicle-mounted panels, which should be as high as practical.

A vehicle-mounted arrow panel should be provided with remote controls.

**Standard:**

**Arrow panel elements shall be capable of at least a 50 percent dimming from full brilliance. The dimmed mode shall be used for nighttime operation of arrow panels.**

## Guidance:

Full brilliance should be used for daytime operation of arrow panels.

**Standard:**

**The arrow panel shall have suitable elements capable of the various operating modes. The color presented by the elements shall be yellow.**

## Guidance:

If an arrow panel consisting of a bulb matrix is used, the elements should be recess-mounted or equipped with an upper hood of not less than 180 degrees.

**Standard:**

**The minimum element on-time shall be 50 percent for the flashing mode, with equal intervals of 25 percent for each sequential phase. The flashing rate shall be not less than 25 nor more than 40 flashes per minute.**

**An arrow panel shall have the following three mode selections:**

- A. A Flashing Arrow, Sequential Arrow, or Sequential Chevron mode; and**
- B. A flashing Double Arrow mode; and**
- C. A flashing Caution mode.**

**An arrow panel in the arrow or chevron mode shall be used only for stationary or moving lane closures on multi-lane roadways.**

**For shoulder work, blocking the shoulder, for roadside work near the shoulder, or for temporarily closing one lane on a two-lane, two-way roadway, an arrow panel shall be used only in the caution mode.**

## Guidance:

For a stationary lane closure, the arrow panel should be located on the shoulder at the beginning of the merging taper.

Where the shoulder is narrow, the arrow panel should be located in the closed lane.

**Standard:**

**When arrow panels are used to close multiple lanes, a separate arrow panel shall be used for each closed lane.**

**Guidance:**

When arrow panels are used to close multiple lanes, if the first arrow panel is placed on the shoulder, the second arrow panel should be placed in the first closed lane at the beginning of the second merging taper (see Figure 6H-37). When the first arrow panel is placed in the first closed lane, the second arrow panel should be placed in the second closed lane at the downstream end of the second merging taper.

For mobile operations where a lane is closed, the arrow panel should be located to provide adequate separation from the work operation to allow for appropriate reaction by approaching drivers.

**Standard:**

**A vehicle displaying an arrow panel shall be equipped with high-intensity rotating, flashing, oscillating, or strobe lights.**

**Arrow panel(s) shall not be used to laterally shift traffic.**

**Option:**

A portable changeable message sign may be used to simulate an arrow panel display.

**Section 6F.57 High-Level Warning Devices (Flag Trees)****Option:**

A high-level warning device (flag tree) may supplement other TTC devices in TTC zones.

**Support:**

A high-level warning device is designed to be seen over the top of typical passenger cars. A typical high-level warning device is shown in Figure 6F-2.

**Standard:**

**A high-level warning device shall consist of a minimum of two flags with or without a Type B high-intensity flashing warning light. The distance from the roadway to the bottom of the lens of the light and to the lowest point of the flag material shall be not less than 2.4 m (8 ft). The flag shall be 400 mm (16 in) square or larger and shall be orange or fluorescent red-orange in color.**

**Option:**

An appropriate warning sign may be mounted below the flags.

**Support:**

High-level warning devices are most commonly used in high-density road user situations to warn road users of short-term operations.

**Section 6F.58 Channelizing Devices****Standard:**


**Designs of various channelizing devices shall be as shown in Figure 6F-7.**

**Support:**

The function of channelizing devices is to warn road users of conditions created by work activities in or near the roadway and to guide road users. Channelizing devices include cones, tubular markers, vertical panels, drums, barricades, and temporary raised islands.

Channelizing devices provide for smooth and gradual vehicular traffic flow from one lane to another, onto a bypass or detour, or into a narrower traveled way. They are also used to separate vehicular traffic from the work space, pavement drop-offs, pedestrian or shared-use paths, or opposing directions of vehicular traffic.

**Figure 6F-6. Advance Warning Arrow Display Specifications**



Panel Type	Minimum Size	Minimum Legibility Distance	Minimum Number of Elements
A	1200 x 600 mm (48 x 24 in)	0.8 km (1/2 mi)	12
B	1500 x 750 mm (60 x 30 in)	1.2 km (3/4 mi)	13
C	2400 x 1200 mm (96 x 48 in)	1.6 km (1 mi)	15

**Standard:**

Devices used to channelize pedestrians shall be detectable to users of long canes and visible to persons having low vision.

Where barricades are used to channelize pedestrians, there shall be continuous detectable bottom and top rails with no gaps between individual barricades to be detectable to users of long canes. The bottom of the bottom rail shall be no higher than 150 mm (6 in) above the ground surface. The top of the top rail shall be no lower than 900 mm (36 in) above the ground surface.

**Option:**

A gap not exceeding 150 mm (6 in) between the bottom rail and the ground surface may be used to facilitate drainage.

**Standard:**

**If drums, cones, or tubular markers are used to channelize pedestrians, they shall be located such that there are no gaps between the bases of the devices, in order to create a continuous bottom, and the height of each individual drum, cone, or tubular marker shall be no less than 900 mm (36 in) to be detectable to users of long canes.**

**Guidance:**

Channelizing devices should be constructed and ballasted to perform in a predictable manner when inadvertently struck by a vehicle. Channelizing devices should be crashworthy. Fragments or other debris from the device or the ballast should not pose a significant hazard to road users or workers.

The spacing of channelizing devices should not exceed a distance in meters (feet) equal to 0.2 times the speed limit in km/h (1.0 times the speed limit in mph) when used for taper channelization, and a distance in meters (feet) equal to 0.4 times the speed limit in km/h (2.0 times the speed limit in mph) when used for tangent channelization.

When channelizing devices have the potential of leading vehicular traffic out of the intended vehicular traffic space as shown in Figure 6H-39, the channelizing devices should be extended a distance in meters (feet) of 0.4 times the speed limit in km/h (2.0 times the speed limit in mph) beyond the end of the transition area.

**Option:**

Warning lights may be added to channelizing devices in areas with frequent fog, snow, or severe roadway curvature, or where visual distractions are present.

**Standard:**

**Warning lights shall flash when placed on channelizing devices used alone or in a cluster to warn of a condition. Warning lights placed on channelizing devices used in a series to channelize road users shall be steady-burn.**

**The retroreflective material used on channelizing devices shall have a smooth, sealed outer surface that will display a similar color day or night.**

**Option:**

The name and telephone number of the highway agency, contractor, or supplier may be shown on the nonretroreflective surface of all types of channelizing devices.

**Standard:**

**The letters and numbers of the name and telephone number shall be nonretroreflective and not over 50 mm (2 in) in height.**

**Guidance:**

Particular attention should be given to maintaining the channelizing devices to keep them clean, visible, and properly positioned at all times.

**Standard:**

**Devices that are damaged or have lost a significant amount of their retroreflectivity and effectiveness shall be replaced.**

**Section 6F.59 Cones****Standard:**

**Cones (see Figure 6F-7, Sheet 1 of 2) shall be predominantly orange and shall be made of a material that can be struck without causing damage to the impacting vehicle. For daytime and low-speed roadways, cones shall be not less than 450 mm (18 in) in height. When cones are used on**

**freeways and other high-speed highways or at night on all highways, or when more conspicuous guidance is needed, cones shall be a minimum of 700 mm (28 in) in height.**

**For nighttime use, cones shall be retroreflectorized or equipped with lighting devices for maximum visibility. Retroreflectorization of cones that are 700 to 900 mm (28 to 36 in) in height shall be provided by a 150 mm (6 in) wide white band located 75 to 100 mm (3 to 4 in) from the top of the cone and an additional 100 mm (4 in) wide white band located approximately 50 mm (2 in) below the 150 mm (6 in) band.**

**Retroreflectorization of cones that are more than 900 mm (36 in) in height shall be provided by horizontal, circumferential, alternating orange and white retroreflective stripes that are 100 to 150 mm (4 to 6 in) wide. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflective spaces between the orange and white stripes shall not exceed 75 mm (3 in) in width.**

Option:

Traffic cones may be used to channelize road users, divide opposing vehicular traffic lanes, divide lanes when two or more lanes are kept open in the same direction, and delineate short duration maintenance and utility work.

Guidance:

Steps should be taken to minimize the possibility of cones being blown over or displaced by wind or moving vehicular traffic.

Cones should not be used for pedestrian channelization or as pedestrian barriers in TTC zones on or along sidewalks unless they are continuous between individual devices and detectable to users of long canes.

Option:

Cones may be doubled up to increase their weight.

Support:

Some cones are constructed with bases that can be filled with ballast. Others have specially weighted bases, or weight such as sandbag rings that can be dropped over the cones and onto the base to provide added stability.

Guidance:

Ballast should be kept to the minimum amount needed.

## **Section 6F.60 Tubular Markers**

**Standard:**

**Tubular markers (see Figure 6F-7, Sheet 1 of 2) shall be predominantly orange and shall be not less than 450 mm (18 in) high and 50 mm (2 in) wide facing road users. They shall be made of a material that can be struck without causing damage to the impacting vehicle.**


**Tubular markers shall be a minimum of 700 mm (28 in) in height when they are used on freeways and other high-speed highways, on all highways during nighttime, or whenever more conspicuous guidance is needed.**

**For nighttime use, tubular markers shall be retroreflectorized. Retroreflectorization of 700 mm (28 in) or larger tubular markers shall be provided by two 75 mm (3 in) wide white bands placed a maximum of 50 mm (2 in) from the top with a maximum of 150 mm (6 in) between the bands.**

Guidance:

Tubular markers should not be used for pedestrian channelization or as pedestrian barriers in TTC zones on or along sidewalks unless they are continuous between individual devices and detectable to users of long canes.

**Figure 6F-7. Channelizing Devices (Sheet 1 of 2)**



Note: If drums, cones, or tubular markers are used to channelize pedestrians, they shall be located such that there are no gaps between the bases of the devices, in order to create a continuous bottom, and the height of each individual drum, cone, or tubular marker shall be no less than 900 mm (36 in) to be detectable to users of long canes.

Tubular markers have less visible area than other devices and should be used only where space restrictions do not allow for the use of other more visible devices.

Tubular markers should be stabilized by affixing them to the pavement, by using weighted bases, or weights such as sandbag rings that can be dropped over the tubular markers and onto the base to provide added stability. Ballast should be kept to the minimum amount needed.

Option:


Tubular markers may be used effectively to divide opposing lanes of road users, divide vehicular traffic lanes when two or more lanes of moving vehicular traffic are kept open in the same direction, and to delineate the edge of a pavement drop-off where space limitations do not allow the use of larger devices.

**Standard:**

**When a noncylindrical tubular marker is used, it shall be attached to the pavement in a manner such that the width facing road users meets the minimum requirements.**

**A tubular marker shall be attached to the pavement to display the minimum 50 mm (2 in) width to the approaching road users.**

**Figure 6F-7. Channelizing Devices (Sheet 2 of 2)**



\* Warning lights (optional)

\*\* Rail stripe widths shall be 150 mm (6 in), except that 100 mm (4 in) wide stripes may be used if rail lengths are less than 900 mm (36 in). The sides of barricades facing traffic shall have retroreflective rail faces.

Note: If barricades are used to channelize pedestrians, there shall be continuous detectable bottom and top rails with no gaps between individual barricades to be detectable to users of long canes. The bottom of the bottom rail shall be no higher than 150 mm (6 in) above the ground surface. The top of the top rail shall be no lower than 900 mm (36 in) above the ground surface.

**Section 6F. 61 Vertical Panels**

**Standard:**

Vertical panels (see Figure 6F-7, Sheet 1 of 2) shall be 200 to 300 mm (8 to 12 in) in width and at least 600 mm (24 in) in height. They shall have orange and white diagonal stripes and be retroreflectorized.

Vertical panels shall be mounted with the top a minimum of 900 mm (36 in) above the roadway.

Where the height of the vertical panel itself is 900 mm (36 in) or greater, a panel stripe width of 150 mm (6 in) shall be used.

**Option:**

Where the height of the vertical panel itself is less than 900 mm (36 in), a panel stripe width of 100 mm (4 in) may be used.

**Standard:**

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward at an angle of 45 degrees in the direction vehicular traffic is to pass. Vertical panels used on freeways, expressways, and other high-speed roadways shall have a minimum of 169,000 mm<sup>2</sup> (270 in<sup>2</sup>) retroreflective area facing vehicular traffic.

**Option:**

Where space is limited, vertical panels may be used to channelize vehicular traffic, divide opposing lanes, or replace barricades.

**Section 6F.62 Drums****Standard:**

Drums (see Figure 6F-7, Sheet 1 of 2) used for road user warning or channelization shall be constructed of lightweight, deformable materials. They shall be a minimum of 900 mm (36 in) in height and have at least a 450 mm (18 in) minimum width regardless of orientation. Metal drums shall not be used. The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 100 to 150 mm (4 to 6 in) wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectorized spaces between the horizontal orange and white stripes shall not exceed 75 mm (3 in) wide. Drums shall have closed tops that will not allow collection of construction debris or other debris.

**Support:**

Drums are highly visible, have good target value, give the appearance of being formidable obstacles and, therefore, command the respect of road users. They are portable enough to be shifted from place to place within a TTC zone in order to accommodate changing conditions, but are generally used in situations where they will remain in place for a prolonged period of time.

**Option:**

Although drums are most commonly used to channelize or delineate road user flow, they may also be used alone or in groups to mark specific locations.

**Guidance:**

Drums should not be used for pedestrian channelization or as pedestrian barriers in TTC zones on or along sidewalks unless they are continuous between individual devices and detectable to users of long canes.

Drums should not be weighted with sand, water, or any material to the extent that would make them hazardous to road users or workers when struck. Drums used in regions susceptible to freezing should have drain holes in the bottom so that water will not accumulate and freeze causing a hazard if struck by a road user.

**Standard:**

**Ballast shall not be placed on the top of a drum.**

**Section 6F.63 Type I, II, or III Barricades****Support:**

A barricade is a portable or fixed device having from one to three rails with appropriate markings and is used to control road users by closing, restricting, or delineating all or a portion of the right-of-way.

As shown in Figure 6F-7, Sheet 2 of 2, barricades are classified as either Type I, Type II, or Type III.

**Standard:**

**Stripes on barricade rails shall be alternating orange and white retroreflective stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. Except as noted in the Option, the stripes shall be 150 mm (6 in) wide.**

## Option:

When rail lengths are less than 900 mm (36 in), 100 mm (4 in) wide stripes may be used.

**Standard:**

**The minimum length for Type I and Type II Barricades shall be 600 mm (24 in), and the minimum length for Type III Barricades shall be 1200 mm (48 in). Each barricade rail shall be 200 to 300 mm (8 to 12 in) wide. Barricades used on freeways, expressways and other high-speed roadways shall have a minimum of 169,000 mm<sup>2</sup> (270 in<sup>2</sup>) of retroreflective area facing road users.**

## Guidance:

Where barricades extend entirely across a roadway, the stripes should slope downward in the direction toward which road users must turn.

Where both right and left turns are provided, the barricade stripes should slope downward in both directions from the center of the barricade or barricades.

Where no turns are intended, the stripes should be positioned to slope downward toward the center of the barricade or barricades.

Barricade rails should be supported in a manner that will allow them to be seen by the road user, and in a manner that provides a stable support that is not easily blown over or displaced.

The width of the existing pedestrian facility should be provided for the temporary facility if practical. Traffic control devices and other construction materials and features should not intrude into the usable width of the sidewalk, temporary pathway, or other pedestrian facility. When it is not possible to maintain a minimum width of 1500 mm (60 in) throughout the entire length of the pedestrian pathway, a 1500 x 1500 mm (60 x 60 in) passing space should be provided at least every 60 m (200 ft) to allow individuals in wheelchairs to pass.

Barricade rail supports should not project into pedestrian circulation routes more than 100 mm (4 in) from the support between 675 mm (27 in) and 2000 mm (80 in) from the surface as described in Section 4.4.1 of the "Americans with Disabilities Act Accessibility Guidelines for Buildings and Facilities (ADAAG)" (see Section 1A.11).

## Option:

For Type I Barricades, the support may include other unstriped horizontal panels necessary to provide stability.

## Guidance:

Barricades should be crashworthy as they are located adjacent to vehicular traffic flow and are subject to impact by errant vehicles.

On high-speed expressways or in other situations where barricades may be susceptible to overturning in the wind, ballasting should be used.

## Option:

Sandbags may be placed on the lower parts of the frame or the stays of barricades to provide the required ballast.

**Standard:**

**Ballast shall not be placed on top of any striped rail. Barricades shall not be ballasted by nondeformable objects such as rocks or chunks of concrete. Ballast shall not extend into the accessible passage width of 1500 mm (60 in).**

**Support:**

Type I or Type II Barricades are intended for use in situations where road user flow is maintained through the TTC zone.

**Option:**

Barricades may be used alone or in groups to mark a specific condition or they may be used in a series for channelizing road users.

Type I Barricades may be used on conventional roads or urban streets.

**Guidance:**

Type II or Type III Barricades should be used on freeways and expressways or other high-speed roadways. Type III Barricades should be used to close or partially close a road.

**Option:**

Type III Barricades used at a road closure may be placed completely across a roadway or from curb to curb.

**Guidance:**

Where provision is made for access of authorized equipment and vehicles, the responsibility for Type III Barricades should be assigned to a person who will provide proper closure at the end of each work day.

**Support:**

When a highway is legally closed but access must still be allowed for local road users, barricades usually are not extended completely across the roadway.

**Standard:**

**A sign (see Section 6F.09) shall be installed with the appropriate legend concerning permissible use by local road users. Adequate visibility of the barricades from both directions shall be provided.**

**Option:**

Signs may be installed on barricades (see Section 6F.03).

**Section 6F.64 Direction Indicator Barricades****Standard:**

**The Direction Indicator Barricade (see Figure 6F-7, Sheet 2 of 2) shall consist of a One-Direction Large Arrow (W1-6) sign mounted above a diagonal striped, horizontally aligned, retroreflective rail.**

**The One-Direction Large Arrow (W1-6) sign shall be black on an orange background. The stripes on the bottom rail shall be alternating orange and white retroreflective stripes sloping downward at an angle of 45 degrees in the direction road users are to pass. The stripes shall be 100 mm (4 in) wide. The One-Direction Large Arrow (W1-6) sign shall be 600 x 300 mm (24 x 12 in). The bottom rail shall have a length of 600 mm (24 in) and a height of 200 mm (8 in).**

**Guidance:**

The Direction Indicator Barricade, including any associated ballast or lights, should be crashworthy.

**Option:**

The Direction Indicator Barricade may be used in tapers, transitions, and other areas where specific directional guidance to drivers is necessary.

**Guidance:**

If used, Direction Indicator Barricades should be used in series to direct the driver through the transition and into the intended travel lane.

**Section 6F.65 Temporary Traffic Barriers as Channelizing Devices****Support:**

Temporary traffic barriers are not TTC devices in themselves; however, when placed in a position identical to a line of channelizing devices and marked and/or equipped with appropriate channelization features to provide guidance and warning both day and night, they serve as TTC devices.

**Standard:**

**Temporary traffic barriers serving as TTC devices shall conform to requirements for such devices as set forth throughout Part 6.**

**Temporary traffic barriers shall not be used solely to channelize road users, but also to protect the work space (see Section 6F.81). If used to channelize vehicular traffic, the temporary traffic barrier shall be supplemented with delineation, pavement markings, or channelizing devices for improved daytime and nighttime visibility.**

**Guidance:**

Temporary traffic barriers should not be used for a merging taper except in low-speed urban areas. Temporary traffic barriers should not be used for a constricted/restricted TTC zone.

When it is necessary to use a temporary traffic barrier for a merging taper in low-speed urban areas or for a constricted/restricted TTC zone, the taper shall be delineated and the taper length should be designed to optimize road user operations considering the available geometric conditions.

When used for channelization, temporary traffic barriers should be of a light color for increased visibility.

**Section 6F.66 Longitudinal Channelizing Barricades****Support:**

Longitudinal channelizing barricades are lightweight, deformable channelizing devices that can be used singly as Type I, II, or III barricades, or connected so they are highly visible and have good target value.

**Guidance:**

When used as a barricade, longitudinal channelizing barricades should conform to the general size, color, stripe pattern, retroreflectivity, and placement characteristics established for the devices described in Chapter 6F.

**Option:**

Longitudinal channelizing barricades may be used instead of a line of cones, drums, or barricades.

Longitudinal channelizing barricades may be hollow and filled with water as a ballast.

**Guidance:**

If used, longitudinal channelizing barricades should be interlocked to delineate or channelize flow including pedestrian traffic control. The interlocking barricade wall should not have gaps that allow pedestrians or vehicles to stray from the channelizing path.

**Support:**

Longitudinal channelizing barricades are often located adjacent to traffic and therefore are subject to impact by errant vehicles.

**Guidance:**

Because of their vulnerable position, longitudinal channelizing barricades should be constructed of lightweight materials and be crashworthy.

Although longitudinal channelizing barricades might give the appearance of being formidable obstacles, they have not met the crashworthy requirements for temporary traffic barriers and, therefore, should not be used to shield pedestrians, including workers, from vehicle impacts or obstacles.

**Option:**

Longitudinal channelizing barricades may be used to channelize pedestrians.

**Section 6F.67 Other Channelizing Devices****Option:**

Channelizing devices other than those described in this Chapter may be used in special situations based on an engineering study.

**Guidance:**

Other channelizing devices should conform to the general size, color, stripe pattern, retroreflection, and placement characteristics established for the devices described in this Chapter.

**Section 6F.68 Detectable Edging for Pedestrians****Support:**

Individual channelizing devices, tape or rope used to connect individual devices, other discontinuous barriers and devices, and pavement markings are not detectable by persons with visual disabilities and are incapable of providing detectable path guidance on temporary or realigned sidewalks or other pedestrian facilities.

**Guidance:**

When it is determined that a facility should be accessible to and detectable by pedestrians with visual disabilities, a continuously detectable edging should be provided throughout the length of the facility such that it can be followed by pedestrians using long canes for guidance. This edging should protrude at least 150 mm (6 in) above the surface of the sidewalk or pathway, with the bottom of the edging a maximum of 62 mm (2.5 in) above the surface. This edging should be continuous throughout the length of the facility except for gaps at locations where pedestrians or vehicles will be turning or crossing. This edging should consist of a prefabricated or formed-in-place curbing or other continuous device that is placed along the edge of the sidewalk or walkway. This edging should be firmly attached to the ground or to other devices. Adjacent sections of this edging should be interconnected such that the edging is not displaced by pedestrian or vehicular traffic or work operations, and such that it does not constitute a hazard to pedestrians, workers, or other road users.

**Support:**

Examples of detectable edging for pedestrians include:

- A. Prefabricated lightweight sections of plastic, metal, or other suitable materials that are interconnected and fixed in place to form a continuous edge.
- B. Prefabricated lightweight sections of plastic, metal, or other suitable materials that are interconnected, fixed in place, and placed at ground level to provide a continuous connection between channelizing devices located at intervals along the edge of the sidewalk or walkway.
- C. Sections of lumber interconnected and fixed in place to form a continuous edge.

- D. Formed-in-place asphalt or concrete curb.
- E. Prefabricated concrete curb sections that are interconnected and fixed in place to form a continuous edge.
- F. Continuous temporary traffic barrier or longitudinal channelizing barricades placed along the edge of the sidewalk or walkway that provides a pedestrian edging at ground level.
- G. Chain link or other fencing equipped with a continuous bottom rail.

Guidance:

Detectable pedestrian edging should be orange, white, or yellow and should match the color of the adjacent channelizing devices or traffic control devices, if any are present.

### **Section 6F.69 Temporary Raised Islands**

**Standard:**

**Temporary raised islands shall be used only in combination with pavement striping and other suitable channelizing devices.**

Guidance:

Temporary raised islands should only be used on roadways with speeds of 70 km/h (40 mph) or less except when recommended by an engineering study.

.Option:

A temporary raised island may be used to separate vehicular traffic flows in two-lane, two-way operations on roadways having a vehicular traffic volume range of 4,000 to 15,000 average daily traffic (ADT) and on freeways having a vehicular traffic volume range of 22,000 ADT to 60,000 ADT.

Temporary raised islands also may be used in other than two-lane, two-way operations where physical separation of vehicular traffic from the TTC zone is not required.

Pavement edge lines may be placed on the island itself.

Guidance:

Temporary raised islands should have the basic dimensions of 100 mm (4 in) high by at least 450 mm (18 in) wide and have rounded or chamfered corners.

The temporary raised islands should not be designed in such a manner that they would cause a motorist to lose control of the vehicle if the vehicle inadvertently strikes the temporary raised island. If struck, pieces of the island should not be dislodged to the extent that they could penetrate the occupant compartment or involve other vehicles.

**Standard:**

**At pedestrian crossing locations, temporary raised islands shall have an opening or be shortened to provide at least a 1500 mm (60 in) wide pathway for the crossing pedestrian.**

### **Section 6F.70 Opposing Traffic Lane Divider**

Support:

Opposing traffic lane dividers are delineation devices used as center lane dividers to separate opposing vehicular traffic on a two-lane, two-way operation.

**Standard:**

**Opposing traffic lane dividers shall not be placed across pedestrian crossings.**

**The Opposing Traffic Lane Divider (W6-4) sign (see Figure 6F-4, Sheet 2 of 4) is an upright, retroreflective orange-colored sign placed on a flexible support and sized at least 300 mm (12 in) wide by 450 mm (18 in) high.**

**Separation of opposing traffic lanes by use of this device shall be limited to locations where speeds are 70 km/h (40 mph) or less.**

## **Section 6F.71 Pavement Markings**

### **Standard:**

The provisions of this Section shall not be considered applicable for short-term, mobile, or incident management TTC zones.

Pavement markings shall be maintained along paved streets and highways in all long- and intermediate-term stationary (see Section 6G.02) TTC zones. All pavement markings shall be in accordance with Chapters 3A and 3B, except as indicated in Section 6F.72. Pavement markings shall match the markings in place at both ends of the TTC zone. Pavement markings shall be placed along the entire length of any surfaced detour or temporary roadway prior to the detour or roadway being opened to road users.

Warning signs, channelizing devices, and delineation shall be used to indicate required road user paths in TTC zones where it is not possible to provide a clear path by pavement markings. All pavement markings and devices used to delineate road user paths shall be carefully reviewed during daytime and nighttime periods.

For long-term stationary operations, pavement markings in the temporary traveled way that are no longer applicable shall be removed or obliterated as soon as practical. Pavement marking obliteration shall leave a minimum of pavement scars and shall remove old marking material. Painting over existing pavement markings with black paint or spraying with asphalt shall not be accepted as a substitute for removal or obliteration.

### **Guidance:**

Road users should be provided pavement markings within a TTC zone comparable to the pavement markings normally maintained along such roadways, particularly at either end of the TTC zone.

The intended vehicle path should be defined in day, night, and twilight periods under both wet and dry pavement conditions.

The work should be planned and staged to provide for the placement and removal of the pavement markings.

Markings should be provided in intermediate-term stationary work zones.

### **Option:**

Removable, nonreflective, preformed tape may be used where markings need to be covered temporarily.

## **Section 6F.72 Temporary Pavement Markings**

### **Support:**

Temporary pavement markings are those that are allowed to remain in place until the earliest date when it is practical and possible to install pavement markings that meet the Part 3 standards for pavement markings.

See Section 6F.44 for information on use of the NO CENTER LINE (W8-H12) sign and the NO EDGE LINE (W8-H12a) sign.

### **Guidance:**

Temporary pavement markings should not be in place for more than 2 weeks unless justified by an engineering study.

### **Standard:**

All temporary pavement markings, including pavement markings for no-passing zones, shall conform to the requirements of Chapters 3A and 3B. All temporary broken-line pavement markings shall use the same cycle length as permanent markings and be at least 0.6 m (2 ft) long.

**Option:**

Half-cycle lengths with a minimum of 0.6 m (2 ft) stripes may be used on roadways with severe curvature (see Section 3A.05) for centerlines in passing zones and for lane lines.

For temporary situations of 3 calendar days or less, for a two- or three-lane road, no-passing zones may be identified by using DO NOT PASS (R4-1), PASS WITH CARE (R4-2), and NO PASSING ZONE (W14-3) signs (see Sections 2B.29, 2B.30, and 2C.35) rather than pavement markings. Also, DO NOT PASS, PASS WITH CARE, and NO PASSING ZONE signs may be used instead of pavement markings on roads with low volumes for longer periods in accordance with the highway agency's policy.

**Guidance:**

If used, the DO NOT PASS, PASS WITH CARE, and NO PASSING ZONE signs should be placed in accordance with Sections 2B.29, 2B.30, and 2C.35.

The temporary use of edge lines, channelizing lines, lane reduction transitions, gore markings, and other longitudinal markings, and the various nonlongitudinal markings (such as stop lines, railroad crossings, crosswalks, words or symbols) should be in accordance with the highway agency's policy.

**Support:**

The ODOT "Traffic Engineering Manual" (see Section 1A.11) includes additional information about the Ohio Department of Transportation's policy regarding temporary pavement marking on ODOT-maintained highways.

**Section 6F.73 Raised Pavement Markers****Standard:**

**If raised pavement markers are used to substitute for broken line segments, at least two retroreflective markers shall be placed, one at each end of a segment of 0.6 m to 1.5 m (2 to 5 ft) in length. For segments longer than 1.5 m (5 ft), a group of at least three retroreflective markers shall be equally spaced at no greater than N/8 (see Section 3B.11). The value of N for a broken or dotted line shall equal the length of one line segment plus one gap. The value of N referenced for solid lines shall equal the N for the broken or dotted lines that might be adjacent to or might extend the solid lines (see Sections 3B.13 and 3B.14).**

**Guidance:**

Raised pavement markers should be considered for use along surfaced detours or temporary roadways, and other changed or new travel-lane alignments.

**Option:**

Retroreflective or internally illuminated raised pavement markers, or nonretroreflective raised pavement markers supplemented by retroreflective or internally illuminated markers, may replace or supplement markings prescribed in Chapters 3A and 3B.

**Section 6F.74 Delineators****Standard:**

**When used, delineators shall combine with or supplement other TTC devices. They shall be mounted on crashworthy supports so that the reflecting unit is approximately 1.2 m (4 ft) above the near roadway edge. The standard color for delineators used along both sides of two-way streets and highways and the right side of one-way roadways shall be white. Delineators used along the left side of one-way roadways shall be yellow.**

**Guidance:**

Spacing along roadway curves should be as set forth in Section 3D.04 and should be such that several delineators are always visible to the driver.

**Option:**

Delineators may be used in TTC zones to indicate the alignment of the roadway and to outline the required vehicle path through the TTC zone.

**Section 6F.75 Lighting Devices****Guidance:**

Lighting devices should be provided in TTC zones based on engineering judgment.

When used to supplement channelization, the maximum spacing for warning lights should be identical to the channelizing device spacing requirements.

**Support:**

Four types of lighting devices are commonly used in TTC zones. They are floodlights, flashing warning beacons, warning lights, and steady-burn electric lamps.

**Option:**

Lighting devices may be used to supplement retroreflectorized signs, barriers, and channelizing devices.

During normal daytime maintenance operations, the functions of flashing warning beacons may be provided by high-intensity rotating, flashing, oscillating, or strobe lights on a maintenance vehicle.

**Standard:**

**Although vehicle hazard warning lights are permitted to be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights, they shall not be used instead of high-intensity rotating, flashing, oscillating, or strobe lights.**

**Section 6F.76 Floodlights****Support:**

Utility, maintenance, or construction activities on highways are frequently conducted during nighttime periods when vehicular traffic volumes are lower. Large construction projects are sometimes operated on a double-shift basis requiring night work (see Section 6G.20).

**Guidance:**

When nighttime work is being performed, floodlights should be used to illuminate the work area, equipment crossings, and other areas.

**Standard:**

**Except in emergency situations, flagger stations shall be illuminated at night.**

**Floodlighting shall not produce a disabling glare condition for approaching road users, flaggers, or workers.**

**Guidance:**

The adequacy of the floodlight placement and elimination of potential glare should be determined by driving through and observing the floodlighted area from each direction on all approaching roadways after the initial floodlight setup, at night, and periodically.

**Support:**

Desired illumination levels vary depending upon the nature of the task involved. An average horizontal luminance of 50 lux (5 foot candles) can be adequate for general activities. Tasks requiring high levels of precision and extreme care can require an average horizontal luminance of 216 lux (20 foot candles).

**Section 6F.77 Flashing Warning Beacons**

Support:

Flashing warning beacons are often used to supplement a TTC device.

**Standard:**

**Flashing warning beacons shall comply with the provisions of Chapter 4K. A flashing warning beacon shall be a flashing yellow light with a minimum nominal diameter of 200 mm (8 in).**

Guidance:

Flashing warning beacons should be operated 24 hours per day.

Support:

The temporary terminus of a freeway is an example of a location where flashing warning beacons alert drivers to the changing roadway conditions and the need to reduce speed in transitioning from the freeway to another roadway type.

**Section 6F.78 Warning Lights**

Support:

Type A, Type B, Type C, and Type D 360-degree warning lights are portable, powered, yellow, lens-directed, enclosed lights.

**Standard:**

**Warning lights shall be in accordance with the current ITE “Purchase Specification for Flashing and Steady-Burn Warning Lights” (see Section 1A.11).**

**When warning lights are used, they shall be mounted on signs or channelizing devices in a manner that, if hit by an errant vehicle, they will not be likely to penetrate the windshield.**

Guidance:

The maximum spacing for warning lights should be identical to the channelizing device spacing requirements.

Support:

The light weight and portability of warning lights are advantages that make these devices useful as supplements to the retroreflectorization on signs and channelizing devices. The flashing lights are effective in attracting road users' attention.

Option:

Warning lights may be used in either a steady-burn or flashing mode.

**Standard:**

**Flashing warning lights shall not be used for delineation, as a series of flashers fails to identify the desired vehicle path.**

**Type A Low-Intensity Flashing warning lights, Type C Steady-Burn warning lights, and Type D 360-degree Steady-Burn warning lights shall be maintained so as to be capable of being visible on a clear night from a distance of 900 m (3,000 ft). Type B High-Intensity Flashing warning lights shall be maintained so as to be capable of being visible on a sunny day when viewed without the sun directly on or behind the device from a distance of 300 m (1,000 ft).**

**Warning lights shall have a minimum mounting height of 750 mm (30 in) to the bottom of the lens.**

**Support:**

Type A Low-Intensity Flashing warning lights are used to warn road users during nighttime hours that they are approaching or proceeding in a potentially hazardous area.

**Option:**

Type A warning lights may be mounted on channelizing devices.

**Support:**

Type B High-Intensity Flashing warning lights are used to warn road users during both daylight and nighttime hours that they are approaching a potentially hazardous area.

**Option:**

Type B warning lights are designed to operate 24 hours per day and may be mounted on advance warning signs or on independent supports.

Type C Steady-Burn warning lights and Type D 360-degree Steady-Burn warning lights may be used during nighttime hours to delineate the edge of the traveled way.

**Guidance:**

When used to delineate a curve, Type C and Type D 360-degree warning lights should only be used on devices on the outside of the curve, and not on the inside of the curve.

**Section 6F.79 Steady-Burn Electric Lamps****Support:**

Steady-Burn electric lamps are a series of low-wattage, yellow, electric lamps, generally hard-wired to a 110-volt external power source.

**Option:**

Steady-Burn electric lamps may be used in place of Type C Steady-Burn warning lights (see Section 6F.78).

**Section 6F.80 Temporary Traffic Control Signals****Standard:**

**Temporary traffic control signals (see Section 4D.20) used to control road user movements through TTC zones and in other TTC situations shall meet the applicable provisions of Part 4.**

**Support:**

Temporary traffic control signals are typically used in TTC zones such as temporary haul road crossings; temporary one-way operations along a one-lane, two-way highway; temporary one-way operations on bridges, reversible lanes, and intersections.

**Standard:**

**One-lane, two-way vehicular traffic flow (see Chapter 4G) requires an all-red interval of sufficient duration for road users to clear the portion of the TTC zone controlled by the traffic control signals. Safeguards shall be incorporated to avoid the possibility of conflicting signal indications at each end of the TTC zone.**

**Guidance:**

Where pedestrian traffic is detoured to a temporary traffic control signal, engineering judgment should be used to determine if pedestrian signals or accessible pedestrian signals (see Section 4E.06) are needed for crossing along an alternate route.

When temporary traffic control signals are used, conflict monitors typical of traditional traffic control signal operations should be used.

Option:

Temporary traffic control signals may be portable or temporarily mounted on fixed supports.

**Standard:**

**The supports for temporary traffic control signals shall not encroach into the minimum required width of a “pedestrian access route” of 1200 mm (48 in) or an “alternate circulation path” or 900 mm (36 in).**

Guidance:

Temporary traffic control signals should only be used in situations where temporary traffic control signals are preferable to other means of traffic control, such as changing the work staging or work zone size to eliminate one-way vehicular traffic movements, using flaggers to control one-way or crossing movements, using STOP or YIELD signs, and using warning devices alone.

Support:

Factors related to the design and application of temporary traffic control signals include the following:

- A. Safety and road user needs;
- B. Work staging and operations;
- C. The feasibility of using other TTC strategies (for example, flaggers, providing space for two lanes, or detouring road users, including bicyclists and pedestrians);
- D. Sight distance restrictions;
- E. Human factors considerations (for example, lack of driver familiarity with temporary traffic control signals);
- F. Road-user volumes including roadway and intersection capacity;
- G. Affected side streets and driveways;
- H. Vehicle speeds;
- I. The placement of other TTC devices;
- J. Parking;
- K. Turning restrictions;
- L. Pedestrians;
- M. The nature of adjacent land uses (such as residential or commercial);
- N. Legal authority;
- O. Signal phasing and timing requirements;
- P. Full-time or part-time operation;
- Q. Actuated, fixed-time, or manual operation;
- R. Power failures or other emergencies;
- S. Inspection and maintenance needs;
- T. Need for detailed placement, timing, and operation records; and
- U. Operation by contractors or by others.

Although temporary traffic control signals can be mounted on trailers or lightweight portable supports, fixed supports offer superior resistance to displacement or damage by severe weather, vehicle impact, and vandalism.

Guidance:

Other TTC devices should be used to supplement temporary traffic control signals, including warning and regulatory signs, pavement markings, and channelizing devices.

The design and placement of temporary traffic control signals should include interconnection to other traffic control signals along the subject roadway.

Temporary traffic control signals not in use should be covered or removed.

## **Section 6F.81 Temporary Traffic Barriers**

### Support:

Temporary traffic barriers are devices designed to help prevent penetration by vehicles while minimizing injuries to vehicle occupants, and are designed to protect workers, bicyclists, and pedestrians.

The four primary functions of temporary traffic barriers are:

- A. To keep vehicular traffic from entering work areas, such as excavations or material storage sites;
- B. To separate workers, bicyclists, and pedestrians from motor vehicle traffic;
- C. To separate opposing directions of vehicular traffic; and
- D. To separate vehicular traffic, bicyclists, and pedestrians from the work area such as false work for bridges and other exposed objects..

### Option:

Temporary traffic barriers, including shifting portable or movable barrier installations to accommodate varying directional vehicular traffic demands, may be used to separate two-way vehicular traffic.

### Guidance:

Because the protective requirements of a TTC situation have priority in determining the need for temporary traffic barriers, their use should be based on an engineering study. When serving the additional function of channelizing vehicular traffic (see Section 6F.65), temporary traffic barriers should be a light color for increased visibility.

### Standard:

**Temporary traffic barriers shall be supplemented with standard delineation, pavement markings, or channelizing devices for improved daytime and nighttime visibility if they are used to channelize vehicular traffic. The delineation color shall match the applicable pavement marking color.**

**In order to mitigate the effect of striking the end of a temporary traffic barrier, the end shall be installed in accordance with AASHTO's "Roadside Design Guide" (see Section 1A.11) by flaring until the end is outside the acceptable clear zone or by providing crashworthy end treatments.**

### Option:

Warning lights or steady-burn electric lamps may be mounted on temporary traffic barrier installations.

### Support:

A movable barrier is a linear system of connected barrier segments that can rapidly be shifted laterally by using a specially designed transfer vehicle. The transfer is accomplished in a manner that does not interfere with vehicular traffic in adjacent lanes. Applications of movable barriers include the following:

- A. Closing an additional lane during work periods while maintaining the advantage of having the travel way separated from the work space by a barrier;
- B. Closing an additional lane during off-peak periods to provide extra space for work activities without adversely impacting vehicular traffic flow; and
- C. Creating a temporary reversible lane, thus providing unbalanced capacity favoring the major direction of vehicular traffic flow.

More specific information on the use of temporary traffic barriers is contained in Chapters 8 and 9 of AASHTO's "Roadside Design Guide" (see Section 1A.11).

## **Section 6F.82 Crash Cushions**

### Support:

Crash cushions are systems that mitigate the effects of errant vehicles that strike obstacles, either by smoothly decelerating the vehicle to a stop when hit head-on, or by redirecting the errant vehicle. The two

types of crash cushions that are used in TTC zones are stationary crash cushions and truck-mounted attenuators. Crash cushions in TTC zones help protect the drivers from the exposed ends of barriers, fixed objects, shadow vehicles, and other obstacles. Specific information on the use of crash cushions can be found in AASHTO's "Roadside Design Guide" (see Section 1A.11).

**Standard:**

**Crash cushions shall be crashworthy. They shall also be designed for each application to stop or redirect errant vehicles under prescribed conditions. Crash cushions shall be periodically inspected to verify that they have not been hit or damaged. Damaged crash cushions shall be promptly repaired or replaced to maintain their crashworthiness.**

Support:

Stationary crash cushions are used in the same manner as permanent highway installations to protect drivers from the exposed ends of barriers, fixed objects, and other obstacles.

**Standard:**

**Stationary crash cushions shall be designed for the specific application intended.**

**Truck-mounted attenuators shall be energy-absorbing devices attached to the rear of shadow trailers or trucks. If used, the shadow vehicle with the attenuator shall be located in advance of the work area, workers, or equipment to reduce the severity of rear-end crashes from errant vehicles.**

Support:

Trucks or trailers are often used as shadow vehicles to protect workers or work equipment from errant vehicles. These shadow vehicles are normally equipped with flashing arrows, changeable message signs, and/or high-intensity rotating, flashing, oscillating, or strobe lights located properly in advance of the workers and/or equipment that they are protecting. However, these shadow vehicles might themselves cause injuries to occupants of the errant vehicles if they are not equipped with truck-mounted attenuators.

Guidance:

The shadow truck should be positioned a sufficient distance in advance of the workers or equipment being protected so that there will be sufficient distance, but not so much so that errant vehicles will travel around the shadow truck and strike the protected workers and/or equipment.

Support:

Chapter 9 of AASHTO's "Roadside Design Guide" (see Section 1A.11) contains additional information regarding the use of shadow vehicles.

Guidance:

If used, the truck-mounted attenuator should be used in accordance with the manufacturer's specifications.

### **Section 6F.83 Vehicle-Arresting Systems**

Support:

Vehicle-arresting systems are designed to prevent penetration into activity areas while providing for smooth, reasonably safe deceleration for the errant vehicles. They can consist of portable netting, cables, and energy-absorbing anchors.

Guidance:

When used, a vehicle-arresting system should be used in accordance with the manufacturer's specifications, and should be located so that vehicles are not likely to penetrate the location that the system is designed to protect.

## **Section 6F.84 Rumble Strips**

### **Support:**

Transverse rumble strips consist of intermittent narrow, transverse areas of rough-textured or slightly raised or depressed road surface that extend across the travel lanes to alert drivers to unusual vehicular traffic conditions. Through noise and vibration they attract the driver's attention to such features as unexpected changes in alignment and to conditions requiring a stop.

Longitudinal rumble strips consist of a series of rough-textured or slightly raised or depressed road surfaces located along the shoulder to alert road users that they are leaving the travel lanes.

### **Standard:**

**If it is desirable to use a color other than the color of the pavement for a longitudinal rumble strip, the color of the rumble strip shall be the same color as the longitudinal line the rumble strip supplements.**

**If the color of a transverse rumble strip used within a travel lane is not the color of the pavement, the color of the rumble strip shall be white.**

### **Option:**

Intervals between transverse rumble strips may be reduced as the distance to the approached conditions is diminished in order to convey an impression that a closure speed is too fast and/or that an action is imminent. A sign warning drivers of the onset of rumble strips may be placed in advance of any transverse rumble strip installation.

### **Guidance:**

Transverse rumble strips should be placed transverse to vehicular traffic movement. They should not adversely affect overall pavement skid resistance under wet or dry conditions.

In urban areas, even though a closer spacing might be warranted, transverse rumble strips should be designed in a manner that does not promote unnecessary braking or erratic steering maneuvers by road users..

Transverse rumble strips should not be placed on sharp horizontal or vertical curves.

Rumble strips should not be placed through pedestrian crossings or on bicycle routes.

Transverse rumble strips should not be placed on roadways used by bicyclists unless a minimum clear path of 1.2 m (4 ft) is provided at each edge of the roadway or on each paved shoulder as described in AASHTO's "Guide to the Development of Bicycle Facilities" (see Section 1A.11).

Longitudinal rumble strips should not be placed on the shoulder of a roadway that is used by bicyclists unless a minimum clear path of 1.2 m (4 ft) is also provided on the shoulder.

## **Sections 6F.85 Screens**

### **Support:**

Screens are used to block the road users' view of activities that can be distracting. Screens might improve safety and vehicular traffic flow where volumes approach the roadway capacity because they discourage gawking and reduce headlight glare from oncoming vehicular traffic.

### **Guidance:**

Screens should not be mounted where they could adversely restrict road user visibility and sight distance and adversely affect the reasonably safe operation of vehicles.

### **Option:**

Screens may be mounted on the top of temporary traffic barriers that separate two-way motor vehicle traffic.

**Guidance:**

Design of screens should be in accordance with Chapter 9 of AASHTO's "Roadside Design Guide" (see Section 1A.11).

**Section 6F.86 Future and Experimental Devices****Support:**

The States, FHWA, AASHTO, the Transportation Research Board, and other organizations conduct research and experimentation on new traffic control and safety devices. Users of this Manual are encouraged to stay abreast of these current efforts and to use such devices with care so as to avoid presenting road users with unusual or confusing situations that might be abnormal or unexpected.

**Standard:**

**New traffic control devices shall conform to the provisions for design, use, and application set forth in this Manual. New traffic control devices that do not conform with the provisions in this Manual shall be subject to experimentation, documentation, and adoption following the provisions of Section 1A.10.**

Intentionally blank.

## **CHAPTER 6G. TYPE OF TEMPORARY TRAFFIC CONTROL ZONE ACTIVITIES**

### **Section 6G.01 Typical Applications**

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

Each TTC zone is different. Many variables, such as location of work, highway type, geometrics, vertical and horizontal alignment, intersections, interchanges, road user volumes, road vehicle mix (buses, trucks, and cars), and road user speeds affect the needs of each zone. The goal of TTC in work zones is safety with minimum disruption to road users. The key factor in promoting TTC zone safety is proper judgment.

Typical applications (TAs) of TTC zones are organized according to duration, location, type of work, and highway type. Table 6H-1 is an index of these typical applications. These typical applications include the use of various TTC methods, but do not include a layout for every conceivable work situation.

Guidance:

Typical applications should be altered, when necessary, to fit the conditions of a particular TTC zone.

Option:

Other devices may be added to supplement the devices shown in the typical applications, while others may be deleted. The sign spacings and taper lengths may be increased to provide additional time or space for driver response.

Support:

Decisions regarding the selection of the most appropriate typical application to use as a guide for a specific TTC zone require an understanding of each situation. Although there are many ways of categorizing TTC zone applications, the four factors mentioned earlier (work duration, work location, work type, and highway type) are used to characterize the typical applications illustrated in Chapter 6H.

### **Section 6G.02 Work Duration**

Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Work duration is a major factor in determining the number and types of devices used in TTC zones. The duration of a TTC zone is defined relative to the length of time a work operation occupies a spot location.

**Standard:**

**The five categories of work duration and their time at a location shall be:**

- A. Long-term stationary is work that occupies a location more than 3 days.**
- B. Intermediate-term stationary is work that occupies a location more than one daylight period up to 3 days, or nighttime work lasting more than 1 hour.**
- C. Short-term stationary is daytime work that occupies a location for more than 1 hour within a single daylight period.**

**D. Short duration is work that occupies a location up to 1 hour.**

**E. Mobile is work that moves intermittently or continuously.**

Support:

At long-term stationary TTC zones, there is ample time to install and realize benefits from the full range of TTC procedures and devices that are available for use. Generally, larger channelizing devices, temporary roadways, and temporary traffic barriers are used.

**Standard:**

**Since long-term operations extend into nighttime, retroreflective and/or illuminated devices shall be used in long-term stationary TTC zones.**

Guidance:

Inappropriate markings in long-term stationary TTC zones should be removed and replaced with temporary markings.

Support:

In intermediate-term stationary TTC zones, it might not be feasible or practical to use procedures or devices that would be desirable for long-term stationary TTC zones, such as altered pavement markings, temporary traffic barriers, and temporary roadways. The increased time to place and remove these devices in some cases could significantly lengthen the project, thus increasing exposure time. In other instances, there might be insufficient pay-back time to economically justify more elaborate TTC measures.

**Standard:**

**Since intermediate-term operations extend into nighttime, retroreflective and/or illuminated devices shall be used in intermediate-term stationary TTC zones.**

Support:

Most maintenance and utility operations are short-term stationary work.

As compared to stationary operations, mobile and short-duration operations are activities that might involve different treatments. Devices having greater mobility might be necessary such as signs mounted on trucks. Devices that are larger, more imposing, or more visible can be used effectively and economically. The mobility of the TTC zone is important.

Maintaining reasonably safe work and road user conditions is a paramount goal in carrying out mobile operations.

Guidance:

Safety in short-duration or mobile operations should not be compromised by using fewer devices simply because the operation will frequently change its location.

Option:

Appropriately colored or marked vehicles with high-intensity rotating, flashing, oscillating, or strobe lights may be used in place of signs and channelizing devices for short-duration or mobile operations. These vehicles may be augmented with signs or arrow panels,

Support:

During short-duration work, it often takes longer to set up and remove the TTC zone than to perform the work. Workers face hazards in setting up and taking down the TTC zone. Also, since the work time is short, delays affecting road users are significantly increased when additional devices are installed and removed.

**Option:**

Considering these factors, simplified control procedures may be warranted for short-duration work. A reduction in the number of devices may be offset by the use of other more dominant devices such as high-intensity rotating, flashing, oscillating, or strobe lights on work vehicles.

**Support:**

Mobile operations often involve frequent short stops for activities such as litter cleanup, pothole patching, or utility operations, and are similar to short-duration operations.

**Guidance:**

Warning signs, high-intensity rotating, flashing, oscillating, or strobe lights on a vehicle, flags, and/or channelizing devices should be used and moved periodically to keep them near the mobile work area.

**Option:**

Flaggers may be used for mobile operations that often involve frequent short stops.

**Support:**

Mobile operations also include work activities where workers and equipment move along the road without stopping, usually at slow speeds. The advance warning area moves with the work area.

**Guidance:**

When mobile operations are being performed, a shadow vehicle equipped with an arrow panel or a sign should follow the work vehicle, especially when vehicular traffic speeds or volumes are high. Where feasible, warning signs should be placed along the roadway and moved periodically as work progresses.

Under high-volume conditions, consideration should be given to scheduling mobile operations work during off-peak hours.

If there are mobile operations on a high-speed travel lane of a multi-lane divided highway, arrow panels should be used.

**Option:**

For mobile operations that move at speeds less than 5 km/h (3 mph), mobile signs or stationary signing that is periodically retrieved and repositioned in the advance warning area may be used.

At higher speeds, vehicles may be used as components of the TTC zones for mobile operations. Appropriately colored and marked vehicles with signs, flags, high-intensity rotating, flashing, oscillating, or strobe lights, truck-mounted attenuators, and arrow panels or portable changeable message signs may follow a train of moving work vehicles.

For some continuously moving operations, such as street sweeping and snow removal, a single work vehicle with appropriate warning devices on the vehicle may be used to provide warning to approaching road users.

**Standard:**

**Mobile operations that move at speeds greater than 30 km/h (20 mph), such as pavement marking operations, shall have appropriate devices on the equipment (that is, high-intensity rotating, flashing, oscillating, or strobe lights, signs, or special lighting), or shall use a separate vehicle with appropriate warning devices.**

**Section 6G.03 Location of Work****Support:**

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

The choice of TTC needed for a TTC zone depends upon where the work is located. As a general rule, the closer the work is to road users (including bicyclists and pedestrians), the greater the number of TTC devices that are needed. Procedures are described later in this Chapter for establishing TTC zones in the following locations:

- A. Outside the shoulder;
- B. On the shoulder with no encroachment;
- C. On the shoulder with minor encroachment;
- D. Within the median; and
- E. Within the traveled way.

**Standard:**

**When the work space is within the traveled way, except for short-duration and mobile operations, advance warning shall provide a general message that work is taking place and shall supply information about highway conditions. TTC devices shall indicate how vehicular traffic can move through the TTC control zone.**

**Section 6G.04 Modifications To Fulfill Special Needs**

**Support:**

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

The typical applications in Chapter 6H illustrate commonly encountered situations in which TTC devices are employed.

**Option:**

Other devices may be added to supplement the devices indicated in the typical applications, and device spacing may be adjusted to provide additional reaction time. When conditions are less complex than those depicted in the typical applications, fewer devices may be needed.

**Guidance:**

When conditions are more complex, typical applications should be modified by giving particular attention to the provisions set forth in Chapter 6B and by incorporating appropriate devices and practices from the following list:

- A. Additional devices:
  - 1. Signs
  - 2. Arrow panels
  - 3. More channelizing devices at closer spacing (see Section 6F.68 for information regarding detectable edging for pedestrians)
  - 4. Temporary raised pavement markers
  - 5. High-level warning devices
  - 6. Portable changeable message signs
  - 7. Temporary traffic control signals (including pedestrian signals and accessible pedestrian signals)
  - 8. Temporary traffic barriers
  - 9. Crash cushions
  - 10. Screens
  - 11. Rumble strips
  - 12. More delineation
- B. Upgrading of devices:
  - 1. A full complement of standard pavement markings
  - 2. Brighter and/or wider pavement markings
  - 3. Larger and/or brighter signs
  - 4. Channelizing devices with greater conspicuity
  - 5. Temporary traffic barriers in place of channelizing devices

- C. Improved geometrics at detours or crossovers
- D. Increased distances:
  1. Longer advance warning area
  2. Longer tapers
- E. Lighting:
  1. Temporary roadway lighting
  2. Steady-burn lights used with channelizing devices
  3. Flashing lights for isolated hazards
  4. Illuminated signs
  5. Floodlights

Where pedestrian or bicycle usage is high, typical applications should also be modified by giving particular attention to the provisions set forth in Chapter 6D, Section 6F.68, and other Sections of Part 6 related to accessibility and detectability provisions in TTC zones.

### **Section 6G.05 Work Affecting Pedestrian and Bicycle Facilities**

#### **Support:**

It is not uncommon, particularly in urban areas, that road work and the associated TTC will affect existing pedestrian or bicycle facilities. It is essential that the needs of all road users, including pedestrians with disabilities, are considered in TTC zones.

In addition to specific provisions identified in Sections 6G.06, 6G.07, 6G.08, 6G.10, 6G.11, 6G.12, and 6G.13, there are a number of provisions that might be applicable for all of the types of activities identified in this Chapter.

#### **Guidance:**

Where pedestrian or bicycle usage is high, the typical applications should be modified by giving particular attention to the provisions set forth in Chapters 6D and 6G, Section 6F.68, and in other Sections of Part 6 related to accessibility and detectability provisions in TTC zones.

Pedestrians should be separated from the worksite by appropriate devices that maintain the accessibility and detectability for pedestrians with disabilities.

Bicyclists and pedestrians should not be exposed to unprotected excavations, open utility access, overhanging equipment, or other such conditions.

Except for short duration and mobile operations, when a highway shoulder is occupied, a SHOULDER WORK sign should be placed in advance of the activity area. When work is performed on a paved shoulder 2.4 m (8 ft) or more in width, channelizing devices should be placed on a taper having a length that conforms to the requirements of a shoulder taper. Signs should be placed such that they do not narrow any existing pedestrian passages to less than 1200 mm (48 in).

Pedestrian detours should be avoided since pedestrians rarely observe them and the cost of providing accessibility and detectability might outweigh the cost of maintaining a continuous route. Whenever possible, work should be done in a manner that does not create a need to detour pedestrians from existing routes or crossings.

#### **Standard:**

**Where pedestrian routes are closed, alternate pedestrian routes shall be provided.**

**When existing pedestrian facilities are disrupted, closed, or relocated in a TTC zone, the temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.**

## **Section 6G.06 Work Outside of Shoulder**

### Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

When work is being performed off the roadway (beyond the shoulders, but within the right-of-way), little or no TTC might be needed. TTC generally is not needed where work is confined to an area 4.6 m (15 ft) or more from the edge of the traveled way. However, TTC is appropriate where distracting situations exist, such as vehicles parked on the shoulder, vehicles accessing the work site via the highway, and equipment traveling on or crossing the roadway to perform the work operations (for example, mowing). For work beyond the shoulder, see Figure 6H-1.

### Guidance:

Where the above situations exist, a single warning sign, such as ROAD WORK AHEAD, should be used. If the equipment travels on the roadway, the equipment should be equipped with appropriate flags, high-intensity rotating, flashing, oscillating, or strobe lights, and/or a SLOW MOVING VEHICLE sign.

### Option:

If work vehicles are on the shoulder, a SHOULDER WORK sign may be used. For mowing operations, the sign MOWING AHEAD may be used.

Where the activity is spread out over a distance of more than 3.2 km (2 mi), the SHOULDER WORK sign may be repeated every 1.6 km (1 mi).

A supplementary plaque with the message NEXT X MILES may be used.

### Guidance:

A general warning sign like ROAD MACHINERY AHEAD should be used if workers and equipment must occasionally move onto the shoulder.

## **Section 6G.07 Work on the Shoulder with No Encroachment**

### Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

The provisions of this Section apply to short-term through long-term stationary operations.

### Standard:

**When paved shoulders having a width of 2.4 m (8 ft) or more are closed, at least one advance warning sign shall be used. In addition, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct motor vehicle traffic to remain within the traveled way.**

### Guidance:

When paved shoulders having a width of 2.4 m (8 ft) or more are closed on freeways and expressways, road users should be warned about potential disabled vehicles that cannot get off the traveled way. An initial general warning sign (such as ROAD WORK AHEAD) should be used, followed by a RIGHT or LEFT SHOULDER CLOSED sign. Where the end of the shoulder closure extends beyond the distance which can be perceived by road users, a supplementary plaque bearing the message NEXT X FEET or MILES should be placed below the SHOULDER CLOSED sign. On multi-lane, divided highways, signs advising of shoulder work or the condition of the shoulder should be placed only on the side of the affected shoulder.

When an improved shoulder is closed on a high-speed roadway, it should be treated as a closure of a portion of the road system because road users expect to be able to use it in emergencies. Road users should be given ample advance warning that shoulders are closed for use as refuge areas throughout a specified

length of the approaching TTC zone. The sign(s) should read **SHOULDER CLOSED** with distances indicated. The work space on the shoulder should be closed off by a taper or channelizing devices with a length of 0.33 L using the formulas in Table 6C-3.

When the shoulder is not occupied but work has adversely affected its condition, the **LOW SHOULDER** or **SOFT SHOULDER** sign should be used, as appropriate.

Where the condition extends over a distance in excess of 1.6 km (1 mi), the sign should be repeated at 1.6 km (1 mi) intervals.

Option:

In addition, a supplementary plaque bearing the message **NEXT X MILES** may be used. Temporary traffic barriers may be needed to inhibit encroachment of errant vehicles into the work space and to protect workers.

**Standard:**

**When used for shoulder work, arrow panels shall operate only in the caution mode.**

Support:

A typical application for stationary work operations on shoulders is shown in Figure 6H-3. Short duration or mobile work on shoulders is shown in Figure 6H-4. Work on freeway shoulders is shown in Figure 6H-5.

### **Section 6G.08 Work on the Shoulder with Minor Encroachment**

Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Guidance:

When work takes up part of a lane, vehicular traffic volumes, vehicle mix (buses, trucks, cars, and bicycles), speed, and capacity should be analyzed to determine whether the affected lane should be closed. Unless the lane encroachment permits a remaining lane width of 3 m (10 ft), the lane should be closed.

Truck off-tracking should be considered when determining whether the minimum lane width of 3 m (10 ft) is adequate.

Option:

A lane width of 2.7 m (9 ft) may be used for short-term stationary work on low-volume, low-speed roadways when vehicular traffic does not include longer and wider heavy commercial vehicles.

Support:

Figure 6H-6 illustrates a method for handling vehicular traffic where the stationary or short duration work space encroaches slightly into the traveled way.

### **Section 6G.09 Work Within the Median**

Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Guidance:

If work in the median of a divided highway is within 4.6 m (15 ft) from the edge of the traveled way for either direction of travel, TTC should be used through the use of advance warning signs and channelizing devices.

## **Section 6G.10 Work Within the Traveled Way of Two-Lane Highways**

### **Support:**

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Detour signs are used to direct road users onto another roadway. At diversions, road users are directed onto a temporary roadway or alignment placed within or adjacent to the right-of-way. Typical applications for detouring or diverting road users on two-lane highways are shown in Figures 6H-7, 6H-8, and 6H-9. Figure 6H-7 illustrates the controls around an area where a section of roadway has been closed and a diversion has been constructed. Channelizing devices and pavement markings are used to indicate the transition to the temporary roadway.

### **Guidance:**

When a detour is long, Detour (M4-8, M4-9) signs should be installed to remind and reassure road users periodically that they are still successfully following the detour.

When an entire roadway is closed, as illustrated in Figure 6H-8, a detour should be provided and road users should be warned in advance of the closure, which in this example is a closure 16 km (10 mi) from the intersection. If local road users are allowed to use the roadway up to the closure, the ROAD CLOSED AHEAD, LOCAL TRAFFIC ONLY sign should be used. The portion of the road open to local road users should have adequate signing, marking, and delineation.

Detours should be signed so that road users will be able to traverse the entire detour route and back to the original roadway as shown in Figure 6H-9.

### **Support:**

Techniques for controlling vehicular traffic under one-lane, two-way conditions are described in Section 6C.10.

### **Option:**

Flaggers may be used as shown in Figure 6H-10.

STOP/YIELD sign control may be used on roads with low traffic volumes as shown in Figure 6H-11.

A temporary traffic control signal may be used as shown in Figure 6H-12.

## **Section 6G.11 Work Within the Traveled Way of Urban Streets**

### **Support:**

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

In urban TTC zones, decisions are needed on how to control vehicular traffic, such as how many lanes are required, whether any turns need to be prohibited at intersections, and how to maintain access to business, industrial, and residential areas.

Pedestrian traffic needs separate attention. Chapter 6D contains information regarding pedestrian movements near TTC zones.

### **Standard:**

**If the TTC zone affects the movement of pedestrians, adequate pedestrian access and walkways shall be provided. If the TTC zone affects an accessible and detectable pedestrian facility, the accessibility and detectability shall be maintained along the alternate pedestrian route.**

**If the TTC zone affects the movement of bicyclists, adequate access to the roadway or shared-use paths shall be provided (see Part 9).**

**Where transit stops are affected or relocated because of work activity, access to temporary transit stops shall be provided.**

Guidance:

If a designated bicycle route is closed because of the work being done, a signed alternate route should be provided. Bicyclists should not be directed onto the path used by pedestrians.

Work sites within the intersection should be protected against inadvertent pedestrian incursion by providing detectable channelizing devices.

Support:

Utility work takes place both within and outside the roadway to construct and maintain services such as power, gas, light, water, or telecommunications. Operations often involve intersections, since that is where many of the network junctions occur. The work force is usually small, only a few vehicles are involved, and the number and types of TTC devices placed in the TTC zone is usually minimal.

**Standard:**

**All TTC devices shall be retroreflective or illuminated if utility work is performed during nighttime hours.**

Guidance:

As discussed under short-duration projects, however, the reduced number of devices in utility work zones should be offset by the use of high-visibility devices, such as high-intensity rotating, flashing, oscillating, or strobe lights on work vehicles or high-level warning devices.

Support:

Figures 6H-6, 6H-10, 6H-15, 6H-18, 6H-21, 6H-22, 6H-23, 6H-26, and 6H-33 are examples of typical applications for utility operations. Other typical applications might apply as well.

### **Section 6G.12 Work Within the Traveled Way of Multi-lane, Nonaccess Controlled Highways**

Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Work on multi-lane (two or more lanes of vehicular traffic in one direction) highways is divided into right-lane closures, left-lane closures, interior-lane closures, multiple-lane closures, and closures on five-lane roadways.

**Standard:**

**When a lane is closed on a multi-lane road for other than a mobile operation, a transition area containing a merging taper shall be used.**

Guidance:

When justified by an engineering study, temporary traffic barriers should be used to prevent incursions of errant vehicles into hazardous areas or work space.

**Standard:**

**When temporary traffic barriers are placed immediately adjacent to the traveled way, they shall be equipped with appropriate channelizing devices, delineation, and/or other TTC devices. For lane closures, the merging taper shall use channelizing devices and the temporary traffic barrier shall be placed beyond the transition area.**

**Support:**

It must be recognized that although temporary traffic barriers are shown in several of the typical applications of Chapter 6H, they are not considered to be TTC devices in themselves.

Figure 6H-34 illustrates a lane closure in which temporary traffic barriers are used.

**Option:**

When the right lane is closed, TTC similar to that shown in Figure 6H-33 may be used for undivided or divided four-lane roads.

**Guidance:**

If morning and evening peak hour vehicular traffic volumes in the two directions are uneven and the greater volume is on the side where the work is being done in the right lane, consideration should be given to closing the inside lane for opposing vehicular traffic and making the lane available to the side with heavier vehicular traffic, as shown in Figure 6H-31.

If the larger vehicular traffic volume changes to the opposite direction at a different time of the day, the TTC should be changed to allow two lanes for opposing vehicular traffic by moving the devices from the opposing lane back to the centerline. When it is necessary to create a temporary centerline that is not consistent with the pavement markings, channelizing devices should be used and closely spaced.

**Option:**

When closing a left lane on a multi-lane undivided road, as vehicular traffic flow permits, the two interior lanes may be closed, as shown in Figure 6H-30, to provide drivers and workers additional lateral clearance and to provide access to the work space.

**Standard:**

**When only the left lane is closed on undivided roads, channelizing devices shall be placed along the centerline as well as along the adjacent lane.**

**Guidance:**

When an interior lane is closed, an adjacent lane should also be considered for closure to provide additional space for vehicles and materials and to facilitate the movement of equipment within the work space.

When multiple lanes in one direction are closed, a capacity analysis should be made to determine the number of lanes needed to accommodate motor vehicle traffic needs. Vehicular traffic should be moved over one lane at a time. As shown in Figure 6H-37, the tapers should be separated by a distance of  $2L$ , with  $L$  being determined by the formulas in Table 6C-3.

**Standard:**

**When a directional roadway is closed, inapplicable WRONG WAY signs and markings, and other existing traffic control devices at intersections within the temporary two-lane, two-way operations section shall be covered, removed, or obliterated.**

**Option:**

When half the road is closed on an undivided highway, both directions of vehicular traffic may be accommodated as shown in Figure 6H-32. When both interior lanes are closed, temporary traffic controls may be used as indicated in Figure 6H-30. When a roadway must be closed on a divided highway, a median crossover may be used (see Section 6G.16).

**Support:**

TTC for lane closures on five-lane roads is similar to other multi-lane undivided roads. Figure 6H-32 can be adapted for use on five-lane roads. Figure 6H-35 can be used on a five-lane road for short duration and mobile operations.

### **Section 6G.13 Work Within the Traveled Way at an Intersection**

#### Support:

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

The typical applications for intersections are classified according to the location of the work space with respect to the intersection area (as defined by the extension of the curb or edge lines). The three classifications are near side, far side, and in-the-intersection. Work spaces often extend into more than one portion of the intersection. For example, work in one quadrant often creates a near-side work space on one street and a far-side work space on the cross street. In such instances, an appropriate TTC plan is obtained by combining features shown in two or more of the intersection and pedestrian typical applications.

TTC zones in the vicinity of intersections might block movements and interfere with normal road user flows. Such conflicts frequently occur at more complex signalized intersections having such features as traffic signal heads over particular lanes, lanes allocated to specific movements, multiple signal phases, signal detectors for actuated control, and accessible pedestrian signals and detectors.

#### Guidance:

The effect of the work upon signal operation should be considered, such as signal phasing for ensuring adequate capacity, maintaining or adjusting signal detectors, and ensuring the appropriate visibility of signal heads.

#### **Standard:**

**When work will occur near an intersection where operational, capacity, or pedestrian accessibility problems are anticipated, the highway agency having jurisdiction shall be contacted.**

#### Guidance:

For work at an intersection, advance warning signs, devices, and markings should be used on all cross streets, as appropriate. The typical applications depict urban intersections on arterial streets. Where the posted speed limit, the off-peak 85th-percentile speed prior to the work starting, or the anticipated speed exceeds 60 km/h (40 mph), additional warning signs should be used in the advance warning area.

Pedestrian crossings near TTC sites should be separated from the worksite by appropriate barriers that maintain the accessibility and detectability for pedestrians with disabilities.

#### Support:

Near-side work spaces, as depicted in Figure 6H-21, are simply handled as a midblock lane closure. A problem that might occur with near-side lane closure is a reduction in capacity, which during certain hours of operation could result in congestion and backups.

#### Option:

When near-side work spaces are used, an exclusive turn lane may be used for through vehicular traffic.

Where space is restricted in advance of near-side work spaces, as with short block spacings, two warning signs may be used in the advance warning area, and a third action-type warning or a regulatory sign (such as Keep Left) may be placed within the transition area.

#### Support:

Far-side work spaces, as depicted in Figures 6H-22 through 6H-25, involve additional treatment because road users typically enter the activity area by straight-through and left- or right-turning movements.

#### Guidance:

When a lane through an intersection must be closed on the far side, it should also be closed on the near-side approach to preclude merging movements within the intersection.

**Option:**

If there are a significant number of vehicles turning from a near-side lane that is closed on the far side, the near-side lane may be converted to an exclusive turn lane.

**Support:**

Figures 6H-26 and 6H-27 provide guidance on applicable procedures for work performed within the intersection.

**Option:**

If the work is within the intersection, any of the following strategies may be used:

- A. A small work space so that road users can move around it, as shown in Figure 6H-26;
- B. Flaggers or uniformed law enforcement officers to direct road users, as shown in Figure 6H-27;
- C. Work in stages so the work space is kept to a minimum; and
- D. Road closures or upstream diversions to reduce road user volumes.

**Guidance:**

Depending on road user conditions, a flagger(s) and/or a uniformed law enforcement officer(s) should be used to control road users.

**Section 6G.14 Work Within the Traveled Way of Freeways and Expressways****Support:**

Problems of TTC might occur under the special conditions encountered where vehicular traffic must be moved through or around TTC zones on high-speed, high-volume roadways. Although the general principles outlined in the previous Sections of this Manual are applicable to all types of highways, high-speed, access-controlled highways need special attention in order to reasonably safely and efficiently accommodate vehicular traffic while also protecting work forces. The road user volumes, road vehicle mix (buses, trucks, cars, and bicycles, if permitted), and speed of vehicles on these facilities require that careful TTC procedures be implemented, for example, to induce critical merging maneuvers well in advance of work spaces and in a manner that creates minimum turbulence and delay in the vehicular traffic stream. These situations often require more conspicuous devices than specified for normal rural highway or urban street use. However, the same important basic considerations of uniformity and standardization of general principles apply for all roadways.

Work under high-speed, high-volume vehicular traffic on a controlled access highway is complicated by the roadway design and operational features. The presence of a median that establishes separate roadways for directional vehicular traffic flow might prohibit the closing of one of the roadways or the diverting of vehicular traffic to the other roadway. Lack of access to and from adjacent roadways prohibits rerouting of vehicular traffic away from the work space in many cases. Other conditions exist where work must be limited to night hours, thereby necessitating increased use of warning lights, illumination of work spaces, and advance warning systems.

TTC for a typical lane closure on a divided highway is shown in Figure 6H-33. Temporary traffic controls for short duration and mobile operations on freeways are shown in Figure 6H-35. A typical application for shifting vehicular traffic lanes around a work space is shown in Figure 6H-36. TTC for multiple and interior lane closures on a freeway is shown in Figures 6H-37 and 6H-38.

**Guidance:**

The method for closing an interior lane when the open lanes have the capacity to carry vehicular traffic should be as shown in Figure 6H-37. When the capacity of the other lanes is needed, the method shown in Figure 6H-38 should be used.

### **Section 6G.15 Two-Lane, Two-Way Traffic on One Roadway of a Normally Divided Highway**

#### Support:

Two-lane, two-way operation on one roadway of a normally divided highway is a typical procedure that requires special consideration in the planning, design, and work phases, because unique operational problems (for example, increasing the risk of head-on crashes) can arise with the two-lane, two-way operation.

#### Standard:

**When two-lane, two-way traffic control must be maintained on one roadway of a normally divided highway, opposing vehicular traffic shall be separated with either temporary traffic barriers (concrete safety-shape or approved alternate) or with channelizing devices throughout the length of the two-way operation. The use of markings and complementary signing, by themselves, shall not be used.**

#### Support:

Figure 6H-39 shows the procedure for two-lane, two-way operation. Treatments for entrance and exit ramps within the two-way roadway segment of this type of work are shown in Figures 6H-40 and 6H-41.

### **Section 6G.16 Crossovers**

#### Guidance:

The following are considered good guiding principles for the design of crossovers:

- A. Tapers for lane drops should be separated from the crossovers, as shown in Figure 6H-39.
- B. Crossovers should be designed for speeds no lower than 16 km/h (10 mph) below the posted speed, the off-peak 85th-percentile speed prior to the work starting, or the anticipated operating speed of the roadway, unless unusual site conditions require that a lower design speed be used.
- C. A good array of channelizing devices, delineators, and full-length, properly placed pavement markings should be used to provide drivers with a clearly defined travel path.
- D. The design of the crossover should accommodate all vehicular traffic, including trucks and buses.

#### Support:

Temporary traffic barriers and the excessive use of TTC devices cannot compensate for poor geometric and roadway cross-section design of crossovers.

### **Section 6G.17 Interchanges**

#### Guidance:

Access to interchange ramps on limited-access highways should be maintained even if the work space is in the lane adjacent to the ramps. Access to exit ramps should be clearly marked and delineated with channelizing devices. For long-term projects, conflicting pavement markings should be removed and new ones placed. Early coordination with officials having jurisdiction over the affected cross streets and providing emergency services should occur before ramp closings.

#### Option:

If access is not possible, ramps may be closed by using signs and Type III barricades. As the work space changes, the access area may be changed, as shown in Figure 6H-42. A TTC zone in the exit ramp may be handled as shown in Figure 6H-43.

When a work space interferes with an entrance ramp, a lane may need to be closed on the freeway (see Figure 6H-44). A TTC zone in the entrance ramp may require shifting ramp vehicular traffic (see Figure 6H-44).

### **Section 6G.18 Movable Barriers**

#### **Support:**

Figure 6H-45 shows a temporary reversible lane using movable barriers.

#### **Option:**

If the work activity in Figure 6H-34 permits, a movable barrier may be used and relocated to the shoulder during nonwork periods or peak-period vehicular traffic conditions.

### **Section 6G.19 Work in the Vicinity of Highway-Rail Grade Crossings**

#### **Standard:**

**When highway-rail grade crossings exist either within or in the vicinity of a TTC zone, lane restrictions, flagging, or other operations shall not create conditions where vehicles can be queued across the railroad tracks. If the queuing of vehicles across the tracks cannot be avoided, a uniformed law enforcement officer or flagger shall be provided at the crossing to prevent vehicles from stopping on the tracks, even if automatic warning devices are in place.**

#### **Support:**

Figure 6H-46 shows work in the vicinity of a highway-rail grade crossing.

#### **Guidance:**

Early coordination with the railroad company should occur before work starts.

### **Section 6G.20 Temporary Traffic Control During Nighttime Hours**

#### **Support:**

Chapter 6D and Sections 6F.68 and 6G.05 contain additional information regarding the steps to follow when pedestrian or bicycle facilities are affected by the worksite.

Conducting highway construction and maintenance activities during night hours could provide an advantage when traditional daytime traffic control strategies cannot achieve an acceptable balance between worker and public safety, traffic and community impact, and constructability. The two basic advantages of working at night are reduced traffic congestion and less involvement with business activities. However, the two basic conditions that must normally be met for night work to offer any advantage are reduced traffic volumes and easy set up and removal of the traffic control patterns on a nightly basis.

Shifting work activities to night hours, when traffic volumes are lower and normal business is less active, might offer an advantage in some cases, as long as the necessary work can be completed and the work site restored to essentially normal operating conditions to carry the higher traffic volume during non-construction hours.

Although working at night might offer advantages, it also includes safety issues. Reduced visibility inherent in night work impacts the performance of both drivers and workers. Because traffic volumes are lower and congestion is minimized, speeds are often higher at night necessitating greater visibility at a time when visibility is reduced. Finally, the incidence of impaired (alcohol or drugs), fatigued, or drowsy drivers might be higher at night.

Working at night also involves other factors, including construction productivity and quality, social impacts, economics, and environmental issues. A decision to perform construction or maintenance activities at night normally involves some consideration of the advantages to be gained compared to the safety and other issues that might be impacted.

**Guidance:**

Considering the safety issues inherent to night work, consideration should be given to enhancing traffic controls (see Section 6G.04) to provide added visibility and driver guidance, and increased protection for workers.

In addition to the enhancements listed in Section 6G.04, consideration should be given to providing additional lights and retroreflective markings to workers, work vehicles, and equipment.

**Option:**

Where reduced traffic volumes at night make it feasible, the entire roadway may be closed by detouring traffic to alternate facilities, thus removing the traffic risk from the activity area.

**Guidance:**

Because typical street and highway lighting is rarely adequate to provide sufficient levels of illumination for work tasks, temporary lighting should be provided where workers are active to supply sufficient illumination to reasonably safely perform the work tasks.

Temporary lighting for night work should be designed such that glare does not interfere with driver visibility, or create visibility problems for truck drivers, equipment operators, flaggers, or other workers.

Consideration should also be given to stationing uniformed law enforcement officers and lighted patrol cars at night work locations where there is a concern that high speeds or impaired drivers might result in undue risks for workers or other drivers.

**Standard:**

**Except in emergencies, temporary lighting shall be provided at all flagger stations.**

**Support:**

Desired illumination levels vary depending upon the nature of the task involved. An average horizontal luminance of 50 lux (5 foot candles) can be adequate for general activities. An average horizontal luminance of 108 lux (10 foot candles) can be adequate for activities around equipment. Tasks requiring high levels of precision and extreme care can require an average horizontal luminance of 216 lux (20 foot candles).

Intentionally blank.

## CHAPTER 6H. TYPICAL APPLICATIONS

### Section 6H.01 Typical Applications

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control.”

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

Chapter 6G contains discussions of typical TTC activities. Chapter 6H presents typical applications for a variety of situations commonly encountered. While not every situation is addressed, the information illustrated can generally be adapted to a broad range of conditions. In many instances, an appropriate TTC plan is achieved by combining features from various typical applications. For example, work at an intersection might present a near-side work zone for one street and a far-side work zone for the other street. These treatments are found in two different typical applications, while a third typical application shows how to handle pedestrian crosswalk closures. For convenience in using the typical application diagrams, Tables 6C-1 and 6C-4 are reproduced in this Chapter as Tables 6H-3 and 6H-4, respectively.

Procedures for establishing TTC zones vary with such conditions as road configuration, location of the work, work activity, duration of work, road user volumes, road vehicle mix (buses, trucks, cars, motorcycles, and bicycles), and road user speeds. Examples are presented in this Chapter showing how to apply principles and standards. Applying these guidelines to actual situations and adjusting to field conditions requires judgment. In general, the procedures illustrated represent minimum solutions for the situations depicted.

Option:

Other devices may be added to supplement the devices and device spacing may be adjusted to provide additional reaction time or delineation. Fewer devices may be used based on field conditions.

Support:

Figures and tables found throughout Part 6 provide information for the development of TTC plans. Also, Table 6H-3 is used for the determination of sign spacing and other dimensions for various area and roadway types.

Table 6H-1 is an index of the 46 typical applications. Typical applications are shown on the right page with notes on the facing page to the left. The legend for the symbols used in the typical applications is provided in Table 6H-2. In many of the typical applications, sign spacings and other dimensions are indicated by letters using the criteria provided in Table 6H-3. The formulas for determining taper lengths are provided in Table 6H-4.

Most of the typical applications show TTC devices for only one direction.


**Table 6H-1. Index to Typical Applications (Sheet 1 of 2)**

Typical Application Description	Typical Application Number
<b>Work Outside of Shoulder (see Section 6G.06)</b>	
Work Beyond the Shoulder	TA-1
Blasting Zone	TA-2
<b>Work on the Shoulder (see Sections 6G.07 and 6G.08)</b>	
Work on Shoulders	TA-3
Short Duration or Mobile Operation on Shoulder	TA-4
Shoulder Closure on Freeway	TA-5
Shoulder Work with Minor Encroachment	TA-6
<b>Work Within the Traveled Way of Two-Lane Highways (see Section 6G.10)</b>	
Road Closed with Diversion	TA-7
Roads Closed with Off-Site Detour	TA-8
Overlapping Routes with Detour	TA-9
Lane Closure on Two-Lane Road Using Flaggers	TA-10
Lane Closure on Two-Lane Road with Low Traffic Volumes	TA-11
Lane Closure on Two-Lane Road Using Traffic Control Signals	TA-12
Temporary Road Closure	TA-13
Haul Road Crossing	TA-14
Work in Center of Road with Low Traffic Volumes	TA-15
Surveying Along Centerline of Road with Low Traffic Volumes	TA-16
Mobile Operations on Two-Lane Road	TA-17
<b>Work Within the Traveled Way of Urban Streets (see Section 6G.11)</b>	
Lane Closure on Minor Street	TA-18
Detour for One Travel Direction	TA-19
Detour for Closed Street	TA-20
<b>Work Within the Traveled Way at an Intersection and Sidewalks (see Section 6G.13)</b>	
Lane Closure on Near Side of Intersection	TA-21
Right Lane Closure on Far Side of Intersection	TA-22
Left Lane Closure on Far Side on Intersection	TA-23
Half Road closure on Far Side of Intersection	TA-24
Multiple Lane Closures at Intersection	TA-25
Closure in Center of Intersection	TA-26
Closure at Side of Intersection	TA-27
Sidewalk Closures and Bypass Sidewalks	TA-28
Crosswalk Closures and Pedestrian Detours	TA-29

**Table 6H-1. Index to Typical Applications (Sheet 2 of 2)**

Typical Application Description	Typical Application Number
Work Within the Traveled Way of Multilane Undivided Highways (see Section 6G.12)	
Interior Lane Closure on Multi-lane Street	TA-30
Lane Closure on Street with Uneven Directional Volume	TA-31
Half Road Closure on Multi-lane, High-Speed Highway	TA-32
Lane Closure on Divided Highway	TA-33
Lane Closure with Temporary Traffic Barrier	TA-34
Mobile Operation on Multi-lane Road	TA-35
Work Within the Traveled Way of Freeways and Expressways (see Section 6G.14)	
Lane Shift on Freeway	TA-36
Double Lane Closure on Freeway	TA-37
Interior Lane Closure on Freeway	TA-38
Median Crossover on Freeway	TA-39
Median Crossover for Entrance Ramp	TA-40
Median Crossover for Exit Ramp	TA-41
Work in Vicinity of Exit Ramp	TA-42
Partial Exit Ramp Closure	TA-43
Work in Vicinity of Entrance Ramp	TA-44
Temporary Reversible Lane Using Movable Barriers	TA-45
Work in the Vicinity of Highway-Rail Grade Crossings (see Section 6G.19)	
Work in Vicinity of Highway-Rail Grade Crossing	TA-46

**Table 6H-2. Meaning of Symbols on Typical Application Diagrams**

	Arrow panel
	Arrow panel support or trailer (shown facing down)
	Changeable message sign or support trailer
	Channelizing device
	Crash cushion
	Direction of temporary traffic detour
	Direction of traffic
	Flagger
	High-level warning device (Flag tree)
	Luminaire
	Pavement markings that should be removed for a long-term project
	Sign (shown facing left)
	Surveyor
	Temporary barrier
	Temporary barrier with warning lights
	Traffic or Pedestrian signal
	Truck-mounted attenuator
	Type III Barricade
	Warning lights
	Work space
	Work vehicle

**Table 6H-3. Meaning of Letter Codes on Typical Application Diagrams**

Road Type	Distance Between Signs **		
	A	B	C
Urban (low speed) *	30 (100)	30 (100)	30 (100)
Urban (high speed) *	100 (350)	100 (350)	100 (350)
Rural	150 (500)	150 (500)	150 (500)
Expressway / Freeway	300 (1,000)	450 (1,500)	800 (2,640)

\* Speed category to be determined by highway agency.

\*\* Distances are shown in meters (feet). The column headings A, B, and C are the dimensions shown in Figures 6H-1 through 6H-46. The A dimension is the distance from the transition or point of restriction to the first sign. The B dimension is the distance between the first and second signs. The C dimension is the distance between the second and third signs. (The third sign is the first one in a three-sign series encountered by a driver approaching a TTC zone.)

**Table 6H-4. Formulas for Determining Taper Lengths**

Speed Limit (S)	Taper Length (L) Meters
60 km/h or less	$L = \frac{WS^2}{155}$
70 km/h or more	$L = \frac{WS}{1.6}$

Speed Limit (S)	Taper Length (L) Feet
40 mph or less	$L = \frac{WS^2}{60}$
45 mph or more	$L = WS$

Where: L = taper length in meters (feet)

W = width of offset in meters (feet)

S = posted speed limit, of off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in km/h (mph)

## **Notes for Figure 6H-1—Typical Application 1**

### **Work Beyond the Shoulder**

**Guidance:**

1. If the work space is in the median of a divided highway, an advance warning sign should also be placed on the left side of the directional roadway.


**Option:**

2. The ROAD WORK AHEAD sign may be replaced with other appropriate signs such as the SHOULDER WORK sign. The SHOULDER WORK sign may be used for work adjacent to the shoulder.
3. The ROAD WORK AHEAD sign may be omitted where the work space is behind a barrier, more than 600 mm (24 in) behind the curb, or 4.6 m (15 ft) or more from the edge of any roadway.
4. For short-term, short-duration or mobile operation, all signs and channelizing devices may be eliminated if a vehicle with activated high-intensity rotating, flashing, oscillating, or strobe lights is used.
5. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

6. **Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-1. Work Beyond the Shoulder (TA-1)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 1**

**Notes for Figure 6H-2—Typical Application 2**  
**Blasting Zone**


**Standard:**

1. **Whenever blasting caps are used within 300 m (1,000 ft) of a roadway, the signing shown shall be used.**
2. **The signs shall be covered or removed when there are no explosives in the area or the area is otherwise secure.**
3. **Whenever a side road intersects the roadway between the BLASTING ZONE AHEAD sign and the END BLASTING ZONE sign, or a side road is within 300 m (1,000 ft) of any blasting cap, similar signing, as on the mainline, shall be installed on the side road.**
4. **Prior to blasting, the blaster in charge shall determine whether road users in the blasting zone will be endangered by the blasting operation. If there is danger, road users shall not be permitted to pass through the blasting zone during blasting operations.**

**Guidance:**

5. On a divided highway, the signs should be mounted on both sides of the directional roadways.

**Figure 6H-2. Blasting Zone (TA-2)**



**Typical Application 2**

### Notes for Figure 6H-3—Typical Application 3 Work on Shoulders

**Guidance:**

1. A SHOULDER WORK sign should be placed on the left side of the roadway for a divided or one-way street only if the left shoulder is affected.


**Option:**

2. The Workers symbol signs may be used instead of SHOULDER WORK signs.
3. The SHOULDER WORK AHEAD sign on an intersecting roadway may be omitted where drivers emerging from that roadway will encounter another advance warning sign prior to this activity area.
4. For short-duration operations of 60 minutes or less, all signs and channelizing devices may be eliminated if a vehicle with activated high-intensity rotating, flashing, oscillating, or strobe lights is used.
5. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

6. **Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**
7. **When paved shoulders having a width of 2.4 m (8 ft) or more are closed, at least one advance warning sign shall be used. In addition, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.**

**Figure 6H-3. Work on Shoulders (TA-3)**



**Notes for Figure 6H-4—Typical Application 4**  
**Short-Duration or Mobile Operation on Shoulder**

**Guidance:**

1. In those situations where multiple work locations within a limited distance make it practical to place stationary signs, the distance between the advance warning sign and the work should not exceed 8 km (5 mi).
2. In those situations where the distance between the advance signs and the work is 3.2 km (2 mi) to 8 km (5 mi), a Supplemental Distance plaque should be used with the ROAD WORK AHEAD sign.


**Option:**

3. The ROAD WORK NEXT XX MILES sign may be used instead of the ROAD WORK AHEAD sign if the work locations occur over a distance of more than 3.2 km (2 mi).
4. Warning signs may be omitted when the work vehicle displays high-intensity rotating, flashing, oscillating, or strobe lights if the distance between work locations is 1.6 km (1 mile) or more, and if the work vehicle travels at vehicular traffic speeds between locations.
5. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

6. **Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**
7. **If an arrow panel is used for an operation on the shoulder, the caution mode shall be used.**

**Figure 6H-4. Short-Duration or Mobile Operation on Shoulder (TA-4)**



**Typical Application 4**

## **Notes for Figure 6H-5—Typical Application 5**

### **Shoulder Closure on Freeway**

**Guidance:**

1. SHOULDER CLOSED signs should be used on limited-access highways where there is no opportunity for disabled vehicles to pull off the roadway.
2. If drivers cannot see a pull-off area beyond the closed shoulder, information regarding the length of the shoulder closure should be provided in meters or kilometers (feet or miles), as appropriate.
3. The use of a temporary traffic barrier should be based on engineering judgment.


**Standard:**

4. **Where temporary traffic barriers are installed, the ends of the barrier shall be treated in accordance with the provisions of Section 6F.81.**

**Option:**

5. The barrier shown in this typical application is an example of one method that may be used to close a shoulder of a long-term project.
6. The warning lights shown on the barrier may be used.

**Figure 6H-5. Shoulder Closure on Freeway (TA-5)**



**Typical Application 5**

## **Notes for Figure 6H-6—Typical Application 6**

### **Shoulder Work with Minor Encroachment**

#### **Guidance:**

1. All lanes should be a minimum of 3 m (10 ft) in width as measured to the near face of the channelizing devices.
2. The treatment shown should be used on a minor road having low speeds. For higher-speed traffic conditions, a lane closure should be used.


#### **Option:**

3. For short-term use on low-volume, low-speed roadways with vehicular traffic that does not include longer and wider heavy commercial vehicles, a minimum lane width of 2.7 m (9 ft) may be used.
4. Where the opposite shoulder is suitable for carrying vehicular traffic and of adequate width, lanes may be shifted by use of closely spaced channelizing devices, provided that the minimum lane width of 3 m (10 ft) is maintained.
5. Additional advance warning may be appropriate, such as a ROAD NARROWS sign.
6. Temporary traffic barriers may be used along the work space.
7. The shadow vehicle may be omitted if a taper and channelizing devices are used.
8. A truck-mounted attenuator may be used on the shadow vehicle.
9. For short-duration work, the taper and channelizing devices may be omitted if a shadow vehicle with activated high-intensity rotating, flashing, oscillating, or strobe lights is used.
10. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

#### **Standard:**

- 11. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-6. Shoulder Work with Minor Encroachment (TA-6)**



## **Notes for Figure 6H-7—Typical Application 7**

### **Road Closure with Diversion**

#### Support:

1. Signs and object markers are shown for one direction of travel only.

#### Standard:

- 2. Devices similar to those depicted shall be placed for the opposite direction of travel.**
- 3. Pavement markings no longer applicable shall be removed or obliterated as soon as practicable.**
- 4. Temporary barriers and end treatments shall be crashworthy.**


#### Guidance:

5. If the tangent distance along the temporary diversion is more than 180 m (600 ft), a Reverse Curve sign, left first, should be used instead of the Double Reverse Curve sign, and a second Reverse Curve sign, right first, should be placed in advance of the second reverse curve back to the original alignment.
6. When the tangent section of the diversion is more than 180 m (600 ft), and the diversion has sharp curves with recommended speeds of 50 km/h (30 mph) or less, Reverse Turn signs should be used.
7. Where the temporary pavement and old pavement are different colors, the temporary pavement should start on the tangent of the existing pavement and end on the tangent of the existing pavement.

#### Option:

8. Flashing warning lights and/or flags may be used to call attention to the warning signs.
9. On sharp curves, large arrow signs may be used in addition to other advance warning signs.
10. Delineators or channelizing devices may be used along the diversion.

**Figure 6H-7. Road Closure with Diversion (TA-7)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

## Notes for Figure 6H-8—Typical Application 8

### Road Closure with Off-Site Detour

#### Guidance:

1. Regulatory traffic control devices should be modified as needed for the duration of the detour.
2. If the road is opened for some distance beyond the intersection and/or there are significant origin/destination points beyond the intersection, the ROAD CLOSED and DETOUR signs on Type III Barricades should be located at the edge of the traveled way.

#### Option:

3. If the road is closed a short distance beyond the intersection and there are few origin/destination points beyond (for example, a few residences), the Type III Barricade shown in the figure may be moved to the center of the traveled lanes.


#### Standard:

4. **If the barricades are located as in Item 3 above, the ROAD CLOSED and DETOUR signs shall be placed only on the barricade centered in the lane of travel of traffic approaching the closure. The barricade centered in the lane of travel of departing traffic shall not be signed. The barricades in adjacent lanes shall be offset longitudinally from each other an adequate distance in order to permit traffic to travel around the barricades (the barricade in the road user's lane located in advance of the barricade located left of the center line).**

#### Option:

5. A Route Sign Directional assembly may be placed on the far left corner of the intersection to augment or replace the one shown on the near right corner.
6. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
7. Cardinal direction plaques may be used with route signs.

**Figure 6H-8. Road Closure with Off-Site Detour (TA-8)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure. See Section 2D.11 and Figure 2D-3 for the correct design of an Ohio State Route sign.

**Typical Application 8**

## **Notes for Figure 6H-9—Typical Application 9 Overlapping Routes with Detour**

Support:

1. TTC devices are shown for one direction of travel only.

**Standard:**

- 2. Devices similar to those depicted shall be placed for the opposite direction of travel.**


Guidance:

3. STOP signs displayed to side roads should be installed as needed along the temporary route.

Option:

4. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
5. Flashing warning lights may be used on the Type III Barricades.
6. Cardinal direction plaques may be used with route signs.

**Figure 6H-9. Overlapping Routes with Detour (TA-9)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this Figure. See Section 2D.11 and Figure 2D-3 for the correct design of an Ohio State Route sign.

**Typical Application 9**

## Notes for Figure 6H-10—Typical Application 10

### Lane Closure on Two-Lane Road Using Flaggers

#### Option:

1. For low-volume situations with short work zones on straight roadways where the flagger is visible to road users approaching from both directions, a single flagger, positioned to be visible to road users approaching from both directions, may be used (see Chapter 6E).
2. The ROAD WORK AHEAD and the END ROAD WORK signs may be omitted for short-duration operations.
3. Flashing warning lights and/or flags may be used to call attention to the advance warning signs. A BE PREPARED TO STOP sign may be added to the sign series.

#### Guidance:

4. The buffer space should be extended so that the two-way traffic taper is placed before a horizontal (or crest vertical) curve to provide adequate sight distance for the flagger and a queue of stopped vehicles.

#### Standard:

- 5. At night, flagger stations shall be illuminated, except in emergencies.**


#### Guidance:

6. When used, the BE PREPARED TO STOP sign should be located between the Flagger sign and the ONE LANE ROAD sign.
7. When a highway-rail grade crossing exists within or upstream of the transition area and it is anticipated that queues resulting from the lane closure might extend through the highway-rail grade crossing, the TTC zone should be extended so that the transition area precedes the highway-rail grade crossing.
8. When a highway-rail grade crossing equipped with active warning devices exists within the activity area, provisions should be made for keeping flaggers informed as to the activation status of these warning devices.
9. When a highway-rail grade crossing exists within the activity area, drivers operating on the left side of the normal centerline should be provided with comparable warning devices as for drivers operating on the right side of the normal centerline.
10. Early coordination with the railroad company should occur before work starts.

#### Option:

11. A flagger or a uniformed law enforcement officer may be used at the highway-rail grade crossing to minimize the probability that vehicles are stopped within 4.6 m (15 ft) of the highway-rail grade crossing, measured from both sides of the outside rails.

**Figure 6H-10. Lane Closure on Two-Lane Road Using Flaggers (TA-10)**




**Typical Application 10**

**Notes for Figure 6H-11—Typical Application 11**  
**Lane Closure on Two-Lane Road with Low Traffic Volumes**

Option:

1. This TTC zone application may be used as an alternate to the TTC application shown in Figure 6H-10 (using flaggers) when the following conditions exist:
  - a. Vehicular traffic volume is such that sufficient gaps exist for vehicular traffic that must yield.
  - b. Road users from both directions are able to see approaching vehicular traffic through and beyond the work site and have sufficient visibility of approaching vehicles.
2. The Type B flashing warning lights may be placed on the ROAD WORK AHEAD and the ONE LANE ROAD AHEAD signs whenever a night lane closure is necessary. For additional information on proper use of warning lights, see Section 6F-78.

**Figure 6H-11. Lane Closure on Two-Lane Road with Low Traffic Volumes (TA-11)**



**Typical Application 11**

**Notes for Figure 6H-12—Typical Application 12**  
**Lane Closure on Two-Lane Road Using Traffic Control Signals**

**Standard:**

1. **TTC signals shall be installed and operated in accordance with the provisions of Part 4. TTC signals shall meet the physical display and operational requirements of conventional traffic control signals.**
2. **TTC signal timing shall be established by authorized officials. Durations of red clearance intervals shall be adequate to clear the one-lane section of conflicting vehicles.**
3. **When the TTC signal is changed to the flashing mode, either manually or automatically, red signal indications shall be flashed to both approaches.**
4. **Stop lines shall be installed with TTC signals for intermediate and long-term closures. Existing conflicting pavement markings and raised pavement marker reflectors between the activity area and the stop line shall be removed. After the TTC signal is removed, the stop lines and other temporary pavement markings shall be removed and the permanent pavement markings restored.**
5. **Safeguards shall be incorporated to avoid the possibility of conflicting signal indications at each end of the TTC zone.**

**Guidance:**

6. Where no-passing lines are not already in place, they should be added.
7. Adjustments in the location of the advance warning signs should be made as needed to accommodate the horizontal or vertical alignment of the roadway, recognizing that the distances shown for sign spacings are minimums. Adjustments in the height of the signal heads should be made as needed to conform to the vertical alignment.


**Option:**

8. Flashing warning lights shown on the ROAD WORK AHEAD and the ONE LANE ROAD AHEAD signs may be used.
9. Removable pavement markings may be used.

**Support:**

10. TTC signals are preferable to flaggers for long-term projects and other activities that would require flagging at night.
11. The maximum length of activity area for one-way operation under TTC signal control is determined by the capacity required to handle the peak demand.

**Figure 6H-12. Lane Closure on Two-Lane Road Using Traffic Control Signals (TA-12)**



**Typical Application 12**

**Notes for Figure 6H-13—Typical Application 13**  
**Temporary Road Closure**

Support:

1. Conditions represented are a planned closure not exceeding 20 minutes during the daytime.

Standard:

- 2. A flagger or uniformed law enforcement officer shall be used for this application. The flagger, if used for this application, shall follow the procedures noted in Sections 6E.04 and 6E.05.**

Guidance:

3. The uniformed law enforcement officer, if used for this application, should follow the procedures noted in Sections 6E.04 and 6E.05.


Option:

4. A BE PREPARED TO STOP sign may be added to the sign series.

Guidance:

5. When used, the BE PREPARED TO STOP sign should be located before the Flagger symbol sign.

**Figure 6H-13. Temporary Road Closure (TA-13)**



## **Notes for Figure 6H-14—Typical Application 14 Haul Road Crossing**

### **Guidance:**

1. Floodlights should be used to illuminate haul road crossings where existing light is inadequate.
2. Where no-passing lines are not already in place, they should be added.

### **Standard:**

3. **The traffic control method selected shall be used in both directions.**



#### **Flagging Method**

4. **When a road used exclusively as a haul road is not in use, the haul road shall be closed with Type III barricades and the Flagger symbol signs covered.**
5. **The flagger shall follow the procedures noted in Sections 6E.04 and 6E.05.**
6. **At night, flagger stations shall be illuminated, except in emergencies.**

#### **Signalized Method**

7. **When a road used exclusively as a haul road is not in use, Type III barricades shall be in place. The signals shall either flash yellow on the main road or be covered, and the Signal Ahead and STOP HERE ON RED signs shall be covered or hidden from view.**
8. **The TTC signals shall control both the highway and the haul road and shall meet the physical display and operational requirements of conventional traffic control signals as described in Part 4. Traffic control signal timing shall be established by authorized officials.**
9. **Stop lines shall be used on existing highway with TTC signals.**
10. **Existing conflicting pavements markings between the stop lines shall be removed. After the TTC signal is removed, the stop lines and other temporary pavement markings shall be removed and the permanent pavement markings restored.**

**Figure 6H-14. Haul Road Crossing (TA-14)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 14**

**Notes for Figure 6H-15—Typical Application 15**  
**Work in Center of Road with Low Traffic Volumes**

Guidance:

1. The lanes on either side of the center work space should have a minimum width of 3 m (10 ft) as measured from the near edge of the channelizing devices to the edge of pavement or the outside edge of paved shoulder.
2. Workers in the roadway should wear high-visibility safety apparel as described in Section 6D.03.


Option:

3. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
4. If the closure continues overnight, warning lights may be used on the channelizing devices.
5. A lane width of 2.7 m (9 ft) may be used for short-term stationary work on low-volume, low-speed roadways when motor vehicle traffic does not include longer and wider heavy commercial vehicles.
6. A work vehicle displaying high-intensity rotating, flashing, oscillating, or strobe lights may be used instead of the channelizing devices forming the tapers or the high-level warning devices.
7. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

- 8. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-15. Work in Center of Road with Low Traffic Volumes (TA-15)**



**Typical Application 15**

**Notes for Figure 6H-16—Typical Application 16**  
**Surveying Along Centerline of Road with Low Traffic Volumes**

Guidance:

1. Cones should be placed 150 mm (6 in) to 300 mm (12 in) on either side of the centerline.
2. When using metric units, spacing of channelizing devices should not exceed a distance in meters equal to 1/5 of the speed limit (km/h) when used for taper channelization and a distance in meters equal to 2/5 of the speed limit (km/h) when used for tangent channelization. When using English units, spacing of channelizing devices should not exceed a distance in feet equal to the speed limit (mph) when used for the taper channelization and a distance in feet of 2 times the speed limit (mph) when used for tangent channelization.
3. A flagger should be used to warn workers who cannot watch road users.
4. Workers in the roadway should wear high-visibility safety apparel as described in Section 6D.03.

**Standard:**

- 5. For surveying on the centerline of a high-volume road, one lane shall be closed using the information illustrated in Figure 6H-10.**


Option:

6. A high-level warning device may be used to protect a surveying device, such as a target on a tripod.
7. Cones may be omitted for a cross-section survey.
8. ROAD WORK AHEAD signs may be used in place of the SURVEY CREW AHEAD signs.
9. Flags may be used to call attention to the advance warning signs.
10. If the work is along the shoulder, the flagger may be omitted.
11. For a survey along the edge of the road or along the shoulder, cones may be placed along the edge line.
12. A BE PREPARED TO STOP sign may be added to the sign series.

Guidance:

13. When used, the BE PREPARED TO STOP sign should be located before the Flagger symbol sign.

**Figure 6H-16. Surveying Along Centerline of Road with Low Traffic Volumes (TA-16)**



**Typical Application 16**

**Notes for Figure 6H-17—Typical Application 17**  
**Mobile Operations on Two-Lane Road**

**Standard:**

1. **Vehicle-mounted signs shall be mounted in a manner such that they are not obscured by equipment or supplies. Sign legends on vehicle-mounted signs shall be covered or turned from view when work is not in progress.**
2. **Shadow and work vehicles shall display high-intensity rotating, flashing, oscillating, or strobe lights.**
3. **If an arrow panel is used, it shall be used in the caution mode.**

## Guidance:

4. Where practical and when needed, the work and shadow vehicles should pull over periodically to allow vehicular traffic to pass.
5. Whenever adequate stopping sight distance exists to the rear, the shadow vehicle should maintain the minimum distance from the work vehicle and proceed at the same speed. The shadow vehicle should slow down in advance of vertical or horizontal curves that restrict sight distance.
6. The shadow vehicles should also be equipped with two high-intensity flashing lights mounted on the rear, adjacent to the sign.

## Option:

7. The distance between the work and shadow vehicles may vary according to terrain, paint drying time, and other factors.
8. Additional shadow vehicles to warn and reduce the speed of oncoming or opposing vehicular traffic may be used. Law enforcement vehicles may be used for this purpose.
9. A truck-mounted attenuator may be used on the shadow vehicle or on the work vehicle.
10. If the work and shadow vehicles cannot pull over to allow vehicular traffic to pass frequently, a DO NOT PASS sign may be placed on the rear of the vehicle blocking the lane.


## Support:

11. Shadow vehicles are used to warn motor vehicle traffic of the operation ahead.

**Standard:**

12. **Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-17. Mobile Operations on Two-Lane Road (TA-17)**



**Typical Application 17**

**Notes for Figure 6H-18—Typical Application 18**  
**Lane Closure on Minor Street**

**Standard:**

1. **This TTC shall be used only for low-speed facilities having low traffic volumes.**

Option:

2. Where the work space is short, where road users can see the roadway beyond, and where volume is low, vehicular traffic may be self-regulating.


**Standard:**

3. **Where vehicular traffic cannot effectively self-regulate, one or two flaggers shall be used as illustrated in Figure 6H-10.**

Option:

4. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
5. A truck-mounted attenuator may be used on the work vehicle and the shadow vehicle.

**Figure 6H-18. Lane Closure on Minor Street (TA-18)**



Typical Application 18

**Notes for Figure 6H-19—Typical Application 19**  
**Detour for One Travel Direction**

**Guidance:**

1. This plan should be used for streets without posted route numbers.
2. On multi-lane streets, Detour signs with an Advance Turn Arrow should be used in advance of a turn.


**Option:**

3. The STREET CLOSED legend may be used in place of ROAD CLOSED.
4. Additional DO NOT ENTER signs may be used at intersections with intervening streets.
5. Warning lights may be used on Type III Barricades.
6. Detour signs may be located on the far side of intersections.
7. A Street Name sign may be mounted with the Detour sign. The Street Name sign may be either white on green or black on orange.

**Standard:**

8. **When used, the Street Name sign shall be placed above the Detour sign.**

**Figure 6H-19. Detour for One Travel Direction (TA-19)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 19**

**Notes for Figure 6H-20—Typical Application 20**  
**Detour for Closed Street**

**Guidance:**

1. This plan should be used for streets without posted route numbers.
2. On multi-lane streets, Detour signs with an Advance Turn Arrow should be used in advance of a turn.

**Option:**

3. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
4. Flashing warning lights may be used on Type III Barricades.
5. Detour signs may be located on the far side of intersections. A Detour sign with an advance arrow may be used in advance of a turn.
6. A Street Name sign may be mounted with the Detour sign. The Street Name sign may be either white on green or black on orange.


**Standard:**

- 7. When used, the Street Name sign shall be placed above the Detour sign.**

**Support:**

8. See Figure 6H-9 for the information for detouring a numbered highway.

**Figure 6H-20. Detour for Closed Street (TA-20)**



**Typical Application 20**

**Notes for Figure 6H-21—Typical Application 21**  
**Lane Closure on Near Side of Intersection**

**Standard:**

- 1. The merging taper shall direct vehicular traffic into either the right or left lane, but not both.**

**Guidance:**

2. In this typical application, a left taper should be used so that right-turn movements will not impede through vehicular traffic. However, the reverse should be true for left-turn movements.
3. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure 6H-29.


**Option:**

4. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
5. A shadow vehicle with a truck-mounted attenuator may be used.
6. A work vehicle with high-intensity rotating, flashing, oscillating, or strobe lights may be used with the high-level warning device.
7. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

- 8. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-21. Lane Closure on Near Side of Intersection (TA-21)**



**Notes for Figure 6H-22—Typical Application 22**  
**Right Lane Closure on Far Side of Intersection**


Guidance:

1. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure 6H-29.

Option:

2. The normal procedure is to close on the near side of the intersection any lane that is not carried through the intersection. However, when this results in the closure of a right lane having significant right turning movements, then the right lane may be restricted to right turns only, as shown. This procedure increases the through capacity by eliminating right turns from the open through lane.
3. For intersection approaches reduced to a single lane, left-turning movements may be prohibited to maintain capacity for through vehicular traffic.
4. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
5. Where the turning radius is large, it may be possible to create a right-turn island using channelizing devices or pavement markings.

**Figure 6H-22. Right Lane Closure on Far Side of Intersection (TA-22)**



**Notes for Figure 6H-23—Typical Application 23**  
**Left Lane Closure on Far Side of Intersection**

Guidance:

1. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure 6H-29.


Option:

2. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
3. The normal procedure is to close on the near side of the intersection any lane that is not carried through the intersection. However, when this results in the closure of a left lane having significant left-turning movements, then the left lane may be reopened as a turn bay for left turns only, as shown.

Support:

4. By first closing off the left lane and then reopening it as a turn bay, an island is created with channelizing devices that allows the LEFT LANE MUST TURN LEFT sign to be repeated on the left adjacent to the lane that it controls.

**Figure 6H-23. Left Lane Closure on Far Side of Intersection (TA-23)**



## **Notes for Figure 6H-24—Typical Application 24**

### **Half Road Closure on Far Side of Intersection**

#### Guidance:

1. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure 6H-29.
2. When turn prohibitions are implemented, two turn prohibition signs should be used, one on the near side and, space permitting, one on the far side of the intersection.


#### Option:

3. A buffer space may be used between opposing directions of vehicular traffic as shown in this application.
4. The normal procedure is to close on the near side of the intersection any lane that is not carried through the intersection. However, if there is a significant right-turning movement, then the right lane may be restricted to right turns only, as shown.
5. Where the turning radius is large, a right-turn island using channelizing devices or pavement markings may be used.
6. There may be insufficient space to place the back-to-back Keep Right sign and No Left Turn symbol signs at the end of the row of channelizing devices separating opposing vehicular traffic flows. In this situation, the No Left Turn symbol sign may be placed on the right and the Keep Right sign may be omitted.
7. For intersection approaches reduced to a single lane, left-turning movements may be prohibited to maintain capacity for through vehicular traffic.
8. Flashing warning lights and/or flags may be used to call attention to advance warning signs.
9. Temporary pavement markings may be used to delineate the travel path through the intersection.

#### Support:

10. Keeping the right lane open increases the through capacity by eliminating right turns from the open through lane.
11. A temporary turn island reinforces the nature of the temporary exclusive right-turn lane and enables a second RIGHT LANE MUST TURN RIGHT sign to be placed in the island.

**Figure 6H-24. Half Road Closure on Far Side of Intersection (TA-24)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 24**

**Notes for Figure 6H-25—Typical Application 25**  
**Multiple Lane Closures at Intersection**


Guidance:

1. If the work space extends across a crosswalk, the crosswalk should be closed using the information and devices shown in Figure 6H-29.
2. If the left through lane is closed on the near-side approach, the LEFT LANE MUST TURN LEFT sign should be placed in the median to discourage through vehicular traffic from entering the left-turn bay.

Option:

3. The normal procedure is to close on the near side of the intersection any lane that is not carried through the intersection. If the left-turning movement that normally uses the closed turn bay is small and/or the gaps in opposing vehicular traffic are frequent, left turns may be permitted on that approach.
4. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.

**Figure 6H-25. Multiple Lane Closures at Intersection (TA-25)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 25**

**Notes for Figure 6H-26—Typical Application 26**  
**Closure in Center of Intersection**

**Guidance:**

1. All lanes should be a minimum of 3 m (10 ft) in width as measured to the near face of the channelizing devices.


**Option:**

2. A high-level warning device may be placed in the work space, if there is sufficient room.
3. For short-term use on low-volume, low-speed roadways with vehicular traffic that does not include longer and wider heavy commercial vehicles, a minimum lane width of 2.7 m (9 ft) may be used.
4. Flashing warning lights and/or flags may be used to call attention to advance warning signs.
5. Unless the streets are wide, it may be physically impossible to turn left, especially for large vehicles. Left turns may be prohibited as required by geometric conditions.
6. For short-duration work operations, the channelizing devices may be eliminated if a vehicle displaying high-intensity rotating, flashing, oscillating, or strobe lights is positioned in the work space.
7. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

**Standard:**

8. **Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-26. Closure in Center of Intersection (TA-26)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 26**

## Notes for Figure 6H-27—Typical Application 27

### Closure at Side of Intersection

#### Guidance:

1. The situation depicted can be simplified by closing one or more of the intersection approaches. If this cannot be done, and/or when capacity is a problem, through vehicular traffic should be directed to other roads or streets.
2. Depending on road user conditions, flagger(s) or uniformed law enforcement officer(s) should be used to direct road users within the intersection.

#### Standard:

- 3. At night, flagger stations shall be illuminated, except in emergencies.**

#### Option:

4. ONE LANE ROAD AHEAD signs may also be used to provide adequate advance warning.
5. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
6. For short-duration work operations, the channelizing devices may be eliminated if a vehicle displaying high-intensity rotating, flashing, oscillating, or strobe lights is positioned in the work space.
7. A BE PREPARED TO STOP sign may be added to the sign series.

#### Guidance:

8. When used, the BE PREPARED TO STOP sign should be located before the Flagger symbol sign.

#### Support:

9. Turns can be prohibited as required by vehicular traffic conditions. Unless the streets are wide, it might be physically impossible to make certain turns, especially for large vehicles.


#### Option:

10. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

#### Standard:

- 11. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.**

**Figure 6H-27. Closure at Side of Intersection (TA-27)**



See Note 2 for flagger information.

Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 27**

## **Notes for Figure 6H-28—Typical Application 28**

### **Sidewalk Closures and Bypass Sidewalks**

**Standard:**

- 1. When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.**


**Guidance:**

2. Where high speeds are anticipated, a temporary traffic barrier and, if necessary, a crash cushion should be used to separate the temporary sidewalks from vehicular traffic.
3. Audible information devices should be considered where midblock closings and changed crosswalk areas cause inadequate communication to be provided to pedestrians who have visual disabilities.

**Option:**

4. Street lighting may be considered.
5. Only the TTC devices related to pedestrians are shown. Other devices, such as lane closure signing or ROAD NARROWS signs, may be used to control vehicular traffic.
6. For nighttime closures, Type A Flashing warning lights may be used on barricades that support signs and close sidewalks.
7. Type C Steady-Burn or Type D 360-degree Steady-Burn warning lights may be used on channelizing devices separating the temporary sidewalks from vehicular traffic flow.
8. Signs, such as KEEP RIGHT (LEFT), may be placed along a temporary sidewalk to guide or direct pedestrians.

**Figure 6H-28. Sidewalk Detour or Diversion (TA-28)**



**Typical Application 28**

Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

## Notes for Figure 6H-29—Typical Application 29

### Crosswalk Closures and Pedestrian Detours

#### Standard:

1. **When crosswalks or other pedestrian facilities are closed or relocated, temporary facilities shall be detectable and shall include accessibility features consistent with the features present in the existing pedestrian facility.**
2. **Curb parking shall be prohibited for at least 15 m (50 ft) in advance of the midblock crosswalk.**


#### Guidance:

3. Audible information devices should be considered where midblock closings and changed crosswalk areas cause inadequate communication to be provided to pedestrians who have visual disabilities.
4. Pedestrian traffic signal displays controlling closed crosswalks should be covered or deactivated.

#### Option:

5. Street lighting may be considered.
6. Only the TTC devices related to pedestrians are shown. Other devices, such as lane closure signing or ROAD NARROWS signs, may be used to control vehicular traffic.
7. For nighttime closures, Type A Flashing warning lights may be used on barricades supporting signs and closing sidewalks.
8. Type C Steady-Burn warning lights may be used on channelizing devices separating the work space from vehicular traffic.
9. In order to maintain the systematic use of the fluorescent yellow-green background for pedestrian, bicycle, and school warning signs in a jurisdiction, the fluorescent yellow-green background for pedestrian, bicycle, and school warning signs may be used in TTC zones.

**Figure 6H-29. Crosswalk Closures and Pedestrian Detours (TA-29)**



**Typical Application 29**

### **Notes for Figure 6H-30—Typical Application 30**

#### **Interior Lane Closure on Multi-lane Street**

**Guidance:**

1. This information applies to low-speed, low-volume urban streets. Where speed or volume is higher, additional signing such as LEFT LANE CLOSED AHEAD should be used between the signs shown.

**Option:**

2. The closure of the adjacent interior lane in the opposing direction may not be necessary, depending upon the activity being performed and the work space needed for the operation.
3. Shadow vehicles with a truck-mounted attenuator may be used.

**Guidance:**

4. When a highway-rail grade crossing exists within or upstream of the transition area and it is anticipated that backups resulting from the lane closure might extend through the highway-rail grade crossing, the TTC zone should be extended so that the transition area precedes the highway-rail grade crossing.
5. Early coordination with the railroad company should occur before work starts.

**Standard:**

6. **When an additional sign is used (see Note 1), the signs shown shall be relocated to accommodate standard sign spacing for the added sign.**



**Notes for Figure 6H-31—Typical Application 31**  
**Lane Closure on Street with Uneven Directional Volumes**

**Standard:**

1. **The illustrated information shall be used only when the vehicular traffic volume indicates that two lanes of vehicular traffic shall be maintained in the direction of travel for which one lane is closed.**

**Option:**

2. The procedure may be used during a peak period of vehicular traffic and then changed to provide two lanes in the other direction for the other peak.


**Guidance:**

3. For high speeds, a RIGHT/LEFT LANE CLOSED XX FT sign should be added for vehicular traffic approaching the lane closure, as shown in Figure 6H-32. Also, where speeds are 50 mile per hour or greater a shifting taper should be approximately L in length (see Table 6C-3).
4. Conflicting pavement markings should be removed for long-term projects. For short-term and intermediate-term projects where this is not practical, the channelizing devices in the area where the pavement markings conflict should be placed at a maximum spacing of 0.1 S m (0.5 S ft) where S is the speed in km/h (mph). Temporary markings should be installed where needed.
5. If the lane shift has curves with recommended speeds of 50 km/h (30 mph) or less, Reverse Turn signs should be used.
6. Where the shifted section is long, a Reverse Curve sign should be used to show the initial shift and a second sign should be used to show the return to the normal alignment.
7. If the tangent distance along the temporary diversion is less than 180 m (600 ft), the Double Reverse Curve sign should be used at the location of the first Two Lane Reverse Curve sign. The second Two Lane Reverse Curve sign should be omitted.

**Option:**

8. A longitudinal buffer space may be used in the activity area to separate opposing vehicular traffic.
9. An ALL LANES THRU supplemental plaque may be used to emphasize the point that all lanes shift and no lanes are closed.
10. A work vehicle or a shadow vehicle may be equipped with a truck-mounted attenuator.
11. The Construction Arrow (W1-H11) sign may be used to accent the lane shift condition.

**Figure 6H-31. Lane Closures on Street with Uneven Directional Volumes (TA-31)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Notes for Figure 6H-32—Typical Application 32**  
**Half Road Closure on Multi-lane, High-Speed Highway**

**Standard:**

- 1. Pavement markings no longer applicable shall be removed or obliterated as soon as practical. Except for intermediate-term and short-term situations, temporary markings shall be provided to clearly delineate the temporary travel path. For short-term and intermediate-term situations where it is not feasible to remove and restore pavement markings, channelization shall be made dominant by using a very close device spacing.**

## Guidance:

2. When paved shoulders having a width of 2.4 m (8 ft) or more are closed, channelizing devices should be used to close the shoulder in advance of the merging taper to direct vehicular traffic to remain within the traveled way.
3. Where channelizing devices are used instead of pavement markings, the maximum spacing should be  $0.1 S$  meters where  $S$  is the speed in km/h ( $0.5 S$  feet where  $S$  is the speed in mph).
4. If the tangent distance along the temporary diversion is more than 180 m (600 ft), a Reverse Curve sign, left first, should be used instead of the Double Reverse Curve sign, and a second Reverse Curve sign, right first, should be placed in advance of the second reverse curve back to the original alignment.

## Option:

5. Warning lights may be used to supplement channelizing devices at night.


## Guidance:

6. When a highway-rail grade crossing exists within or upstream of the merging taper and it is anticipated that backups resulting from the lane closure might extend through the highway-rail grade crossing, the TTC zone should be extended so that the merging taper precedes the highway-rail grade crossing.
7. When a highway-rail grade crossing exists within the activity area, provisions should be made to provide road users operating on the left side of the normal centerline with comparable warning devices as supplied for road users operating on the right side of the normal centerline.
8. When a highway-rail grade crossing exists within the activity area, early coordination with the railroad company should occur before work starts.

## Option:

9. When a highway-rail grade crossing exists within the activity area, a flagger may be used at the highway-rail grade crossing to minimize the probability that vehicles are stopped within 4.6 m (15 ft) of the highway-rail grade crossing, measured from both sides of the outside rails.
10. A truck-mounted attenuator may be used on the work vehicle and/or the shadow vehicle.
11. The Construction Arrow (W1-H11) sign may be used to accent the lane shift condition.

**Figure 6H-32. Half Road Closure on Multi-lane, High-Speed Highway (TA-32)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 32**

**Notes for Figure 6H-33—Typical Application 33**  
**Stationary Lane Closure on Divided Highway**

**Standard:**

- 1. This information also shall be used when work is being performed in the lane adjacent to the median on a divided highway. In this case, the LEFT LANE CLOSED signs and the corresponding Lane Ends signs shall be substituted.**
- 2. When a side road intersects the highway within the TTC zone, additional TTC devices shall be placed as needed.**

**Guidance:**

3. When paved shoulders having a width of 2.4 m (8 ft) or more are closed, channelizing devices should be used to close the shoulder in advance of the merging taper to direct vehicular traffic to remain within the traveled way.


**Option:**

4. A truck-mounted attenuator may be used on the work vehicle and/or shadow vehicle.

**Support:**

5. Where conditions permit, restricting all vehicles, equipment, workers, and their activities to one side of the roadway might be advantageous.

**Figure 6H-33. Stationary Lane Closure on Divided Highway (TA-33)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 33**

## **Notes for Figure 6H-34—Typical Application 34**

### **Lane Closure with Temporary Traffic Barrier**

**Standard:**

- 1. This information also shall be used when work is being performed in the lane adjacent to the median on a divided highway. In this case, the LEFT LANE CLOSED signs and the corresponding Lane Ends signs shall be substituted.**

## Guidance:

- For long-term lane closures on facilities with permanent edge lines, a temporary edge line should be installed from the start of the merging taper to the far end of the downstream taper, and conflicting pavement markings should be removed.
- The use of a barrier should be based on engineering judgment.

**Standard:**

- 4. Where temporary traffic barriers are installed, the ends of the barrier shall be treated in accordance with the provisions of Section 6F.81**
- 5. The barrier shall not be placed along the merging taper. The lane shall first be closed using channelizing devices and pavement markings.**

## Option:

- The barrier shown in this typical application is an example of one method that may be used to close a lane for a long-term project. If the work activity permits, a movable barrier may be used and relocated to the shoulder during nonwork periods or peak-period vehicular traffic conditions, as appropriate.
- Type C Steady-Burn warning lights may be placed on channelizing devices and the barrier parallel to the edge of pavement for nighttime lane closures.


**Standard:**

- 8. If a movable barrier is used, the temporary white edge line shown in the typical application shall not be used. During the period when the right lane is opened, the sign legends and the channelization shall be changed to indicate that only the shoulder is closed, as illustrated in Figure 6H-5. The arrow panel, if used, shall be placed at the end of the shoulder taper and shall display the caution mode.**

## Guidance:

- If a movable barrier is used, the shift should be performed in the following manner. When closing the lane, the lane should be initially closed with channelizing devices placed along a merging taper using the same information employed for a stationary lane closure. The lane closure should then be extended with the movable-barrier transfer vehicle moving with vehicular traffic. When opening the lane, the movable-barrier transfer vehicle should travel against vehicular traffic from the termination area to the transition area. The merging taper should then be removed using the same information employed for a stationary lane closure.

**Figure 6H-34. Lane Closure with Temporary Traffic Barrier (TA-34)**



**Notes for Figure 6H-35—Typical Application 35**  
**Mobile Operation on Multi-lane Road**

**Standard:**

- 1. Arrow panels shall, as a minimum, be Type B, with a size of 1500 x 750 mm (60 x 30 in).**


**Guidance:**

2. Vehicles used for these operations should be made highly visible with appropriate equipment, such as: high-intensity rotating, flashing, oscillating, or strobe lights, flags, signs, or arrow panels.
3. Shadow Vehicle 1 should be equipped with an arrow panel and truck-mounted attenuator.
4. Shadow Vehicle 2 should be equipped with an arrow panel. An appropriate lane closure sign should be placed on Shadow Vehicle 2 so as not to obscure the arrow panel.
5. Shadow Vehicle 2 should travel at a varying distance from the work operation so as to provide adequate sight distance for vehicular traffic approaching from the rear.
6. The spacing between the work vehicles and the shadow vehicles, and between each shadow vehicle should be minimized to deter road users from driving in between.
7. Work should normally be accomplished during off-peak hours.
8. When the work vehicle occupies an interior lane (a lane other than the far right or far left) of a directional roadway having a right shoulder 3 m (10 ft) or more in width, Shadow Vehicle 2 should drive the right shoulder with a sign indicating that work is taking place in the interior lane.

**Option:**

9. A truck-mounted attenuator may be used on Shadow Vehicle 2.
10. On high-speed roadways, a third shadow vehicle (not shown) may be used with Shadow Vehicle 1 in the closed lane, Shadow Vehicle 2 straddling the edge line, and Shadow Vehicle 3 on the shoulder.
11. Where adequate shoulder width is not available, Shadow Vehicle 3 may drive partially in the lane.

**Figure 6H-35. Mobile Operation on Multi-lane Road (TA-35)**



**Typical Application 35**

## Notes for Figure 6H-36—Typical Application 36

### Lane Shift on Freeway

#### Guidance:

1. The lane shift should be used when the work space extends into either the right or left lane of a divided highway and it is not practical, for capacity reasons, to reduce the number of available lanes.
2. When a lane shift is accomplished by using (1) geometry that meets the design speed at which the permanent highway was designed, (2) full normal cross-section (full lane width and full shoulders), and (3) complete pavement markings, then only the initial general work-zone warning sign is required.
3. When the conditions in Note 2 are not met, the information shown in the typical application should be employed and all the following notes apply.

#### Standard:

4. **Where temporary traffic barriers are installed, the ends of the barrier shall be treated in accordance with the provisions of Section 6F.81.**
5. **A warning sign shall be used to show the changed alignment.**

#### Guidance:

6. Where the shifted section is longer than 180 m (600 ft), one set of Reverse Curve signs should be used to show the initial shift and a second set should be used to show the return to the normal alignment. If the tangent distance along the temporary diversion is less than 180 m (600 ft), the Double Reverse Curve sign should be used instead of the first Reverse Curve sign. The second Reverse Curve sign should be omitted.
7. If a STAY IN LANE sign is used, then solid white lane lines should be used.

#### Standard:

8. **The minimum width of the shoulder lane shall be 3 m (10 ft).**
9. **For long-term stationary work, existing conflicting pavement markings shall be removed and temporary markings shall be installed before traffic patterns are changed.**

#### Option:

10. For short-term stationary work, lanes may be delineated by channelizing devices or removable pavement markings instead of temporary pavement markings.
11. Three Lane Reverse Curve signs may be used in place of the Reverse Curve signs. ALL LANES THRU supplemental plaques may be used to emphasize the point that all lanes shift and no lanes are closed.
12. If the shoulder cannot adequately accommodate trucks, trucks may be directed to use the travel lanes.
13. The barrier shown in this typical application is one method that may be used to close a lane for a long-term project.
14. The shifting taper may be approximately 0.5L where speeds are less than 50 miles per hour.


#### Guidance:

15. The use of a barrier should be based on engineering judgment.

#### Option:

16. Type C Steady-Burn warning lights may be placed on channelizing devices and the barrier parallel to the edge of pavement for nighttime lane closures.
17. The Construction Arrow (W1-H11) sign may be used to accent the lane shift condition.

**Figure 6H-36. Lane Shift on Freeway (TA-36)**



**Notes for Figure 6H-37—Typical Application 37**  
**Double Lane Closure on Freeway**

Guidance:

1. Ordinarily, the preferred position for the second arrow panel is in the closed exterior lane at the beginning of the second merging taper. However, the second arrow panel should be placed in the closed interior lane at the end of the second merging taper in the following situations:
  - a. When a shadow vehicle is used in the interior closed lane, and the second arrow panel is mounted on the shadow vehicle;
  - b. If alignment or other conditions create any confusion as to which lane is closed by the second arrow panel; and
  - c. When the first arrow panel is placed in the closed exterior lane at the end of the first merging taper (the alternative position when the shoulder is narrow).

Option:

2. Flashing warning lights and/or flags may be used to call attention to the initial warning signs.
3. A truck-mounted attenuator may be used on the shadow vehicle.
4. If a paved shoulder having a minimum width of 3 m (10 ft) and sufficient strength is available, the left and adjacent interior lanes may be closed and vehicular traffic carried around the work space on the right lane and a right shoulder.
5. When a shoulder lane is used that cannot adequately accommodate trucks, trucks may be directed to use the normal travel lanes.



### **Notes for Figure 6H-38—Typical Application 38**

#### **Interior Lane Closure on Freeway**

##### Guidance:

1. For a long-term closure, a barrier should be used to provide additional safety to the operation in the closed interior lane. A buffer space should be used at the upstream end of the closed interior lane.
2. The first arrow panel displaying a right arrow should be on the left shoulder at the beginning of the taper. The arrow panel displaying a double arrow should be centered in the closed interior lane and placed at the downstream end of the shifting taper.
3. The placement of signs should not obstruct or obscure arrow panels.
4. For long-term use, the dashed lane lines should be made solid white in the two-lane section.

##### Option:

5. The arrow panel closing the exterior lane may be moved or omitted if the alignment is such that the two panels create confusion.
6. As an alternative to initially closing the left lane, as shown in the typical application, the right lane may be closed in advance of the interior lane closure with appropriate channelization and signs.
7. A short, single row of channelizing devices in advance of the vehicular traffic split to restrict vehicular traffic to their respective lanes may be added.
8. DO NOT PASS signs may be used.
9. If a paved shoulder having a minimum width of 3 m (10 ft) and sufficient strength is available, the left and center lanes may be closed and vehicular traffic carried around the work space on the right lane and a right shoulder.
10. When a shoulder lane is used that cannot adequately accommodate trucks, trucks may be directed to use the normal travel lanes.
11. The shifting taper may be approximately 0.5L where speeds are less than 50 miles per hour.



## Notes for Figure 6H-39—Typical Application 39

### Median Crossover on Freeway

#### Standard:

1. Channelizing devices or temporary traffic barriers shall be used to separate opposing vehicular traffic.

#### Guidance:

2. For long-term work on high-speed, high-volume highways, consideration should be given to using a temporary traffic barrier to separate opposing vehicular traffic.

#### Option:

3. When a temporary traffic barrier is used to separate opposing vehicular traffic, the Two-Way Traffic, DO NOT PASS, KEEP RIGHT, and DO NOT ENTER signs may be eliminated.
4. The alignment of the crossover may be designed as a reverse curve.

#### Guidance:

5. When the crossover follows a curved alignment, the design criteria contained in the AASHTO “Policy on the Geometric Design of Highways and Streets” should be used (see Section 1A.11).
6. When channelizing devices have the potential of leading vehicular traffic out of the intended traffic space, the channelizing devices should be extended a distance in meters (feet) of 0.4 times the speed limit in km/h (2 times the speed limit in mph) beyond the end of the transition area as depicted.
7. Where channelizing devices are used, the Two-Way Traffic signs should be repeated every 1.6 km (1 mi).


#### Option:

8. NEXT X MILES Supplemental Distance plaques may be used with the Two-Way Traffic signs, where X is the distance to the end of the two-way section.

#### Support:

9. When the distance is sufficiently short that road users entering the section can see the far end of the section, they are less likely to forget that there is opposing vehicular traffic.
10. The sign legends for the four pairs of signs approaching the lane closure for the noncrossover direction of travel are not shown. They are similar to the series shown for the crossover direction, except that the left lane is closed.

**Figure 6H-39. Median Crossover on Freeway (TA-39)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 39**

**Notes for Figure 6H-40—Typical Application 40**  
**Median Crossover for Entrance Ramp**


Guidance:

1. The typical application illustrated should be used for carrying an entrance ramp across a closed directional roadway of a divided highway.
2. A temporary acceleration lane should be used to facilitate merging.
3. When used, the YIELD or STOP sign should be located far enough forward to provide adequate sight distance of oncoming mainline vehicular traffic to select a reasonably safe gap. If needed, yield or stop lines should be installed across the ramp to indicate the point at which road users should yield or stop. Also, a longer acceleration lane should be provided beyond the sign to reduce the gap size needed.

Option:

4. If vehicular traffic conditions allow, the ramp may be closed.
5. A broken edge line may be carried across the temporary entrance ramp to assist in defining the through vehicular traffic lane.
6. When a temporary traffic barrier is used to separate opposing vehicular traffic, the Two-Way Traffic signs and the DO NOT ENTER signs may be eliminated.

**Figure 6H-40. Median Crossover for Entrance Ramp (TA-40)**



**Typical Application 40**

## **Notes for Figure 6H-41—Typical Application 41**

### **Median Crossover for Exit Ramp**

#### **Guidance:**

1. This typical application should be used for carrying an exit ramp across a closed directional roadway of a divided highway. The design criteria contained in the AASHTO “Policy on the Geometric Design of Highways and Streets” (see Section 1A.11) should be used for determining the curved alignment.
2. The guide signs should indicate that the ramp is open, and where the temporary ramp is located. Conversely, if the ramp is closed, guide signs should indicate that the ramp is closed.
3. When the exit is closed, a black on orange EXIT CLOSED panel should be placed diagonally across the interchange/intersection guide signs.
4. In the situation (not shown) where channelizing devices are placed along the mainline roadway, the devices’ spacing should be reduced in the vicinity of the off ramp to emphasize the opening at the ramp itself. Channelizing devices and/or temporary pavement markings should be placed on both sides of the temporary ramp where it crosses the median and the closed roadway.
5. Advance guide signs providing information related to the temporary exit should be relocated or duplicated adjacent to the temporary roadway.


#### **Standard:**

- 6. A temporary EXIT sign shall be located in the temporary gore. For better visibility, it shall be mounted a minimum of 2.1 m (7 ft) from the pavement surface to the bottom of the sign.**

#### **Option:**

7. Guide signs referring to the exit may need to be relocated to the median.
8. The temporary EXIT sign placed in the temporary gore may be either black on orange or white on green.
9. In some instances, a temporary deceleration lane may be useful in facilitating the exiting maneuver.
10. When a temporary traffic barrier is used to separate opposing vehicular traffic, the Two-Way Traffic signs may be omitted.

**Figure 6H-41. Median Crossover for Exit Ramp (TA-41)**



**Typical Application 41**

Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Notes for Figure 6H-42—Typical Application 42**  
**Work in Vicinity of Exit Ramp**

**Guidance:**

1. The guide signs should indicate that the ramp is open, and where the temporary ramp is located. However, if the ramp is closed, guide signs should indicate that the ramp is closed.
2. When the exit ramp is closed, a black on orange EXIT CLOSED panel should be placed diagonally across the interchange/intersection guide signs.
3. The design criteria contained in the AASHTO “Policy on the Geometric Design of Highways and Streets” should be used for determining the alignment (see Section 1A.11).


**Standard:**

4. **A temporary EXIT sign shall be located in the temporary gore. For better visibility, it shall be mounted a minimum of 2.1 m (7 ft) from the pavement surface to the bottom of the sign.**

**Option:**

5. An alternative procedure that may be used is to channelize exiting vehicular traffic onto the right shoulder and close the lane as necessary.

**Figure 6H-42. Work in Vicinity of Exit Ramp (TA-42)**




**Typical Application 42**

**Notes for Figure 6H-43—Typical Application 43**  
**Partial Exit Ramp Closure**

**Guidance:**

1. Truck off-tracking should be considered when determining whether the minimum lane width of 3 m (10 ft) is adequate (see Section 6G.07).

**Figure 6H-43. Partial Exit Ramp Closure (TA-43)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 43**

**Notes for Figure 6H-44—Typical Application 44**  
**Work in Vicinity of Entrance Ramp**

Guidance:

1. An acceleration lane of sufficient length should be provided whenever possible as shown on the left diagram.

**Standard:**

2. **For the information shown on the diagram on the right side of the typical application, where inadequate acceleration distance exists for the temporary entrance, the YIELD sign shall be replaced with STOP signs (one on each side of the approach).**


Guidance:

3. When used, the YIELD or STOP sign should be located so that ramp vehicular traffic has adequate sight distance of oncoming mainline vehicular traffic to select a reasonably safe gap in the mainline vehicular traffic flow. Also, a longer acceleration lane should be provided beyond the sign to reduce the gap size needed. If insufficient gaps are available, consideration should be given to closing the ramp.
4. Where STOP signs are used, a temporary stop line should be placed across the ramp at the desired stop location.
5. The mainline merging taper with the arrow panel at its starting point should be located sufficiently in advance so that the arrow panel is not confusing to drivers on the entrance ramp, and so that the mainline merging vehicular traffic from the lane closure has the opportunity to stabilize before encountering the vehicular traffic merging from the ramp.
6. If the ramp curves sharply to the right, warning signs with Advisory Speed Limits located in advance of the entrance terminal should be placed in pairs (one on each side of the ramp).

Option:

7. A Type B high-intensity warning flasher with a red lens may be placed above the STOP sign.
8. Where the acceleration distance is significantly reduced, a supplemental plaque may be placed below the YIELD AHEAD sign reading NO MERGE AREA.

**Figure 6H-44. Work in Vicinity of Entrance Ramp (TA-44)**



**Typical Application 44**

## **Notes for Figure 6H-45—Typical Application 45**

### **Temporary Reversible Lane Using Movable Barriers**

#### Support:

1. This application addresses one of several uses for movable barriers in highway work zones. In this example, one side of a 6-lane divided highway is closed to perform the work operation, and vehicular traffic is carried in both directions on the remaining 3-lane roadway by means of a median crossover. To accommodate unbalanced peak-period vehicular traffic volumes, the direction of travel in the center lane is switched to the direction having the greater volume, with the transfer typically being made twice daily. Thus, there are four vehicular traffic phases described as follows:
  - a. Phase A—two travel lanes northbound and one lane southbound;
  - b. Transition A to B—one travel lane in each direction;
  - c. Phase B—one travel lane northbound and two lanes southbound; and
  - d. Transition B to A—one travel lane in each direction.

The typical application on the left illustrates the placement of devices during Phase A. The typical application on the right shows conditions during the transition (Transition A to B) from Phase A to Phase B.


#### Guidance:

2. For the reversible-lane situation depicted, the ends of the movable barrier should terminate in a protected area or a crash cushion should be provided. During Phase A, the transfer vehicle should be parked behind the end of the movable barrier. During Phase B, the transfer vehicle should be parked behind the end of the movable barrier.

The transition shift from Phase A to B should be as follows:

- a. Change the signs in the northbound advance warning area and transition area from a LEFT LANE CLOSED AHEAD to a LEFT TWO LANES CLOSED AHEAD. Change the mode of the second northbound arrow panel from Caution to Right Arrow.
  - b. Place channelizing devices to close the northbound center lane.
  - c. Move the transfer vehicle from south to north to shift the movable barrier from the west side to the east side of the reversible lane.
  - d. Remove the channelizing devices closing the southbound center lane.
  - e. Change the signs in the southbound transition area and advance warning area from a LEFT TWO LANES CLOSED AHEAD to LEFT LANE CLOSED AHEAD. Change the mode of the second southbound arrow panel from Right Arrow to Caution.
3. Where the lane to be opened and closed is an exterior lane (adjacent to the edge of the traveled way or the work space), the lane closure should begin by closing the lane with channelizing devices placed along a merging taper using the same information employed for a stationary lane closure. The lane closure should then be extended with the movable-barrier transfer vehicle moving with vehicular traffic. When opening the lane, the transfer vehicle should travel against vehicular traffic. The merging taper should be removed in a method similar to a stationary lane closure.

**Figure 6H-45. Movable Barriers (TA-45)**



**Typical Application 45**

Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure. Although leader lines point to signs on the right side of the roadway, most signs should be installed on both sides of the roadway.

**Notes for Figure 6H-46—Typical Application 46**  
**Work in Vicinity of Highway-Rail Grade Crossing**

**Guidance:**

1. When highway-rail grade crossings exist either within or in the vicinity of roadway work activities, extra care should be taken to minimize the probability of conditions being created, either by lane restrictions, flagging, or other operations, where vehicles might be stopped within the highway-rail grade crossing, considered as being 4.6 m (15 ft) on either side of the closest and farthest rail.

**Standard:**

2. **If the queuing of vehicles across active rail tracks cannot be avoided, a uniformed law enforcement officer or flagger shall be provided at the highway-rail grade crossing to prevent vehicles from stopping within the highway-rail grade crossing (as described in Note 1), even if automatic warning devices are in place.**

**Guidance:**

3. Early coordination with the railroad company should occur before work starts.
4. In the example depicted, the buffer space of the activity area should be extended upstream of the highway-rail grade crossing (as shown) so that a queue created by the flagging operation will not extend across the highway-rail grade crossing.
5. The DO NOT STOP ON TRACKS sign should be used on all approaches to a highway-rail grade crossing within the limits of a TTC zone.

**Option:**

6. Flashing warning lights and/or flags may be used to call attention to the advance warning signs.
7. A BE PREPARED TO STOP sign may be added to the sign series.


**Guidance:**

8. When used, the BE PREPARED TO STOP sign should be located before the Flagger symbol sign.

**Standard:**

9. **At night, flagger stations shall be illuminated, except in emergencies.**

**Figure 6H-46. Work in Vicinity of Highway-Rail Grade-Crossing (TA-46)**



Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

**Typical Application 46**

Intentionally blank.

## CHAPTER 6I. CONTROL OF TRAFFIC THROUGH TRAFFIC INCIDENT MANAGEMENT AREAS

### Section 6I.01 General

Support:

Whenever the acronym “TTC” is used in this Chapter, it refers to “temporary traffic control”.

**Standard:**

**The needs and control of all road users (motorists, bicyclists, and pedestrians within the highway, including persons with disabilities in accordance with the Americans with Disabilities Act of 1990 (ADA), Title II, Paragraph 35.130) through a TTC zone shall be an essential part of highway construction, utility work, maintenance operations, and the management of traffic incidents.**

Support:

A traffic incident is an emergency road user occurrence, a natural disaster, or other unplanned event that affects or impedes the normal flow of traffic.

A traffic incident management area is an area of a highway where temporary traffic controls are imposed by authorized officials in response to a road user incident, natural disaster, hazardous material spill, or other unplanned incident. It is a type of TTC zone and extends from the first warning device (such as a sign, light, or cone) to the last TTC device or to a point where vehicles return to the original lane alignment and are clear of the incident.

Traffic incidents can be divided into three general classes of duration, each of which has unique traffic control characteristics and needs. These classes are:

- A. Major—expected duration of more than 2 hours;
- B. Intermediate—expected duration of 30 minutes to 2 hours; and
- C. Minor—expected duration under 30 minutes.

The primary functions of TTC at a traffic incident management area are to move road users reasonably safely and expeditiously past or around the traffic incident, to reduce the likelihood of secondary traffic crashes, and to preclude unnecessary use of the surrounding local road system. Examples include a stalled vehicle blocking a lane, a traffic crash blocking the traveled way, a hazardous material spill along a highway, and natural disasters such as floods and severe storm damage.

Guidance:

In order to reduce response time for traffic incidents, highway agencies, appropriate public safety agencies (law enforcement, fire and rescue, emergency communications, emergency medical, and other emergency management), and private sector responders (towing and recovery and hazardous materials contractors) should mutually plan for occurrences of traffic incidents along the major and heavily traveled highway and street system.


On-scene responders should be trained in safe practices for accomplishing their tasks in and near traffic. Responders should always be aware of their visibility to oncoming traffic and take measures to move the traffic incident as far off the traveled roadway as possible or to provide for appropriate warning.

Responders arriving at a traffic incident should, within 15 minutes of arrival on-scene, estimate the magnitude of the traffic incident, the expected time duration of the traffic incident, and the expected vehicle queue length, and then should set up the appropriate temporary traffic controls for these estimates.

Option:

Warning and guide signs used for TTC traffic incident management situations may have a black legend and border on a fluorescent pink background (see Figure 6I-1).

**Figure 6I-1. Examples of Traffic Incident Management Area Signs**



**Support:**

While some traffic incidents might be anticipated and planned for, emergencies and disasters might pose more severe and unpredictable problems. The ability to quickly install proper temporary traffic controls might greatly reduce the effects of an incident, such as secondary crashes or excessive traffic delays. An essential part of fire, rescue, spill clean-up, highway agency, and enforcement activities is the proper control of road users through the traffic incident management area in order to protect responders, victims, and other personnel at the site while providing reasonably safe traffic flow. These operations might need corroborating legislative authority for the implementation and enforcement of appropriate road user regulations, parking controls, and speed zoning. It is desirable for these statutes to provide sufficient flexibility in the authority for, and implementation of, TTC to respond to the needs of changing conditions found in traffic incident management areas.

**Option:**

For traffic incidents, particularly those of an emergency nature, TTC devices on hand may be used for the initial response as long as they do not themselves create unnecessary additional hazards.

**Section 6I.02 Major Traffic Incidents**

**Support:**

Major traffic incidents are typically traffic incidents involving hazardous materials, fatal traffic crashes involving numerous vehicles, and other natural or man-made disasters. These traffic incidents typically involve closing all or part of a roadway facility for a period exceeding 2 hours.

**Guidance:**

If the traffic incident is anticipated to last more than 24 hours, applicable procedures and devices set forth in other Chapters of Part 6 should be used.

**Support:**

A road closure can be caused by a traffic incident such as a road user crash that blocks the traveled way. Road users are usually diverted through lane shifts or detoured around the traffic incident and back to the original roadway. A combination of traffic engineering and enforcement preparations is needed to determine

the detour route and to install, maintain or operate, and then to remove the necessary traffic control devices when the detour is terminated. Large trucks are a significant concern in such a detour, especially when detouring them from a controlled-access roadway onto local or arterial streets.

During traffic incidents, large trucks might need to follow a route separate from that of automobiles because of bridge, weight, clearance, or geometric restrictions. Also, vehicles carrying hazardous material might need to follow a different route from other vehicles.

Some traffic incidents such as hazardous material spills might require closure of an entire highway. Through road users must have adequate guidance around the traffic incident. Maintaining good public relations is desirable. The cooperation of the news media in publicizing the existence of, and reasons for, traffic incident management areas and their TTC can be of great assistance in keeping road users and the general public well informed.

The establishment, maintenance, and prompt removal of lane diversions can be effectively managed by inter-agency planning that includes representatives of highway and public safety agencies.

Guidance:

All traffic control devices needed to set up the TTC at a traffic incident should be available so that they can be readily deployed for all major traffic incidents. The TTC should include the proper traffic diversions, tapered lane closures, and upstream warning devices to alert approaching traffic of the end of a queue.

Attention should be paid to the end of the traffic queue such that warning is given to road users approaching the end of the queue.

If manual traffic control is needed, it should be provided by qualified flaggers or uniformed law enforcement officers.

Option:

If flaggers are used to provide traffic control for an incident management situation, the flaggers may use appropriate traffic control devices that are readily available or that can be brought to the traffic incident scene on short notice.

Guidance:

When flares are used to initiate TTC at traffic incidents, more permanent traffic control devices should replace them as soon as practical. Both the flare and its supporting device should then be removed from the roadway.

On-scene responders should be trained in safe practices for accomplishing their tasks in and near traffic. Responders should always be aware of their visibility to oncoming traffic and take measures to move the traffic incident as far off the traveled roadway as possible or to provide for appropriate warning.

### **Section 6I.03 Intermediate Traffic Incidents**

Support:

Intermediate traffic incidents typically affect travel lanes for a time period of 30 minutes to 2 hours, and usually require traffic control on the scene to divert road users past the blockage. Full roadway closures might be needed for short periods during traffic incident clearance to allow traffic incident responders to accomplish their tasks.

The establishment, maintenance, and prompt removal of lane diversions can be effectively managed by inter-agency planning that includes representatives of highway and public safety agencies.

Guidance:

All traffic control devices needed to set up the TTC at a traffic incident should be available so that they can be readily deployed for intermediate traffic incidents. The TTC should include the proper traffic diversions, tapered lane closures, and upstream warning devices to alert approaching traffic of the end of a queue.

Attention should be paid to the end of the traffic queue such that warning is given to road users approaching the end of the queue.

If manual traffic control is needed, it should be provided by qualified flaggers or uniformed law enforcement officers.

Option:

If flaggers are used to provide traffic control for an incident management situation, the flaggers may use appropriate traffic control devices that are readily available or that can be brought to the traffic incident scene on short notice.

Guidance:

When flares are used to initiate TTC at traffic incidents, more permanent traffic devices should replace them as soon as practical. Both the flare and its supporting device should then be removed from the roadway.

On-scene responders should be trained in safe practices for accomplishing their tasks in and near traffic. Responders should always be aware of their visibility to oncoming traffic and take measures to move the traffic incident as far off the traveled roadway as possible or to provide for appropriate warning.

#### **Section 6I.04 Minor Traffic Incidents**

Support:

Minor traffic incidents are typically disabled vehicles and minor crashes that result in lane closures of less than 30 minutes. On-scene responders are typically law enforcement and towing companies, and occasionally highway agency service patrol vehicles.

Diversion of traffic into other lanes is often not needed or is needed only briefly. It is not generally possible or practical to set up a lane closure with traffic control devices for a minor traffic incident. Traffic control is the responsibility of on-scene responders.

Guidance:

When a minor traffic incident blocks a travel lane, it should be removed from that lane to the shoulder as quickly as possible.

#### **Section 6I.05 Use of Emergency-Vehicle Lighting**

Support:

The use of emergency-vehicle lighting (such as high-intensity rotating, flashing, oscillating, or strobe lights) is essential, especially in the initial stages of a traffic incident, for the safety of emergency responders and persons involved in the traffic incident, as well as road users approaching the traffic incident. Emergency-vehicle lighting, however, provides warning only and provides no effective traffic control. It is often confusing to road users, especially at night. Road users approaching the traffic incident from the opposite direction on a divided facility are often distracted by emergency-vehicle lighting and slow their vehicles to look at the traffic incident posing a hazard to themselves and others traveling in their direction.

The use of emergency-vehicle lighting can be reduced if good traffic control has been established at a traffic incident scene. This is especially true for major traffic incidents that might involve a number of emergency vehicles. If good traffic control is established through placement of advanced warning signs and traffic control devices to divert or detour traffic, then public safety agencies can perform their tasks on scene with minimal emergency-vehicle lighting.

Guidance:

Public safety agencies should examine their policies on the use of emergency-vehicle lighting, especially after a traffic incident scene is secured, with the intent of reducing the use of this lighting as much as possible while not endangering those at the scene. Special consideration should be given to reducing or extinguishing

forward facing emergency-vehicle lighting, especially on divided roadways, to reduce distractions to on-coming road users.

Vehicle headlights not needed for illumination, or to provide notice to other road users of the incident response vehicle being in an unexpected location, should be turned off at night.

Intentionally blank.

**PART 7. TRAFFIC CONTROLS FOR SCHOOL AREAS****TABLE OF CONTENTS**

	<u>Page</u>
<b>CHAPTER 7A.</b>	<b>GENERAL</b>
Section 7A.01	Need for Standards..... 7A-1
Section 7A.02	School Routes and Established School Crossings ..... 7A-1
Section 7A.03	School Crossing Control Criteria..... 7A-2
Section 7A.04	Scope..... 7A-2
Section 7A.05	Application of Standards ..... 7A-2
Section 7A.06	Engineering Study Required ..... 7A-2
Section 7A.07	Maintenance of Traffic Control Devices ..... 7A-2
Section 7A.08	Placement Authority ..... 7A-2
Section 7A.09	Unauthorized Devices and Messages ..... 7A-3
Section 7A.10	Meaning of Standard, Guidance, Option, and Support..... 7A-3
<b>CHAPTER 7B.</b>	<b>SIGNS</b>
Section 7B.01	Size of School Signs ..... 7B-1
Section 7B.02	Illumination and Reflectorization ..... 7B-1
Section 7B.03	Position of Signs ..... 7B-1
Section 7B.04	Height of Signs ..... 7B-1
Section 7B.05	Installation of Signs ..... 7B-1
Section 7B.06	Lettering..... 7B-1
Section 7B.07	Sign Color for School Warning Signs ..... 7B-3
Section 7B.08	School Advance Warning Assembly (S1-1 with Supplemental Plaque) ..... 7B-3
Section 7B.09	School Crosswalk Warning Assembly (S1-1 with Diagonal Arrow) ..... 7B-7
Section 7B.10	SCHOOL BUS STOP/TURN AHEAD Signs (S3-1, S3-H2)..... 7B-8
Section 7B.11	School Speed Limit Assembly (S4-1, S4-3, S4-H5, S4-6, S5-H3, S5-H4, S5-H5)..... 7B-8
Section 7B.12	Reduced Speed School Zone Ahead Sign (S4-5, S4-5a) ..... 7B-10
Section 7B.13	END SCHOOL ZONE Sign (S5-2) ..... 7B-10
Section 7B.14	Parking and Stopping Signs (R7 and R8 Series) ..... 7B-10
Section 7B.15	STOP FOR SCHOOL BUS LOADING OR UNLOADING Sign (R16-H3) ..... 7B-11
<b>CHAPTER 7C.</b>	<b>MARKINGS</b>
Section 7C.01	Functions and Limitations ..... 7C-1
Section 7C.02	Standardization of Application ..... 7C-1
Section 7C.03	Crosswalk Markings ..... 7C-1
Section 7C.04	Stop and Yield Lines..... 7C-2
Section 7C.05	Curb Markings for Parking Regulations ..... 7C-3
Section 7C.06	Pavement Word and Symbol Markings ..... 7C-3
<b>CHAPTER 7D.</b>	<b>SIGNALS</b>
Section 7D.01	General..... 7D-1
<b>CHAPTER 7E.</b>	<b>CROSSING SUPERVISION</b>
Section 7E.01	Types of Crossing Supervision ..... 7E-1
Section 7E.02	Adult Crossing Guards..... 7E-1
Section 7E.03	Qualifications of Adult Crossing Guards ..... 7E-1
Section 7E.04	Uniform of Adult Crossing Guards and Student Patrols ..... 7E-1
Section 7E.05	Operating Procedures for Adult Crossing Guards ..... 7E-2

Section 7E.06	Uniformed Law Enforcement Officers .....	7E-2
Section 7E.07	Student Patrols .....	7E-2
Section 7E.08	Choice of Student Patrols .....	7E-3
Section 7E.09	Operating Procedures for Student Patrols .....	7E-3

**CHAPTER 7F. GRADE-SEPARATED CROSSINGS**

Section 7F.01	Function .....	7F-1
Section 7F.02	Types of Grade-Separated Crossings.....	7F-1
Section 7F.03	Criteria for Use of Grade-Separated Crossings .....	7F-1

**FIGURES**

**CHAPTER 7A.**

**GENERAL**

Figure 7A-1	Example of School Route Plan Map.....	7A-3
-------------	---------------------------------------	------

**CHAPTER 7B.**

**SIGNS**

Figure 7B-1	School Area Signs.....	7B-4
Figure 7B-2	Examples of Signing for School Crosswalk Warning Assembly .....	7B-5
Figure 7B-3	Examples of Signing for School Area Traffic Control with School Speed Limits .....	7B-6
Figure 7B-4	In-Street Signs in School Areas .....	7B-7

**CHAPTER 7C.**

**MARKINGS**

Figure 7C-1	Two-Lane Pavement Marking of “SCHOOL” .....	7C-4
-------------	---	------

**TABLES**

**CHAPTER 7B.**

**SIGNS**

Table 7B-1	Size of School Area Signs and Plaques .....	7B-2
------------	---	------

## CHAPTER 7A. GENERAL

### Section 7A.01 Need for Standards

#### Support:

It is important to stress that regardless of the school location, the best way to achieve reasonably safe and effective traffic control is through the uniform application of realistic policies, practices, and standards developed through engineering judgment.

Pedestrian safety depends upon public understanding of accepted methods for efficient traffic control. This principle is especially important in the control of pedestrians, bicycles, and other vehicles in the vicinity of schools. Neither pedestrians on their way to or from school nor road users can be expected to move safely in school areas unless they understand both the need for traffic controls and how these controls function for their benefit.

Procedures and devices that are not uniform might cause confusion among pedestrians and other road users, prompt wrong decisions, and contribute to crashes. To achieve uniformity of traffic control in school areas, comparable traffic situations need to be treated in a consistent manner. Each traffic control device and control method described in Part 7 fulfills a specific function related to specific traffic conditions.

A uniform approach to school area traffic controls assures the use of similar controls for similar situations (which promotes uniform behavior on the part of motorists, pedestrians, and bicyclists).

A school traffic control plan permits the orderly review of school area traffic control needs, and the coordination of school/pedestrian safety education and engineering activities.

#### Guidance:

A school route plan for each school serving elementary to high school students should be prepared in order to develop uniformity in the use of school area traffic controls and to serve as the basis for a school traffic control plan for each school.

The school route plan, developed in a systematic manner by the school, law enforcement, and traffic officials responsible for school pedestrian safety, should consist of a map (see Figure 7A-1) showing streets, the school, existing traffic controls, established school walk routes, and established school crossings.

The type(s) of school area traffic control devices used, either warning or regulatory, should be related to the volume and speed of vehicular traffic, street width, and the number and age of the students using the crossing.

School area traffic control devices should be included in a school traffic control plan.

#### Support:

Reduced speed limit signs for school areas and crossings are included in this Manual solely for the purpose of standardizing signing for these zones and not as an endorsement of mandatory reduced speed zones.

### Section 7A.02 School Routes and Established School Crossings

#### Support:

The planning criterion for school walk routes might make it necessary for children to walk an indirect route to an established school crossing located where there is existing traffic control and to avoid the use of a direct crossing where there is no existing traffic control.

#### Guidance:

School walk routes should be planned to take advantage of existing traffic controls.

The following factors should be considered when determining the feasibility of requiring children to walk a longer distance to a crossing with existing traffic control:

- A. The availability of adequate sidewalks or off-roadway sidewalk areas to and from the location with existing control;
- B. The number of students using the crossing;
- C. The age levels of the students using the crossing; and
- D. The total extra walking distance.

### **Section 7A.03 School Crossing Control Criteria**

Support:

Alternate gaps and blockades are inherent in the traffic stream and are different at each crossing location. For safety, students need to wait for a gap in traffic that is of sufficient duration to permit reasonably safe crossing. When the delay between the occurrence of adequate gaps becomes excessive, students might become impatient and endanger themselves by attempting to cross the street during an inadequate gap.

A recommended method for determining the frequency and adequacy of gaps in the traffic stream is given in the Institute of Transportation Engineers' publication, "School Trip Safety Program Guidelines" (see Section 1A.11).

### **Section 7A.04 Scope**

Standard:

**Part 7 sets forth basic principles and prescribes standards that shall be followed in the design, application, installation, and maintenance of all traffic control devices (including signs, signals, and markings) and other controls (including adult crossing guards, student patrols, and grade-separated crossings) required for the special pedestrian conditions in school areas.**

Option:

In-roadway signs for school traffic control areas may be used consistent with the requirements of Sections 2B.12, 7B.08, and 7B.09.

Support:

Requirements discussed in Chapter 2A and Section 2B.05 are applicable in school areas.

### **Section 7A.05 Application of Standards**

Support:

Sections 1A.02 and 1A.07 contain information regarding the application of standards.

### **Section 7A.06 Engineering Study Required**

Support:

Section 1A.09 contains information regarding engineering studies.

### **Section 7A.07 Maintenance of Traffic Control Devices**

Support:

Section 1A.05 contains information regarding the maintenance of traffic control devices.

### **Section 7A.08 Placement Authority**

Support:

Section 1A.08 contains information regarding placement authority for traffic control devices.

**Section 7A.09 Unauthorized Devices and Messages**

Support:

Sections 1A.01 and 1A.08 contain information regarding unauthorized devices and messages.

**Section 7A.10 Meaning of Standard, Guidance, Option, and Support**

Support:

The introduction to this Manual contains information regarding the meaning of the headings Standard, Guidance, Option, and Support, and the use of the words shall, should, and may.

**Figure 7A-1. Example of School Route Plan Map**



**Legend**

- |   |                  |   |                         |
|---|------------------|---|-------------------------|
|  | School           |  | Signalized Intersection |
|  | Marked Crosswalk |  | STOP Sign Approach      |
|  | Crossing Guard   |  | Pedestrian Route        |

Intentionally blank.

## CHAPTER 7B. SIGNS

### Section 7B.01 Size of School Signs

#### Standard:

The sizes of signs and plaques to be used on conventional roadways in school areas shall be as shown in Table 7B-1.

The Conventional Road sign size shall be used on public roads, streets, and highways unless engineering judgment determines that a Minimum or Oversized sign size would be more appropriate.

The Oversized sign size shall be used on expressways.

#### Option:

The Oversized sign size may be used for applications that require increased emphasis, improved recognition, or increased legibility.

The Minimum sign size may be used on local residential streets, in urban areas, and where there are low traffic volumes and low vehicle speeds, as determined by engineering judgment.

### Section 7B.02 Illumination and Reflectorization

#### Standard:

The signs used for school area traffic control shall be retroreflectorized or illuminated.

### Section 7B.03 Position of Signs

#### Guidance:

Signs should be placed in positions where they will convey their messages most effectively without restricting lateral clearance or sight distances. Placement therefore should consider highway design, alignment, vehicle speed, and roadside development.

Signs should have a maximum practical clearance from the edge of the traveled way for the safety of vehicles that might leave the roadway and strike the sign supports. Except as noted in the Option, signs should not be closer than 1.8 m (6 ft) from the edge of a paved shoulder, or if none, 3.7 m (12 ft) from the edge of the traveled way.

#### Option:

In urban areas, a lesser clearance of not less than 0.6 m (2 ft) from the face of the curb may be used. In urban areas, where sidewalk width is limited or existing poles are close to the curb, a clearance of 0.3 m (1 ft) from the curb face may be used.

### Section 7B.04 Height of Signs

#### Support:

Section 2A.18 contains information regarding the mounting height of signs.

### Section 7B.05 Installation of Signs

#### Support:

Section 2A.16 contains information regarding the installation of signs.

### Section 7B.06 Lettering

#### Support:

The "Sign Design Manual" (SDM) (see Section 1A.11) contains information regarding sign lettering.

**Table 7B-1. Size of School Area Signs and Plaques**

Sign	Sign Code	Section	Conventional Road	Minimum	Oversized
School Advance Warning	S1-1	7B.08	900 x 900 mm (36 x 36 in)	750 x 750 mm (30 x 30 in)	1200 x 1200 mm (48 x 48 in)
SCHOOL BUS STOP/TURN AHEAD	S3-1 S3-H2	7B.10	750 x 750 mm (30 x 30 in)	—	900 x 900 mm (36 x 36 in)
END SCHOOL ZONE	S5-2	7B.13	600 x 750 mm (24 x 30 in)	—	900 x 1200 mm (36 x 48 in)
Reduced Speed School Zone Ahead	S4-5 S4-5a	7B.12	900 x 900 mm (36 x 36 in)	750 x 750 mm (30 x 30 in)	1200 x 1200 mm (48 x 48 in)
SCHOOL SPEED LIMIT DURING RESTRICTED HOURS	S5-H3	7B.11	600 x 1200 mm (24 x 48 in)	—	900 x 1875 mm (36 x 78 in)
School Speed Limit Sign (variable display)	S5-H4	7B.11	600 x 950 mm (24 x 38 in)	—	900 x 1500 mm (36 x 60 in)
School Speed Limit Sign (variable display with beacons in the face of the sign)	S5-H5	7B.11	600 x 1050 mm (24 x 42 in)	—	900 x 1200 mm (36 x 48 in)
In-Street Pedestrian Crossing	R1-6	7B.09	300 X 900 mm (12 X 36 in)	—	—
Speed Limit (School Use)	R2-1	7B.11	600 x 750 mm (24 x 30 in)	—	900 x 1200 mm (36 x 48 in)
STOP FOR SCHOOL BUS LOADING OR UNLOADING...	R16-H3	7B.15	750 x 750 mm (30 x 30 in)	—	1050 x 1050 mm (42 x 42 in)

Plaque	Sign Code	Section	Conventional Road	Minimum	Oversized
X:XX - X:XX AM X:XX - X:XX PM	S4-1	7B.11	600 x 250 mm (24 x 10 in)	—	900 x 450 mm (36 x 18 in)
SCHOOL	S4-3	7B.11	600 x 200 mm (24 x 8 in)	—	900 x 300 mm (36 x 12 in)
DURING RESTRICTED HOURS	S4-H5	7B.11	600 x 250 mm (24 x 10 in)	—	900 x 375 mm (36 x 18 in)
MON - FRI	S4-6	7B.11	600 x 250 mm (24 x 10 in)	—	900 x 450 mm (36 x 18 in)
XXX FEET	W16-2	7B.08	600 x 450 mm (24 x 18 in)	—	750 x 600 mm (30 x 24 in)
XXX FT	W16-2a	7B.08	600 x 300 mm (24 x 12 in)	—	750 x 450 mm (30 x 18 in)
Diagonal Arrow	W16-7p	7B.09	600 x 300 mm (24 x 12 in)	—	750 x 450 mm (30 x 18 in)
Diagonal Arrow (Optional Size)	W16-7p	7B.09	525 x 375 mm (21 x 15 in)	—	—
AHEAD	W16-9p	7B.08	600 x 300 mm (24 x 12 in)	—	750 x 450 mm (30 x 18 in)

## **Section 7B.07 Sign Color for School Warning Signs**

### **Standard:**

**Except as noted in the Option, school warning signs shall have a yellow background with a black legend and border unless otherwise stated in this Manual for a specific sign.**

### **Option:**

All school warning signs in addition to the following signs may have a fluorescent yellow-green background with a black legend and border:

- A. School Advance Warning sign (S1-1);
- B. SCHOOL BUS STOP/TURN AHEAD signs (S3-1, S3-H2);
- C. SCHOOL plaque (S4-3);
- D. The "SCHOOL" portion of the School Speed Limit signs (S5-1, S5-H3, S5-H4, S5-H5);
- E. XXX FEET plaque (W16-2 series);
- F. AHEAD plaque (W16-9p);
- G. Diagonal Arrow plaque (W16-7p); and
- H. Reduced Speed School Zone Ahead sign (S4-5, S4-5a).

### **Guidance:**

When the fluorescent yellow-green background color is used, a systematic approach featuring one background color within a zone or area should be used. The mixing of standard yellow and fluorescent yellow-green backgrounds within a zone or area should be avoided.

## **Section 7B.08 School Advance Warning Assembly (S1-1 with Supplemental Plaque)**

### **Guidance:**

The School Advance Warning assembly (see Figure 7B-1) should be installed in advance of locations where school buildings or grounds are adjacent to the highway, except where a physical barrier such as fencing separates school children from the highway.

### **Standard:**

**The School Advance Warning assembly shall be used in advance of any installation of the School Crosswalk Warning assembly (see Figure 7B-2), or the School Speed Limit assembly (see Figure 7B-3).**

**If used, the School Advance Warning assembly shall be installed not less than 45 m (150 ft) nor more than 210 m (700 ft) in advance of the school grounds, school crossings, or School Speed Limit assembly (see Figure 7B-1).**


**If used, the School Advance Warning assembly shall consist of a School Advance Warning (S1-1) sign supplemented with a plaque with the legend AHEAD (W16-9p) or XXX FEET (W16-2 or W16-2a) to provide advance notice to road users of crossing activity.**

### **.Option:**


A 300 mm (12 in) reduced size in-street School Advance Warning (S1-1) sign (see Figure 7B-4), installed in compliance with the mounting height and breakaway requirements for In-Street Pedestrian Crossing (R1-6 or R1-6a) signs (see Section 2B.12), may be used in advance of a school crossing to supplement the ground-mounted school warning signs. A 300 x 150 mm (12 x 6 in) reduced size AHEAD (W16-9p) plaque may be mounted below the reduced size in-street School Advance Warning (S1-1) sign.

**Figure 7B-1. School Area Signs**

School Advance Warning Assembly




School Crosswalk Warning Assembly



Example of Optional Fluorescent Yellow-Green

School Speed Limit Assembly



S3-1



S3-H2



S4-5




S4-5a



S5-2




S5-H4




S5-H5

**Figure 7B-2. Examples of Signing for School Crosswalk Warning Assembly**



**Figure 7B-3. Examples of Signing for School Area Traffic Control with School Speed Limits**




\* See Sections 7B.11 and 7B-13.

OMUTCD - English units are preferred.


**Figure 7B-4. In-Street Signs in School Areas**

**a - In advance of the school crossing**



\* Reduced size signs:  
 S1-1 300 x 300 mm (12 x 12)  
 S4-3 300 x 100 mm (12 x 4)  
 W16-7p 300 x 150 mm (12 x 6)  
 W16-9p 300 x 150 mm (12 x 6)

**b - At the school crossing**



**Section 7B.09 School Crosswalk Warning Assembly (S1-1 with Diagonal Arrow)**

**Standard:**

If used, the School Crosswalk Warning assembly (see Figure 7B-1) shall be installed at the marked crosswalk, or as close to it as possible, and shall consist of a School Advance Warning (S1-1) sign supplemented with a diagonal downward pointing arrow (W16-7p) plaque to show the location of the crossing.

The School Crosswalk Warning assembly shall not be used at marked crosswalks other than those adjacent to schools and those on established school pedestrian routes.

The School Crosswalk Warning assembly shall not be installed on approaches controlled by a STOP sign.

**Guidance:**

The School Crosswalk Warning assembly should be installed at marked crosswalk(s), including those at signalized locations, used by students going to and from school (see Figure 7B-2) as determined by an engineering study.

**Option:**

The In-Street Pedestrian Crossing (R1-6 or R1-6a) sign (see Section 2B.12) may be used at unsignalized school crossings. When used at a school crossing, a 300 x 100 mm (12 x 4 in) SCHOOL (S4-3) plaque (see Figure 7B-4) may be mounted above the sign.

A 300 mm (12 in) reduced size School Advance Warning (S1-1) sign (see Figure 7B-4) may be used at an unsignalized school crossing instead of the In-Street Pedestrian Crossing (R1-6 or R1-6a) sign. A 300 x 150 mm (12 x 6 in) reduced size Diagonal Arrow (W16-7p) plaque may be mounted below the reduced size in-street School Advance Warning (S1-1) sign.

**Standard:**

**If an In-Street Pedestrian Crossing sign or a reduced size in-street School Advance Warning (S1-1) sign is placed in the roadway, the sign support shall comply with the mounting height and breakaway requirements for In-Street Pedestrian Crossing (R1-6 or R1-6a) signs (see Section 2B.12).**

**The In-Street Pedestrian Crossing sign and the reduced size in-street School Advance Warning (S1-1) sign shall not be used at signalized locations.**

**Section 7B.10 SCHOOL BUS STOP/TURN AHEAD Signs (S3-1, S3-H2)****Guidance:**

The SCHOOL BUS STOP AHEAD (S3-1) or SCHOOL BUS TURN AHEAD (S3-H2) sign (see Figure 7B-1) should be installed in advance of locations where a school bus, when turning or when stopped to pick up or discharge passengers, is not visible to road users for a distance of 150 m (500 ft) in advance and where there is no opportunity to relocate the bus stop (or turn) to provide 150 m (500 ft) of visibility.

**Standard:**

**These signs shall be erected only on the basis of a traffic engineering study and after the school transportation officials have confirmed the need for the stop or turn.**

**Guidance:**

The need for these signs at existing locations should be reevaluated periodically.

**Section 7B.11 School Speed Limit Assembly (S4-1, S4-3, S4-H5, S4-6, S5-H3, S5-H4, S5-H5)****Support:**

Section 4511.21(B)(1)(a) of the Ohio Revised Code (O.R.C.) establishes a 20 mile per hour speed limit for School Zones, and establishes when that speed limit is in effect (see Appendix B2).

**Standard:**

**A School Speed Limit assembly (see Figure 7B-1) or a School Speed Limit (S5-1) sign (see Figure 7B-1) shall be used to indicate the speed limit for a School Zone established per Section 4511.21 of the O.R.C. The School Speed Limit assembly or School Speed Limit sign shall be placed at or as near as practical to the point where the reduced speed zone begins.**

**Support:**

Section 4511.21(B)(1)(c) of the O.R.C. defines a School Zone and establishes a means by which the Ohio Department of Transportation (ODOT), upon request from a local authority, may approve extensions of the traditional School Zone boundaries. Section 4511.21 (B)(2) also provides that ODOT, upon request, may designate a School Zone on a portion of a state route for certain crosswalks customarily used by children going to or leaving a school.

Complete instructions and a form for submitting an application for approval of a non-traditional (extended) School Zone are available from the ODOT Office of Traffic Engineering and each ODOT District Office.

**Guidance:**

Requests for extensions of the traditional School Zone boundaries should be submitted to the ODOT District Deputy Director in accordance with the procedure described in Part 7 of the ODOT "Traffic Engineering Manual" (TEM) (see Section 1A.11).

**Standard:**

**The School Speed Limit assembly shall be either a fixed-message sign assembly or a changeable message sign.**

**The fixed-message School Speed Limit assembly shall consist of a top plaque (S4-3) with the legend SCHOOL, a Speed Limit (R2-1) sign, and a bottom plaque (S4-1, S4-H5, or S4-6) (see Figure 7B-1).**

**Option:**

Changeable message signs (see Sections 2A.07 and 6F.55) may be used to inform drivers of the special school speed limit. If the sign is internally illuminated, it may have a white legend on a black background. Changeable message signs with flashing beacons may be used for the more critical situations, where greater emphasis of the special school speed limit is needed.

**Guidance:**

Even though it might not always be practical because of special features to make changeable message signs conform in all respects to the accepted standards, during the periods that the school speed limit is in effect, their basic shape, message, legend layout, and colors should conform to the standards for fixed-message signs.

A confirmation beacon or device to indicate that the speed limit message is in operation should be considered for inclusion on the back of the changeable message sign.

**Option:**

Fluorescent yellow-green pixels may be used when school-related messages are shown on a changeable message sign.

Changeable message signs may use blank-out messages or other methods in order to display the school speed limit only during the periods it applies.

Changeable message signs that display the speed of approaching drivers (see Section 2B.13) may be used in a school speed limit zone.

A Speed Limit Sign Beacon also may be used to identify the periods that the school speed limit is in effect. The lenses of the Speed Limit Sign Beacon may be positioned within the face of the School Speed Limit (S5-H5) sign (see Figure 7B-1).

A FINES HIGHER (R2-6) sign (see Section 2B.17) may be used to advise road users when increased fines are imposed for traffic violations in school zones.

**Standard:**

**Where a side street intersects the highway within the School Zone, additional School Speed Limit signs shall be erected on the highway as needed to notify motorists entering the School Zone from the side street of the School Zone speed limit. The School Speed Limit sign shall be mounted along the right hand side of the roadway.**

**Option:**

Where side mounting does not provide adequate sight distance or is otherwise impractical, the School Speed Limit sign may be mounted overhead.

**Guidance:**

Overhead mounting should be used on all divided and four-lane highways.

There should be no Speed Limit signs (except School Speed Limit signs) erected or in place within the limits of the School Zone.

There should be no Speed Limit signs within the space between either the School Advance Warning assembly (S1-1 with Supplemental Plaque) or the Reduced Speed School Zone Ahead sign and the beginning of the School Zone, or closer than 150 m (500 ft) in advance of the School Advance Warning assembly or the Reduced Speed School Zone Ahead sign.

**Section 7B.12 Reduced Speed School Zone Ahead Sign (S4-5, S4-5a)****Option:**

The Reduced Speed School Zone Ahead (S4-5, S4-5a) sign (see Figure 7B-1) may be used to inform road users of a reduced speed zone when engineering judgment indicates that advance notice would be appropriate.

**Standard:**

**If used, the Reduced Speed School Zone Ahead sign shall be followed by a School Speed Limit sign or a School Speed Limit assembly.**

**The speed limit displayed on the Reduced Speed School Zone Ahead sign shall be identical to the speed limit displayed on the subsequent School Speed Limit sign or School Speed Limit assembly.**

**Section 7B.13 END SCHOOL ZONE Sign (S5-2)****Standard:**

**The end of an authorized and posted school speed zone shall be marked with a standard Speed Limit sign showing the speed limit for the section of highway that follows or with an END SCHOOL ZONE (S5-2) sign (see Figure 7B-1).**

**When the end of the school zone is marked with an END SCHOOL ZONE sign, and the adjacent section of highway is an authorized Speed Zone, a Speed Limit sign shall be placed just beyond the end of the School Zone.**

**Option:**

When the END SCHOOL ZONE sign is used, a Speed Limit sign may be placed just beyond the end of the School Zone to post a statutory speed limit.

**Section 7B.14 Parking and Stopping Signs (R7 and R8 Series)****Option:**

Parking and stopping regulatory signs may be used to prevent parked or waiting vehicles from blocking pedestrians' views, and drivers' views of pedestrians, and to control vehicles as a part of the school traffic plan.

**Support:**

Parking signs and other signs governing the stopping and standing of vehicles in school areas cover a wide variety of regulations. Typical examples of regulations are as follows:

- A. No Parking X:XX AM to X:XX PM School Days Only;
- B. No Stopping X:XX AM to X:XX PM School Days Only;
- C. X Min Loading X:XX AM to X:XX PM School Days Only; and
- D. No Standing X:XX AM to X:XX PM School Days Only.

Sections 2B.39, 2B.40, and 2B.41 contain information regarding the signing of parking regulations in school zone areas.

**Section 7B.15 STOP FOR SCHOOL BUS LOADING OR UNLOADING Sign (R16-H3)**

Option:

The STOP FOR SCHOOL BUS LOADING OR UNLOADING (R16-H3) sign (see Appendix C) may be used to remind road users of the provisions of Section 4511.75 of the Ohio Revised Code (see Appendix B2) prohibiting passing of school buses in either direction on undivided highways when loading or unloading school children.

Intentionally blank.

## CHAPTER 7C. MARKINGS

### Section 7C.01 Functions and Limitations

Support:

Markings have definite and important functions in a proper scheme of school area traffic control. In some cases, they are used to supplement the regulations or warnings provided by other devices, such as traffic signs or signals. In other instances, they are used alone and produce results that cannot be obtained by the use of any other device. In such cases they serve as an effective means of conveying certain regulations, guidance, and warnings that could not otherwise be made clearly understandable.

Pavement markings have limitations. They might be obliterated by snow, might not be clearly visible when wet, and might not be durable when subjected to heavy traffic. In spite of these limitations, they have the advantage, under favorable conditions, of conveying warnings or information to the road user without diverting attention from the road.

### Section 7C.02 Standardization of Application

Standard:

**Each standard marking shall be used only to convey the meaning prescribed for it in this Manual.**

### Section 7C.03 Crosswalk Markings

Support:

Crosswalk markings provide guidance for pedestrians who are crossing roadways by defining and delineating paths on approaches to and within signalized intersections, and on approaches to other intersections where traffic stops.

Crosswalk markings also serve to alert road users of a pedestrian crossing point across roadways not controlled by highway traffic signals or STOP signs.

At nonintersection locations, crosswalk markings legally establish the crosswalk.

Standard:

**When transverse crosswalk lines are used, they shall be solid white, marking both edges of the crosswalk, except as noted in the Option. They shall be not less than 150 mm (6 in) nor greater than 600 mm (24 in) in width.**

Guidance:

If transverse lines are used to mark a crosswalk, the gap between the lines should not be less than 1.8 m (6 ft). If diagonal or longitudinal lines are used without transverse lines to mark a crosswalk, the crosswalk should be not less than 1.8 m (6 ft) wide.

Crosswalk lines on both sides of the crosswalk should extend across the full width of pavement or to the edge of the intersecting crosswalk to discourage diagonal walking between crosswalks.

Crosswalks should be marked at all intersections on established routes to school where there is substantial conflict between motorists, bicyclists, and pedestrian movements, where students are encouraged to cross between intersections, or where students would not otherwise recognize the proper place to cross (see Figure 7A-1).

Crosswalk lines should not be used indiscriminately. An engineering study should be performed before they are installed at locations away from traffic control signals or STOP signs.

**Option:**

For added visibility, the area of the crosswalk may be marked with white diagonal lines at a 45-degree angle to the line of the crosswalk or with white longitudinal lines parallel to traffic flow. When diagonal or longitudinal lines are used to mark a crosswalk, the transverse crosswalk lines may be omitted.

**Guidance:**

The diagonal or longitudinal lines should be 300 to 600 mm (12 to 24 in) wide and spaced 300 to 1500 mm (12 to 60 in) apart. The spacing design should avoid the wheel paths.

**Section 7C.04 Stop and Yield Lines****Standard:**

**If used, stop lines shall consist of solid white lines extending across approach lanes to indicate the point at which the stop is intended or required to be made.**

**If used, yield lines (see Figure 3B-14) shall consist of a row of solid white isosceles triangles pointing toward approaching vehicles extending across approach lanes to indicate the point at which the yield is intended or required to be made.**

**Guidance:**

Stop lines should be 300 to 600 mm (12 to 24 in) wide.

Stop lines should be used to indicate the point behind which vehicles are required to stop, in compliance with a STOP (R1-1) sign (see Figure 2B-1), traffic control signal, or some other traffic control device.

The individual triangles comprising the yield line should have a base 300 to 600 mm (12 to 24 in) wide and a height equal to 1.5 times the base. The space between the triangles should be 75 to 300 mm (3 to 12 in).

**Option:**

Yield lines may be used to indicate the point behind which vehicles are required to yield in compliance with a YIELD (R1-2) sign (see Figure 2B-1) or a Yield Here to Pedestrians (R1-5 or R1-5a) sign (see Figure 2B-2).

**Guidance:**

If used, stop and yield lines should be placed a minimum of 1.2 m (4 ft) in advance of and parallel to the nearest crosswalk line at controlled intersections, except for yield lines at roundabout intersections as provided for in Section 3B.24 and at midblock crosswalks. In the absence of a marked crosswalk, the stop line or yield line should be placed at the desired stopping or yielding point, but should be placed no more than 9 m (30 ft) nor less than 1.2 m (4 ft) from the nearest edge of the intersecting traveled way. Stop lines should be placed to allow sufficient sight distance to all other approaches to an intersection.

If used at an unsignalized midblock crosswalk, yield lines should be placed adjacent to the Yield Here to Pedestrians sign located 6.1 to 15 m (20 to 50 ft) in advance of the nearest crosswalk line, and parking should be prohibited in the area between the yield line and the crosswalk (see Figure 3B-15).

Stop lines at midblock signalized locations should be placed at least 12 m (40 ft) in advance of the nearest signal indication (see Section 4D.15).

**Support:**

Drivers who yield too close to crosswalks on multi-lane approaches place pedestrians at risk by blocking other drivers' views of pedestrians, and pedestrians' views of other vehicles.

### **Section 7C.05 Curb Markings for Parking Regulations**

#### **Standard:**

**Signs shall be used with curb markings in those areas where curb markings are frequently obliterated by snow and ice accumulation, unless the no parking zone is controlled by statute or local ordinance.**

#### **Guidance:**

When curb markings are used without signs to convey parking regulations, a legible word marking regarding the regulation (such as “No Parking” or “No Standing”) should be placed on the curb.

#### **Option:**

Local highway agencies may prescribe special colors for curb markings to supplement standard signs for parking regulation.

#### **Support:**

Since yellow and white curb markings are frequently used for curb delineation and visibility, it is advisable to establish parking regulations through the installation of standard signs (see Sections 2B.39 through 2B.41).

### **Section 7C.06 Pavement Word and Symbol Markings**

#### **Support:**

Word and symbol markings on the pavement are used for the purpose of guiding, warning, or regulating traffic. Symbol messages are preferable to word messages.

#### **Standard:**

**Word and symbol markings shall be white. Word and symbol markings shall not be used for mandatory messages except in support of standard signs.**

#### **Guidance:**

Letters and numerals should be 1.8 m (6 ft) or more in height. All letters, numerals, and symbols should be in accordance with the SDM (see Section 1A.11)

Word and symbol markings should not exceed three lines of information.

If a pavement marking word message consists of more than one line of information, it should read in the direction of travel. The first word of the message should be nearest to the road user.

The longitudinal space between word or symbol message markings, including arrow markings, should be at least four times the height of the characters for low speed roads, but not more than ten times the height of the characters under any conditions.

The number of different word and symbol markings used should be minimized to provide effective guidance and avoid misunderstanding.

When the SCHOOL marking is used, it should be placed at least 30 m (100 ft) in advance of the School Zone.

Except as noted in the Option below, pavement word and symbol markings should be no more than one lane in width.

#### **Option:**


The SCHOOL word marking may extend to the width of two approach lanes (see Figure 7C-1).

Guidance:

If the two-lane SCHOOL word marking is used, the letters should be 3 m (10 ft) or more in height.

---

**Figure 7C-1. Two-Lane Pavement Marking of “SCHOOL”**



## CHAPTER 7D. SIGNALS

### Section 7D.01 General

Support:

Part 4 contains information regarding highway traffic signals in school areas. The School Crossing signal warrant is described in Section 4C.06.

Intentionally blank.

## **CHAPTER 7E. CROSSING SUPERVISION**

### **Section 7E.01 Types of Crossing Supervision**

Support:

There are two types of school crossing supervision:

- A. Adult control of pedestrians and vehicles by adult crossing guards or uniformed law enforcement officers; and
- B. Student control of only pedestrians with student patrols.

Information for the organization, operation, and administration of an adult crossing guard program are given in “Civilian Guards For School Crossings” (available from the Center for Public Safety of Northwestern University, 405 Church Street, Evanston, IL 60204) and “Adult School Crossing Guards” (available from the American Automobile Association, 1000 AAA Drive, Heathrow, FL 32746).

Information for the organization, administration and operation of a student patrol program are given in “Policies and Practices for School Safety Patrols” (available from the American Automobile Association, 1000 AAA Drive, Heathrow, FL 32746).

### **Section 7E.02 Adult Crossing Guards**

Option:

Adult crossing guards may be used to provide gaps in traffic at school crossings where an engineering study has shown that adequate gaps need to be created (see Section 7A.03), and where authorized by law.

Adult crossing guards should be special law enforcement officers appointed by the local law enforcement agency.

The local law enforcement agency should be responsible for selection, training and supervision of adult crossing guards.

### **Section 7E.03 Qualifications of Adult Crossing Guards**

Support:

High standards for selection of adult crossing guards are essential.

Guidance:

Adult crossing guards should possess the following qualifications:

- A. Average intelligence;
- B. Good physical condition, including sight, hearing, and mobility;
- C. Mental alertness;
- D. Neat appearance;
- E. Good character;
- F. Dependability; and
- G. Sense of responsibility for safety of students.

### **Section 7E.04 Uniform of Adult Crossing Guards and Student Patrols**

Guidance:

Adult crossing guards should be uniformed so that road users and pedestrians can recognize them and respond to their signals. The uniforms should be distinctively different from those worn by regular law enforcement officers.

**Standard:**

**Adult crossing guards shall wear high-visibility retroreflective safety apparel labeled as ANSI 107-1999 standard performance for Class 2 as described in Section 6E.02.**

**Student patrols shall wear high-visibility retroreflective safety apparel labeled as ANSI 107-1999 standard performance for Class 1 as described in Section 6E.02.**

Guidance:

Law enforcement officers should wear high-visibility retroreflective material over their uniforms when directing nighttime operations.

### **Section 7E.05 Operating Procedures for Adult Crossing Guards**

Guidance:

Adult crossing guards should not direct traffic in the usual law enforcement regulatory sense. In the control of traffic, they should pick opportune times to create a reasonably safe gap. At these times, they should stand in the roadway to indicate that pedestrians are about to use or are using the crosswalk, and that all vehicular traffic must stop.

Adult crossing guards should use a STOP paddle. The STOP paddle should be the primary hand-signaling device.

**Standard:**

**The STOP paddle shall be an octagonal shape. The background of the STOP face shall be red with at least 150 mm (6 in) series capital white letters and border. The paddle shall be at least 450 mm (18 in) in size and have the word message STOP on both sides. The paddle shall be retroreflectorized or illuminated when used during hours of darkness.**

Option:

The STOP paddle may be modified to improve conspicuity by incorporating red or white flashing lights on both sides of the paddle. The red or white flashing lights may be arranged in any of the following patterns:

- A. Two red or white lights centered vertically above and below the STOP legend;
- B. Two red or white lights centered horizontally on each side of the STOP legend;
- C. One red or white light centered below the STOP legend; or
- D. A series of eight or more small red or white lights no larger than 6 mm (0.25 in) in diameter along the outer edge of the paddle, arranged in an octagonal pattern at the eight corners of the STOP paddle. More than eight lights may be used only if the arrangement of the lights is such that it clearly conveys the octagonal shape of the STOP paddle.
- E. A series of white lights forming the shapes of the letters in the legend.

**Standard:**

**If flashing lights are used on the STOP paddle, the flash rate shall be at least 50, but not more than 60, flash periods per minute.**

### **Section 7E.06 Uniformed Law Enforcement Officers**

Option:

Uniformed law enforcement officers may be used for school crossing supervision.

Guidance:

Uniformed law enforcement officers should be used for school crossing supervision on a temporary basis in emergency situations or at very hazardous school crossings where the use of adult crossing guards is not feasible.

### **Section 7E.07 Student Patrols**

Guidance:

Student patrols should be authorized by the local school board. School authorities should be responsible for organizing, instructing and supervising patrols with the assistance of the local law enforcement agency.

OMUTCD - English units are preferred.

**Option:**

Student patrols may be used to direct and control pedestrians at crossings near schools where adequate gaps in traffic occur frequently enough so that gaps do not need to be created.

Student patrols may be used to direct and control pedestrians at signalized intersections where turning movements are not a significant problem, and may be used to assist adult crossing guards in the control of pedestrians at crossing locations used by large numbers of pedestrians.

**Guidance:**

Student patrols should not be responsible for directing vehicular traffic. They should not function as uniformed law enforcement officers or adult crossing guards.

**Section 7E.08 Choice of Student Patrols****Guidance:**

Student patrols should be carefully selected. They should be students from the fifth grade or higher. Leadership and reliability should be determining qualities for patrol membership.

Parental approval should be obtained in writing before a student is used as a member of a student patrol.

**Section 7E.09 Operating Procedures for Student Patrols****Guidance:**

Student patrols should use a flagging device to stop pedestrians behind the curb or edge of the roadway, and should allow them to cross only when there is an adequate gap in traffic.

**Standard:**

**Flagging devices used during periods of twilight or darkness shall be retroreflective or illuminated.**

**Because they are not authorized to direct vehicular traffic, student patrols shall not use a STOP paddle.**

Intentionally blank.

## CHAPTER 7F. GRADE-SEPARATED CROSSINGS

### Section 7F.01 Function

Option:

Grade-separated crossings may be used to physically separate the crossing of school pedestrian traffic and vehicular flow.

### Section 7F.02 Types of Grade-Separated Crossings

Option:

Grade-separated crossings may be either overpasses over the highway or underpasses under the highway.

Guidance:

The design should follow the guidelines given in the published policies of the American Association of State Highway and Transportation Officials, such as “A Policy on Geometric Design of Highways and Streets” (see Section 1A.11).

Support:

Experience has shown that overpasses are more satisfactory than underpasses for pedestrian crossings, as overpasses are easier to maintain and supervise.

### Section 7F.03 Criteria for Use of Grade-Separated Crossings

Guidance:

If use of the grade separation will be less convenient to pedestrians than an at-grade crossing, barriers or supervision should be considered to assure a satisfactory level of use.

Intentionally blank.

## PART 8. TRAFFIC CONTROLS FOR HIGHWAY-RAIL GRADE CROSSINGS

### TABLE OF CONTENTS

		<u>Page</u>
<b>CHAPTER 8A.</b>	<b>GENERAL</b>	
Section 8A.01	Introduction.....	8A-1
Section 8A.02	Use of Standard Devices, Systems, and Practices .....	8A-3
Section 8A.03	Uniform Provisions.....	8A-4
Section 8A.04	Highway-Rail Grade Crossing Elimination .....	8A-4
Section 8A.05	Temporary Traffic Control Zones.....	8A-4
<b>CHAPTER 8B.</b>	<b>SIGNS AND MARKING</b>	
Section 8B.01	Purpose.....	8B-1
Section 8B.02	Sizes of Grade Crossing Signs.....	8B-1
Section 8B.03	Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1) and Number of Tracks Sign (R15-2).....	8B-1
Section 8B.04	Highway-Rail Grade Crossing Advance Warning Signs (W10 Series).....	8B-2
Section 8B.05	EXEMPT Highway-Rail Grade Crossing Signs (R15-3, W10-1a).....	8B-6
Section 8B.06	Turn Restrictions During Preemption.....	8B-6
Section 8B.07	DO NOT STOP ON TRACKS Sign (R8-8) .....	8B-6
Section 8B.08	STOP (R1-1) or YIELD (R1-2) Signs at Highway-Rail Grade Crossings .....	8B-7
Section 8B.09	TRACKS OUT OF SERVICE Sign (R8-9).....	8B-8
Section 8B.10	STOP HERE WHEN FLASHING Sign (R8-10).....	8B-8
Section 8B.11	STOP HERE ON RED Sign (R10-6).....	8B-8
Section 8B.12	Emergency Notification Sign (I-13 or I-13a).....	8B-9
Section 8B.13	TRAINS MAY EXCEED 80 MPH Sign (W10-8) .....	8B-9
Section 8B.14	NO TRAIN HORN Sign (W10-9) .....	8B-10
Section 8B.15	NO SIGNAL Sign (W10-10) or NO GATES OR LIGHTS Sign (W10-13).....	8B-10
Section 8B.16	LOOK Sign (R15-8) .....	8B-10
Section 8B.17	Low Ground Clearance Highway-Rail Grade Crossing Sign (W10-5) .....	8B-10
Section 8B.18	Storage Space Signs (W10-11, W10-11a, W10-11b) .....	8B-12
Section 8B.19	Skewed Crossing Sign (W10-12).....	8B-12
Section 8B.20	Pavement Markings .....	8B-12
Section 8B.21	Stop Lines .....	8B-13
Section 8B.22	Dynamic Envelope Markings.....	8B-13
<b>CHAPTER 8C.</b>	<b>ILLUMINATION</b>	
Section 8C.01	Illumination at Highway-Rail Grade Crossings.....	8C-1
<b>CHAPTER 8D.</b>	<b>FLASHING-LIGHT SIGNALS, GATES, AND TRAFFIC CONTROL SIGNALS</b>	
Section 8D.01	Introduction.....	8D-1
Section 8D.02	Flashing-Light Signals, Post-Mounted .....	8D-2
Section 8D.03	Flashing-Light Signals, Overhead Structures .....	8D-3
Section 8D.04	Automatic Gates .....	8D-3
Section 8D.05	Four-Quadrant Gate Systems .....	8D-5
Section 8D.06	Train Detection .....	8D-7
Section 8D.07	Traffic Control Signals at or Near Highway-Rail Grade Crossings .....	8D-8

**FIGURES****CHAPTER 8A.****GENERAL**

Figure 8A-1 Train Dynamic Envelope ..... 8A-2

**CHAPTER 8B.****SIGNS AND MARKINGS**

Figure 8B-1 Highway-Rail Grade Crossing (Crossbuck) Regulatory Signs ..... 8B-5

Figure 8B-2 Advance Warning Signs ..... 8B-5

Figure 8B-3 Regulatory Signs ..... 8B-7

Figure 8B-4 Examples of Emergency Notification Signs ..... 8B-9

Figure 8B-5 Warning Signs ..... 8B-11

Figure 8B-6 Example of Placement of Warning Signs and Pavement Markings at  
Highway-Rail Grade Crossings ..... 8B-14

Figure 8B-7 Examples of Highway-Rail Grade Crossing Pavement Markings ..... 8B-15

Figure 8B-8 Typical Train Dynamic Envelope Pavement Markings ..... 8B-16

**CHAPTER 8D.****FLASHING LIGHT SIGNALS, GATES, AND TRAFFIC CONTROL  
SIGNALS**

Figure 8D-1 Composite Drawing of Active Traffic Control Devices for Highway-Rail  
Grade Crossings Showing Clearances ..... 8D-4

Figure 8D-2 Example of Location Plan for Flashing-Light Signals and Four-Quadrant  
Gates ..... 8D-6

**TABLES****CHAPTER 8B.****SIGNS AND MARKINGS**

Table 8B-1 Sign Sizes for Grade Crossing Signs ..... 8B-3

## CHAPTER 8A. GENERAL

### Section 8A.01 Introduction

#### Support:

Traffic control for highway-rail grade crossings includes all signs, signals, markings, other warning devices, and includes their supports along highways approaching and at highway-rail grade crossings. The function of this traffic control is to permit reasonably safe and efficient operation of both rail and highway traffic at highway-rail grade crossings.

For purposes of installation, operation, and maintenance of traffic control devices at highway-rail grade crossings, it is recognized that the crossing of the highway and rail tracks is situated on a right-of-way available for the joint use of both highway traffic and railroad traffic.

The highway agency or authority with jurisdiction and the regulatory agency with statutory authority, if applicable, jointly determine the need and selection of devices at a highway-rail grade crossing.


In Part 8, the combination of devices selected or installed at a specific highway-rail grade crossing is referred to as a “traffic control system.”

#### Standard:

**The traffic control devices, systems, and practices described herein shall be used at all highway-rail grade crossings open to public travel, consistent with Federal, State, and local laws and regulations.**

To promote an understanding of common terminology between highway and railroad signaling issues, the following definitions shall be used:

1. **Advance Preemption**—the notification of an approaching train that is forwarded to the highway traffic signal controller unit or assembly by the railroad equipment in advance of the activation of the railroad warning devices.
2. **Advance Preemption Time**—the period of time that is the difference between the required maximum highway traffic signal preemption time and the activation of the railroad warning devices.
3. **Cantilevered Signal Structure**—a structure that is rigidly attached to a vertical pole and is used to provide overhead support of signal units.
4. **Clear Storage Distance**—the distance available for vehicle storage measured between 1.8 m (6 ft) from the rail nearest the intersection to the intersection stop line or the normal stopping point on the highway. At skewed highway-rail grade crossings and intersections, the 1.8 m (6 ft) distance shall be measured perpendicular to the nearest rail either along the centerline or edge line of the highway, as appropriate, to obtain the shorter distance. Where exit gates are used, the distance available for vehicle storage is measured from the point where the rear of the vehicle would be clear of the exit gate arm. In cases where the exit gate arm is parallel to the track(s) and is not perpendicular to the highway, the distance is measured either along the centerline or edge line of the highway, as appropriate, to obtain the shorter distance.
5. **Design Vehicle**—the longest vehicle permitted by statute of the road authority (State or other) on that roadway.
6. **Dynamic Envelope**— the clearance required for the train and its cargo overhang due to any combination of loading, lateral motion, or suspension failure (see Figure 8A-1).
7. **Dynamic Exit Gate Operating Mode**—a mode of operation where the exit gate operation is based on the presence of vehicles within the minimum track clearance distance.
8. **Exit Gate Clearance Time**—for Four-Quadrant Gate systems, the exit gate clearance time is the amount of time provided to delay the descent of the exit gate arm(s) after entrance gate arm(s) begin to descend.
9. **Exit Gate Operating Mode**—for Four-Quadrant Gate systems, the mode of control used to govern the operation of the exit gate arms.

**Figure 8A-1. Train Dynamic Envelope**

10. **Flashing-Light Signals**—a warning device consisting of two red signal indications arranged horizontally that are activated to flash alternately when a train is approaching or present at a highway-rail grade crossing.
11. **Interconnection**—the electrical connection between the railroad active warning system and the highway traffic signal controller assembly for the purpose of preemption.
12. **Maximum Highway Traffic Signal Preemption Time**—the maximum amount of time needed following initiation of the preemption sequence for the highway traffic signals to complete the timing of the right-of-way transfer time, queue clearance time, and separation time.
13. **Minimum Track Clearance Distance**—for standard two-quadrant railroad warning devices, the minimum track clearance distance is the length along a highway at one or more railroad tracks, measured either from the highway stop line, warning device, or 3.7 m (12 ft) perpendicular to the track centerline, to 1.8 m (6 ft) beyond the track(s) measured perpendicular to the far rail, along the centerline or edge line of the highway, as appropriate, to obtain the longer distance. For Four-Quadrant Gate systems, the minimum track clearance distance is the length along a highway at one or more railroad tracks, measured either from the highway stop line or entrance warning device, to the point where the rear of the vehicle would be clear of the exit gate arm. In cases where the exit gate arm is parallel to the track(s) and is not perpendicular to the highway, the distance is measured either along the centerline or edge of the highway, as appropriate, to obtain the longer distance.
14. **Minimum Warning Time—Through Train Movements**—the least amount of time active warning devices shall operate prior to the arrival of a train at a highway-rail grade crossing.
15. **Preemption**—the transfer of normal operation of highway traffic signals to a special control mode.
16. **Pre-signal**—supplemental highway traffic signal faces operated as part of the highway intersection traffic signals, located in a position that controls traffic approaching the highway-rail grade crossing in advance of the intersection.
17. **Queue Clearance Time**—the time required for the design vehicle of maximum length stopped just inside the minimum track clearance distance to start up and move through and clear the entire minimum track clearance distance. If pre-signals are present, this time shall be long enough to allow the vehicle to move through the intersection, or to clear the tracks if there is sufficient clear storage distance. If a Four-Quadrant Gate system is present, this time shall be long enough to permit the exit gate arm to lower after the design vehicle is clear of the minimum track clearance distance.

18. **Right-of-Way Transfer Time**—the maximum amount of time needed for the worst case condition, prior to display of the track clearance green interval. This includes any railroad or highway traffic signal control equipment time to react to a preemption call, and any traffic control signal green, pedestrian walk and clearance, yellow change, and red clearance intervals for conflicting traffic.
19. **Separation Time**—the component of maximum highway traffic signal preemption time during which the minimum track clearance distance is clear of vehicular traffic prior to the arrival of the train.
20. **Simultaneous Preemption**—notification of an approaching train is forwarded to the highway traffic signal controller unit or assembly and railroad active warning devices at the same time.
21. **Timed Exit Gate Operating Mode**—a mode of operation where the exit gate descent is based on a predetermined time interval.
22. **Vehicle Intrusion Detection Devices**—a detector or detectors used as a part of a system incorporating processing logic to detect the presence of vehicles within the minimum track clearance distance and to control the operation of the exit gates.
23. **Wayside Equipment**—the signals, switches, and/or control devices for railroad operations housed within one or more enclosures located along the railroad right-of-way and/or on railroad property.

### **Section 8A.02 Use of Standard Devices, Systems, and Practices**

Support:

Because of the large number of significant variables to be considered, no single standard system of traffic control devices is universally applicable for all highway-rail grade crossings.

Option:

The engineering study may include the Highway-Rail Intersection (HRI) components of the National Intelligent Transportation Systems (ITS) architecture, which is a USDOT accepted method for linking the highway, vehicles, and traffic management systems with rail operations and wayside equipment.

Support:

More detail on Highway-Rail Intersection components is available from USDOT's Federal Railroad Administration 1120 Vermont Ave., NW, Washington, DC 20590, or [www.fra.dot.gov](http://www.fra.dot.gov).

**Standard:**

**Traffic control devices, systems, and practices shall be consistent with the design and application of the Standards contained herein.**

**The highway agency or authority with jurisdiction, the regulatory agency with statutory authority and the railroad, as applicable, shall determine the need and selection of devices at a highway-rail grade crossing in accordance with Sections 4511.61, 4513.40, 4907.47, 4907.471, 4907.476, 4907.48, 4907.49, 4907.52 and 4955.33 of the Ohio Revised Code.**

Guidance:

To stimulate effective responses from vehicle operators and pedestrians, these devices, systems, and practices should use the five basic considerations employed generally for traffic control devices and described fully in Section 1A.02: design, placement, operation, maintenance, and uniformity.

Support:

Many other details of highway-rail grade crossing traffic control systems that are not set forth in Part 8 are contained in the publications listed in Section 1A.11.

### **Section 8A.03 Uniform Provisions**

#### **Standard:**

**All signs used in highway-rail grade crossing traffic control systems shall be retroreflectORIZED or illuminated as described in Section 2A.08 to show the same shape and similar color to an approaching road user during both day and night.**

**No sign or signal shall be located in the center of an undivided highway, except in a raised island.**

#### **Guidance:**

Such signs or signals should be installed with a clearance of at least 0.6 m (2 ft) from the outer edge of the raised island to the nearest edge of the sign or signal, except as allowed in Section 2A.19.

Where the distance between tracks, measured along the highway between the inside rails, exceeds 30 m (100 ft), additional signs or other appropriate traffic control devices should be used.

### **Section 8A.04 Highway-Rail Grade Crossing Elimination**

#### **Guidance:**

Because highway-rail grade crossings are a potential source of crashes and congestion, agencies should conduct engineering studies to determine the cost and benefits of eliminating these crossings.

#### **Standard:**

**When a highway-rail grade crossing is eliminated, the traffic control devices for the crossing shall be removed.**

**The tracks shall also be removed and the space previously occupied by the rail bed filled with the same material that comprises the road or highway at the crossing.**

**If the existing traffic control devices at a multiple-track highway-rail grade crossing become improperly placed or inaccurate because of the removal of some of the tracks, the existing devices shall be relocated and/or modified.**

#### **Guidance:**

Any highway-rail grade crossing that cannot be justified should be eliminated.

Where a roadway is removed from a highway-rail grade crossing, the roadway approaches in the railroad right-of-way should also be removed and appropriate signs should be placed at the roadway end in accordance with Section 3C.04.

#### **Option:**

Based on engineering judgment, the TRACKS OUT OF SERVICE (R8-9) sign (see Figure 8B-3) may be temporarily installed until the tracks are removed or paved over. The length of time before the tracks will be removed or paved over may be considered in making the decision as to whether to install the sign.

### **Section 8A.05 Temporary Traffic Control Zones**

#### **Support:**

Temporary traffic control planning provides for continuity of operations (such as movement of traffic, pedestrians and bicycles, transit operations, and access to property/utilities) when the normal function of a roadway at a highway-rail grade crossing is suspended because of temporary traffic control operations.

#### **Standard:**

**Traffic controls for temporary traffic control zones that include highway-rail grade crossings shall be as outlined in Part 6.**

**When a highway-rail grade crossing exists either within or in the vicinity of a temporary traffic control zone, lane restrictions, flagging, or other operations shall not be performed in a manner that**

**would cause vehicles to stop on the railroad tracks, unless a law enforcement officer or flagger is provided at the highway-rail grade crossing to minimize the possibility of vehicles stopping on the tracks, even if automatic warning devices are in place.**

Guidance:

Public and private agencies, including emergency services, businesses, and railroad companies, should meet to plan appropriate traffic detours and the necessary signing, marking, and flagging requirements for operations during temporary traffic control zone activities. Consideration should be given to the length of time that the highway-rail grade crossing is to be closed, the type of rail and highway traffic affected, the time of day, and the materials and techniques of repair.

Temporary traffic control operations should minimize the inconvenience, delay, and crash potential to affected traffic. Prior notice should be given to affected public or private agencies, emergency services, businesses, railroad companies, and road users before the free movement of vehicles or trains is infringed upon or blocked.

Temporary traffic control zone activities should not be permitted to extensively prolong the closing of the highway-rail grade crossing.

The width, grade, alignment, and riding quality of the highway surface at a highway-rail grade crossing should, at a minimum, be restored to correspond with the quality of the approaches to the highway-rail grade crossing.

Intentionally blank.

## CHAPTER 8B. SIGNS AND MARKINGS

### Section 8B.01 Purpose

Support:

Passive traffic control systems, consisting of signs and pavement markings, identify and direct attention to the location of a highway-rail grade crossing and advise motorists, bicyclists, and pedestrians to take appropriate action.

### Section 8B.02 Sizes of Grade Crossing Signs

Standard:

The sizes of grade crossing signs shall be as shown in Table 8B-1.

Option:

Signs larger than those shown in Table 8B-1 may be used (see Section 2A.12).

### Section 8B.03 Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1) and Number of Tracks Sign (R15-2)

Standard:

As provided in Section 4955.33 of the Ohio Revised Code (see Appendix B2):

*At all points where its railroad crosses a public road at a common grade, each company shall erect crossbuck signing at positions at each such crossing that are in accordance with the department of transportation manual for uniform traffic control devices, adopted under section 4511.09 of the Revised Code, to give notice of the proximity of the railroad and warn persons to be on the lookout for the locomotive.*

Option:

Section 4955.33 of the Ohio Revised Code also provides that:

*The director of transportation may erect experimental signs at certain crossings in lieu of the above required signing, for the purpose of conducting research for the development of better signing systems.*

Standard:

The Highway-Rail Grade Crossing (R15-1) sign, commonly identified as the Crossbuck sign, shall be retroreflectorized white with the words RAILROAD CROSSING in black lettering, mounted as shown in Figure 8B-1.

As a minimum, one Crossbuck sign shall be used on each highway approach to every highway-rail grade crossing, alone or in combination with other traffic control devices.

If automatic gates are not present and if there are two or more tracks at the highway-rail grade crossing, the number of tracks shall be indicated on a supplemental Number of Tracks (R15-2) sign of inverted T shape mounted below the Crossbuck sign in the manner and at the height indicated in Figure 8B-1.

Option:

The supplemental Number of Tracks sign may also be used at highway-rail grade crossings with automatic gates.

Standard:

The Crossbuck sign shall be installed on the right side of the highway on each approach to the highway-rail grade crossing. Where restricted sight distance or unfavorable highway geometry exists on an approach to a highway-rail grade crossing, an additional Crossbuck sign shall be installed on the left side of the highway, possibly placed back-to-back with the Crossbuck sign for the opposite approach, or otherwise located so that two Crossbuck signs are displayed for that approach.

A strip of retroreflective white material not less than 50 mm (2 in) in width shall be used on the back of each blade of each Crossbuck sign for the length of each blade, at all highway-rail grade crossings, except those where Crossbuck signs have been installed back-to-back.

A strip of retroreflective white material, not less than 50 mm (2 in) in width, shall be used on each support at passive highway-rail grade crossings for the full length of the front and back of the support from the Crossbuck sign or Number of Tracks sign to within 0.6 m (2 ft) above the edge of the roadway, except on the side of those supports where a STOP (R1-1) or YIELD(R1-2) sign or flashing lights have been installed or on the back side of supports for Crossbuck signs installed on one-way streets.

Guidance:

Crossbuck signs should be located with respect to the highway pavement or shoulder in accordance with the criteria in Chapter 2A and Figures 2A-1 and 2A-2, and should be located with respect to the nearest track in accordance with Figure 8D-2.

The minimum lateral clearance for the nearest edge of the Crossbuck sign should be 1.8 m (6 ft) from the edge of the shoulder or 3.7 m (12 ft) from the edge of the traveled way in rural areas (whichever is greater), and 0.6 m (2 ft) from the face of the curb in urban areas.

Where unusual conditions make variations in location and lateral clearance appropriate, engineering judgment should be used to provide the best practical combination of view and safety clearances.

#### **Section 8B.04 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series)**

**Standard:**

A Highway-Rail Grade Crossing Advance Warning (W10-1) sign (see Figure 8B-2) shall be used on each highway in advance of every highway-rail grade crossing except in the following circumstances:

- A. On an approach to a highway-rail grade crossing from a T-intersection with a parallel highway, if the distance from the edge of the track to the edge of the parallel roadway is less than 30 m (100 ft), and W10-3 signs are used on both approaches of the parallel highway; or
- B. On low-volume, low-speed highways crossing minor spurs or other tracks that are infrequently used and are flagged by train crews; or
- C. In business districts where active highway-rail grade crossing traffic control devices are in use; or
- D. Where physical conditions do not permit even a partially effective display of the sign.

Placement of the Highway-Rail Grade Crossing Advance Warning sign shall be in accordance with Chapter 2A and Table 2C-4.

Option:

On divided highways and one-way streets, an additional W10-1 sign may be installed on the left side of the roadway.

If a highway-rail grade crossing is rough, a ROUGH CROSSING (W10-15) plaque may be used with the Highway-Rail Grade Crossing Advance Warning sign.

**Standard:**

If the distance between the railroad tracks and a parallel highway, from the edge of the tracks to the edge of the parallel roadway, is less than 30 m (100 ft), W10-2, W10-3, or W10-4 signs (see Figure 8B-2) shall be installed on each approach of the parallel highway to warn road users making a turn that they will encounter a highway-rail grade crossing soon after making a turn, and a W10-1 sign for the approach to the tracks shall not be required to be between the tracks and the parallel highway.

If the W10-2, W10-3, or W10-4 signs are used, sign placement in accordance with the guidelines for Intersection Warning signs in Table 2C-4 using the speed of through traffic shall be measured from the highway intersection.

**Table 8B-1. Sign Sizes for Grade Crossing Signs (Sheet 1 of 2)**


Sign	Sign Code	Section	Conventional Road	Expressway	Minimum	Oversized
NO RIGHT TURN ACROSS TRACKS	R3-1a	8B.06, 10C.09	600 x 750 (24 x 30)	—	—	—
NO LEFT TURN ACROSS TRACKS	R3-2a	8B.06, 10C.09	600 x 750 (24 x 30)	—	—	—
DO NOT STOP ON TRACKS	R8-8	8B.07, 10C.05	600 x 750 (24 x 30)	—	—	—
TRACKS OUT OF SERVICE	R8-9	8B.09, 10C.06	600 x 600 (24 x 24)	—	—	—
STOP HERE WHEN FLASHING	R8-10	8B.10, 10C.08	600 x 900 (24 x 36)	—	—	—
STOP HERE ON RED	R10-6	8B.11, 10C.07	600 x 900 (24 x 36)	—	—	—
NO TURN ON RED	R10-11a	8B.07, 10C.09	600 x 750 (24 x 30)	—	—	—
Highway-Rail Grade Crossing (Crossbuck)	R15-1	8B.03, 10C.02	1200 x 225 (48 x 9)	—	—	—
Number of Tracks	R15-2	8B.03, 10C.02	675 x 450 (27 x 18)	—	—	—
EXEMPT	R15-3	8B.05, 10C.10	600 x 300 (24 x 12)	—	—	—
LIGHT RAIL ONLY RIGHT LANE	R15-4a	10C.13	600 x 750 (24 x 30)	—	—	—
LIGHT RAIL ONLY LEFT LANE	R15-4b	10C.13	600 x 750 (24 x 30)	—	—	—
LIGHT RAIL ONLY CENTER LANE	R15-4c	10C.13	600 x 750 (24 x 30)	—	—	—
LIGHT RAIL DO NOT PASS	R15-5	10C.14	600 x 750 (24 x 30)	—	—	—
DO NOT PASS STOPPED TRAIN	R15-5a	10C.14	600 x 750 (24 x 30)	—	—	—
Do Not Drive On Tracks Light Rail Symbol	R15-6	10C.12	600 x 600 (24 x 24)	—	—	—
DO NOT DRIVE ON TRACKS	R15-6a	10C.12	600 x 750 (24 x 30)	—	—	—
Light rail Divided Highway Symbol	R15-7	10C.11	600 x 600 (24 x 24)	—	—	—
Light Rail Divided Highway Symbol (T-Intersection)	R15-7a	10C.11	600 x 600 (24 x 24)	—	—	—
LOOK	R15-8	8B.16, 10C.03	900 x 450 (36 x 18)	—	—	—
Highway-Rail Grade Crossing Advance Warning	W10-1	8B.04, 10C.15	900 Dia. (36 Dia.)	—	—	—
EXEMPT	W10-1a	8B.05, 10C.10	600 x 300 (24 x 12)	—	—	—
Highway-Rail Grade Crossing Advance Warning	W10-2, 3, 4	8B.04, 10C.15	900 x 900 (36 x 36)	—	—	—
Low Ground Clearance Highway-Rail Grade Crossing	W10-5	8B.17, 10C.16	900 x 900 (36 x 36)	—	—	—

**Table 8B-1. Sign Sizes for Grade Crossing Signs (Sheet 2 of 2)**


Sign	Sign Code	Section	Conventional Road	Expressway	Minimum	Oversized
Light Rail Activated Blank-Out Symbol	W10-7	10C.17	750 x 750 (30 x 30)	—	—	—
TRAINS MAY EXCEED 80 MPH	W10-8	8B.13	900 x 900 (36 x 36)	—	—	—
NO TRAIN HORN	W10-9	8B.14	600 x 450 (24 x 18)	—	—	—
NO SIGNAL	W10-10	8B.15	600 x 450 (24 x 18)	—	—	—
Storage Space Symbol	W10-11	8B.18, 10C.18	900 x 900 (36 x 36)	—	—	—
STORAGE SPACE XX FEET BETWEEN TRACKS & HIGHWAY	W10-11a	8B.18, 10C.18	750 x 900 (30 x 36)	—	—	—
STORAGE SPACE XX FREE BETWEEN HIGHWAY & TRACKS BEHIND YOU	W10-11b	8B.18, 10C.18	750 x 900 (30 x 36)	—	—	—
Skewed Crossing	W10-12	8B.19, 10C.19	900 x 900 (36 x 36)	—	—	—
NO GATES OR LIGHTS	W10-13	8B.15	600 x 450 (24 x 18)	—	—	—
NEXT CROSSING	W10-14	8B.17	600 x 450 (24 x 18)	—	—	—
USE NEXT CROSSING	W10-14a	8B.17	600 x 450 (24 x 18)	—	—	—
ROUGH CROSSING	W10-15	8B.17	600 x 450 (24 x 18)	—	—	—
Light Rail Station Symbol	I-12	10C.20	600 x 600 (24 x 24)	—	—	—
Emergency Notification	I-13	8B.12, 10C.21	750 x 750 (30 x 30)	—	—	—
Emergency Notification	I-13a	8B.12, 10C.21	750 x 450 (30 x 18)	—	—	—

- Notes: 1. Larger signs may be used when appropriate.  
2. Dimensions are shown in millimeters followed by inches in parentheses and are shown as width x height .

**Figure 8B-1. Highway-Rail Grade Crossing (Crossbuck) Regulatory Signs**



**Figure 8B-2. Advance Warning Signs**



**Guidance:**

If the distance between the railroad tracks and the parallel highway, from the edge of the tracks to the edge of the parallel roadway, is 30 m (100 ft) or more, a W10-1 sign should be installed in advance of the highway-rail grade crossing, and the W10-2, W10-3, or W10-4 signs should not be used on the parallel highway.

**Section 8B.05 EXEMPT Highway-Rail Grade Crossing Signs (R15-3, W10-1a)****Option:**

When authorized by the Public Utilities Commission, a supplemental EXEMPT (R15-3) sign (see Figure 8B-3) with a white background bearing the word EXEMPT may be used below the Crossbuck sign or Number of Tracks sign, if present, at the highway-rail grade crossing, and a supplemental EXEMPT (W10-1a) sign (see Figure 8B-5) with a yellow background bearing the word EXEMPT may be used below the Highway-Rail Advance Warning (W10-1) sign.

**Support:**

Section 4511.63 of the Ohio Revised Code (O.R.C.) requires certain vehicles to stop, look and listen at highway-rail grade crossings (see Appendix B2). Supplemental EXEMPT signs (R15-3, W10-1a) inform drivers of these vehicles that a stop is not required at certain designated highway-rail grade crossings, except when a train, locomotive, or other railroad equipment is approaching or occupying the highway-rail grade crossing.

**Section 8B.06 Turn Restrictions During Preemption****Guidance:**

At a signalized intersection that is located within 60 m (200 ft) of a highway-rail grade crossing, measured from the edge of the track to the edge of the roadway, where the intersection traffic control signals are preempted by the approach of a train, all existing turning movements toward the highway-rail grade crossing should be prohibited during the signal preemption sequences.

**Option:**

A blank-out or changeable message sign and/or appropriate highway traffic signal indication or other similar type sign may be used to prohibit turning movements toward the highway-rail grade crossing during preemption. The R3-1a and R3-2a signs shown in Figure 8B-3 may be used for this purpose.

**Standard:**

**Turn prohibition signs that are associated with preemption shall be visible only when the highway-rail grade crossing restriction is in effect.**

**Section 8B.07 DO NOT STOP ON TRACKS Sign (R8-8)****Guidance:**

Whenever engineering judgment determines that the potential for vehicles stopping on the tracks is high, a DO NOT STOP ON TRACKS (R8-8) sign (see Figure 8B-3) should be used.

The sign, if used, should be located on the right side of the highway on either the near or far side of the highway-rail grade crossing, depending upon which side provides better visibility to approaching drivers.

**Option:**

DO NOT STOP ON TRACKS signs may be placed on both sides of the track.

On divided highways and one-way streets, a second DO NOT STOP ON TRACKS sign may be placed on the near or far left side of the highway-rail grade crossing to further improve visibility of the sign.

**Section 8B.08 STOP (R1-1) or YIELD (R1-2) Signs at Highway-Rail Grade Crossings**

Option:

As noted in Section 4511.61 of the Ohio Revised Code (see Appendix B2):

*The department of transportation and local authorities in their respective jurisdictions, with the approval of the department, may designate dangerous highway crossings over railroad tracks whether on state, county, or township highways or on streets or ways within municipal corporations, and erect stop signs thereat.*


**Standard:**

**In accordance with Section 4511.61 of the Ohio Revised Code, STOP signs shall be installed at highway-rail grade crossings only with the approval of the Ohio Department of Transportation.**

Option:

For other highway-rail grade crossings with passive warning devices, YIELD signs may be used based on an engineering study.

**Figure 8B-3. Regulatory Signs**



**Guidance:**

The engineering study should take into consideration such factors as highway and train traffic characteristics (including volume and speed), collision history, the need for active control devices, and sight distance to the approaching train.

**Option:**

If a STOP or YIELD sign is installed at a highway-rail grade crossing, it may be installed on the Crossbuck post or on a separate post at a point where the vehicle is to stop, or as near to that point as practical.

**Standard:**

**For all highway-rail grade crossings where STOP or YIELD signs are installed, the placement shall conform to the requirements of Sections 2B.06 and 2B.10. Stop Ahead (W3-1) or Yield Ahead (W3-2) Advance Warning signs (see Figure 2C-4) shall also be installed if the criteria for their installation given in Section 2C.29 is met.**

**Section 8B.09 TRACKS OUT OF SERVICE Sign (R8-9)****Option:**

The TRACKS OUT OF SERVICE (R8-9) sign (see Figure 8B-3) may be used at a highway-rail grade crossing instead of a Crossbuck (R15-1) sign and a Number of Tracks (R15-2) sign (see Figure 8B-1) when the abandonment of the railroad tracks has been approved by the regulatory authority with statutory authority, but only until such time that the tracks are removed and the space previously occupied by the rails filled with the same material that comprises the road or highway at the crossing.

**Standard:**

**When tracks are abandoned, traffic control devices, signal heads and gate arms shall be removed.**

**The R8-9 sign shall be removed when the tracks have been removed and the space previously occupied by the rail bed filled with the same material that comprises the road or highway at the crossing or when the highway-rail grade crossing is returned to service.**

**Section 8B.10 STOP HERE WHEN FLASHING Sign (R8-10)****Option:**

The STOP HERE WHEN FLASHING (R8-10) sign (see Figure 8B-3) may be used at a highway-rail grade crossing to inform drivers of the location of the stop line or the point at which to stop when the flashing-light signals (see Section 8D.02) are activated.

**Section 8B.11 STOP HERE ON RED Sign (R10-6)****Support:**

The STOP HERE ON RED (R10-6) sign (see Figure 8B-3) defines and facilitates observance of stop lines at traffic control signals.

**Option:**

A STOP HERE ON RED sign may be used at locations where vehicles frequently violate the stop line or where it is not obvious to road users where to stop.

**Guidance:**

If possible, stop lines should be placed at a point where the vehicle driver has adequate sight distance along the track.

### **Section 8B.12 Emergency Notification Sign (I-13 or I-13a)**

#### Guidance:

An Emergency Notification (I-13 or I-13a) sign (see Figure 8B-4) should be installed at all highway-rail grade crossings to provide for emergency notification. The sign should have a white message on blue background.

Location and placement should be decided cooperatively by the railroad company and the public or private highway agencies based on specific site conditions. However, these signs are typically located on the railroad right-of-way.

This sign, which is for emergency notification, should convey a clear and simple message that is visible to anyone stalled or disabled on the railroad tracks, and to anyone with other emergencies.

#### Support:

Examples of sign messages are shown in Figure 8B-4.

### **Section 8B.13 TRAINS MAY EXCEED 80 MPH Sign (W10-8)**

#### Guidance:

Where trains are permitted to travel at speeds exceeding 130 km/h (80 mph), a TRAINS MAY EXCEED 80 MPH (W10-8) sign (see Figure 8B-5) should be installed facing road users approaching the highway-rail grade crossing.

If used, the TRAINS MAY EXCEED 80 MPH signs should be installed between the Highway-Rail Grade Crossing Advance Warning (W10-1) sign (see Figure 8B-2) and the highway-rail grade crossing on all approaches to the highway-rail grade crossing. The locations should be determined based on specific site conditions.

---

**Figure 8B-4. Examples of Emergency Notification Signs**



**Section 8B.14 NO TRAIN HORN Sign (W10-9)****Standard:**

A NO TRAIN HORN (W10-9) sign (see Figure 8B-5) shall be installed at each highway-rail grade crossing where there is a Federal Railroad Administration authorization for trains to not sound a horn. The sign shall be mounted as a supplemental plaque below the Highway-Rail Grade Crossing Advance Warning (W10-1) sign (see Figure 8B-2).

**Section 8B.15 NO SIGNAL Sign (W10-10) or NO GATES OR LIGHTS Sign (W10-13)****Option:**

A NO SIGNAL (W10-10) sign or a NO GATES OR LIGHTS (W10-13) sign (see Figure 8B-5) may be installed at highway-rail grade crossings that are not equipped with automated signals.

The NO SIGNAL (W10-10) sign or the NO GATES OR LIGHTS (W10-13) sign may be mounted as a supplemental plaque below the Advance Warning (W10-1) sign.

**Section 8B.16 LOOK Sign (R15-8)****Option:**

At highway-rail grade crossings, the LOOK (R15-8) sign (see Figure 8B-3) may be mounted as a supplemental plaque on the Crossbuck (R15-1) sign post, or as a separate sign in the immediate vicinity of the highway-rail grade crossing on the railroad right-of-way.

**Section 8B.17 Low Ground Clearance Highway-Rail Grade Crossing Sign (W10-5)****Guidance:**

If the highway profile conditions are sufficiently abrupt to create a hang-up situation for long wheelbase vehicles or for trailers with low ground clearance, the Low Ground Clearance Highway-Rail Grade Crossing (W10-5) sign (see Figure 8B-5) should be installed in advance of the highway-rail grade crossing.

**Standard:**

**Because this symbol might not be readily recognizable by the public, the Low Ground Clearance Highway-Rail Grade Crossing (W10-5) warning sign shall be accompanied by an educational plaque, LOW GROUND CLEARANCE. The LOW GROUND CLEARANCE educational plaque shall remain in place for at least 3 years after the initial installation of the W10-5 sign (see Section 2A.13).**

**Guidance:**


Auxiliary plaques such as AHEAD, NEXT CROSSING, or USE NEXT CROSSING (with appropriate arrows), or a supplemental distance plaque should be placed below the W10-5 sign at the nearest intersecting highway where a vehicle can detour or at a point on the highway wide enough to permit a U-turn.

If engineering judgment of roadway geometric and operating conditions confirms that vehicle speeds across the railroad tracks should be below the posted speed limit, a W13-1 advisory speed plaque should be posted.

**Option:**

If the highway-rail grade crossing is rough, word message signs such as BUMP, DIP, or ROUGH CROSSING may be installed. A W13-1 advisory speed plaque may be installed below the word message sign in advance of rough crossings.

**Figure 8B-5. Warning Signs**



Note: The W10-11 sign is a W10-3 sign modified for geometrics. Other signs can be oriented or revised as needed to satisfy the geometrics of the roadways and the railroad tracks.

**Support:**

Information on railroad ground clearance requirements is also available in the “American Railway Engineering and Maintenance-of-Way Association’s Engineering Manual,” or the American Association of State Highway and Transportation Officials’ “Policy on Geometric Design of Highways and Streets” (see Section 1A.11).

**Section 8B.18 Storage Space Signs (W10-11, W10-11a, W10-11b)****Guidance:**

A Storage Space (W10-11) sign supplemented by a word message storage distance (W10-11a) sign (see Figure 8B-5) should be used where there is a highway intersection in close proximity to the highway-rail grade crossing and an engineering study determines that adequate space is not available to store a design vehicle(s) between the highway intersection and the train dynamic envelope.

The Storage Space (W10-11 and W10-11a) signs should be mounted in advance of the highway-rail grade crossing at an appropriate location to advise drivers of the space available for vehicle storage between the highway intersection and the highway-rail grade crossing.

**Option:**

A Storage Space (W10-11b) sign (see Figure 8B-5) may be mounted beyond the highway-rail grade crossing at the highway intersection under the STOP or YIELD sign or just prior to the signalized intersection to remind drivers of the storage space between the tracks and the highway intersection.

**Section 8B.19 Skewed Crossing Sign (W10-12)****Option:**

The Skewed Crossing (W10-12) sign (see Figure 8B-5) may be used at a skewed highway-rail grade crossing to warn drivers that the railroad tracks are not perpendicular to the highway.

**Guidance:**

If the Skewed Crossing sign is used, the symbol should show the direction of the crossing (near left to far right as shown in Figure 8B-5, or the mirror image if the track goes from far left to near right). If the Skewed Crossing sign is used where the angle of the crossing is significantly different than 45 degrees, the symbol should show the approximate angle of the crossing.

**Standard:**

**The Skewed Crossing sign shall not be used as a replacement for the required Advance Warning (W10-1) sign. If used, the Skewed Crossing sign shall supplement the W10-1 sign and shall be mounted on a separate post.**

**Section 8B.20 Pavement Markings****Standard:**

**All highway-rail grade crossing pavement markings shall be retroreflectorized white. All other markings shall be in accordance with Part 3.**

**Pavement markings in advance of a highway-rail grade crossing shall consist of an X, the letters RR, a no-passing marking (two-lane highways where centerline markings are used), and certain transverse lines as shown in Figures 8B-6 and 8B-7.**

**Identical markings shall be placed in each approach lane on all paved approaches to highway-rail grade crossings where signals or automatic gates are located, and at all other highway-rail grade crossings where the posted or statutory highway speed is 60 km/h (40 mph) or greater.**

**Pavement markings shall not be required at highway-rail grade crossings where the posted or statutory highway speed is less than 60 km/h (40 mph), or in urban areas, if an engineering study indicates that other installed devices provide suitable warning and control.**

Guidance:

When pavement markings are used, a portion of the X symbol should be directly opposite the Advance Warning sign. The X symbol and letters should be elongated to allow for the low angle at which they will be viewed.

Option:

When justified by engineering judgment, supplemental pavement marking symbol(s) may be placed between the Advance Warning sign and the highway-rail grade crossing.

### **Section 8B.21 Stop Lines**

Guidance:

The stop line should be a transverse line at a right angle to the traveled way at a point where a vehicle is to stop or as near to that point as possible. The stop line should be placed approximately 2.4 m (8 ft) from the gate (if present), but no closer than 4.6 m (15 ft) nor more than 15m (50 ft) from the nearest rail.

### **Section 8B.22 Dynamic Envelope Markings**

Option:

Dynamic envelope markings may be used to mark the edges of the dynamic envelope where there is a highway intersection in close proximity to the highway-rail grade crossing and an engineering study determines that vehicles might stop within the dynamic envelope area.

Dynamic envelope markings may be installed at all highway-rail grade crossings, unless a Four-Quadrant Gate system (see Section 8D.05) is used.


**Standard:**

**If used, pavement markings for indicating the dynamic envelope shall conform to Part 3 and shall be a 100 mm (4 in) normal solid white line or contrasting pavement color and/or contrasting pavement texture.**


Guidance:

If used, dynamic envelope pavement markings should be placed on the highway 1.8 m (6 ft) from the nearest rail, installed parallel to the tracks, unless the operating railroad company advises otherwise. The pavement markings should extend across the roadway as shown in Figure 8B-8.

**Figure 8B-6. Example of Placement of Warning Signs and Pavement Markings at Highway-Rail Grade Crossings**




**Figure 8B-7. Examples of Highway-Rail Grade Crossing Pavement Markings**



**Highway-rail grade crossing alternative (narrow) pavement markings**


Note: Refer to Figure 8B-6 for placement



**Highway-rail grade crossing pavement markings**

\*Width may vary according to lane width

**Figure 8B-8. Typical Train Dynamic Envelope Pavement Markings**



## CHAPTER 8C. ILLUMINATION

### Section 8C.01 Illumination at Highway-Rail Grade Crossings

#### Option:

Illumination may be installed at or adjacent to a highway-rail grade crossing.

#### Guidance:

If an engineering study is conducted and if the engineering study determines that better nighttime visibility of the train and the highway-rail grade crossing is needed (for example, where a substantial amount of railroad operation is conducted at night, where train speeds are low and highway-rail grade crossings are blocked for long periods, or crash history indicates that drivers experience difficulty in seeing trains or traffic control devices during hours of darkness), then illumination should be installed at and adjacent to the highway-rail grade crossing.

#### Support:

Types and location of luminaires for highway-rail grade crossing illumination are contained in the American National Standards Institute's (ANSI) "Practice for Roadway Lighting RP-8" available from the Illuminating Engineering Society (see Section 1A.11).

Intentionally blank.

## CHAPTER 8D. FLASHING-LIGHT SIGNALS, GATES, AND TRAFFIC CONTROL SIGNALS

### Section 8D.01 Introduction

#### Support:

Active traffic control systems inform motorists, bicyclists, and pedestrians of the approach or presence of trains, locomotives, or other railroad equipment at highway-rail grade crossings.

A composite drawing (see Figure 8D-1) shows a post-mounted flashing-light signal (two light units mounted in a horizontal line), a flashing-light signal mounted on an overhead structure, and an automatic gate assembly.

#### Option:

Post-mounted and overhead-mounted flashing-light signals may be used separately or in combination with each other as determined by an engineering study. Also, flashing-light signals may be used without automatic gate assemblies, as determined by an engineering study.

#### Standard:

**The meaning of flashing-light signals and gates shall be as defined in Section 4511.62 and 4511.64 of the Ohio Revised Code. Requirements for the erection and operation of the signal equipment, gates, bells and related traffic control devices at railroad grade crossings are contained in Sections, 4513.40, 4907.47, 4907.48, 4907.49, 4907.52 and 4907.476 of the Ohio Revised Code (see Appendix B2).**

**Location and clearance dimensions for flashing-light signals and gates shall be as shown in Figure 8D-1.**

**When there is a curb, a horizontal clearance of at least 0.6 m (2 ft) shall be provided from the face of the vertical curb to the closest part of the signal or gate arm in its upright position. When a cantilevered-arm flashing-light signal is used, the vertical clearance shall be at least 5.2 m (17 ft) above the crown of the highway to the lowest point of the signal unit.**

**Where there is a shoulder, but no curb, a horizontal clearance of at least 0.6 m (2 ft) from the edge of a paved or surfaced shoulder shall be provided, with a clearance of at least 1.8 m (6 ft) from the edge of the traveled way.**

**Where there is no curb or shoulder, the minimum horizontal clearance shall be 1.8 m (6 ft) from the edge of the traveled way.**

#### Guidance:

Equipment housings (controller cabinets) should have a lateral clearance of at least 9 m (30 ft) from the edge of the highway, and where railroad property and conditions allow, at least 7.6 m (25 ft) from the nearest rail.

If a pedestrian route is provided, sufficient clearance from supports, posts, and gate mechanisms should be maintained for pedestrian travel.

For a shared-use facility, if automatic gates are provided, a pedestrian gate long enough to block the full width of the path, for both pedestrians and bicyclists, should also be used.

When determined by an engineering study, a lateral escape route to the right of the highway in advance of the highway-rail grade crossing traffic control devices should be kept free of guardrail or other ground obstructions. Where guardrail is not deemed necessary or appropriate, barriers should not be used for protecting signal supports.

The same lateral clearance and roadside safety features should apply to flashing-light signal and automatic gate locations on both the right and left sides of the roadway.

**Option:**

In industrial or other areas involving only low-speed highway traffic or where signals are vulnerable to damage by turning truck traffic, guardrail may be installed to provide protection for the signal assembly.

**Section 8D.02 Flashing-Light Signals, Post-Mounted****Standard:**

**The flashing-light signal assembly (shown in Figure 8D-1) on the side of the highway shall include a standard Crossbuck (R15-1) sign, and where there is more than one track, a supplemental Number of Tracks (R15-2) sign, all of which indicate to motorists, bicyclists, and pedestrians the location of a highway-rail grade crossing.**

**Option:**

Bells or other audible warning devices may be included in the assembly and may be operated in conjunction with the flashing lights to provide additional warning for pedestrians and bicyclists.

**Standard:**

**When indicating the approach or presence of a train, the flashing-light signal shall display toward approaching highway traffic two red lights mounted in a horizontal line flashing alternately.**

**Flashing-light signals shall be placed to the right of approaching highway traffic on all highway approaches to a highway-rail grade crossing. They shall be located laterally with respect to the highway in conformance with Figure 8D-1 except where such location would adversely affect signal visibility.**

**At highway-rail grade crossings with highway traffic in both directions, back-to-back pairs of lights shall be placed on each side of the tracks. On multi-lane one-way streets and divided highways, flashing light signals shall be placed on the approach side of the highway-rail grade crossing on both sides of the roadway or shall be placed above the highway.**

**Each red signal unit in the flashing-light signal shall flash alternately. The number of flashes per minute for each lamp shall be 35 minimum and 65 maximum. Each lamp shall be illuminated approximately the same length of time. Total time of illumination of each pair of lamps shall be the entire operating time. Flashing-light units shall use either 200 mm (8 in) or 300 mm (12 in) nominal diameter lenses.**

**Guidance:**

In choosing between the 200 mm (8 in) or 300 mm (12 in) nominal diameter lenses for use in highway-rail grade crossing flashing-light signals, consideration should be given to the principles stated in Section 4D.15.

**Standard:**

**Highway-rail grade crossing flashing-light signals shall operate at a low voltage using storage batteries either as a primary or stand-by source of electrical energy. Provision shall be made to provide a source of energy for charging batteries.**

**Option:**

Additional pairs of flashing-light units may be mounted on the same supporting post and directed toward vehicular traffic approaching the highway-rail grade crossing from other than the principal highway route, such as where there are approaching routes on highways closely adjacent to and parallel to the railroad.

### **Section 8D.03 Flashing-Light Signals, Overhead Structures**

#### **Option:**

Flashing-light signals may be installed on overhead structures or cantilevered supports as shown in Figure 8D-1 where needed for additional emphasis, or for better visibility to approaching traffic, particularly on multi-lane approaches or highways with profile restrictions.

If it is determined by an engineering study that one set of flashing lights on the cantilever arm is not sufficiently visible to road users, one or more additional sets of flashing lights may be mounted on the supporting post and/or on the cantilever arm.

#### **Standard:**

**Breakaway or frangible bases shall not be used for overhead structures or cantilevered supports.**

### **Section 8D.04 Automatic Gates**

#### **Support:**

An automatic gate is a traffic control device used as an adjunct to flashing-light signals.

#### **Standard:**

**The automatic gate (see Figure 8D-1) shall consist of a drive mechanism and a fully retroreflectorized red- and white-striped gate arm with lights. When in the down position, the gate arm shall extend across the approaching lanes of highway traffic.**

**In the normal sequence of operation, unless constant warning time or other advanced system requires otherwise, the flashing-light signals and the lights on the gate arm (in its normal upright position) shall be activated immediately upon detection of the approaching train. The gate arm shall start its downward motion not less than 3 seconds after the flashing-light signals start to operate, shall reach its horizontal position at least 5 seconds before the arrival of the train, and shall remain in the down position as long as the train occupies the highway-rail grade crossing.**

**When the train clears the highway-rail grade crossing, and if no other train is detected, the gate arm shall ascend to its upright position, following which the flashing lights and the lights on the gate arm shall cease operation.**

**Gate arms shall be fully retroreflectorized on both sides, have 45-degree diagonal stripes alternately red and white at 400 mm (16 in) intervals measured horizontally, and shall have at least three red lights as indicated in Figure 8D-1.**

**When activated, the gate arm light nearest the tip shall be illuminated continuously and the other lights shall flash alternately in unison with the flashing-light signals.**

**The entrance lane gate arm mechanism shall be designed to fail safe in the down position.**

#### **Guidance:**

The gate arm should ascend to its upright position in not more than 12 seconds.

In its normal upright position, when no train is approaching or occupying the highway-rail grade crossing, the gate arm should be either vertical or nearly so (see Figure 8D-1).


In the design of individual installations, consideration should be given to timing the operation of the gate arm to accommodate large and/or slow-moving vehicles.

The gates should cover the approaching highway to block all motor vehicles from being driven around the gate without crossing the centerline.

#### **Option:**

Automatic gate installations may include median islands between opposing lanes on an approach to a highway-rail grade crossing.

**Figure 8D-1. Composite Drawing of Active Traffic Control Devices for Highway-Rail Grade Crossings Showing Clearance**



\* For locating this reference line at other than curb section installation, see Section 8D.01.

Where gates are located in the median, additional median width may be required to provide the minimum clearance for the counterweight supports.

### **Section 8D.05 Four-Quadrant Gate Systems**

Option:

Four-Quadrant Gate systems may be installed to improve safety at highway-rail grade crossings based on an engineering study when less restrictive measures, such as automatic gates and median islands, are not effective.

**Standard:**

**A Four-Quadrant Gate system shall consist of a series of automatic gates used as an adjunct to flashing-light signals to control traffic on all lanes entering and exiting the highway-rail grade crossing.**

**The Four-Quadrant Gate system shall consist of a drive mechanism and fully retroreflectorized red- and white-striped gate arms with lights, and when in the down position the gate arms extend individually across the entrance and exit lanes of highway traffic as shown in Figure 8D-2. Standards contained in Sections 8D.01 through 8D.03 for flashing-light signals shall be followed for signal specifications, location, and clearance distances.**

**In the normal sequence of operation, unless constant warning time or other advanced system requires otherwise, the flashing-light signals and the lights on the gate arms (in their normal upright positions) shall be activated immediately upon detection of the approaching train. The gate arms for the entrance lanes of traffic shall start their downward motion not less than 3 seconds after the flashing-light signals start to operate and shall reach their horizontal position at least 5 seconds before the arrival of the train. Exit gate arm activation and downward motion shall be based on detection or timing requirements established by an engineering study of the individual site. The gate arms shall remain in the down position as long as the train occupies the highway-rail grade crossing.**

**When the train clears the highway-rail grade crossing, and if no other train is detected, the gate arms shall ascend to their upright positions, following which the flashing lights and the lights on the gate arms shall cease operation.**

**Gate arm design, colors, and lighting requirements shall be in accordance with the Standards contained in Section 8D.04.**

**Except as noted in the Option below, the exit gate arm mechanism shall be designed to fail-safe in the up position.**

**At locations where gate arms are offset a sufficient distance for vehicles to drive between the entrance and exit gate arms, median islands shall be installed in accordance with the needs established by an engineering study.**

Guidance:

The gate arm should ascend to its upright position in not more than 12 seconds.



Four-Quadrant Gate systems should only be used in locations with constant-warning-time train detection.

The operating mode of the exit gates should be determined based upon an engineering study, with input from the affected railroad company.

If the Timed Exit Gate Operating Mode is used, the engineering study, with input from the affected railroad company, should also determine the Exit Gate Clearance Time (see Section 8A.01).

If the Dynamic Exit Gate Operating Mode is used, vehicle intrusion detection devices should be installed to control exit gate operation based on vehicle presence within the minimum track clearance distance.

**Figure 8D-2. Example of Location Plan for Flashing-Light Signals and Four-Quadrant Gates**



Lateral clearances shall be in accordance with Figure 8D-1 and Chapter 8D.

Note: In an effort to simplify the figure to show typical location plans for flashing-light signals and four-quadrant gates, not all traffic control devices are shown on this figure.

**Legend**  
 → Direction of travel

Regardless of which exit gate operating mode is used, the Exit Gate Clearance Time should be considered when determining additional time requirements for the Minimum Warning Time.

If a Four-Quadrant Gate system is used at a location that is adjacent to an intersection that could cause vehicles to queue within the minimum track clearance distance, the Dynamic Exit Gate Operating Mode should be used unless an engineering study indicates otherwise.

If a Four-Quadrant Gate system is interconnected with a highway traffic signal, backup or standby power should be considered for the highway traffic signal. Also, circuitry should be installed to prevent the highway traffic signal from leaving the track clearance green interval until all of the gates are lowered.

At locations where sufficient space is available, exit gates should be set back from the track a distance that provides a safety zone long enough to accommodate at least one design vehicle between the exit gate and the nearest rail.

Four-Quadrant Gate systems should include remote health (status) monitoring capable of automatically notifying railroad signal maintenance personnel when anomalies have occurred within the system.

Option:

Exit gate arms may fail in the down position if the highway-rail grade crossing is equipped with remote health (status) monitoring.

Four-Quadrant Gate installations may include median islands between opposing lanes on an approach to a highway-rail grade crossing.

Guidance:

Where sufficient space is available, median islands should be at least 18 m (60 ft) in length.

### **Section 8D.06 Train Detection**

**Standard:**

**The devices employed in active traffic control systems shall be actuated by some form of train detection.**

**Train detection circuits, insofar as practical, shall be designed on the fail-safe principle.**

**Flashing-light signals shall operate for at least 20 seconds before the arrival of any train, except as noted in the Option below.**

Option:

On tracks where all trains operate at less than 30 km/h (20 mph) and where flagging is performed by an employee on the ground, a shorter signal operating time for the flashing-light signals may be used.

Additional warning time may be provided when determined by an engineering study.

Guidance:

Where the speeds of different trains on a given track vary considerably under normal operation, special devices or circuits should be installed to provide reasonably uniform notice in advance of all train movements over the highway-rail grade crossing. Special control features should be used to eliminate the effects of station stops and switching operations within approach control circuits to prevent excessive activation of the traffic control devices while trains are stopped on or switching upon the approach track control circuits.

### **Section 8D.07 Traffic Control Signals at or Near Highway-Rail Grade Crossings**

Option:

Traffic control signals may be used instead of flashing-light signals to control road users at industrial highway-rail grade crossings and other places where train movements are very slow, such as in switching operations.

**Standard:**

**The appropriate provisions of Part 4 relating to traffic control signal design, installation, and operation shall be applicable where traffic control signals are used to control road users instead of flashing-light signals at highway-rail grade crossings.**

**Traffic control signals shall not be used instead of flashing-light signals to control road users at a mainline highway-rail grade crossing.**

**Guidance:**

The highway agency with jurisdiction, the regulatory agency with statutory authority, if applicable, and the railroad company should jointly determine the preemption operation at highway-rail grade crossings adjacent to signalized highway intersections.

If a highway-rail grade crossing is equipped with a flashing-light signal system and is located within 60 m (200 ft) of an intersection or midblock location controlled by a traffic control signal, the traffic control signal should be provided with preemption in accordance with Section 4D.13.

Coordination with the flashing-light signal system, queue detection, or other alternatives should be considered for traffic control signals located farther than 60 m (200 ft) from the highway-rail grade crossing. Factors to be considered should include traffic volumes, vehicle mix, vehicle and train approach speeds, frequency of trains, and queue lengths.

**Standard:**

**If preemption is provided, the normal sequence of traffic control signal indications shall be preempted upon the approach of trains to avoid entrapment of vehicles on the highway-rail grade crossing by conflicting aspects of the traffic control signals and the highway-rail grade crossing flashing-light signals.**

**This preemption feature shall have an electrical circuit of the closed-circuit principle, or a supervised communication circuit between the control circuits of the highway-rail grade crossing warning system and the traffic control signal controller. The traffic control signal controller preemptor shall be activated via the supervised communication circuit or the electrical circuit that is normally energized by the control circuits of the highway-rail grade crossing warning system. The approach of a train to a highway-rail grade crossing shall de-energize the electrical circuit or activate the supervised communication circuit, which in turn shall activate the traffic control signal controller preemptor. This shall establish and maintain the preemption condition during the time the highway-rail grade crossing warning system is activated, except that when crossing gates exist, the preemption condition shall be maintained until the crossing gates are energized to start their upward movement. When multiple or successive preemptions occur, train activation shall receive first priority.**

**Guidance:**

If a highway-rail grade crossing is located within 15 m (50 ft) (or within 23 m (75 ft) for a highway that is regularly used by multi-unit vehicles) of an intersection controlled by a traffic control signal, the use of pre-signals to control traffic approaching the grade crossing should be considered.

**Standard:**

**If used, the pre-signals shall display a red signal indication during the track clearance portion of a signal preemption sequence to prohibit additional vehicles from crossing the railroad track.**

**Guidance:**

Consideration should be given to using visibility-limited signal faces (see Section 4A.02) at the intersection for the downstream signal faces that control the approach that is equipped with pre-signals.

**Option:**

The pre-signal phase sequencing may be timed with an offset from the signalized intersection such that the railroad track area and the area between the railroad track and the downstream signalized intersection is generally kept clear of stopped vehicles.

**Standard:**

**If a pre-signal is installed at an interconnected highway-rail grade crossing near a signalized intersection, a STOP HERE ON RED (R10-6) sign shall be installed near the pre-signal or at the stop line if used. If there is a nearby signalized intersection with insufficient clear storage distance for a design vehicle, or the highway-rail grade crossing does not have gates, a NO TURN ON RED (R10-11) sign shall be installed for the approach that crosses the railroad track.**

**Option:**

At locations where a highway-rail grade crossing is located more than 15 m (50 ft) (or more than 23 m (75 ft) for a highway regularly used by multi-unit vehicles) from an intersection controlled by a traffic control signal, a pre-signal may be used if an engineering study determines a need.

If highway traffic signals must be located within close proximity to the flashing-light signal system, the highway traffic signals may be mounted on the same overhead structure as the flashing-light signals.

**Support:**

Section 4D.13 describes additional considerations regarding preemption of traffic control signals at or near highway-rail grade crossings.

Intentionally blank.

**PART 9. TRAFFIC CONTROLS FOR BICYCLE FACILITIES**

**TABLE OF CONTENTS**

	<u>Page</u>
<b>CHAPTER 9A.</b>	<b>GENERAL</b>
Section 9A.01	Requirements for Bicyclist Traffic Control Devices..... 9A-1
Section 9A.02	Scope..... 9A-1
Section 9A.03	Definitions Relating to Bicycles..... 9A-1
Section 9A.04	Maintenance..... 9A-1
Section 9A.05	Relation to Other Documents..... 9A-1
Section 9A.06	Placement Authority..... 9A-2
Section 9A.07	Meaning of Standard, Guidance, Option, and Support..... 9A-2
Section 9A.08	Colors..... 9A-2
<b>CHAPTER 9B.</b>	<b>SIGNS</b>
Section 9B.01	Application and Placement of Signs..... 9B-1
Section 9B.02	Design of Bicycle Signs..... 9B-1
Section 9B.03	STOP and YIELD Signs (R1-1, R1-2)..... 9B-1
Section 9B.04	Bicycle Lane Signs (R3-17, R3-17a, R3-17b)..... 9B-2
Section 9B.05	BEGIN RIGHT TURN LANE YIELD TO BIKES Sign (R4-4)..... 9B-6
Section 9B.06	Bicycle WRONG WAY sign and RIDE WITH TRAFFIC Plaque (R5-1b, R9-3c)..... 9B-6
Section 9B.07	NO MOTOR VEHICLES Sign (R5-3)..... 9B-6
Section 9B.08	No Bicycles Sign (R5-6)..... 9B-6
Section 9B.09	No Parking BIKE LANE Signs (R7-9, R7-9a)..... 9B-7
Section 9B.10	Bicycle Regulatory Signs (R9-5, R9-6, R10-3)..... 9B-7
Section 9B.11	Shared-Use Path Restriction Sign (R9-7)..... 9B-7
Section 9B.12	Bicycle Signal Actuation Sign (R10-22)..... 9B-7
Section 9B.13	Other Regulatory Signs..... 9B-7
Section 9B.14	Turn or Curve Warning Signs (W1 Series)..... 9B-7
Section 9B.15	Intersection Warning Signs (W2 Series)..... 9B-9
Section 9B.16	Bicycle Surface Condition Warning Sign (W8-10)..... 9B-9
Section 9B.17	Bicycle Warning Sign (W11-1)..... 9B-10
Section 9B.18	Other Bicycle Warning Signs..... 9B-10
Section 9B.19	Bicycle Route Guide Signs (D11-1)..... 9B-10
Section 9B.20	Bicycle Route Signs (M1-8, M1-9)..... 9B-11
Section 9B.21	Destination Arrow and Supplemental Plaque Signs for Bicycle Route Signs... 9B-15
Section 9B.22	Bicycle Parking Area Sign (D4-3)..... 9B-15
<b>CHAPTER 9C.</b>	<b>MARKINGS</b>
Section 9C.01	Functions of Markings..... 9C-1
Section 9C.02	General Principles..... 9C-1
Section 9C.03	Marking Patterns and Colors on Shared-Use Paths..... 9C-1
Section 9C.04	Markings for Bicycle Lanes..... 9C-2
Section 9C.05	Bicycle Detector Symbol ..... 9C-3
Section 9C.06	Pavement Markings for Obstructions..... 9C-3

**CHAPTER 9D.****SIGNALS**

Section 9D.01	Application.....	9D-1
Section 9D.02	Signal Operations for Bicycles.....	9D-1

**FIGURES****CHAPTER 9B.****SIGNS**

Figure 9B-1	Sign Placement on Shared-Use Paths.....	9B-2
Figure 9B-2	Regulatory Signs for Bicycle Facilities.....	9B-5
Figure 9B-3	Warning Signs for Bicycle Facilities.....	9B-8
Figure 9B-4	Guide Signs for Bicycle Facilities.....	9B-11
Figure 9B-5	Example of Signing for the Beginning and End of a Designated Bicycle Route on a Shared-Use Path .....	9B-12
Figure 9B-6	Example of Signing for an On-Roadway Bicycle Route.....	9B-13
Figure 9B-7	Examples of Signing and Markings for Shared-Use Paths.....	9B-14

**CHAPTER 9C.****MARKINGS**

Figure 9C-1	Example of Intersection Pavement Markings—Designated Bicycle Lane with Left-Turn Area, Heavy Turn Volumes, Parking, One-Way Traffic, or Divided Highway.....	9C-4
Figure 9C-2	Examples of Centerline Markings for Shared-Use Paths.....	9C-5
Figure 9C-3	Example of Bicycle Lane Treatment at a Right Turn Only Lane.....	9C-6
Figure 9C-4	Example of Bicycle Lane Treatment at Parking Lane into a Right Turn Only Lane.....	9C-7
Figure 9C-5	Example of Pavement Markings for Bicycle Lanes on a Two-Way Street.....	9C-8
Figure 9C-6	Example of Optional Word and Symbol Pavement Markings for Bicycle Lanes.....	9C-9
Figure 9C-7	Example of Bicycle Detector Pavement Marking.....	9C-10
Figure 9C-8	Example of Obstruction Pavement Marking.....	9C-11

**TABLES****CHAPTER 9B.****SIGNS**

Table 9B-1	Minimum Sign Sizes for Bicycle Facilities .....	9B-3
------------	---	------

## CHAPTER 9A. GENERAL

### **Section 9A.01 Requirements for Bicyclist Traffic Control Devices**

Support:

General information and definitions concerning traffic control devices are found in Part 1.

### **Section 9A.02 Scope**

Support:

Part 9 covers signs, pavement markings, and highway traffic signals specifically related to bicycle operation on both roadways and shared-use paths.

Guidance:

Parts 1, 2, 3, and 4 should be reviewed for general provisions, signs, pavement markings, and signals.

**Standard:**

**None of the bikeway designations in this Manual shall be construed to preclude permitted bicycle travel on roadways or portions of roadways that do not have bikeway designations.**

### **Section 9A.03 Definitions Relating to Bicycles**

**Standard:**

**The following terms shall be defined as follows when used in Part 9:**

- 1. Bicycle Facilities**—a general term denoting improvements and provisions that accommodate or encourage bicycling, including parking and storage facilities, and shared roadways not specifically defined for bicycle use.
- 2. Bicycle Lane**—a portion of a roadway that has been designated by signs and pavement markings for preferential or exclusive use by bicyclists.
- 3. Bikeway**—a generic term for any road, street, path, or way that in some manner is specifically designated for bicycle travel, regardless of whether such facilities are designated for the exclusive use of bicycles or are to be shared with other transportation modes.
- 4. Designated Bicycle Route**—a system of bikeways designated by the jurisdiction having authority with appropriate directional and informational route signs, with or without specific bicycle route numbers. Bicycle routes, which might be a combination of various types of bikeways, should establish a continuous routing.
- 5. Shared-Use Path**—a bikeway outside the traveled way and physically separated from motorized vehicular traffic by an open space or barrier and either within the highway right-of-way or within an independent alignment. Shared-use paths are also used by pedestrians (including skaters, users of manual and motorized wheelchairs, and joggers) and other authorized motorized and non-motorized users.

### **Section 9A.04 Maintenance**

Guidance:

All signs, signals, and markings, including those on bicycle facilities, should be properly maintained to command respect from both the motorist and the bicyclist. When installing signs and markings on bicycle facilities, an agency should be designated to maintain these devices.

### **Section 9A.05 Relation to Other Documents**

Support:

“The Uniform Vehicle Code and Model Traffic Ordinance” published by the National Committee on Uniform Traffic Laws and Ordinances and the Ohio Revised Code (see Section 1A.11) have provisions for bicycles and are the basis for the traffic control devices included herein.

Informational documents used during the development of the signing and marking recommendations in Part 9 include the following:

- A. "Guide for Development of Bicycle Facilities," which is available from the American Association of State Highway and Transportation Officials (see the Preface for the address);
- B. State and local government design guides; and
- C. "Selecting Roadway Design Treatments to Accommodate Bicycles," FHWA Publication No. FHWA-RD-92-073, which is available from the FHWA Research and Technology Report Center, 9701 Philadelphia Court, Unit Q, Lanham, MD 20106.

Other publications that relate to the application of traffic control devices in general are listed in Section 1A.11.

### **Section 9A.06 Placement Authority**

Support:

Section 1A.08 contains information regarding placement authority for traffic control devices.

### **Section 9A.07 Meaning of Standard, Guidance, Option, and Support**

Support:

The introduction to this Manual contains information regarding the meaning of the headings Standard, Guidance, Option, and Support, and the use of the words shall, should, and may.

### **Section 9A.08 Colors**

Support:

Section 1A.12 contains information regarding the color codes.

## CHAPTER 9B. SIGNS

### Section 9B.01 Application and Placement of Signs

#### Standard:

**Bicycle signs shall be standard in shape, legend, and color.**

**All signs shall be retroreflectorized for use on bikeways, including shared-use paths and bicycle lane facilities.**

**Where signs serve both bicyclists and other road users, vertical mounting height and lateral placement shall be as specified in Part 2.**

**On shared-use paths, lateral sign clearance shall be a minimum of 0.9 m (3 ft) and a maximum of 1.8 m (6 ft) from the near edge of the sign to the near edge of the path (see Figure 9B-1).**

**Mounting height for ground-mounted signs on shared-use paths shall be a minimum of 1.2 m (4 ft) and a maximum of 1.5 m (5 ft), measured from the bottom edge of the sign to the near edge of the path surface (see Figure 9B-1).**

**When overhead signs are used on shared-use paths, the clearance from the bottom edge of the sign to the path surface directly under the sign shall be a minimum of 2.4 m (8 ft).**

#### Guidance:

Signs for the exclusive use of bicyclists should be located so that other road users are not confused by them.

The clearance for overhead signs on shared-use paths should be adjusted when appropriate to accommodate typical maintenance vehicles.

### Section 9B.02 Design of Bicycle Signs

#### Standard:

**If the sign applies to motorists and bicyclists, then the size shall be as shown for conventional roads in Table 2B-1.**

**The minimum sign sizes for shared-use paths shall be those shown in Table 9B-1, and shall be used only for signs installed specifically for bicycle traffic applications. The minimum sign sizes for bicycle facilities shall not be used for signs that are placed in a location that would have any application to other vehicles.**

#### Option:

Larger size signs may be used on bicycle facilities when appropriate.

#### Guidance:

Except for size, the design of signs for bicycle facilities should be identical to that specified in this Manual for vehicular travel.

#### Support:


Uniformity in design includes shape, color, symbols, wording, lettering, and illumination or retroreflectorization.

### Section 9B.03 STOP and YIELD Signs (R1-1, R1-2)

#### Standard:

**STOP (R1-1) signs (see Figure 9B-2) shall be installed on shared-use paths at points where bicyclists are required to stop.**

**Figure 9B-1. Sign Placement on Shared-Use Paths**



**YIELD (R1-2) signs (see Figure 9B-2) shall be installed on shared-use paths at points where bicyclists have an adequate view of conflicting traffic as they approach the sign, and where bicyclists are required to yield the right-of-way to that conflicting traffic.**

Option:

A 750 x 750 mm (30 x 30 in) STOP sign or a 900 x 900 x 900 mm (36 x 36 x 36 in) YIELD sign may be used on shared-use paths for added emphasis.

Guidance:

Where conditions require path users, but not roadway users, to stop or yield, the STOP sign or YIELD sign should be placed or shielded so that it is not readily visible to road users.

When placement of STOP or YIELD signs is considered, priority at a shared-use path/roadway intersection should be assigned with consideration of the following:

- A. Relative speeds of shared-use path and roadway users;
- B. Relative volumes of shared-use path and roadway traffic; and
- C. Relative importance of shared-use path and roadway.

Speed should not be the sole factor used to determine priority, as it is sometimes appropriate to give priority to a high-volume shared-use path crossing a low-volume street, or to a regional shared-use path crossing a minor collector street.

When priority is assigned, the least restrictive control that is appropriate should be placed on the lower priority approaches. STOP signs should not be used where YIELD signs would be acceptable.

#### **Section 9B.04 Bicycle Lane Signs (R3-17, R3-17a, R3-17b)**

**Standard:**

The **BIKE LANE (R3-17) sign (see Figure 9B-2) shall be used only in conjunction with marked bicycle lanes as described in Section 9C.04, and shall be placed at periodic intervals along the bicycle lanes.**


**Table 9B-1. Minimum Sign Sizes for Bicycle Facilities (Sheet 1 of 2)**

Sign	Sign Code	Minimum Sign Size – mm (in)	
		Shared-Use Path	Roadway
STOP	R1-1	450 x 450 (18 x 18)	750 x 750 (30 x 30)
YIELD	R1-2	450 x 450 x 450 (18 x 18 x 18)	750 x 750 x 750 (30 x 30 x 30)
BIKE LANE	R3-17	—	750 x 600 (30 x 24)
Bicycle Lane Supplemental Plaques	R3-17a,b	—	750 x 300 (30 x 12)
Movement Restriction	R4-1, 2, 3, 7	300 x 450 (12 x 18)	450 x 600 (18 x 24)
BEGIN RIGHT TURN LANE YIELD TO BIKES	R4-4	—	900 x 750 (36x 30)
Bicycle WRONG WAY	R5-1b	300 x 450 (12 x 18)	300 x 450 (12x 18)
NO MOTOR VEHICLES	R5-3	600 x 600 (24 x 24)	600 x 600 (24 x 24)
No Bicycles	R5-6	600 x 600 (24 x 24)	600 x 600 (24 x 24)
NO PARKING BIKE LANE	R7-9, 9a	—	300 x 450 (12 x 18)
Pedestrians Prohibited	R9-3a	450 x 450 (18 x 18)	450 x 450 (18 x 18)
RIDE WITH TRAFFIC Plaque	R9-3c	300 x 300 (12 x 12)	300 x 300 (12 x 12)
Bicycle Regulatory	R9-5,6	300 x 450 (12 x 18)	300 x 450 (12 x 18)
Shared-Use Path Restriction	R9-7	300 x 450 (12 x 18)	—
PUSH BUTTON FOR GREEN LIGHT	R10-3	225 x 300 (9 x 12)	225 x 300 (9 x 12)
TO REQUEST GREEN WAIT ON Symbol	R10-22	300 x 450 (12 x 18)	300 x 450 (12 x 18)
Railroad Crossbuck	R15-1	600 x 112 (24 x 4.5)	1200 x 225 (48 x 9)
Turn and Curve Warning	W1-1, 2, 3, 4, 5	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Arrow Warning	W1-6, 7	600 x 300 (24 x 12)	900 x 450 (36 x 18)
Intersection Warning	W2-1, 2, 3, 4, 5	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Stop, Yield, Signal Ahead	W3-1, 2, 3	450 x 450 (18 x 18)	750 x 750 (30 x 30)
NARROW BRIDGE	W5-2	450 x 450 (18 x 18)	750 x 750 (30 x 30)
BIKEWAY NARROWS	W5-4a	450 x 450 (18 x 18)	750 x 750 (30 x 30)

**Table 9B-1. Minimum Sign Sizes for Bicycle Facilities (Sheet 2 of 2)**

Sign	Sign Code	Minimum Sign Size – mm (in)	
		Shared-Use Path	Roadway
Hill	W7-5	450 x 450 (18 x 18)	600 x 600 (24 x 24)
BUMP or DIP	W8-1,2	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Bicycle Surface Condition	W8-10	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Bicycle Surface Condition Plaque	W8-10p	300 x 225 (12 x 9)	300 x 225 (12 x 9)
Advance Grade Crossing	W10-1	375 Dia. (15 Dia.)	375 Dia. (15 Dia.)
Bicycle Warning	W11-1	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Pedestrian Crossing	W11-2	450 x 450 (18 x 18)	600 x 600 (24 x 24)
Low Clearance	W12-2	450 x 450 (18 x 18)	750 x 750 (30 x 30)
Playground	W15-1	450 x 450 (18 x 18)	600 x 600 (24 x 24)
SHARE THE ROAD Plaque	W16-1	—	450 x 600 (18 x 24)
Diagonal Arrow Plaque	W16-7p	—	600 x 300 (24 x 12)
Bicycle Guide	D1-1b	600 x 150 (24 x 6)	600 x 150 (24 x 6)
Street Name	D1-1c	450 x 150 (18 x 6)	450 x 150 (18 x 6)
Bicycle Parking	D4-3	300 x 450 (12 x 18)	300 x 450 (12 x 18)
Bike Route	D11-1	600 x 450 (24 x 18)	600 x 450 (24 x 18)
Bicycle Route Sign	M1-8	300 x 450 (12 x 18)	300 x 450 (12 x 18)
Interstate Bicycle Route Sign	M1-9	450 x 600 (18 x 24)	450 x 600 (18 x 24)
Bicycle Route Supplemental Plaques	M4-11,12,13	300 x 100 (12 x 4)	300 x 100 (12 x 4)
Route Sign Supplemental Plaques	M7-1, 2, 3, 4, 5, 6, 7	300 x 225 (12 x 9)	300 x 225 (12 x 9)

**Figure 9B-2. Regulatory Signs for Bicycle Facilities**



**Guidance:**

The BIKE LANE (R3-17) sign spacing should be determined by engineering judgment based on prevailing speed of bicycle and other traffic, block length, distances from adjacent intersections, and other considerations.

The AHEAD (R3-17a) sign (see Figure 9B-2) should be mounted directly below a R3-17 sign in advance of the beginning of a marked bicycle lane.

The ENDS (R3-17b) sign (see Figure 9B-2) should be mounted directly below a R3-17 sign at the end of a marked bicycle lane.

**Section 9B.05 BEGIN RIGHT TURN LANE YIELD TO BIKES Sign (R4-4)****Option:**

Where motor vehicles entering an exclusive right-turn lane must weave across bicycle traffic in bicycle lanes, the BEGIN RIGHT TURN LANE YIELD TO BIKES (R4-4) sign (see Figure 9B-2) may be used to inform both the motorist and the bicyclist of this weaving maneuver.

**Guidance:**

The R4-4 sign should not be used when bicyclists need to move left because of a right-turn lane drop situation.

**Section 9B.06 Bicycle WRONG WAY Sign and RIDE WITH TRAFFIC Plaque (R5-1b, R9-3c)****Option:**

The Bicycle WRONG WAY (R5-1b) sign and RIDE WITH TRAFFIC (R9-3c) plaque (see Figure 9B-2) may be placed facing wrong-way bicycle traffic, such as on the left side of a roadway.

This sign and plaque may be mounted back-to-back with other signs to minimize visibility to other traffic.

**Guidance:**

The RIDE WITH TRAFFIC plaque should be used only in conjunction with the Bicycle WRONG WAY sign, and should be mounted directly below the Bicycle WRONG WAY sign.

**Section 9B.07 NO MOTOR VEHICLES Sign (R5-3)****Standard:**

**The NO MOTOR VEHICLES (R5-3) sign (see Figure 9B-2) shall be installed at the entrance to a shared-use path.**

**Section 9B.08 No Bicycles Sign (R5-6)****Guidance:**

Where bicyclists are prohibited, the No Bicycles (R5-6) sign (see Figure 9B-2) should be installed at the entrance to the facility.

**Option:**

When used on a sidewalk, the No Bicycles (R5-6) sign may be 450 x 450 mm (18 x 18 inches).

Where pedestrians and motor-driven cycles are also prohibited, it may be more desirable to use the R5-10a word message sign that is described in Section 2B.36.

**Section 9B.09 No Parking BIKE LANE Signs (R7-9, R7-9a)****Standard:**

**If the installation of signs is necessary to restrict parking, standing, or stopping in a bicycle lane, appropriate signs as described in Sections 2B.39 through 2B.41, or the No Parking Bike Lane (R7-9 or R7-9a) signs (see Figure 9B-2) shall be installed.**

**Section 9B.10 Bicycle Regulatory Signs (R9-5, R9-6, R10-3)****Option:**

The R9-5 sign (see Figure 9B-2) may be used where the crossing of a street by bicyclists is controlled by pedestrian signal indications.

Where it is not intended for bicyclists to be controlled by pedestrian signal indications, the R10-3 sign (see Figure 9B-2 and Section 2B.45) may be used.

The R9-6 sign (see Figure 9B-2) may be used where a bicyclist is required to cross or share a facility used by pedestrians and is required to yield to the pedestrians.

**Guidance:**

If used, the R9-5 or R10-3 signs should be installed near the edge of the sidewalk, in the vicinity of where bicyclists will be crossing the street.

**Section 9B.11 Shared-Use Path Restriction Sign (R9-7)****Option:**

The Shared-Use Path Restriction (R9-7) sign (see Figure 9B-2) may be installed on facilities that are to be shared by pedestrians and bicyclists. The symbols may be switched as appropriate.

A designated pavement area may be provided for each mode of travel (see Section 9C.03).

**Section 9B.12 Bicycle Signal Actuation Sign (R10-22)****Option:**

The Bicycle Signal Actuation (R10-22) sign (see Figure 9B-2) may be installed at signalized intersections where markings are used to indicate the location where a bicyclist is to be positioned to actuate the signal (see Section 9C.05).

**Guidance:**

If the Bicycle Signal Actuation sign is installed, it should be placed at the roadside adjacent to the marking to emphasize the connection between the marking and the sign.

**Section 9B.13 Other Regulatory Signs****Option:**

Other regulatory signs described in Chapter 2B may be installed on bicycle facilities as appropriate.

**Section 9B.14 Turn or Curve Warning Signs (W1 Series)****Guidance:**

To warn bicyclists of unexpected changes in shared-use path direction, appropriate turn or curve (W1-1 through W1-7) signs (see Figure 9B-3) should be used.

The W1-1 through W1-5 signs should be installed no less than 15 m (50 ft) in advance of the beginning of the change of alignment.

**Figure 9B-3. Warning Signs for Bicycle Facilities (Sheet 1 of 2)**



W1-1



W1-2



W1-3



W1-4



W1-5



W1-6



W1-7



W2-1



W2-2



W2-3



W2-4



W2-5



W3-1



W3-2



W3-3



W5-2



W5-4a



W7-5



W8-1



W8-2



W8-10




W8-10p



W10-1

**Figure 9B-3. Warning Signs for Bicycle Facilities (Sheet 2 of 2)**



### **Section 9B.15 Intersection Warning Signs (W2 Series)**

Option:

Intersection Warning (W2-1 through W2-5) signs (see Figure 9B-3) may be used on a roadway, street, or shared-use path in advance of an intersection to indicate the presence of an intersection and the possibility of turning or entering traffic.

Guidance:

When engineering judgment determines that the visibility of the intersection is limited on the shared-use path approach, Intersection Warning signs should be used.

Intersection Warning signs should not be used where the shared-use path approach to the intersection is controlled by a STOP sign, YIELD sign, or a traffic control signal.

### **Section 9B.16 Bicycle Surface Condition Warning Sign (W8-10)**

Option:

The Bicycle Surface Condition Warning (W8-10) sign (see Figure 9B-3) may be installed where roadway or shared-use path conditions could cause a bicyclist to lose control of the bicycle.

Signs warning of other conditions that might be of concern to bicyclists, including BUMP (W8-1), DIP (W8-2), PAVEMENT ENDS (W8-3), and any other word message that describes conditions that are of concern to bicyclists, may also be used.

A supplemental plaque may be used to clarify the specific type of surface condition.

### **Section 9B.17 Bicycle Warning Sign (W11-1)**

#### Support:

The Bicycle Warning (W11-1) sign (see Figure 9B-3) alerts the road user to unexpected entries into the roadway by bicyclists, and other crossing activities that might cause conflicts. These conflicts might be relatively confined, or might occur randomly over a segment of roadway.

#### Option:

A supplemental plaque with the legend AHEAD or XXX FEET may be used with the Bicycle Warning sign.

#### Guidance:

If used in advance of a specific crossing point, the Bicycle Warning sign should be placed at a distance in advance of the crossing location that conforms with the guidance given in Table 2C-4.

#### Standard:

**Bicycle Warning signs, when used at the location of the crossing, shall be supplemented with a diagonal downward pointing arrow (W16-7p) plaque (see Figure 9B-3) to show the location of the crossing.**

#### Option:

A fluorescent yellow-green background color with a black legend and border may be used for Bicycle Warning signs and supplemental plaques.

#### Guidance:

When the fluorescent yellow-green background color is used, a systematic approach featuring one background color within a zone or area should be used. The mixing of standard yellow and fluorescent yellow-green backgrounds within a zone or area should be avoided.

### **Section 9B.18 Other Bicycle Warning Signs**

#### Option:

Other bicycle warning signs (see Figure 9B-3) such as BIKEWAY NARROWS (W5-4a) and Hill (W7-5) may be installed on bicycle facilities to warn bicyclists of conditions not readily apparent.

In situations where there is a need to warn motorists to watch for bicyclists traveling along the highway, the SHARE THE ROAD (W16-1) plaque (see Figure 9B-3) may be used in conjunction with the W11-1 sign.

#### Guidance:

If used, other advance bicycle warning signs should be installed no less than 15 m (50 ft) in advance of the beginning of the condition.

Where temporary traffic control zones are present on bikeways, appropriate signs from Part 6 should be used.

#### Option:


Other warning signs described in Chapter 2C may be installed on bicycle facilities as appropriate.

### **Section 9B.19 Bicycle Route Guide Signs (D11-1)**

#### Guidance:

If used, Bicycle Route Guide (D11-1) signs (see Figure 9B-4) should be provided at decision points along designated bicycle routes, including signs to inform bicyclists of bicycle route direction changes and confirmation signs for route direction, distance, and destination.

**Figure 9B-4. Guide Signs for Bicycle Facilities**



If used, Bicycle Route Guide signs should be repeated at regular intervals so that bicyclists entering from side streets will have an opportunity to know that they are on a bicycle route. Similar guide signing should be used for shared roadways with intermediate signs placed for bicyclist guidance.

Support:

Figure 9B-5 shows an example of the signing for the beginning and end of a designated bicycle route on a shared-use path. Figure 9B-6 shows an example of signing for an on-roadway bicycle route. Figure 9B-7 shows examples of signing and markings for shared-use paths.

**Section 9B.20 Bicycle Route Signs (M1-8, M1-9)**


Option:

To establish a unique identification (route designation) for a State or local bicycle route, the Bicycle Route (M1-8) sign (see Figure 9B-4) may be used.


**Standard:**

**The Bicycle Route sign shall contain a route designation and shall have a green background with a retroreflectorized white legend and border.**


**Figure 9B-5. Example of Signing for the Beginning and End of a Designated Bicycle Route on a Shared-Use Path**



**Figure 9B-6. Example of Signing for an On-Roadway Bicycle Route**



**Figure 9B-7. Examples of Signing and Markings for Shared-Use Paths**



**Option:**

Where a designated bicycle route extends for long distances through two or more States, a coordinated submittal by the affected States for an assignment of an Interstate Bicycle Route number designation may be sent to the American Association of State Highway and Transportation Officials (see the Preface for the address).

**Standard:**

**The Interstate Bicycle Route (M1-9) sign (see Figure 9B-4) shall contain the assigned route number designation and have a black legend and border with a retroreflectorized white background.**

**Guidance:**

If used, the Bicycle Route or Interstate Bicycle Route signs should be placed at intervals frequent enough to keep bicyclists informed of changes in route direction and to remind motorists of the presence of bicyclists.

**Option:**

Bicycle Route or Interstate Bicycle Route signs may be installed on shared roadways or on shared-use paths to provide guidance for bicyclists.

The Bicycle Route Guide (D11-1) sign (see Figure 9B-4) may be installed where no unique designation of routes is desired.

**Section 9B.21 Destination Arrow and Supplemental Plaque Signs for Bicycle Route Signs****Option:**

Destination (D1-1b and D1-1c) signs (see Figure 9B-4) may be mounted below Bicycle Route Guide signs, Bicycle Route signs, or Interstate Bicycle Route signs to furnish additional information, such as directional changes in the route, or intermittent distance and destination information.

The M4-11 through M4-13 supplemental plaques (see Figure 9B-4) may be mounted above the appropriate Bicycle Route Guide signs, Bicycle Route signs, or Interstate Bicycle Route signs.

**Guidance:**

If used, the appropriate arrow (M7-1 through M7-7) sign (see Figure 9B-4) should be placed below the Bicycle Route Guide sign, Bicycle Route sign, or Interstate Bicycle Route sign.

**Standard:**

**The arrow signs and supplemental plaques used with the D11-1 or M1-8 signs shall have a white legend and border on a green background.**

**The arrow signs and supplemental plaques used with the M1-9 sign shall have a white legend and border on a black background.**

**Section 9B.22 Bicycle Parking Area Sign (D4-3)****Option:**

The Bicycle Parking Area (D4-3) sign (see Figure 9B-4) may be installed where it is desirable to show the direction to a designated bicycle parking area. The arrow may be reversed as appropriate.

**Standard:**

**The legend and border of the Bicycle Parking Area sign shall be green on a retroreflectorized white background.**

Intentionally blank.

## CHAPTER 9C. MARKINGS

### **Section 9C.01 Functions of Markings**

Support:

Markings indicate the separation of the lanes for road users, assist the bicyclist by indicating assigned travel paths, indicate correct position for traffic control signal actuation, and provide advance information for turning and crossing maneuvers.

### **Section 9C.02 General Principles**

Guidance:

Bikeway design guides should be used when designing markings for bicycle facilities (see Section 9A.05).

**Standard:**

**Markings used on bikeways shall be retroreflectorized.**

Guidance:

Pavement marking symbols and/or word messages should be used in bikeways where appropriate. Consideration should be given to selecting pavement marking materials that will minimize loss of traction for bicycles under wet conditions.

**Standard:**

**Except as specified in the first Option in Section 9C.03, the colors, width of lines, patterns of lines, and symbols used for marking bicycle facilities shall be as defined in Sections 3A.04, 3A.05, and 3B.22.**

Support:

Figures 9B-7 and 9C-1 through 9C-8 show examples of the application of lines, word messages, and symbols on designated bikeways.

Option:

A dotted line may be used to define a specific path for a bicyclist crossing an intersection (see Figure 9C-1) as described in Sections 3A.05 and 3B.08.

### **Section 9C.03 Marking Patterns and Colors on Shared-Use Paths**

Option:

Where shared-use paths are of sufficient width to designate two minimum width lanes, a solid yellow line may be used to separate the two directions of travel where passing is not permitted, and a broken yellow line may be used where passing is permitted (see Figure 9C-2).

If used, edge lines on a shared-use path may be 50 to 100 mm (2 to 4 in) wide. A stop line, when used on a shared-use path, at a roadway intersection may be 300 mm (12 in) wide.

Guidance:

Broken lines used on shared-use paths should have the usual 1-to-3 segment-to-gap ratio. A nominal 0.9 m (3 ft) segment with a 2.7 m (9 ft) gap should be used.

If conditions make it desirable to separate two directions of travel on shared-use paths at particular locations, a solid yellow line should be used to indicate no passing and no traveling to the left of the line.

Markings as shown in Figure 9C-2 should be used at the location of obstructions in the center of the path, including vertical elements intended to physically prevent unauthorized motor vehicles from entering the path.

**Option:**

A solid white line may be used on shared-use paths to separate different types of users. The R9-7 sign (see Figure 9B-2) may be used to supplement the solid white line.

Smaller size letters and symbols may be used on shared-use paths. Where arrows are needed on shared-use paths, half-size layouts of the arrows may be used (see Section 3B.19).

Fixed objects adjacent to shared-use paths may be marked with object markers (Type 1, 2, or 3). The size of Type 2 and Type 3 object markers may be reduced when placed along bicycle paths.


**Standard:**

**All object markers shall be retroreflective.**

**Markers such as those described in Section 3C.01 shall also be used on shared-use paths, if needed.**

**Obstructions in the traveled way of a shared-use path shall be marked with retroreflectorized material or appropriate object markers.**

**On Type 3 markers, the alternating black and retroreflective yellow stripes shall be sloped down at an angle of 45 degrees toward the side on which traffic is to pass the obstruction. See Section 3C.01 for additional information about these object markers.**



Type 1



Type 2



Type 3

**Section 9C.04 Markings For Bicycle Lanes****Guidance:**

Longitudinal pavement markings should be used to define bicycle lanes.

**Support:**

Pavement markings designate that portion of the roadway for preferential use by bicyclists. Markings inform all road users of the restricted nature of the bicycle lane.

Examples of bicycle lane markings at right-turn lanes are shown in Figures 9C-1, 9C-3, and 9C-4. Examples of pavement markings for bicycle lanes on a two-way street are shown in Figure 9C-5. Pavement symbols and markings for bicycle lanes are shown in Figure 9C-6.

**Standard:**

**If used, the bicycle lane symbol marking (see Figure 9C-6) shall be placed immediately after an intersection and at other locations as needed. The bicycle lane symbol marking shall be white. If the bicycle lane symbol marking is used in conjunction with other word or symbol messages, it shall precede them.**

**If the word or symbol pavement markings shown in Figure 9C-6 are used, Bicycle Lane signs (see Section 9B.04) shall also be used, but the signs need not be adjacent to every symbol to avoid overuse of the signs.**

**A through bicycle lane shall not be positioned to the right of a right turn only lane.**

## Support:

A bicyclist continuing straight through an intersection from the right of a right turn lane would be inconsistent with normal traffic behavior and would violate the expectations of right-turning motorists.

## Guidance:

When the right through lane is dropped to become a right turn only lane, the bicycle lane markings should stop at least 30 m (100 ft) before the beginning of the right turn lane. Through bicycle lane markings should resume to the left of the right turn only lane.

An optional through-right turn lane next to a right turn only lane should not be used where there is a through bicycle lane. If a capacity analysis indicates the need for an optional through-right turn lane, the bicycle lane should be discontinued at the intersection approach.

Posts or raised pavement markers should not be used to separate bicycle lanes from adjacent travel lanes.

## Support:

Using raised devices creates a collision potential for bicyclists by placing fixed objects immediately adjacent to the travel path of the bicyclist. In addition, raised devices can prevent vehicles turning right from merging with the bicycle lane, which is the preferred method for making the right turn. Raised devices used to define a bicycle lane can also cause problems in cleaning and maintaining the bicycle lane.

**Standard:**

**Bicycle lanes shall not be provided on the circular roadway of a roundabout intersection.**

**Section 9C.05 Bicycle Detector Symbol**

## Option:

A symbol (see Figure 9C-7) may be placed on the pavement indicating the optimum position for a bicyclist to actuate the signal.


An R10-22 sign (see Section 9B.12 and Figure 9B-2) may be installed to supplement the pavement marking.

**Section 9C.06 Pavement Markings for Obstructions**


## Guidance:

In roadway situations where it is not practical to eliminate a drain grate or other roadway obstruction that is inappropriate for bicycle travel, white markings applied as shown in Figure 9C-8 should be used.


**Figure 9C-1. Example of Intersection Pavement Markings—Designated Bicycle Lane with Left-Turn Area, Heavy Turn Volumes, Parking, One-Way Traffic, or Divided Highway**




**Figure 9C-2. Examples of Centerline Markings for Shared-Use Paths**




**Figure 9C-3. Example of Bicycle Lane Treatment at a Right Turn Only Lane**




**Figure 9C-4. Example of Bicycle Lane Treatment at Parking Lane into a Right Turn Only Lane**




**Figure 9C-5. Example of Pavement Markings for Bicycle Lanes on a Two-Way Street**




**Figure 9C-6. Example of Optional Word and Symbol Pavement Markings for Bicycle Lanes**



**Figure 9C-7. Example of Bicycle Detector Pavement Marking**



**Figure 9C-8. Example of Obstruction Pavement Marking**



For metric units:

$L \text{ (m)} = 0.6 WS$ , where  $W$  is the width in meters and  $S$  is the bicycle approach speed in kilometers per hour

For English units:

$L \text{ (ft)} = WS$ , where  $W$  is the width in feet and  $S$  is the bicycle approach speed in miles per hour

Intentionally blank.

## CHAPTER 9D. SIGNALS

### Section 9D.01 Application

#### Support:

Part 4 contains information regarding signal warrants and other requirements relating to signal installations.

#### Option:

For purposes of signal warrant evaluation, bicyclists may be counted as either vehicles or pedestrians.

### Section 9D.02 Signal Operations for Bicycles

#### Standard:

**At installations where visibility-limited signal faces are used, signal faces shall be adjusted so bicyclists for whom the indications are intended can see the signal indications. If the visibility-limited signal faces cannot be aimed to serve the bicyclist, then separate signal faces shall be provided for the bicyclist.**

**On bikeways signal timing and actuation shall be reviewed and adjusted to consider the needs of bicyclists.**

Intentionally blank.

**PART 10. TRAFFIC CONTROLS FOR HIGHWAY-  
LIGHT RAIL TRANSIT GRADE CROSSINGS**

**TABLE OF CONTENTS**

	<u>Page</u>
<b>CHAPTER 10A. GENERAL</b>	
Section 10A.01 Introduction.....	10A-1
Section 10A.02 Use of Standard Devices, Systems, and Practices .....	10A-1
Section 10A.03 Uniform Provisions.....	10A-2
Section 10A.04 Highway-Light Rail Transit Grade Crossing Elimination .....	10A-2
Section 10A.05 Temporary Traffic Control Zones.....	10A-3
<b>CHAPTER 10B. HIGHWAY-LIGHT RAIL TRANSIT GRADE CROSSING CONTROL SYSTEMS</b>	
Section 10B.01 Introduction.....	10B-1
<b>CHAPTER 10C. SIGNS, ILLUMINATION, AND MARKINGS</b>	
Section 10C.01 Purpose.....	10C-1
Section 10C.02 Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1) and Number of Tracks Sign (R15-2).....	10C-1
Section 10C.03 LOOK Sign (R15-8) .....	10C-2
Section 10C.04 STOP (R1-1) or YIELD (R1-2) Signs at Highway-Light Rail Transit Grade Crossings.....	10C-4
Section 10C.05 DO NOT STOP ON TRACKS Sign (R8-8) .....	10C-4
Section 10C.06 TRACKS OUT OF SERVICE Sign (R8-9) .....	10C-5
Section 10C.07 STOP HERE ON RED Sign (R10-6).....	10C-5
Section 10C.08 STOP HERE WHEN FLASHING Sign (R8-10).....	10C-5
Section 10C.09 Light Rail Transit-Activated Blank-Out Turn Prohibition Signs (R3-1a, R3-2a) .....	10C-5
Section 10C.10 EXEMPT Highway-Rail Grade Crossing Signs (R15-3, W10-1a).....	10C-6
Section 10C.11 Divided Highway With Light Rail Transit Crossing Signs (R15-7 Series).....	10C-6
Section 10C.12 No Vehicles On Tracks Signs (R15-6, R15-6a).....	10C-6
Section 10C.13 Light Rail Transit Only Lane Signs (R15-4 Series) .....	10C-7
Section 10C.14 Do Not Pass Light Rail Transit Signs (R15-5, R15-5a).....	10C-7
Section 10C.15 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series).....	10C-8
Section 10C.16 Low Ground Clearance Highway-Rail Grade Crossing Sign (W10-5) .....	10C-8
Section 10C.17 Light Rail Transit Approaching-Activated Blank-Out Warning Sign (W10-7).....	10C-9
Section 10C.18 Storage Space Signs (W10-11, W10-11a, W10-11b) .....	10C-9
Section 10C.19 Skewed Crossing Sign (W10-12).....	10C-10
Section 10C.20 Light Rail Transit Station Sign (I-12).....	10C-10
Section 10C.21 Emergency Notification Sign (I-13 or I-13a).....	10C-10
Section 10C.22 Illumination at Highway-Light Rail Transit Crossings .....	10C-10
Section 10C.23 Pavement Markings .....	10C-10
Section 10C.24 Stop Lines .....	10C-11
Section 10C.25 Dynamic Envelope Markings.....	10C-11
<b>CHAPTER 10D. HIGHWAY-LIGHT RAIL TRANSIT ACTIVE TRAFFIC CONTROL GRADE CROSSING SYSTEMS</b>	
Section 10D.01 Introduction.....	10D-1
Section 10D.02 Flashing-Light Signals .....	10D-1

Section 10D.03	Automatic Gates .....	10D-1
Section 10D.04	Four-Quadrant Gate Systems.....	10D-2
Section 10D.05	Traffic Control Signals .....	10D-3
Section 10D.06	Highway Traffic Signal Preemption Turning Restrictions.....	10D-4
Section 10D.07	Use of Traffic Control Signals for Control of Light Rail Transit Vehicles at Grade Crossings.....	10D-5
Section 10D.08	Pedestrian and Bicycle Signals and Crossings .....	10D-7

## **FIGURES**

### **CHAPTER 10C. SIGNS, ILLUMINATION, AND MARKINGS**

Figure 10C-1	Highway-Rail Grade Crossing (Crossbuck) Regulatory Signs.....	10C-2
Figure 10C-2	Regulatory Signs.....	10C-3
Figure 10C-3	Warning Signs and Light Rail Station Sign.....	10C-9
Figure 10C-4	Examples of Emergency Notification Signs.....	10C-11
Figure 10C-5	Example of Placement of Warning Signs and Pavement Markings at Highway-Light Rail Transit Grade Crossings .....	10C-13
Figure 10C-6	Examples of Highway-Light Rail Transit Grade Crossing Pavement Markings .....	10C-14
Figure 10C-7	Light Rail Transit Vehicle Dynamic Envelope .....	10C-15
Figure 10C-8	Typical Light Rail Transit Vehicle Dynamic Envelope Pavement Markings ..	10C-15
Figure 10C-9	Example of Light Rail Transit Vehicle Dynamic Envelope Pavement Markings .....	10C-16
Figure 10C-10	Example of Light Rail Transit Vehicle Dynamic Envelope Contrasting Color and/or Texture .....	10C-16

### **CHAPTER 10D. HIGHWAY-LIGHT RAIL TRANSIT ACTIVE TRAFFIC CONTROL GRADE CROSSING SYSTEMS**

Figure 10D-1	Examples of Light Rail Transit Signals.....	10D-6
Figure 10D-2	Example of Light Rail Transit Flashing-Light Signal Assembly for Pedestrian Crossings.....	10D-8
Figure 10D-3	Example of Pedestrian Gate Placement Behind the Sidewalk.....	10D-9
Figure 10D-4	Example of Pedestrian Gate Placement with Pedestrian Gate Arm.....	10D-9
Figure 10D-5	Examples of Placement of Pedestrian Gates .....	10D-10
Figure 10D-6	Example of Swing Gates.....	10D-11
Figure 10D-7	Example of Pedestrian Barriers at an Offset Highway-Light Rail Transit Crossing .....	10D-11
Figure 10D-8	Examples of Pedestrian Barrier Installation at an Offset Nonintersection Light Rail Transit Crossing .....	10D-12

## CHAPTER 10A. GENERAL

### **Section 10A.01 Introduction**

Support:

Part 10 provides standards and guidelines for the design, installation, and operation of traffic control devices at grade crossings of highway traffic and light rail transit vehicles to facilitate the reasonably safe, orderly, and integrated movement of all traffic. The principles in Section 8A.01 are the same but, because light rail vehicles sometimes operate along streets and highways in mixed traffic with automotive vehicles, the traffic controls and associated standards and guidelines for highway-light rail transit grade crossings presented in Part 10 can be different than those presented in Part 8.

Light rail transit is a mode of metropolitan transportation that employs light rail transit vehicles (commonly known as light rail vehicles, streetcars, or trolleys) that operate on rails in streets in mixed traffic, in semiexclusive rights-of-way, or in exclusive rights-of-way. Grade crossings with light rail transit can occur at intersections or at midblock locations, including public and private driveways.

An initial educational campaign along with an ongoing program to continue to educate new drivers is beneficial when introducing light rail operations to an area and, hence, new traffic control devices.

Light rail alignments can be grouped into one of the following three types:

- A. **Exclusive:** A light rail transit right-of-way that is grade-separated or protected by a fence or traffic barrier. Motor vehicles, pedestrians, and bicycles are prohibited within the right-of-way. Subways and aerial structures are included within this group. This type of alignment does not have grade crossings and is not further addressed in Part 10.
- B. **Semiexclusive:** A light rail transit alignment that is in a separate right-of-way or along a street or railroad right-of-way where motor vehicles, pedestrians, and bicycles have limited access and cross at designated locations only.
- C. **Mixed-Use:** An alignment where light rail transit operates in mixed traffic with all types of road users. This includes streets, transit malls, and pedestrian malls where the right-of-way is shared.

**Standard:**

**Where light rail transit and railroads use the same tracks or adjacent tracks, the traffic control devices, systems, and practices for highway-rail grade crossings described in Part 8 shall be used.**

Support:

Section 8A.01 contains a set of definitions, most of which also apply to Part 10.

### **Section 10A.02 Use of Standard Devices, Systems, and Practices**

Support:

Because of the large number of significant variables to be considered, no single standard system of traffic control devices is universally applicable for all highway-light rail transit grade crossings.

Guidance:

The appropriate traffic control system to be used at a highway-light rail transit grade crossing should be determined by an engineering study conducted by the transit or highway agency in cooperation with other appropriate State and local organizations.

**Standard:**

**Traffic control devices, systems, and practices shall be consistent with the design and application of the Standards contained herein.**

**The traffic control devices, systems, and practices described herein shall be used at all highway-light rail transit grade crossings.**

**Before any new highway-light rail transit grade crossing traffic control system is installed or modifications are made to an existing system, approval shall be obtained from the local agencies having statutory authority to grant such approval.**

Guidance:

To stimulate effective responses from vehicle operators and pedestrians, these devices, systems, and practices should use the five basic considerations employed generally for traffic control devices and described fully in Section 1A.02: design, placement, operation, maintenance, and uniformity.

Support:

Many other details of highway-light rail transit grade crossing traffic control systems that are not set forth in Part 10 are contained in the publications listed in Section 1A.11.

### **Section 10A.03 Uniform Provisions**

**Standard:**

**All signs used in highway-light rail transit grade crossing traffic control systems shall be retroreflectorized or illuminated as described in Section 2A.08 to show the same shape and similar color to an approaching road user during both day and night.**

**No sign or signal shall be located in the center of an undivided highway, except in a raised island.**

Guidance:

Such signs or signals should be installed with a clearance of at least 0.6 m (2 ft) from outer edge of the raised island to the nearest edge of the sign or signal, except as allowed in Section 2A.19.

Where the distance between tracks, measured along the highway between the inside rails, exceeds 30 m (100 ft), additional signs or other appropriate traffic control devices should be used.

### **Section 10A.04 Highway-Light Rail Transit Grade Crossing Elimination**

Guidance:

Because highway-light rail transit grade crossings are a potential source of crashes and congestion, agencies should conduct engineering studies to determine the cost and benefits of eliminating these crossings.

**Standard:**

**When a highway-light rail transit grade crossing is eliminated, the traffic control devices for the crossing shall be removed.**

**If the existing traffic control devices at a multiple-track highway-light rail transit grade crossing become improperly placed or inaccurate because of the removal of some of the tracks, the existing devices shall be relocated and/or modified.**

Guidance:

Where a roadway is removed from a highway-light rail transit grade crossing, the roadway approaches in the light rail transit right-of-way should also be removed and appropriate signs should be placed at the roadway end in accordance with Section 3C.04.

Where light rail transit is eliminated at a highway-light rail transit grade crossing, the tracks should be removed or paved over.

Option:

Based on engineering judgment, the TRACKS OUT OF SERVICE (R8-9) sign (see Figure 10C-2) may be temporarily installed until the tracks are removed or paved over. The length of time before the tracks will be removed or paved over may be considered in making the decision as to whether to install the sign.

## **Section 10A.05 Temporary Traffic Control Zones**

### **Support:**

Temporary traffic control planning provides for continuity of operations (such as movement of traffic, pedestrians and bicycles, transit operations, and access to property/utilities) when the normal function of a roadway at a highway-light rail transit grade crossing is suspended because of temporary traffic control operations.

### **Standard:**

**Temporary traffic control operations on highways with highway-light rail transit grade crossings shall be as outlined in Part 6.**

**When a highway-light rail transit grade crossing exists either within or in the vicinity of a temporary traffic control zone, lane restrictions, flagging, or other operations shall not be performed in a manner that would cause vehicles to stop on the light rail transit tracks, unless a law enforcement officer or flagger is provided at the highway-light rail transit grade crossing to minimize the possibility of vehicles stopping on the tracks, even if automatic warning devices are in place.**

### **Guidance:**

The agencies responsible for the operation of the light rail transit and highway should be contacted when the initial planning begins for any temporary traffic control zone that may directly or indirectly influence the flow of traffic on mixed-use facilities where light rail transit and road users operate. Responsible agencies, along with others affected, such as emergency services and businesses, should meet to plan appropriate traffic detours and the necessary signing, marking, and flagging requirements for operations during temporary traffic control activities. Consideration should be given to the length of time that the grade crossing is to be closed, roadway classification, type of vehicle and traffic affected, the time of day, and the materials and techniques of repair.

Temporary traffic control operations should minimize the inconvenience, delay, and crash potential to affected traffic. Prior notice should be given to affected public or private parties, emergency services, businesses, and road users before the free movement of vehicles or light rail transit is infringed on or blocked.

Temporary traffic control activities should not be permitted to extensively prolong the closing of a grade crossing.

The width, grade, alignment, and riding quality of the highway surface at a light rail transit crossing should, at a minimum, be restored to correspond with the quality of the approaches to the highway-light rail transit grade crossing.

Intentionally blank.

## CHAPTER 10B. HIGHWAY-LIGHT RAIL TRANSIT GRADE CROSSING CONTROL SYSTEMS

### Section 10B.01 Introduction

#### Support:

The combination of devices selected or installed at a specific highway-light rail transit grade crossing is referred to as a Light Rail Transit Traffic Control System.

For the safety and integrity of operations by highway and light rail transit users, the highway agency with jurisdiction, the regulatory agency with statutory authority, if applicable, and the light rail transit authority jointly determine the need and selection of traffic control devices and the assignment of priority to light rail transit at a highway-light rail transit grade crossing. See Sections 4951.02 and 4951.14 of the Ohio Revised Code (see Appendix B2).

The normal rules of the road and traffic control priority identified in the Uniform Vehicle Code govern the order assigned to the movement of vehicles at an intersection unless the local agency determines that it is appropriate to assign a higher priority to light rail transit. Examples of different types of light rail transit priority control include separate traffic control signal phases for light rail transit movements, restriction of movement of roadway vehicles in favor of light rail transit operations, and preemption of highway traffic signal control to accommodate light rail transit movements.

#### Standard:

**Highway-light rail transit grade crossings in semiexclusive alignments shall be equipped with a combination of automatic gates and flashing-light signals, or flashing-light signals only, or traffic control signals, unless an engineering study indicates that the use of STOP, YIELD, or advance warning signs alone would be adequate.**

#### Option:

Highway-light rail transit grade crossings in mixed-use alignments may be equipped with traffic control signals unless an engineering study indicates that the use of STOP, YIELD, or advance warning signs alone would be adequate.

#### Support:

Section 10C.04 describes the appropriate conditions for the use of STOP or YIELD signs alone at a highway-light rail transit grade crossing.

Intentionally blank.

## CHAPTER 10C. SIGNS, ILLUMINATION, AND MARKINGS

### Section 10C.01 Purpose

Support:

Signs and markings regulate, warn, and guide the road users so that they, as well as light rail transit vehicle operators, can take appropriate action.

**Standard:**

**The design and location of signs shall conform to Part 2.**

Support:

Section 8B.02 contains information regarding the sizes of signs for grade crossings.

### Section 10C.02 Highway-Rail Grade Crossing (Crossbuck) Sign (R15-1) and Number of Tracks Sign (R15-2)

**Standard:**

**The Highway-Rail Grade Crossing (R15-1) sign, commonly identified as the Crossbuck sign, shall be retroreflectorized white with the words RAILROAD CROSSING in black lettering, mounted as shown in Figure 10C-1.**

**As a minimum, one Crossbuck sign shall be used on each highway approach to every highway-light rail transit grade crossing on a semiexclusive alignment, alone or in combination with other traffic control devices.**

Option:

A Crossbuck sign may be used on a highway approach to a highway-light rail transit grade crossing on a mixed-use alignment, alone or in combination with other traffic control devices.

**Standard:**

**If automatic gates are not present where a Crossbuck sign is being used and if there are two or more tracks at the highway-light rail transit grade crossing, the number of tracks shall be indicated on a supplemental Number of Tracks (R15-2) sign of inverted T shape mounted below the Crossbuck sign in the manner and at the height indicated in Figure 10C-1.**

Option:

The supplemental Number of Tracks sign may also be used at highway-light rail transit grade crossings with automatic gates.

**Standard:**

**If used, the Crossbuck sign shall be installed on the right side of the highway on each approach to the highway-light rail transit grade crossing. Where restricted sight distance or unfavorable highway geometry exists on an approach to a highway-light rail transit grade crossing, an additional Crossbuck sign shall be installed on the left side of the highway, possibly placed back-to-back with the Crossbuck sign for the opposite approach, or otherwise located so that two Crossbuck signs are displayed for that approach.**

**A strip of retroreflective white material not less than 50 mm (2 in) in width shall be used on the back of each blade of each Crossbuck sign for the length of each blade, at all highway-light rail transit grade crossings, except those where Crossbuck signs have been installed back-to-back.**

**A strip of retroreflective white material, not less than 50 mm (2 in) in width, shall be used on each support at passive highway-light rail transit grade crossings for the full length of the front and back of the support from the Crossbuck sign or Number of Tracks sign to within 0.6 m (2 ft) above the edge of the roadway, except on the side of those supports where a STOP (R1-1) or YIELD (R1-2) sign or**



**Figure 10C-2. Regulatory Signs**



R3-1a  
Activated Blank-Out



R3-2a  
Activated Blank-Out



R8-8




R8-9



R8-10



R10-6



R10-11a



R15-3



R15-4a



R15-4b



R15-4c



R15-5



R15-5a



R15-6




R15-6a



R15-7



R15-7a



R15-8

## **Section 10C.04 STOP (R1-1) or YIELD (R1-2) Signs at Highway-Light Rail Transit Grade Crossings**

### **Standard:**

For all highway-light rail transit grade crossings where STOP (R1-1) or YIELD (R1-2) signs are installed, the placement shall conform to the requirements of Sections 2B.06 and 2B.10. Stop Ahead (W3-1) or Yield Ahead (W3-2) Advance Warning signs (see Figure 2C-4) shall also be installed if the criteria for their installation given in Section 2C.29 is met.

### **Guidance:**

The use of STOP or YIELD signs for road users at highway-light rail transit grade crossings should be limited to those crossings where the need and feasibility is established by an engineering study. Such crossings should have all of the following characteristics:

- A. The crossing roadways should be secondary in character (such as a minor street with one lane in each direction, an alley, or a driveway) with low traffic volumes and low speed limits. The specific thresholds of traffic volumes and speed limits should be determined by the local agencies.
- B. Light rail transit speeds do not exceed 40 km/h (25 mph).
- C. The line of sight for an approaching light rail transit operator is adequate from a sufficient distance such that the operator can sound an audible signal and bring the light rail transit vehicle to a stop before arriving at the crossing.
- D. The road user has sufficient sight distance at the stop line to permit the vehicle to cross the tracks before the arrival of the light rail transit vehicle.
- E. If at an intersection of two roadways, the intersection does not meet the warrants for a traffic control signal as specified in Chapter 4C.
- F. The light rail transit tracks are located such that vehicles are not likely to stop on the tracks while waiting to enter a cross street or highway.

If a STOP or YIELD sign is installed beyond the light rail transit crossing such that vehicle queues are likely to extend into the path of the light rail transit, a DO NOT STOP ON TRACKS sign (R8-8) should be posted in accordance with Section 10C.05.

### **Option:**

If a STOP or YIELD sign is installed at a highway-light rail transit grade crossing, it may be installed on the Crossbuck post or on a separate post at the point where the vehicle is to stop, or as near to that point as practical.

## **Section 10C.05 DO NOT STOP ON TRACKS Sign (R8-8)**

### **Guidance:**

A DO NOT STOP ON TRACKS (R8-8) sign (see Figure 10C-2) should be installed whenever an engineering study determines that the potential for vehicles stopping on the tracks at a highway-light rail transit grade crossing is significant. Placement of the R8-8 sign should be determined as part of the engineering study. The sign, if used, should be located on the right side of the highway on either the near or far side of the grade crossing, depending upon which position provides better visibility to approaching drivers.

### **Option:**

DO NOT STOP ON TRACKS signs may be placed on both sides of the track.

On divided highways and one-way streets, a second DO NOT STOP ON TRACKS sign may be placed on the near or far left side of the highway at the grade crossing to further improve visibility of the sign.

**Section 10C.06 TRACKS OUT OF SERVICE Sign (R8-9)****Option:**

The TRACKS OUT OF SERVICE (R8-9) sign (see Figure 10C-2) may be used at a highway-light rail transit grade crossing instead of a Crossbuck (R15-1) sign and a Number of Tracks (R15-2) sign when light rail transit tracks have been temporarily or permanently abandoned, but only until such time that the tracks are removed or paved over.

**Standard:**

**When tracks are out of service, traffic control devices and gate arms shall be removed and the signal heads shall be removed or hooded or turned from view to clearly indicate that they are not in operation.**

**The R8-9 sign shall be removed when the tracks have been removed or covered or when the highway-light rail transit grade crossing is returned to service.**

**Section 10C.07 STOP HERE ON RED Sign (R10-6)****Support:**

The STOP HERE ON RED (R10-6) sign (see Figure 10C-2) defines and facilitates observance of the stop lines at traffic control signals.

**Option:**

A STOP HERE ON RED sign may be used at locations where vehicles frequently violate the stop line or where it is not obvious to road users where to stop.

**Guidance:**

If possible, stop lines should be placed at a point where the vehicle driver has adequate sight distance along the track.

**Section 10C.08 STOP HERE WHEN FLASHING Sign (R8-10)****Option:**

The STOP HERE WHEN FLASHING (R8-10) sign (see Figure 10C-2) may be used at a highway-light rail transit grade crossing to inform drivers of the location of the stop line or the point at which to stop when the flashing-light signals (see Section 10D.02) are activated.

**Section 10C.09 Light Rail Transit-Activated Blank-Out Turn Prohibition Signs (R3-1a, R3-2a)****Support:**

Light rail transit operations can include the use of activated blank-out sign technology for turn prohibition (R3-1a, R3-2a) signs (see Figure 10C-2). The signs are typically used on roads paralleling a semiexclusive or mixed-use light rail transit alignment where road users might turn across the light rail transit tracks. A blank-out sign displays its message only when activated. When not activated, the sign face is blank.

**Guidance:**

A light rail transit-activated blank-out turn prohibition sign should be used where an intersection adjacent to a highway-light rail transit crossing is controlled by STOP signs, or is controlled by traffic control signals with permissive turn movements for road users crossing the tracks.

**Option:**

A light rail transit-activated blank-out turn prohibition sign may be used for turning movements that cross the tracks.

As an alternative to light rail transit-activated blank-out turn prohibition signs at intersections with traffic control signals, exclusive traffic control signal phases such that all movements that cross the tracks have a red indication may be used in combination with NO TURN ON RED (R10-11a) signs.

**Standard:**

**Turn prohibition signs that are associated with preemption shall be visible only when the highway-light rail transit grade crossing restriction is in effect.**

**Section 10C.10 EXEMPT Highway-Rail Grade Crossing Sign (R15-3, W10-1a)****Option:**

When authorized by law or regulation, a supplemental EXEMPT (R15-3) sign (see Figure 10C-2) with a white background may be used below the Crossbuck sign or Number of Tracks sign, if present, at the highway-light rail transit grade crossing, and a supplemental EXEMPT (W10-1a) sign (see Figure 10C-3) with a yellow background may be used below the Highway-Rail Advance Warning (W10-1) sign. Where neither the Crossbuck nor the advance warning signs exist for a particular crossing, an EXEMPT (R15-3) sign with a white background may be placed on its own post on the near right side of the approach to the crossing.

**Support:**

These supplemental signs are intended to inform drivers of vehicles carrying passengers for hire, school buses carrying students, or vehicles carrying hazardous materials that a stop is not required at certain designated highway-light-rail grade crossings, except when a light rail transit vehicle is approaching or occupying the grade crossing, or the driver's view is blocked.

**Section 10C.11 Divided Highway with Light Rail Transit Crossing Signs (R15-7 Series)****Option:**

The Divided Highway With Light Rail Transit Crossing (R15-7) sign (see Figure 10C-2) may be used as a supplemental sign on the approach legs of a roadway that intersects with a divided highway where light rail transit vehicles operate in the median. The sign may be placed beneath a STOP sign or mounted separately.

**Guidance:**

The number of tracks shown on the R15-7 sign should be the same as the actual number of tracks.

**Standard:**

**When the Divided Highway With Light Rail Transit Crossing sign is used at a four-legged intersection, the R15-7 sign shall be used. When used at a T-intersection, the R15-7a sign shall be used.**

**Section 10C.12 No Vehicles On Tracks Signs (R15-6, R15-6a)****Support:**

The No Vehicles On Tracks (R15-6) sign (see Figure 10C-2) is used where there are adjacent traffic lanes separated from the light rail transit lane by a curb or pavement markings.

**Guidance:**

The DO NOT ENTER (R5-1) sign should be used where a road user could wrongly enter a light rail transit only street.

**Option:**

A No Vehicles On Tracks sign may be used to deter vehicles from driving on the trackway. It may be installed either on a 0.9 m (3 ft) flexible post between double tracks, on a post alongside the tracks, or overhead.

Instead of the R15-6 symbol sign, a regulatory sign with the word message DO NOT DRIVE ON TRACKS (R15-6a) may be used (see Figure 10C-2).

A reduced size of 300 x 300 mm (12 x 12 in) may be used if the R15-6 sign is installed between double tracks.

**Standard:**

**The smallest size for the R15-6 sign shall be 300 x 300 mm (12 x 12 in).**

**Section 10C.13 Light Rail Transit Only Lane Signs (R15-4 Series)****Support:**

The Light Rail Transit Only Lane (R15-4 series) signs (see Figure 10C-2) are used for multi-lane operations, where road users might need additional guidance on lane use and/or restrictions.

**Option:**

Light Rail Transit Only Lane signs may be used on a roadway lane limited to only light rail transit use to indicate the restricted use of a lane in semiexclusive and mixed alignments.

**Guidance:**

If used, the R15-4a, R15-4b, and R15-4c signs should be installed on posts adjacent to the roadway containing the light rail transit tracks or overhead above the light rail transit only lane.

**Option:**

If the trackway is paved, preferential lane markings (see Section 3B.22) may be installed but only in combination with light rail transit only lane signs.

**Support:**

The trackway is the continuous way designated for light rail transit, including the entire dynamic envelope. Section 10C.25 contains more information regarding the dynamic envelope.

**Section 10C.14 Do Not Pass Light Rail Transit Signs (R15-5, R15-5a)****Support:**

A Do Not Pass Light Rail Transit (R15-5) sign (see Figure 10C-2) is used to indicate that vehicles are not allowed to pass light rail transit vehicles that are loading or unloading passengers where there is no raised platform or physical separation from the lanes upon which other motor vehicles are operating.

**Option:**

The R15-5 sign may be used in mixed-use alignments and may be mounted overhead where there are multiple lanes.

Instead of the R15-5 symbol sign, a regulatory sign with the word message DO NOT PASS STOPPED TRAIN (R15-5a) may be used (see Figure 10C-2).

**Guidance:**

If used, the R15-5 sign should be located immediately before the light rail transit boarding area.

## **Section 10C.15 Highway-Rail Grade Crossing Advance Warning Signs (W10 Series)**

### **Standard:**

A Highway-Rail Grade Crossing Advance Warning (W10-1) sign (see Figure 10C-3) shall be used on each highway in advance of every highway-light rail transit grade crossing in semiexclusive alignments except in the following circumstances:

- A. On an approach to a highway-light rail transit grade crossing from a T-intersection with a parallel highway, if the distance from the edge of the track to the edge of the parallel roadway is less than 30 m (100 ft), and W10-3 signs are used on both approaches of the parallel highway; or
- B. On low-volume, low-speed highways crossing minor spurs or other tracks that are infrequently used and are flagged by transit crews; or
- C. In business districts where active highway-light rail transit grade crossing traffic control devices are in use; or
- D. Where physical conditions do not permit even a partially effective display of the sign.

Placement of the Highway-Rail Grade Crossing Advance Warning sign shall be in accordance with Chapter 2A and Table 2C-4.

### **Option:**

On divided highways and one-way streets, an additional W10-1 sign may be installed on the left side of the roadway.

### **Standard:**

If the distance between the light rail transit tracks in a semiexclusive alignment and a parallel highway, from the edge of the tracks to the edge of the parallel roadway, is less than 30 m (100 ft), W10-2, W10-3, or W10-4 signs (see Figure 10C-3) shall be installed on each approach of the parallel highway to warn road users making a turn that they will encounter a highway-light rail transit grade crossing soon after making a turn, and a W10-1 sign for the approach to the tracks shall not be required to be between the tracks and the parallel highway.

If the W10-2, W10-3, or W10-4 signs are used, sign placement in accordance with the guidelines for Intersection Warning signs in Table 2C-4 using the speed of through traffic shall be measured from the highway intersection.

### **Guidance:**

If the distance between the light rail transit tracks and the parallel highway, from the edge of the tracks to the edge of the parallel roadway, is 30 m (100 ft) or more, a W10-1 sign should be installed in advance of the highway-light rail transit grade crossing, and the W10-2, W10-3, or W10-4 signs should not be used on the parallel highway.

## **Section 10C.16 Low Ground Clearance Highway-Rail Grade Crossing Sign (W10-5)**


### **Guidance:**

If the highway profile conditions are sufficiently abrupt to create a hang-up situation for long wheelbase vehicles or for trailers with low ground clearance, the Low Ground Clearance Highway-Rail Grade Crossing (W10-5) sign (see Figure 10C-3) should be installed in advance of the highway-light rail transit grade crossing.

### **Support:**

Information regarding the use of the W10-5 sign is contained in Section 8B.17.

**Figure 10C-3. Warning Signs and Light Rail Station Sign**



**Section 10C.17 Light Rail Transit Approaching-Activated Blank-Out Warning Sign (W10-7)**

Support:

The Light Rail Transit Approaching-Activated Blank-Out (W10-7) warning sign (see Figure 10C-3) supplements the traffic control signal to warn road users turning across the tracks of an approaching parallel light rail transit vehicle.

Option:

A Light Rail Transit Approaching-Activated Blank-Out warning sign may be used at signalized intersections near grade crossings or at crossings controlled by STOP signs or automatic gates.

**Section 10C.18 Storage Space Signs (W10-11, W10-11a, W10-11b)**

Guidance:

A Storage Space (W10-11) sign supplemented by a word message storage distance (W10-11a) sign (see Figure 10C-3) should be used where there is a highway intersection in close proximity to the highway-light rail transit grade crossing and an engineering study determines that adequate space is not available to store a design vehicle(s) between the highway intersection and the light rail transit vehicle dynamic envelope.

Support:

Information regarding the use of the W10-11, W10-11a, and W10-11b signs is contained in Section 8B.18.

### **Section 10C.19 Skewed Crossing Sign (W10-12)**

Option:

The Skewed Crossing (W10-12) sign (see Figure 10C-3) may be used at a skewed highway-light rail transit grade crossing to warn drivers that the light rail transit tracks are not perpendicular to the highway.

Support:

Information regarding the use of the W10-12 sign is contained in Section 8B.19.

### **Section 10C.20 Light Rail Transit Station Sign (I-12)**

Option:

The Light Rail Transit Station (I-12) sign (see Figure 10C-3) may be used to direct road users to a light rail transit station or boarding location. It may be supplemented by the name of the transit system and by arrows as provided in Section 2D.08.

### **Section 10C.21 Emergency Notification Sign (I-13 or I-13a)**

Guidance:

An Emergency Notification (I-13 or I-13a) sign (see Figure 10C-4) should be installed at all highway-light rail transit grade crossings on semiexclusive alignments to provide for emergency notification. The sign should have a white message on blue background.

Location and placement should be decided cooperatively by the transit company and the public or private highway agencies based on specific site conditions.

This sign, which is for emergency notification, should convey a clear and simple message that is visible to anyone stalled or disabled on the transit tracks, and to anyone with other emergencies.

Support:

Examples of sign messages are shown in Figure 10C-4.

### **Section 10C.22 Illumination at Highway-Light Rail Transit Crossings**

Guidance:

Where light rail transit operations are conducted at night, illumination at and adjacent to the highway-light rail transit grade crossing should be considered.

Support:

Recommended types and location of luminaires for highway-rail (light rail transit) grade crossings are contained in the American National Standards Institute's (ANSI) "Practice for Roadway Lighting RP-8," available from the Illuminating Engineering Society (see Section 1A.11).

### **Section 10C.23 Pavement Markings**

Standard:

**All highway-light rail transit grade crossing pavement markings shall be retroreflectorized white. All other markings shall be in accordance with Part 3.**

**Pavement markings in advance of a highway-light rail transit grade crossing shall consist of an X, the letters RR, a no-passing marking (two-lane highways where centerline markings are used), and certain transverse lines as shown in Figures 10C-5 and 10C-6.**

### Figure 10C-4. Examples of Emergency Notification Signs



I-13



I-13a

**Identical markings shall be placed in each approach lane on all paved approaches to highway-light rail transit grade crossings where signals or automatic gates are located, and at all other highway-light rail transit grade crossings where the posted or statutory highway speed is 60 km/h (40 mph) or greater.**

**Pavement markings shall not be required at highway-light rail transit grade crossings where the posted or statutory highway speed is less than 60 km/h (40 mph), or in urban areas, if an engineering study indicates that other installed devices provide suitable warning and control.**

Guidance:

When pavement markings are used, a portion of the X symbol should be directly opposite the Advance Warning sign. The X symbol and letters should be elongated to allow for the low angle at which they will be viewed.

Option:

When justified by engineering judgment, supplemental pavement marking symbol(s) may be placed between the Advance Warning sign and the highway-light rail transit grade crossing.

#### **Section 10C.24 Stop Lines**

Support:

Information regarding the use of stop lines at grade crossings is contained in Section 8B.21.

#### **Section 10C.25 Dynamic Envelope Markings**

Support:

The dynamic envelope (see Figure 10C-7) markings indicate the clearance required for the light rail transit vehicle overhang resulting from any combination of loading, lateral motion, or suspension failure.

Option:

The dynamic envelope may be delineated on the pavement using pavement markings (see Figures 10C-8 and 10C-9) or contrasting pavement color and/or contrasting pavement texture (see Figure 10C-10).

**Standard:**

**If used, pavement markings for indicating the dynamic envelope shall conform to Part 3 and shall be a 100 mm (4 in) normal solid white line or contrasting pavement color and/or contrasting pavement texture.**

**Guidance:**

If pavement markings are used to convey the dynamic envelope, they should be placed completely outside of the dynamic envelope. If used at light-rail transit grade crossings, dynamic envelope pavement markings should be placed on the highway 1.8 m (6 ft) from the nearest rail and installed parallel to the tracks, unless the transit authority and/or operating company advises otherwise. The pavement markings should extend across the roadway as shown in Figure 10C-8.

**Option:**


In semiexclusive alignments, the dynamic envelope markings may be along the light rail transit trackway between intersections where the trackway is immediately adjacent to travel lanes and no physical barrier is present.

In mixed-use alignments the dynamic envelope markings may be continuous between intersections.


Dynamic envelope markings may be installed at all highway-light rail transit grade crossings, unless a Four-Quadrant Gate system (see Section 10D.04) is used.

Pavement markings for adjacent travel or parking lanes may be used instead of dynamic envelope markings if the lines are outside the dynamic envelope.

**Figure 10C-5. Example of Placement of Warning Signs and Pavement Markings at Highway-Light Rail Transit Grade Crossings**




**Figure 10C-6. Examples of Highway-Light Rail Transit Grade Crossing Pavement Markings**



**Highway-Light Rail Transit grade crossing alternative (narrow) pavement markings**


Note: Refer to Figure 10C-5 for placement




**Highway-Light Rail Transit grade crossing pavement markings**

\*Width may vary according to lane width


**Figure 10C-7. Light Rail Transit Vehicle Dynamic Envelope**




**Figure 10C-8. Typical Light Rail Transit Vehicle Dynamic Envelope Pavement Markings**



**Figure 10C-9. Example of Light Rail Transit Vehicle Dynamic Envelope Pavement Markings**



**Figure 10C-10. Example of Light Rail Transit Vehicle Dynamic Envelope Contrasting Color and/or Texture**



## CHAPTER 10D. HIGHWAY-LIGHT RAIL TRANSIT ACTIVE TRAFFIC CONTROL GRADE CROSSING SYSTEMS

### Section 10D.01 Introduction

#### Support:

Active light rail transit traffic control systems inform motorists, bicyclists, and pedestrians of the approach or presence of light rail transit vehicles at highway-light rail transit grade crossings. These systems include four-quadrant gate systems, automatic gates, flashing-light signals, traffic control signals, actuated blank-out and variable message signs, and other active traffic control devices.

#### Guidance:

Where both traffic control signals and flashing-light signals (with or without automatic gates) are in operation at the same highway-light rail transit grade crossing, the operation of the devices should be coordinated to avoid any display of conflicting signal indications.

If a pedestrian route is provided, sufficient clearance from supports, posts, and gate mechanisms should be maintained for pedestrian travel.

#### Option:

Audible devices may be operated in conjunction with the flashing lights or traffic control signals.

#### Support:

Light rail transit typically operates through grade crossings in semiexclusive and mixed-use alignments at speeds between 16 km/h (10 mph) and 105 km/h (65 mph).

When light rail transit speed is cited in this Part, it refers to the maximum speed at which light rail transit vehicles are permitted to traverse a particular grade crossing.

### Section 10D.02 Flashing-Light Signals

#### Support:

Sections 8D.02 and 8D.03 contain additional details regarding flashing-light signals.

#### Standard:

**Highway-light rail transit grade crossings in semiexclusive alignments shall be equipped with flashing-light signals where light rail transit speeds exceed 60 km/h (35 mph). Flashing-light signals shall be clearly visible to motorists, pedestrians, and bicyclists.**

#### Guidance:

Where the crossing is at a location other than an intersection, where light rail transit speeds exceed 40 km/h (25 mph), flashing-light signals should be installed.

#### Option:

Traffic control signals may be used instead of flashing-light signals at highway-light rail transit grade crossings within highway-highway intersections where light rail transit speeds do not exceed 60 km/h (35 mph). Traffic control signals or flashing-light signals may be used where the crossing is at a location other than an intersection, where light rail transit speeds do not exceed 40 km/h (25 mph), and when the roadway is a low-volume street where prevailing speeds do not exceed 40 km/h (25 mph).

### Section 10D.03 Automatic Gates

#### Support:

An automatic gate is a traffic control device used as an adjunct to flashing-light signals.

Section 8D.04 contains further details regarding automatic gates.

**Guidance:**

Highway-light rail transit grade crossings in semiexclusive alignments should be equipped with automatic gates and flashing-light signals (see Section 10D.02) where light rail transit speeds exceed 60 km/h (35 mph).

**Option:**

Where the grade crossing is at a location other than an intersection, where light rail transit speeds exceed 40 km/h (25 mph), automatic gates and flashing-light signals may be installed.

Traffic control signals may be used instead of automatic gates at highway-light rail transit grade crossings within highway-highway intersections where light rail transit speeds do not exceed 60 km/h (35 mph). Traffic control signals or flashing-light signals without automatic gates may be used where the crossing is at a location other than an intersection and where light rail transit speeds do not exceed 40 km/h (25 mph) and the roadway is a low-volume street where prevailing speeds do not exceed 40 km/h (25 mph).

Automatic gates may be supplemented by cantilevered flashing-light signals (see Figure 8D-1) where there is a need for additional emphasis or better visibility.

The effectiveness of gates may be enhanced by the use of channelizing devices or raised median islands to discourage driving around lowered automatic gates.

**Section 10D.04 Four-Quadrant Gate Systems****Option:**

Four-Quadrant Gate systems may be installed to improve safety at highway-light rail transit grade crossings based on an engineering study when less restrictive measures, such as automatic gates and channelization devices, are not effective.

**Standard:**

**A Four-Quadrant Gate system shall consist of a series of automatic gates used as an adjunct to flashing-light signals to control traffic on all lanes entering and exiting the highway-light rail transit grade crossing.**

**The Four-Quadrant Gate system shall consist of a drive mechanism and fully retroreflectorized red- and white-striped gate arms with lights, and which in the down position extends individually across the entrance and exit lanes of highway traffic as shown in Figure 8D-2. Standards contained in Section 10D.02 for flashing-light signals shall be followed for signal specifications, location, and clearance distances.**

**In the normal sequence of operation, unless constant warning time or other advanced system requires otherwise, the flashing-light signals and the lights on the gate arms (in their normal upright positions) shall be activated immediately upon detection of the approaching light rail transit vehicle. The gate arms for the entrance lanes of traffic shall start their downward motion not less than 3 seconds after the flashing-light signals start to operate and shall reach their horizontal position at least 5 seconds before the arrival of the light rail transit vehicle. Exit gate arm activation and downward motion shall be based on timing requirements established by an engineering study of the individual site. The gate arms shall remain in the down position as long as the light rail transit vehicle occupies the highway-light rail transit crossing.**

**When the light rail transit vehicle clears the highway-light rail transit grade crossing, and if no other light rail transit vehicle is detected, the gate arms shall ascend to their upright positions, following which the flashing lights and the lights on the gate arms shall cease operation.**

**Gate arm design, colors, and lighting requirements shall be in accordance with the Standards contained in Section 8D.04.**

**Except as noted in the Option below, the exit gate arms shall be designed to fail-safe in the up position.**

**At locations where gate arms are offset a sufficient distance for vehicles to drive between the entrance and exit gate arms, median islands shall be installed in accordance with the needs established by an engineering study.**

Guidance:

The gate arm should ascend to its upright position in not more than 12 seconds.

Four-Quadrant Gate systems should only be used in locations with constant-warning-time light rail transit vehicle detection.

The operating mode of the exit gates should be determined based upon an engineering study, with input from the affected transit agency.

If the Timed Exit Gate Operating Mode is used, the engineering study, with input from the affected transit agency, should also determine the Exit Gate Clearance Time.

If the Dynamic Exit Gate Operating Mode is used, vehicle intrusion detection devices should be installed to control exit gate operation based on vehicle presence within the minimum track clearance distance.

Regardless of which exit gate operating mode is used, the Exit Gate Clearance Time (see Section 8A.01) should be considered when determining additional time requirements for the Minimum Warning Time.

If a Four-Quadrant Gate system is used at a location that is adjacent to an intersection that could cause vehicles to queue within the minimum track clearance distance, the Dynamic Exit Gate Operating Mode should be used unless an engineering study indicates otherwise.

If a Four-Quadrant Gate system is interconnected with a highway traffic signal, backup or standby power should be considered for the highway traffic signal. Also, circuitry should be installed to prevent the highway traffic signal from leaving the track clearance green interval until all of the gates are lowered.

At locations where sufficient space is available, exit gates should be set back from the track a distance that provides a safety zone long enough to accommodate at least one design vehicle between the exit gate and the nearest rail.

Four-Quadrant Gate systems should include remote health (status) monitoring capable of automatically notifying light rail transit signal maintenance personnel when anomalies have occurred within the system.

Option:

Exit gate arms may fail in the down position if the highway- light rail transit grade crossing is equipped with remote health (status) monitoring.

Four-Quadrant Gate system installations may include median islands between opposing lanes on an approach to a highway-light rail transit grade crossing.

Guidance:

Where sufficient space is available, median islands should be at least 18 m (60 ft) in length.

### **Section 10D.05 Traffic Control Signals**

Support:

There are two types of traffic control signals for controlling vehicular and light rail transit movements at interfaces of the two modes. The first is the standard traffic control signal described in Part 4, which is the focus of this section. The other type of signal is referred to as a light rail transit signal and is discussed in Section 10D.07.

**Standard:**

**The provisions of Parts 4 and 8 relating to traffic control signal design, installation, and operation, including interconnection with nearby automatic gates or flashing-light signals, shall be applicable as appropriate where traffic control signals are used at highway-light rail transit grade crossings.**

**Guidance:**

When a highway-light rail transit grade crossing equipped with a flashing-light signal system is located within 60 m (200 ft) of an intersection or midblock location controlled by a traffic control signal, the traffic control signal should be provided with preemption in accordance with Section 4D.13.

Coordination with the flashing-light signal system should be considered for traffic control signals located more than 60 m (200 ft) from the crossing. Factors to be considered should include traffic volumes, vehicle mix, vehicle and light rail transit approach speeds, frequency of light rail transit vehicles, and queue lengths.

If the highway traffic signal has emergency vehicle preemption capability, it should be coordinated with light rail transit operation.

Where light rail transit operates in a wide median, vehicles crossing the tracks and being controlled by both near and far side traffic signal faces should receive a protected left-turn green phase from the far side signal face to clear vehicles from the crossing when light rail transit vehicles are approaching the crossing.

**Option:**

Green indications may be provided during light rail transit phases for vehicle, pedestrian, and bicycle movements that do not conflict with light rail transit movements.

Traffic control signals may be installed in addition to four-quadrant gate systems and automatic gates at a highway-light rail transit crossing if the crossing occurs within a highway-highway intersection and if the traffic control signals meet the warrants described in Chapter 4C.

At a location other than an intersection, when light rail transit speeds are less than 40 km/h (25 mph), traffic control signals alone may be used to control road users at highway-light rail transit grade crossings only when justified by an engineering study.

Typical circumstances may include:

- A. Geometric conditions preclude the installation of highway-light rail transit grade crossing warning devices.
- B. Light rail transit vehicles share the same roadway with road users.
- C. Traffic control signals already exist.

**Support:**

See Section 4D.13 for considerations regarding traffic control signals at or near highway-light rail transit grade crossings that are not equipped with highway-light rail transit grade crossing warning devices.

**Section 10D.06 Highway Traffic Signal Preemption Turning Restrictions****Guidance:**

When a light rail transit grade crossing exists within a signalized intersection, consideration should be given to providing separately controlled Protected Only Mode turn phases for the movements crossing the tracks (see Section 4A.02).

**Standard:**

**Signal faces that are provided for separately controlled Protected Only Mode turn movements toward the crossing shall display a red indication during the approach and/or passage of light rail transit vehicles.**

**Guidance:**

When a signalized intersection that is located within 60 m (200 ft) of a highway-light rail transit grade crossing is preempted, all existing turning movements toward the highway-light rail transit grade crossing should be prohibited.

**Support:**

Part 4 contains information regarding signal phasing and timing requirements.

**Option:**

An activated blank-out or changeable message sign and/or an appropriate highway traffic signal display may be used to prohibit turning movements toward the crossing during preemption (see Section 10C.09).

**Standard:**

**Messages on the activated blank-out or changeable message signs shall be visible only when the highway-light rail transit intersection restriction is in effect.**

**Section 10D.07 Use of Traffic Control Signals for Control of Light Rail Transit Vehicles at Grade Crossings****Guidance:**

Light rail transit movements in semiexclusive alignments at nongated grade crossings that are equipped with traffic control signals should be controlled by special light rail transit signal indications.

**Support:**

Examples of light rail transit traffic control signals, used to control light rail transit movements only, are shown in Figure 10D-1.

**Option:**

Standard traffic control signals may be used instead of light rail transit traffic control signals to control the movement of light rail transit vehicles (see Section 10D.05).

**Standard:**

**If a separate set of standard traffic control signal indications (red, yellow, and green circular and arrow indications) is used to control light rail transit movements, the indications shall be positioned so they are not visible to motorists, pedestrians, and bicyclists (see Section 4D.17).**

**If the light rail transit crossing control is separate from the intersection control, the two shall be interconnected. The light rail phase shall not be terminated until after the light rail transit vehicle has cleared the crossing.**


**Option:**

Light rail transit signals may be used at grade crossings and at intersections in mixed-use alignments in conjunction with standard traffic control signals where special light rail transit signal phases are used to accommodate turning light rail transit vehicles or where additional light rail transit clearance time is desirable.

**Guidance:**

Light rail transit signal faces should be separated vertically or horizontally from the nearest highway traffic signal face for the same approach by at least 0.9 m (3 ft).

**Figure 10D-1. Examples of Light Rail Transit Signals**

	Three-Lens Signal	Two-Lens Signal
<p>SINGLE LRT ROUTE</p> 	<p>STOP </p> <p>PREPARE TO STOP  Flashing</p> <p>GO </p>	<p> STOP</p> <p><sup>(2)</sup> GO</p>
<p>TWO LRT ROUTE DIVERSION</p> 	<p></p> <p> Flashing</p> <p> <sup>(1)</sup></p>	<p></p> <p> <sup>(1),(2)</sup></p>
	<p></p> <p>Flashing </p> <p> <sup>(1)</sup></p>	<p></p> <p> <sup>(1),(2)</sup></p>
<p>THREE LRT ROUTE DIVERSION</p> 	<p></p> <p> Flashing</p> <p>  <sup>(1)</sup></p>	<p></p> <p>  <sup>(1),(2)</sup></p>

Notes:

All aspects (or signal indications) are white.

(1) Could be in single housing.

(2) "Go" lens may be used in flashing mode to indicate "prepare to stop".

**Section 10D.08 Pedestrian and Bicycle Signals and Crossings****Standard:**

**Pedestrian signals shall be in accordance with Section 4E.04.**

**Guidance:**

Where light rail transit tracks are immediately adjacent to other tracks or a road, pedestrian signalization should be designed to avoid having pedestrians wait between sets of tracks or between the tracks and the road. If adequate space exists for a pedestrian refuge and is justified based on engineering judgment, additional pedestrian signal indicators, signing, and detectors should be installed (see Section 4E.08).

Flashing-light signals (see Figure 10D-2) with a Crossbuck (R15-1) sign should be installed at pedestrian and bicycle crossings where an engineering study has determined that the sight distance is not sufficient for pedestrians and bicyclists to complete their crossing prior to the arrival of the light rail transit vehicle at the crossing, or where light rail transit speeds exceed 60 km/h (35 mph).

If an engineering study shows that flashing-light signals alone would not provide sufficient notice of an approaching light rail transit vehicle, the LOOK (R15-8) sign (see Figure 10D-2) and/or pedestrian gates should be considered (see Figures 10D-3, 10D-4, and 10D-5).

For a shared-use facility, the gate should be long enough to block the full width of the path, for both pedestrians and bicycles.

**Support:**

A pedestrian gate is similar to an automatic gate except the gate arm is shorter.


The swing gate alerts pedestrians to the light rail transit tracks that are to be crossed. Swing gates are designed to open away from the tracks, requiring users to pull the gate open to cross, but permitting a quick exit from the trackway, and to automatically close.

**Option:**


Swing gates may be installed across pedestrian and bicycle walkways (see Figure 10D-6).

Pedestrian barriers at offset crossings may be used at pedestrian and bicycle crossings as passive devices that force users to face approaching light rail transit before entering the trackway (see Figures 10D-7 and 10D-8).


**Figure 10D-2. Example of Light Rail Transit Flashing-Light Signal Assembly for Pedestrian Crossings**



**Figure 10D-3. Example of Pedestrian Gate Placement Behind the Sidewalk**





**Figure 10D-4. Example of Pedestrian Gate Placement with Pedestrian Gate Arm**




\*For locating this reference line at other than curb section installation, see Section 8D.01.


**Figure 10D-5. Examples of Placement of Pedestrian Gates**




**Figure 10D-6. Example of Swing Gates**



**Figure 10D-7. Example of Pedestrian Barriers at an Offset Highway-Light Rail Transit Crossing**



**Figure 10D-8. Examples of Pedestrian Barrier Installation at an Offset Nonintersection Light Rail Transit Crossing**



## **APPENDIX A1. CONGRESSIONAL LEGISLATION REGARDING THE NATIONAL MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES**

For background information, references to Congressional legislation involving the national Manual on Uniform Traffic Control Devices (MUTCD) have been included in this Appendix. Information about Ohio Revised Code references related to information in this Manual is provided in Appendix B

### **PUBLIC LAW 102-240-DEC. 18, 1991 (INTERMODAL SURFACE TRANSPORTATION EFFICIENCY ACT OF 1991)**

**Section 1077. REVISION OF MANUAL** — Not later than 90 days after the date of the enactment of this Act, the Secretary shall revise the Manual of Uniform Traffic Control Devices and such other regulations and agreements of the Federal Highway Administration as may be necessary to authorize States and local governments, at their discretion, to install stop or yield signs at any rail-highway grade crossing without automatic traffic control devices with 2 or more trains operating across the rail-highway grade crossing per day.

### **PUBLIC LAW 102-388-OCT. 6, 1992 (DEPARTMENT OF TRANSPORTATION AND RELATED AGENCIES APPROPRIATIONS ACT, 1993)**

**Section 406** — The Secretary of Transportation shall revise the Manual of Uniform Traffic Control Devices to include —

- (a) a standard for a minimum level of retroreflectivity that must be maintained for pavement markings and signs, which shall apply to all roads open to public travel; and
- (b) a standard to define the roads that must have a centerline or edge lines or both, provided that in setting such standard the Secretary shall consider the functional classification of roads, traffic volumes, and the number and width of lanes.

### **PUBLIC LAW 104-59-NOV. 28, 1995 (NATIONAL HIGHWAY SYSTEM DESIGNATION ACT OF 1995)**

#### **Section 205. RELIEF FROM MANDATES** —

##### (c) METRIC REQUIREMENTS —

(1) PLACEMENT AND MODIFICATION OF SIGNS — The Secretary shall not require the States to expend any Federal or State funds to construct, erect, or otherwise place or to modify any sign relating to a speed limit, distance, or other measurement on a highway for the purpose of having such sign establish such speed limit, distance, or other measurement using the metric system.

(2) OTHER ACTIONS — Before September 30, 2000, the Secretary shall not require that any State use or plan to use the metric system with respect to designing or advertising, or preparing plans, specifications, estimates, or other documents, for a Federal-aid highway project eligible for assistance under title 23, United States Code.

(3) DEFINITIONS — In this subsection, the following definitions apply:

(A) HIGHWAY — The term ‘highway’ has the meaning such term has under section 101 of title 23, United State Code.

(B) METRIC SYSTEM — the term ‘metric system’ has the meaning the term ‘metric system of measurement’ has under section 4 of the Metric Conversion Act of 1975 (15 U.S.C. 205c).

**Section 306. MOTORIST CALL BOXES** — Section 111 of title 23, United States Code, is amended by adding at the end the following:

##### (c) MOTORIST CALL BOXES—

(1) IN GENERAL— Notwithstanding subsection (a), a State may permit the placement of motorist call boxes on rights-of-way of the National Highway System. Such motorist call boxes may include the identification and sponsorship logos of such call boxes.

(2) SPONSORSHIP LOGOS—

(A) **APPROVAL BY STATE AND LOCAL AGENCIES**—All call box installations displaying sponsorship logos under this subsection shall be approved by the highway agencies having jurisdiction of the highway on which they are located.

(B) **SIZE ON BOX**—A sponsorship logo may be placed on the call box in a dimension not to exceed the size of the call box or a total dimension in excess of 12 inches by 18 inches.

(C) **SIZE ON IDENTIFICATION SIGN**—Sponsorship logos in a dimension not to exceed 12 inches by 30 inches may be displayed on a call box identification sign affixed to the call box post.

(D) **SPACING OF SIGNS**—Sponsorship logos affixed to an identification sign on a call box post may be located on the rights-of-way at intervals not more frequently than 1 per every 5 miles.

(E) **DISTRIBUTION THROUGHOUT STATE**—Within a State, at least 20 percent of the call boxes displaying sponsorship logos shall be located on highways outside of urbanized areas with a population greater than 50,000.

(3) **NONSAFETY HAZARDS**—The call boxes and their location, posts, foundations, and mountings shall be consistent with requirements of the Manual on Uniform Traffic Control Devices or any requirements deemed necessary by the Secretary to assure that the call boxes shall not be a safety hazard to motorists.

**Section 353(a) SIGNS** — Traffic control signs referred to in the experimental project conducted in the State of Oregon in December 1991 shall be deemed to comply with the requirements of Section 2B-4 of the Manual on Uniform Traffic Control Devices of the Department of Transportation.

**Section 353(b) STRIPES** — Notwithstanding any other provision of law, a red, white, and blue center line in the Main Street of Bristol, Rhode Island, shall be deemed to comply with the requirements of Section 3B-1 of the Manual on Uniform Traffic Control Devices of the Department of Transportation.

## **APPENDIX B1. CROSS-REFERENCE GUIDE TO THE OHIO REVISED CODE**

The Ohio Revised Code (O.R.C.) contains many laws which apply to the control of traffic on the streets and highways of the State. It is important that officials responsible for the erection and maintenance of traffic control devices be well informed regarding these laws and their application to the operation of vehicles and the movement of pedestrians. A list of references follows, including important laws relative to traffic control and vehicle operation. These references are grouped by subject.

Code sections referenced in this Manual, as well as some others, have been reprinted in Appendix B2 for your convenience. An asterisk (\*) next to the code number in the following cross-reference list indicates that a copy of that section is available in Appendix B2. Copies of other sections of the O.R.C. are available through local libraries. The O.R.C., the Ohio Administrative Code and legislation submitted, can be viewed on-line at <http://www.legislature.state.oh.us/laws.cfm>

### **PART 1. GENERAL**

#### **R.C. Section Title / Description**

§ 4511.01	Definitions.
§ 4511.07*	Local traffic regulations.
§ 4511.09*	Uniform system of traffic control devices.
§ 4511.10*	Placing and maintaining traffic control devices.
§ 4511.11*	Uniformity of traffic control devices.
§ 4511.12*	Obeying traffic control devices.
§ 4511.16*	Prohibition against unauthorized signs and signals.
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.

### **PART 2. SIGNS**

#### **R.C. Section Title / Description**

§ 3767.32	Restrictions on depositing litter on public property, on private property owned by others and in state waters.
§ 4511.03	Emergency vehicles to proceed cautiously past red or stop signals.
§ 4511.051*	Prohibitions on use of freeways.
§ 4511.07*	Local traffic regulations.
§ 4511.09*	Uniform system of traffic control devices.
§ 4511.091	Arrest or citation based on radar, timing device or radio message from another officer.
§ 4511.10*	Placing and maintaining traffic control devices.
§ 4511.101*	Business logos on directional signs along interstates.
§ 4511.102*	Definitions. (Tourist-Oriented Directional Sign Programs)
§ 4511.103*	Rules for placement of tourist-oriented directional signs and trailblazer markers.
§ 4511.104*	Advertising agreement with tourist-oriented attractions.
§ 4511.105*	Signs to conform to federal manual; logos.
§ 4511.106*	Local authority programs.
§ 4511.11*	Uniformity of traffic control devices.
§ 4511.12*	Obeying traffic control devices.
§ 4511.13*	Signal lights.
§ 4511.15*	Flashing traffic signals.
§ 4511.16*	Prohibition against unauthorized signs and signals.
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.
§ 4511.21*	Speed limits. (Speed Limit Signs)
§ 4511.211*	Speed limit on private residential road or driveway.
§ 4511.212*	Complaint that local authority is not complying with school zone sign laws.
§ 4511.213*	Duties upon approaching stationary public safety vehicle displaying emergency light.
§ 4511.22*	Slow speed. (Minimum Speed Limit Sign)
§ 4511.23*	Speed regulations on bridges.
§ 4511.25*	Lanes of travel upon roadways.
§ 4511.28*	Permission to overtake and pass on the right.
§ 4511.31*	Hazardous zones.
§ 4511.33*	Rules for driving in marked lanes.

**R.C. Section Title / Description**

§ 4511.35*	Divided roadways.
§ 4511.36*	Rules for turns at intersections.
§ 4511.37*	Turning in roadway prohibited; exception for emergency or public safety vehicle.
§ 4511.43*	Right-of-way at through highways; stop signs; yield signs.
§ 4511.432*	Stop signs on private residential road or driveway.
§ 4511.47	Right of way yielded to blind person.
§ 4511.50	Pedestrian walking along highway.
§ 4511.61*	Stop Signs at grade crossings.
§ 4511.65*	Through highways.
§ 4511.66*	Prohibition against parking on highways.
§ 4511.68*	Parking prohibitions.
§ 4511.69*	Parking near curb, facing direction of travel; locations and privileges for walking- impaired persons.
§ 4511.71	Prohibition against driving upon closed highway.
§ 4511.712*	Obstructing passage of other vehicles.
§ 4511.75*	Stopping for school bus; signals.
§ 4513.33	Weighing vehicle; scales; alteration of weight limits by local authorities. (Load Limits, Weigh Stations Signs)
§ 4513.40*	Warning sign before safety device at street crossing. (Railroad Signs)
§ 4519.40*	Prohibitions. (Snowmobiles, Off-highway Motorcycles and All-Purpose Vehicles)
§ 4519.41	Operation on or near highway, street or road. (Snowmobiles, Off-highway Motorcycles and All-Purpose Vehicles).
§ 4955.33*	Crossbuck signs; additional reflective signs; experimental signs.
§ 5511.01	State highway system; changes or additions; memorial highways; abandonment of highways; maps; state highway within municipalities.
§ 5511.02	"Limited access highways" and "freeways."
§ 5511.05	State park and school land access roads; trail intersection markers.
§ 5515.04	Attaching guideposts or signs to utility poles.
§ 5515.13	Prohibition of Signs on the Right-of- Way Without Consent of the Director.
§ 5516	Advertising on Interstate Highways.
§ 5517.03	Highways closed to traffic. (Barricades, Detour Signs)
§ 5529.03	Land acquisition for highway beautification or rest and recreation areas. (Rest Area, Scenic Enhancements)
§ 5533	Memorial Highways. (Memorial Signs)
§ 5543.18	Erection of signposts. (County Road Name Sign)
§ 5571.01	Power of township trustees to improve roads and highways; signposts at intersections; traffic control devices, signals. (Township Road Name Sign)
§ 5577.05	Maximum width, height, and length. (Low Clearance Sign)
§ 5577.07	Reduction of weight and speed during times of thaws and moisture. (Weight Limit Sign)
§ 5577.09	Rules; signs. (County and Township Load Limits)
§ 5589.32	Erection of advertising signs resembling those required of railroad companies.
§ 5589.33	Advertising on public highway.
§ 5591.42*	Carrying capacity of bridges; warning notice. (County and State Bridge Weight Limit Signs)

**PART 3. MARKINGS****R.C. Section Title / Description**

§ 4511.09*	Uniform system of traffic control devices.
§ 4511.10*	Placing and maintaining traffic control devices.
§ 4511.11*	Uniformity of traffic control devices.
§ 4511.12*	Obeying traffic control devices.
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.
§ 4511.27*	Rules governing overtaking and passing of vehicles.
§ 4511.28*	Permission to overtake and pass on the right.
§ 4511.29*	Driving to left of center line.
§ 4511.30*	Prohibition against driving upon left side of roadway.
§ 4511.31*	Hazardous zones.

<b>R.C. Section</b>	<b>Title / Description</b>
§ 4511.33*	Rules for driving in marked lanes.
§ 4511.35*	Divided roadways.
§ 4511.36*	Rules for turns at intersections.
§ 4511.46*	Pedestrian on crosswalk has right-of-way.
§ 4511.48*	Right of way yielded by pedestrian.
§ 4511.49	Pedestrians.
§ 4511.60	Driving through safety zone.
§ 4511.68*	Parking prohibitions.
§ 5521.01	Establishment and improvement of state highways within municipal corporations. (Center Line Paint in Villages)

### **HIGHWAY TRAFFIC SIGNALS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 4511.03	Emergency vehicles to proceed cautiously past red or stop signals.
§ 4511.09*	Uniform system of traffic control devices.
§ 4511.11*	Uniformity of traffic control devices.
§ 4511.12*	Obeying traffic control devices.
§ 4511.13*	Signal lights.
§ 4511.131*	Signals over reversible lanes.
§ 4511.132*	Malfunctioning traffic signals.
§ 4511.14*	Pedestrian control signals
§ 4511.15*	Flashing traffic signals.
§ 4511.16*	Prohibition against unauthorized signs and signals..
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.
§ 4511.68*	Parking prohibitions.
§ 5555.02	General powers of board of county commissioners relating to public roads.
§ 5571.01	Power of township trustees to improve roads and highways; signposts at intersections; traffic control devices, signals.

### **PART 6. TEMPORARY TRAFFIC CONTROL**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 3767.201	Destruction or removal of barriers along limited access highways prohibited; vehicles to enter and leave at designated intersections.
§ 4511.04*	Exceptions. (Work Within an Area Designated by Traffic Control Devices)
§ 4511.07*	Local traffic regulations.
§ 4511.09*	Uniform system of traffic control devices.
§ 4511.10*	Placing and maintaining traffic control devices.
§ 4511.11*	Uniformity of traffic control devices.
§ 4511.12*	Obeying traffic control devices.
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.
§ 4511.25*	Lanes of travel upon roadways.
§ 4511.68*	Parking prohibitions.
§ 4511.69*	Parking near curb, facing direction of travel; locations and privileges for walking- impaired persons.
§ 4511.71	Prohibition against driving upon closed highway.
§ 4511.74	Prohibition against placing injurious material on highway.
§ 4511.98*	Warning signs as to increased penalties in construction zones.
§ 5501.27*	Rules for warning signs in construction zones.
§ 5515.01	Permits granted to use or occupy portions of road or highway.
§ 5515.02	Removal of structures constituting obstructions or interferences.
§ 5515.03	Occupants of land to remove all obstructions.
§ 5515.04	Attaching guideposts or signs to utility poles.
§ 5517.03	Highways closed to traffic.
§ 5517.04	Director to repair damage to county or township roads.
§ 5589.10	Digging, excavating, piling earth, or building fence on highway.

**R.C. Section Title / Description**

§ 5589.31 Construction of walk or ditch across highway.

**PART 7. SCHOOL AREAS****R.C. Section Title / Description**

§ 4511.21\* Speed limits.

§ 4511.212\* Complaint that local authority is not complying with school zone sign laws.

§ 4511.75\* Stopping for school bus; signals.

§ 4511.76\* School bus construction, design, equipment, operation and licensing rules.

**PART 8. HIGHWAY-RAILROAD GRADE CROSSINGS****R.C. Section Title / Description**

§ 4511.61\* Stop signs at grade crossings.

§ 4511.62 Driver's duties relating to railroad grade crossings.

§ 4511.63\* Vehicles required to stop at grade crossings.

§ 4511.64\* Slow-moving vehicles or equipment crossing railroad tracks.

§ 4511.68\* Parking prohibitions.

§ 4513.40\* Warning sign before safety device at street crossing.

§ 4905.04 Power to regulate public utilities and railroads.

§ 4907.47\* Installation of crossing signals; apportionment of costs; additional protective devices.

§ 4907.471\* Survey to determine crossings with highest probability of accident; additional protective devices.

§ 4907.474 Closing of municipal crossings; court action.

§ 4907.475 Closing of rural crossings not on state highway; court action.

§ 4907.48\* Regulation of crossing signals.

§ 4907.49\* Dangerous crossings. (Abandonment of Gates or Flagman Requires PUCO Consent)

§ 4907.52\* Safety devices at grade crossings.

§ 4951.02\* Grant of right to construct. (Street Railways and Interurban Railroads)

§ 4951.12 Use of public highways.

§ 4951.14\* Acquisition or appropriation for crossings.

§ 4955.201\* Abandonment of track; restoration of roadway.

§ 4955.33\* Crossbuck signs; additional reflective signs; experimental signs.

§ 5589.32 Erection of advertising signs resembling those required of railroad companies.

**PART 9. BICYCLE FACILITIES****R.C. Section Title / Description**

§ 4501.01 Definitions.

§ 4511.01 Definitions.

§ 4511.051\* Prohibitions on use of freeways.

§ 4511.07\* Local traffic regulations.

§ 4511.512 Electric personal assistive mobility devices.

§ 4511.52 Bicycles.

§ 4511.521 Rules governing operation of motorized bicycles.

§ 4511.53 Rules for bicycles, motorcycles and snowmobiles.

§ 4511.55 Riding bicycles; motorcycles abreast.

§ 4511.68\* Parking prohibitions.

§ 4511.711 Driving upon sidewalk area.

§ 4511.713 Paths exclusively for bicycles.

**PART 10. LIGHT-RAIL TRANSIT****R.C. Section Title / Description**

§ 715.33 Streetcars.

§ 4511.01 Definitions.

§ 4511.07\* Local traffic regulations.

§ 4511.12\* Obeying traffic control devices.

<b>R.C. Section</b>	<b>Title / Description</b>
§ 4511.13*	Signal lights.
§ 4511.132*	Malfunctioning traffic signals.
§ 4511.14*	Pedestrian control signals.
§ 4511.15*	Flashing traffic signals.
§ 4511.20*	Willful or wanton operation on street or highway.
§ 4511.201*	Willful or wanton operation off street or highway; competitive operation exception.
§ 4511.202*	Operating a motor vehicle without reasonable control.
§ 4511.21*	Speed limits.
§ 4511.23*	Speed regulations on bridges.
§ 4511.34*	Space between moving vehicles.
§ 4511.36*	Rules for turns at intersections.
§ 4511.38	Rules for starting and backing vehicles.
§ 4511.41*	Right-of-way at intersections.
§ 4511.42*	Right of way when turning left.
§ 4511.44*	Right of way on public highway.
§ 4511.45	Right of way of public safety or coroner's vehicle.
§ 4511.46*	Pedestrian on crosswalk has right-of-way.
§ 4511.48*	Right of way yielded by pedestrian.
§ 4511.50	Pedestrian walking along highway.
§ 4511.57	Passing on left side of streetcar.
§ 4511.58	Vehicle shall not pass streetcar discharging passengers; exception.
§ 4511.59	Driving and turning in front of streetcars.
§ 4511.61*	Stop Signs at grade crossings.
§ 4511.712*	Obstructing passage of other vehicles.
§ 4513.40*	Warning sign before safety device at street crossing
§ 4951.02*	Grant of right to construct. (Street Railways and Interurban Railroads)
§ 4951.12	Use of public highways.
§ 4951.45	Electric railways or interurban railroads operating cars along third rail required to maintain fences.

### **HAZARDOUS MATERIALS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 4905.80	Rules for uniform registration and permitting of persons engaging in highway transportation of hazardous materials; hazardous materials transportation fund.
§ 4905.81	Rules for highway routing of hazardous materials; advisory panel.

### **MEMORIAL HIGHWAYS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 5511.01	State highway system; changes or additions; memorial highways; abandonment of highways; maps; state highway within municipalities.
§ 5533	Memorial Highways.
§ 5541.04	Changing name of road. (County Highway)
§ 5543.04	Naming and numbering of roads and bridges; map of roads, bridges, and trails.
§ 5511.09	Procedure for naming of highway by local authorities.
§ 5529.08	Memorial markers listing POWS/MIAS.
§ 5913.30	Committees for placement of memorial markers listing POWS/MIAS at highway rest areas.

### **MOTORCYCLES**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 505.17	Regulations for engine noise and vehicle parking.
§ 4511.01	Definitions.
§ 4511.53	Rules for bicycles, motorcycles and snowmobiles.
§ 4511.55	Riding bicycles; motorcycles abreast.
§ 4513.221	Regulation of vehicle and engine noise in unincorporated areas.
§ 4519.41	Operation on or near highway, street or road.

**PEDESTRIANS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 729.12	Ramped curbing for handicapped.
§ 737.022	Authority of director to promulgate certain traffic regulations.
§ 4511.01	Definitions.
§ 4511.051*	Prohibitions on use of freeways.
§ 4511.12*	Obeying traffic control devices.
§ 4511.13*	Signal lights.
§ 4511.14*	Pedestrian control signals.
§ 4511.441	Pedestrian on sidewalk has right-of-way.
§ 4511.452	Pedestrian to yield right-of-way to public safety vehicle.
§ 4511.46*	Pedestrian on crosswalk has right-of-way.
§ 4511.47	Right of way yielded to blind person.
§ 4511.48*	Right of way yielded by pedestrian.
§ 4511.481*	Intoxicated or drugged pedestrian hazard on highway.
§ 4511.49	Pedestrians.
§ 4511.50	Pedestrian walking along highway.
§ 4511.511	Pedestrian on bridge or railroad crossing.
§ 4511.512	Electric personal assistive mobility devices.
§ 4907.474	Closing of municipal crossings; court action.
§ 4907.475	Closing of rural crossings not on state highway; court action.

**SPEEDS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 4511.07*	Local traffic regulations.
§ 4511.091	Arrest or citation based on radar, timing device or radio message from another officer.
§ 4511.21*	Speed limits.
§ 4511.22*	Slow speed.
§ 4511.23*	Speed regulations on bridges.
§ 4511.24*	Emergency vehicles excepted from speed limitations.

**TRAFFIC REGULATIONS**

<b>R.C. Section</b>	<b>Title / Description</b>
§ 3767.201	Destruction or removal of barriers along limited access highways prohibited; vehicles to enter and leave at designated intersections.
§ 4511.07*	Local traffic regulations.
§ 4511.12*	Obeying traffic control devices.
§ 4511.16*	Prohibition against unauthorized signs and signals.
§ 4511.17*	Tampering with sign, device or manhole cover; driving on freshly applied marking material.
§ 4511.202*	Operating vehicle without reasonable control.
§ 4511.213*	Duties upon approaching stationary public safety vehicle displaying emergency light.
§ 4511.25*	Lanes of travel upon roadways.
§ 4511.26*	Vehicles traveling in opposite directions.
§ 4511.32*	One-way highways and rotary traffic islands.
§ 4511.34*	Space between moving vehicles.
§ 4511.36*	Rules for turns at intersections.
§ 4511.37*	Turning in roadway prohibited; exception for emergency or public safety vehicle.
§ 4511.41*	Right-of-way at intersections.
§ 4511.42*	Right of way when turning left.
§ 4511.43*	Right-of-way at through highways; stop signs; yield signs.
§ 4511.431*	Stop at sidewalk area.
§ 4511.44*	Right of way on public highway.
§ 4511.47	Right of way yielded to blind person.
§ 4511.481*	Intoxicated or drugged pedestrian hazard on highway.
§ 4511.50	Pedestrian walking along highway.
§ 4511.65*	Through highways.

**R.C. Section Title / Description**

§ 4511.66*	Prohibition against parking on highways.
§ 4511.68*	Parking prohibitions.
§ 4511.681*	Parking prohibitions on private property.
§ 4511.69*	Parking near curb, facing direction of travel; locations and privileges for walking- impaired persons.
§ 4511.75*	Stopping for school bus; signals.
§ 4513.03	Lighted lights and illuminating devices required.
§ 4513.17	Number of lights permitted; direction of beam; flashing, oscillating or rotating lights.
§ 4519.40*	Prohibitions. (Snowmobiles, Off-highway Motorcycles and All-Purpose Vehicles)
§ 4519.41	Operation on or near highway, street or road. (Snowmobiles, Off-highway Motorcycles and All-Purpose Vehicles).
§ 5516	Advertising on Interstate Highways.
§ 5547.04	Removal of obstructions by landowners; consent and approval; signs and advertising. (County Highways)
§ 5577.07	Reduction of weight and speed during times of thaws and moisture.
§ 5577.09	Rules; signs. (County and Township load limits)
§ 5591.42*	Carrying capacity of bridges; warning notice. (County and State)

**MISCELLANEOUS****R.C. Section Title / Description**

§ 505.17	Regulations for engine noise and vehicle parking. (Township Authority)
§ 723.01	Care, supervision, and control of public roads.
§ 951.02	Animals running at large on public roads; grazing on another's land.
§ 4511.06*	Uniform application and precedence of traffic law.
§ 4511.18*	Possession or sale of sign or device prohibited.
§ 4511.20*	Willful or wanton operation on street or highway.
§ 4511.201*	Willful or wanton operation off street or highway; competitive operation exception.
§ 4511.76*	School bus construction design, equipment, operation and licensing rules.
§ 4905.80	Rules for uniform registration and permitting of persons engaging in highway transportation of hazardous materials; hazardous materials transportation fund.
§ 4905.81	Rules for highway routing of hazardous materials; advisory panel.
§ 5501.49	Lift bridges on state highway system within municipal corporation.
§ 5511.01	State highway system; changes or additions; memorial highways; abandonment of highways; maps; state highway within municipalities.
§ 5515.01	Permits granted to use or occupy portions of road or highway.
§ 5515.02	Removal of structures constituting obstructions or interferences.
§ 5515.03	Occupants of land to remove all obstructions.
§ 5515.07	Use of rest areas; commercial activities prohibited.
§ 5529.03	Land acquisition for highway beautification or rest and recreation areas.

Intentionally blank.

## APPENDIX B2. OHIO REVISED CODE SECTIONS

For your convenience, the following Ohio Revised Code (O.R.C.) Sections have been reprinted in this Appendix. Although we have checked for any recent changes in the sections quoted, we cannot guarantee the accuracy of the following copies of O.R.C. text at any particular time. The O.R.C. is available through local libraries, and a searchable version is also available on the web at <http://www.legislature.state.oh.us/laws.cfm>.

<b>R.C. Section</b>	<b>Title/Description</b>	<b>Page in Appendix B2</b>
§ 4511.04	Exceptions .....	3
§ 4511.051	Prohibitions on use of freeways.....	3
§ 4511.06	Uniform application and precedence of traffic law .....	3
§ 4511.07	Local traffic regulations .....	4
§ 4511.09	Uniform system of traffic control devices .....	4
§ 4511.10	Placing and maintaining traffic control devices .....	4
§ 4511.101	Business logos on directional signs along interstates .....	5
§ 4511.102	Definitions.....	5
§ 4511.103	Rules for placement of tourist-oriented directional signs and trailblazer markers.....	6
§ 4511.104	Advertising agreement with tourist-oriented attractions .....	6
§ 4511.105	Signs to conform to federal manual; logos.....	7
§ 4511.106	Local authority programs.....	7
§ 4511.11	Uniformity of traffic control devices .....	7
§ 4511.12	Obeying traffic control devices .....	8
§ 4511.13	Signal lights .....	8
§ 4511.131	Signals over reversible lanes.....	9
§ 4511.132	Malfunctioning traffic signals .....	10
§ 4511.14	Pedestrian control signals .....	10
§ 4511.15	Flashing traffic signals.....	10
§ 4511.16	Prohibition against unauthorized signs and signals.....	11
§ 4511.17	Tampering with sign, device or manhole cover; driving on freshly applied marking material.....	11
§ 4511.18	Possession or sale of sign or device prohibited .....	12
§ 4511.20	Willful or wanton operation on street or highway.....	12
§ 4511.201	Willful or wanton operation off street or highway; competitive operation exception.....	12
§ 4511.202	Operating vehicle without reasonable control.....	13
§ 4511.21	Speed limits .....	13
§ 4511.211	Speed limit on private residential road or driveway .....	19
§ 4511.212	Complaint that local authority is not complying with school zone sign laws .....	20
§ 4511.213	Duties upon approaching stationary public safety vehicle displaying emergency light.....	20
§ 4511.22	Slow speed .....	21
§ 4511.23	Speed regulations on bridges.....	21
§ 4511.24	Emergency vehicles excepted from speed limitations .....	22
§ 4511.25	Lanes of travel upon roadways.....	22
§ 4511.26	Vehicles traveling in opposite directions.....	23
§ 4511.27	Rules governing overtaking and passing of vehicles .....	23
§ 4511.28	Permission to overtake and pass on the right .....	24
§ 4511.29	Driving to left of center line .....	24
§ 4511.30	Prohibition against driving upon left side of roadway .....	24
§ 4511.31	Hazardous zones.....	25
§ 4511.32	One-way highways and rotary traffic islands .....	25
§ 4511.33	Rules for driving in marked lanes .....	25
§ 4511.34	Space between moving vehicles .....	26
§ 4511.35	Divided roadways .....	26
§ 4511.36	Rules for turns at intersections.....	27
§ 4511.37	Turning in roadway prohibited; exception for emergency or public safety vehicle .....	27
§ 4511.41	Right-of-way at intersections .....	28
§ 4511.42	Right of way when turning left .....	28
§ 4511.43	Right-of-way at through highways; stop signs; yield signs .....	28
§ 4511.431	Stop at sidewalk area .....	29

<b>R.C. Section</b>	<b>Title/Description</b>	<b>Page in Appendix B2</b>
§ 4511.432	Stop signs on private residential road or driveway .....	29
§ 4511.44	Right of way on public highway .....	30
§ 4511.46	Pedestrian on crosswalk has right-of-way.....	30
§ 4511.48	Right of way yielded by pedestrian .....	31
§ 4511.481	Intoxicated or drugged pedestrian hazard on highway.....	31
§ 4511.61	Stop signs at grade crossings .....	31
§ 4511.62	Driver's duties relating to railroad grade crossings .....	32
§ 4511.63	Vehicles required to stop at grade crossings .....	32
§ 4511.64	Slow-moving vehicles or equipment crossing railroad tracks .....	33
§ 4511.65	Through highways .....	34
§ 4511.66	Prohibition against parking on highways .....	34
§ 4511.661	Condition when motor vehicle left unattended .....	35
§ 4511.67	Police may remove illegally parked vehicle .....	35
§ 4511.68	Parking prohibitions.....	35
§ 4511.681	Parking on private property .....	36
§ 4511.69	Parking near curb, facing direction of travel; locations and privileges for walking-impaired persons.....	36
§ 4511.712	Obstructing passage of other vehicles .....	38
§ 4511.75	Stopping for school bus; signals .....	39
§ 4511.76	School bus construction, design, equipment, operation and licensing rules.....	40
§ 4511.98	Warning signs as to increased penalties in construction zones.....	40
§ 4513.40	Warning sign before safety device at street crossing .....	41
§ 4519.40	Prohibitions.....	41
§ 4907.47	Installation of crossing signals; apportionment of cost; additional protective devices.....	41
§ 4907.471	Survey to determine crossings with highest probability of accident; additional protective devices .....	42
§ 4907.48	Regulation of crossing signals .....	44
§ 4907.49	Dangerous crossings .....	44
§ 4907.52	Safety devices at grade crossings.....	44
§ 4951.02	Grant of right to construct.....	44
§ 4951.14	Acquisition or appropriation for crossings .....	45
§ 4955.201	Abandonment of track; restoration of roadway .....	45
§ 4955.33	Crossbuck signs; additional reflective signs; experimental signs .....	45
§ 5501.27	Rules for warning signs in construction zones .....	46
§ 5591.42	Carrying capacity of bridges; warning notice.....	46

**§ 4511.04. Exceptions.**

- (A) Sections 4511.01 to 4511.18, 4511.20 to 4511.78, 4511.99, and 4513.01 to 4513.37 of the Revised Code do not apply to persons, teams, motor vehicles, and other equipment while actually engaged in work upon the surface of a highway within an area designated by traffic control devices, but apply to such persons and vehicles when traveling to or from such work.
- (B) The driver of a highway maintenance vehicle owned by this state or any political subdivision of this state, while the driver is engaged in the performance of official duties upon a street or highway, provided the highway maintenance vehicle is equipped with flashing lights and such other markings as are required by law, and such lights are in operation when the driver and vehicle are so engaged, shall be exempt from criminal prosecution for violations of sections 4511.22, 4511.25, 4511.26, 4511.27, 4511.28, 4511.30, 4511.31, 4511.33, 4511.35, 4511.66, 4513.02, and 5577.01 to 5577.09 of the Revised Code.
- (C) (1) This section does not exempt a driver of a highway maintenance vehicle from civil liability arising from the violation of sections 4511.22, 4511.25, 4511.26, 4511.27, 4511.28, 4511.30, 4511.31, 4511.33, 4511.35, 4511.66, or 4513.02 or sections 5577.01 to 5577.09 of the Revised Code.
- (2) This section does not exempt the driver of a vehicle that is engaged in the transport of highway maintenance equipment from criminal liability for a violation of sections 5577.01 to 5577.09 of the Revised Code.
- (D) As used in this section, “highway maintenance vehicle” means a vehicle used in snow and ice removal or road surface maintenance, including a snow plow, traffic line striper, road sweeper, mowing machine, asphalt distributing vehicle, or other such vehicle designed for use in specific highway maintenance activities.

HISTORY: GC § 6307-4; 119 v 766, § 4; Bureau of Code Revision, 10-1-53; 133 v S 77. Eff 11-17-69; 150 v H 87, § 1, eff.6-30-03.

**§ 4511.051. Prohibition against pedestrians and slow-moving vehicles on freeways.**

- (A) No person, unless otherwise directed by a police officer, shall:
- (1) As a pedestrian, occupy any space within the limits of the right-of-way of a freeway, except: in a rest area; on a facility that is separated from the roadway and shoulders of the freeway and is designed and appropriately marked for pedestrian use; in the performance of public works or official duties; as a result of an emergency caused by an accident or breakdown of a motor vehicle; or to obtain assistance;
  - (2) Occupy any space within the limits of the right-of-way of a freeway, with: an animal-drawn vehicle; a ridden or led animal; herded animals; a pushcart; a bicycle, except on a facility that is separated from the roadway and shoulders of the freeway and is designed and appropriately marked for bicycle use; a bicycle with motor attached; a motor driven cycle with a motor which produces not to exceed five brake horsepower; an agricultural tractor; farm machinery; except in the performance of public works or official duties.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 131 v 1099 (Eff 9-1-65); 132 v H 1 (Eff 2-21-67); 143 v H 258. Eff 11-2-89; 149 v S 123, § 1, eff. 1-1-04..

**§ 4511.06. Uniform application and precedence of traffic law.**

Sections 4511.01 to 4511.78, 4511.99, and 4513.01 to 4513.37 of the Revised Code shall be applicable and uniform throughout this state and in all political subdivisions and municipal corporations of this state. No local authority shall enact or enforce any rule in conflict with such sections, except that this section does not prevent local authorities from exercising the rights granted them by Chapter 4521. of the Revised Code and does not limit the effect or application of the provisions of that chapter.

HISTORY: GC § 6307-6; 119 v 766, § 6; Bureau of Code Revision, 10-1-53; 139 v H 707. Eff 1-1-83.

#### **§ 4511.07. Local traffic regulations.**

Sections 4511.01 to 4511.78, 4511.99, and 4513.01 to 4513.37 of the Revised Code do not prevent local authorities from carrying out the following activities with respect to streets and highways under their jurisdiction and within the reasonable exercise of the police power:

- (A) Regulating the stopping, standing, or parking of vehicles, trackless trolleys, and streetcars;
- (B) Regulating traffic by means of police officers or traffic control devices;
- (C) Regulating or prohibiting processions or assemblages on the highways;
- (D) Designating particular highways as one-way highways and requiring that all vehicles, trackless trolleys, and streetcars on the one-way highways be moved in one specific direction;
- (E) Regulating the speed of vehicles, streetcars, and trackless trolleys in public parks;
- (F) Designating any highway as a through highway and requiring that all vehicles, trackless trolleys, and streetcars stop before entering or crossing a through highway, or designating any intersection as a stop intersection and requiring all vehicles, trackless trolleys, and streetcars to stop at one or more entrances to the intersection;
- (G) Regulating or prohibiting vehicles and trackless trolleys from passing to the left of safety zones;
- (H) Regulating the operation of bicycles and requiring the registration and licensing of bicycles, including the requirement of a registration fee;
- (I) Regulating the use of certain streets by vehicles, streetcars, or trackless trolleys.

No ordinance or regulation enacted under division (D), (E), (F), (G), or (I) of this section shall be effective until signs giving notice of the local traffic regulations are posted upon or at the entrance to the highway or part of the highway affected, as may be most appropriate.

Every ordinance, resolution, or regulation enacted under division (A) of this section shall be enforced in compliance with section 4511.071 of the Revised Code, unless the local authority that enacted it also enacted an ordinance, resolution, or regulation pursuant to division (A) of section 4521.02 of the Revised Code that specifies that a violation of it shall not be considered a criminal offense, in which case the ordinance, resolution, or regulation shall be enforced in compliance with Chapter 4521. of the Revised Code.

HISTORY: GC § 6307-7; 119 v 766; Bureau of Code Revision, 10-1-53; 129 v 1037 (Eff 8-11-61); 133 v S 452 (Eff 7-17-70); 135 v H 995 (Eff 1-1-75); 138 v S 257 (Eff 6-25-80); 139 v H 707. Eff 1-1-83.

#### **§ 4511.09. Uniform system of traffic control devices.**

The department of transportation shall adopt a manual and specifications for a uniform system of traffic control devices, including signs denoting names of streets and highways, for use upon highways within this state. Such uniform system shall correlate with, and so far as possible conform to, the system approved by the American Association of State Highway Officials.

HISTORY: GC § 6307-9; 119 v 766, § 9; Bureau of Code Revision, 10-1-53; 135 v H 200. Eff 9-28-73.

The manual referred to is the "Ohio Manual of Uniform Traffic Control Devices for Streets and Highways" prepared by the Ohio Department of Transportation, Office of Traffic Engineering, and for sale by the Office of Contracts, 1980 W. Broad St., P.O. Box 899, Columbus, Ohio 43216-0899.

#### **§ 4511.10. Placing and maintaining traffic control devices.**

The department of transportation may place and maintain traffic control devices, conforming to its manual and specifications, upon all state highways as are necessary to indicate and to carry out sections 4511.01 to 4511.78 and 4511.99 of the Revised Code, or to regulate, warn, or guide traffic.

No local authority shall place or maintain any traffic control device upon any highway under the jurisdiction of the department except by permission of the director of transportation.

HISTORY: GC § 6307-10; 119 v 766, § 10; Bureau of Code Revision, 10-1-53; 135 H 200. Eff 9-28-73.

The manual referred to is the "Ohio Manual of Uniform Traffic Control Devices for Streets and Highways" prepared by the Ohio Department of Transportation, Office of Traffic Engineering, and for sale by the Office of Contracts, 1980 W. Broad St., P.O. Box 899, Columbus, Ohio 43216-0899.

**§ 4511.101. Business logos on directional signs along interstates.**

- (A) The director of transportation, in accordance with 23 U.S.C.A. 109(d), 131(f), and 315, as amended, shall establish a program for the placement of business logos for identification purposes on state directional signs within the rights-of-way of divided, multi-lane, limited access highways in both rural and urban areas.
- (B) All direct and indirect costs of the business logo sign program established pursuant to this section shall be fully paid by the businesses applying for participation in the program. At any interchange where a business logo sign is erected, such costs shall be divided equally among the participating businesses. The direct and indirect costs of the program shall include, but not be limited to, the cost of capital, directional signs, blanks, posts, logos, installation, repair, engineering, design, insurance, removal, replacement, and administration. Nothing in this chapter shall be construed to prohibit the director from establishing such a program.
- (C) The director, in accordance with rules adopted pursuant to Chapter 119. of the Revised Code, may contract with any private person to operate, maintain, and market the business logo sign program. The rules shall describe the terms of the contract, and shall allow for a reasonable profit to be earned by the successful applicant. In awarding the contract, the director shall consider the skill, expertise, prior experience, and other qualifications of each applicant.
- (D) As used in this section, "urban area" means an area having a population of fifty thousand or more according to the most recent federal census and designated as such on urban maps prepared by the department.
- (E) Neither the department nor the director shall do either of the following:
  - (1) Limit the right of any person to erect, maintain, repair, remove, or utilize any off-premises or on-premises advertising device;
  - (2) Make participation in the business logo sign program conditional upon a business agreeing to limit, discontinue, withdraw, modify, alter, or change any advertising or sign.

HISTORY: 143 v H 356 (Eff 11-2-89); 143 v H 737 (Eff 4-11-91); 145 v H 154 (Eff 6-30-93); 146 v H 107 (Eff 6-30-95); 146 v H 353 (Eff 9-17-96); 146 v H 670 (Eff 12-2-96); 147 v H 210 (Eff 6-30-97); 147 v H 462. Eff 3-18-99.

**§ 4511.102. Definitions.**

As used in sections 4511.102 to 4511.106 of the Revised Code:

- (A) "Tourist-oriented activity" includes any lawful cultural, historical, recreational, educational, or commercial activity a major portion of whose income or visitors are derived during the normal business season from motorists not residing in the immediate area of the activity and attendance at which is no less than two thousand visitors in any consecutive twelve-month period.
- (B) "Eligible attraction" means any tourist-oriented activity that meets all of the following criteria:
  - (1) Is not eligible for inclusion in the business logo sign program established under section 4511.101 of the Revised Code;
  - (2) If currently advertised by signs adjacent to a highway on the interstate system or state system, those signs are consistent with Chapter 5516. of the Revised Code and the "National Highway Beautification Act of 1965," 79 Stat. 1028, 23 U.S.C. 131, and the national standards, criteria, and rules adopted pursuant to that act;
  - (3) Is within ten miles of the highway for which signing is sought under sections 4511.102 to 4511.105 of the Revised Code;
  - (4) Meets any additional criteria developed by the director of transportation and adopted by the director as rules in accordance with Chapter 119. of the Revised Code.

- (C) "Interstate system" has the same meaning as in section 5516.01 of the Revised Code.
- (D) "Commercial activity" means a farm market, winery, bed and breakfast, lodging that is not a franchise or part of a national chain, antiques shop, craft store, or gift store.

HISTORY: 145 v H 687 (Eff 10-12-94); 146 v H 217 (Eff 11-1-95); 147 v H 210 (Eff 6-30-97); 147 v H 215. Eff 6-30-97.

**§ 4511.103. Rules for placement of tourist-oriented directional signs and trailblazer markers.**

- (A) The director of transportation, in accordance with 23 U.S.C. 109(d) and 315, with the provisions of the federal manual of uniform traffic control devices relating to tourist-oriented directional signs and trailblazer markers, and with Chapter 119. of the Revised Code, shall adopt rules to carry out a program for the placement of tourist-oriented directional signs and trailblazer markers within the rights-of-way of those portions of rural state highways that are not on the interstate system. The rules shall prohibit the placement of tourist-oriented directional signs and trailblazer markers at interchanges on state system expressways and freeways. The rules shall include, but need not be limited to, all of the following:
- (1) The form of the application to participate in the program. The form shall include such necessary information as the director requires to ensure that a tourist-oriented activity for which signing is sought is an eligible attraction.
  - (2) Provisions for covering or otherwise obscuring signs during off-seasons for eligible attractions that operate on a seasonal basis;
  - (3) A determination as to the circumstances that justify including on a sign the hours of operation of an eligible attraction;
  - (4) Criteria for use of the signs at at-grade intersections on expressways.
- (B) The program established pursuant to division (A) of this section may be operated, maintained, and marketed either by the department of transportation or by any private person with whom the director, in accordance with rules adopted by the director pursuant to Chapter 119. of the Revised Code, contracts for the operation, maintenance, and marketing. The rules shall describe the terms of the contract and shall allow for a reasonable profit to be made by the successful applicant. In awarding the contract, the director shall consider the skill, expertise, prior experience, and other qualifications of each applicant.
- (C) All direct and indirect costs of the program shall be fully paid by the eligible attractions that participate in the program. The director shall develop a fee schedule for participation in the program, and shall charge each program participant the appropriate fee. Direct and indirect costs include, but are not limited to, the cost of all of the following:
- (1) Capital;
  - (2) Insurance;
  - (3) Directional signs, sign blanks, and posts, and the design, engineering, installation, repair, replacement, and removal of directional signs and posts;
  - (4) Program administration.

HISTORY: 145 v H 687 (Eff 10-12-94); 146 v H 217. Eff 11-1-95.

**§ 4511.104. Advertising agreement with tourist-oriented attractions.**

- (A) The operator of any tourist-oriented activity who wishes to participate in the tourist-oriented directional sign program established under sections 4511.102 to 4511.105 of the Revised Code shall forward a completed application, as provided in section 4511.103 of the Revised Code, to the director of transportation or person holding a contract under division (B) of section 4511.103 of the Revised Code. If the director or person finds the application to be complete and determines that the activity constitutes an eligible attraction, the director or person shall so notify the applicant in writing. Upon receipt of the notice, the applicant shall forward to the director or person, in a manner determined by the director, the amount of the fee due and thereupon shall execute an advertising agreement in a form prescribed by the director.
- (B) The operator of any eligible attraction for which an advertising agreement is in effect under this section immediately shall forward the advertising agreement to the director or person holding a contract under

division (B) of section 4511.103 of the Revised Code for cancellation if the eligible attraction ceases to be such an attraction.

- (C) The director, when having reasonable cause to believe that an eligible attraction for which an advertising agreement is in effect has ceased to be such an attraction, immediately and without conducting an adjudication shall issue an order canceling the advertising agreement and forward notice of the cancellation in writing to the operator of the attraction together with information that the cancellation may be appealed in accordance with section 119.12 of the Revised Code. If no appeal is entered within the period specified in that section or if an appeal is entered but cancellation of the advertising agreement subsequently is affirmed, the director shall order the removal of the signs relating to the former eligible attraction.
- (D) Any person holding a contract under division (B) of section 4511.103 of the Revised Code, when having reasonable cause to believe that an eligible attraction for which an advertising agreement is in effect has ceased to be such an attraction, immediately shall notify the director in writing of that fact. Upon receipt of the notice, the director shall proceed in accordance with division (C) of this section.

HISTORY: 145 v H 687 (Eff 10-12-94); 146 v H 217. Eff 11-1-95.

**§ 4511.105. Signs to conform to federal manual; logos.**

Tourist-oriented directional signs shall conform to the specifications contained in the federal manual of uniform traffic control devices.

If more than one eligible attraction requires a sign at the same location, multiple signs may be combined on the same panel in accordance with the federal manual of uniform traffic control devices.

Advance signing may be installed in those situations where sight distance, intersection vehicle maneuvers, or other vehicle operating characteristics require advance notice of an eligible attraction in order to reduce vehicle conflicts and improve highway safety.

The design, arrangement, size, and location of tourist-oriented directional signs, including advance signs and trailblazer markers, authorized under sections 4511.102 to 4511.105 of the Revised Code shall conform to the applicable specifications contained in the federal manual of uniform traffic control devices.

HISTORY: 145 v H 687 (Eff 10-12-94); 146 v H 217. Eff 11-1-95.

**§ 4511.106. Local authority programs.**

The legislative authority of a local authority may adopt a resolution establishing a program for the placement of tourist-oriented directional signs and trailblazer markers within the rights-of-way of streets and highways under its jurisdiction. Any program established under this section shall conform to the rules and specifications contained in the program established by the director of transportation pursuant to sections 4511.102 to 4511.105 of the Revised Code and the applicable provisions of the federal manual of uniform traffic control devices. If a local authority establishes a program under this section, the local authority may request guidance from the department of transportation in structuring, implementing, and administering its program, but the local authority is solely responsible for the structure and actual implementation and administration of its program, including, but not limited to, the evaluation and review of applications to participate in the local

program and the execution of advertising agreements with eligible attractions.

HISTORY: 145 v H 687 (Eff 10-12-94); 146 v H 217. Eff 11-1-95.

**§ 4511.11. Uniformity of traffic control devices.**

- (A) Local authorities in their respective jurisdictions shall place and maintain traffic control devices in accordance with the department of transportation manual and specifications for a uniform system of traffic control devices, adopted under section 4511.09 of the Revised Code, upon highways under their jurisdiction as are necessary to indicate and to carry out sections 4511.01 to 4511.76 and 4511.99 of the Revised Code, local traffic ordinances, or to regulate, warn, or guide traffic.
- (B) The director of transportation may require to be removed any traffic control device that does not conform to the manual and specifications for a uniform system of traffic control devices on the extensions of the state highway system within municipal corporations.

- (C) No village shall place or maintain any traffic control signal upon an extension of the state highway system within the village without first obtaining the permission of the director. The director may revoke the permission and may require to be removed any traffic control signal that has been erected without the director's permission on an extension of a state highway within a village, or that, if erected under a permit granted by the director, does not conform to the state manual and specifications, or that is not operated in accordance with the terms of the permit.
- (D) All traffic control devices erected on a public road, street, or alley, shall conform to the state manual and specifications.
- (E) No person, firm, or corporation shall sell or offer for sale to local authorities any traffic control device that does not conform to the state manual and specifications, except by permission of the director.
- (F) No local authority shall purchase or manufacture any traffic control device that does not conform to the state manual and specifications, except by permission of the director.
- (G) Whoever violates division (E) of this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-11; 119 v 766, § 11; 121 v 684; Bureau of Code Revision, 10-1-53; 130 v 1081 (Eff 10-14-63); 130 v PtlI, H 5 (Eff 12-16-64); 131 v 1100 (Eff 11-1-65); 135 v H 200 (Eff 9-28-73); 143 v H 258 (Eff 11-2-89); 143 v H 162. Eff 6-28-90; 149 v S 123, § 1, eff. 1-1-04.

#### **§ 4511.12. Obeying traffic control devices.**

- (A) No pedestrian, driver of a vehicle, or operator of a streetcar or trackless trolley shall disobey the instructions of any traffic control device placed in accordance with this chapter, unless at the time otherwise directed by a police officer.

No provisions of this chapter for which signs are required shall be enforced against an alleged violator if at the time and place of the alleged violation an official sign is not in proper position and sufficiently legible to be seen by an ordinarily observant person. Whenever a particular section of this chapter does not state that signs are required, that section shall be effective even though no signs are erected or in place.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-12; 119 v 766, § 12; 124 v 514; Bureau of Code Revision, 10-1-53; 143 v H 258. Eff 11-2-89; 149 v S123, § 1, eff. 1-1-04.

#### **§ 4511.13. Signal lights.**

Whenever traffic is controlled by traffic control signals exhibiting different colored lights, or colored lighted arrows, successively one at a time or in combination, only the colors green, red, and yellow shall be used, except for special pedestrian signals carrying words or symbols, and said lights shall indicate and apply to drivers of vehicles, streetcars, and trackless trolleys, and to pedestrians as follows:

- (A) Green indication:
  - (1) Vehicular traffic, streetcars, and trackless trolleys facing a circular green signal may proceed straight through or turn right or left unless a sign at such place prohibits either such turn. But vehicular traffic, streetcars, and trackless trolleys, including vehicles, streetcars, and trackless trolleys turning right or left, shall yield the right-of-way to other vehicles, streetcars, trackless trolleys, and pedestrians lawfully within the intersection or an adjacent crosswalk at the time such signal is exhibited.
  - (2) Vehicular traffic, streetcars, and trackless trolleys facing a green arrow signal, shown alone or in combination with another indication, may cautiously enter the intersection only to make the movement indicated by such arrow, or such other movement as is permitted by other indications shown at the same time. Such vehicular traffic, streetcars, and trackless trolleys shall yield the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.

- (3) Unless otherwise directed by a pedestrian-control signal, as provided in section 4511.14 of the Revised Code, pedestrians facing any green signal, except when the sole green signal is a turn arrow, may proceed across the roadway within any marked or unmarked crosswalk.
- (B) Steady yellow indication:
- (1) Vehicular traffic, streetcars, and trackless trolleys facing a steady circular yellow or yellow arrow signal are thereby warned that the related green movement is being terminated or that a red indication will be exhibited immediately thereafter when vehicular traffic, streetcars, and trackless trolleys shall not enter the intersection.
  - (2) Pedestrians facing a steady circular yellow or yellow arrow signal, unless otherwise directed by a pedestrian-control signal as provided in section 4511.14 of the Revised Code, are thereby advised that there is insufficient time to cross the roadway before a red indication is shown and no pedestrian shall then start to cross the roadway.
- (C) Steady red indication:
- (1) Vehicular traffic, streetcars, and trackless trolleys facing a steady red signal alone shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or if none, then before entering the intersection and shall remain standing until an indication to proceed is shown except as provided in divisions (C)(2) and (3) of this section.
  - (2) Unless a sign is in place prohibiting a right turn as provided in division (C)(5) of this section, vehicular traffic, streetcars, and trackless trolleys facing a steady red signal may cautiously enter the intersection to make a right turn after stopping as required by division (C)(1) of this section. Such vehicular traffic, streetcars, and trackless trolleys shall yield the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.
  - (3) Unless a sign is in place prohibiting a left turn as provided in division (C)(5) of this section, vehicular traffic, streetcars, and trackless trolleys facing a steady red signal on a one-way street that intersects another one-way street on which traffic moves to the left may cautiously enter the intersection to make a left turn into the one-way street after stopping as required by division (C)(1) of this section, and yielding the right-of-way to pedestrians lawfully within an adjacent crosswalk and to other traffic lawfully using the intersection.
  - (4) Unless otherwise directed by a pedestrian-control signal as provided in section 4511.14 of the Revised Code, pedestrians facing a steady red signal alone shall not enter the roadway.
  - (5) Local authorities may by ordinance, or the director of transportation on state highways may, prohibit a right or a left turn against a steady red signal at any intersection, which shall be effective when signs giving notice thereof are posted at the intersection.
- (D) In the event an official traffic-control signal is erected and maintained at a place other than an intersection, the provisions of this section shall be applicable except as to those provisions which by their nature can have no application. Any stop required shall be made at a sign or marking on the pavement indicating where the stop shall be made, but in the absence of any such sign or marking the stop shall be made at the signal.

HISTORY: GC § 6307-13; 119 v 766, § 13; 124 v 514; Bureau of Code Revision, 10-1-53; 130 v 1081 (Eff 8-9-63); 135 v S 263 (Eff 7-3-74); 135 v H 99 (Eff 7-1-75); 137 v H 171 (Eff 8-26-77); 140 v H 703. Eff 3-28-85.

**§ 4511.131. Signals over reversible lanes.**

When lane-use control signals are placed over individual lanes of a street or highway, said signals shall indicate and apply to drivers of vehicles and trackless trolleys as follows:

- (A) A steady downward green arrow:  
Vehicular traffic and trackless trolleys may travel in any lane over which a green arrow signal is shown.
- (B) A steady yellow "X":  
Vehicular traffic and trackless trolleys are warned to vacate in a safe manner any lane over which such signal is shown to avoid occupying that lane when a steady red "X" signal is shown.

## (C) A flashing yellow "X":

Vehicular traffic and trackless trolleys may use with proper caution any lane over which such signal is shown for only the purpose of making a left turn.

## (D) A steady red "X":

Vehicular traffic and trackless trolleys shall not enter or travel in any lane over which such signal is shown.

HISTORY: 130 v 1083 (Eff 8-9-63); 135 v S 263. Eff 7-3-74.

**§ 4511.132. Malfunctioning traffic signals.**

(A) The driver of a vehicle, streetcar, or trackless trolley who approaches an intersection where traffic is controlled by traffic control signals shall do all of the following, if the signal facing the driver either exhibits no colored lights or colored lighted arrows or exhibits a combination of such lights or arrows that fails to clearly indicate the assignment of right-of-way:

- (1) Stop at a clearly marked stop line, but if none, stop before entering the crosswalk on the near side of the intersection, or, if none, stop before entering the intersection;
- (2) Yield the right-of-way to all vehicles, streetcars, or trackless trolleys in the intersection or approaching on an intersecting road, if the vehicles, streetcars, or trackless trolleys will constitute an immediate hazard during the time the driver is moving across or within the intersection or junction of roadways;
- (3) Exercise ordinary care while proceeding through the intersection.

(B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 143 v S 44. Eff 7-25-89; 149 v S123, § 1, eff. 1-1-04.

**§ 4511.14. Pedestrian control signals.**

Whenever special pedestrian control signals exhibiting the words "walk" or "don't walk," or the symbol of a walking person or an upraised palm are in place, such signals shall indicate the following instructions:

- (A) "Walk" or the symbol of a walking person: Pedestrians facing such signal may proceed across the roadway in the direction of the signal and shall be given the right of way by the operators of all vehicles, streetcars, and trackless trolleys.
- (B) "Don't walk" or the symbol of an upraised palm: No pedestrian shall start to cross the roadway in the direction of the signal.
- (C) Nothing in this section shall be construed to invalidate the continued use of pedestrian control signals utilizing the word "wait" if those signals were installed prior to the effective date of this act.

HISTORY: GC § 6307-14; 119 v 766, § 14; 124 v 514; Bureau of Code Revision, 10-1-53; 140 v H 703. Eff 3-28-85

**§ 4511.15. Flashing traffic signals.**

Whenever an illuminated flashing red or yellow traffic signal is used in a traffic signal or with a traffic sign it shall require obedience as follows:

- (A) Flashing red stop signal: Operators of vehicles, trackless trolleys, and streetcars shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or if none, then at the point nearest the intersecting roadway where the driver has a view of approaching traffic on the intersecting roadway before entering it, and the right to proceed shall be subject to the rules applicable after making a stop at a stop sign.

- (B) Flashing yellow caution signal: Operators of vehicles, trackless trolleys, and streetcars may proceed through the intersection or past such signal only with caution.

This section shall not apply at railroad grade crossings. Conduct of drivers of vehicles, trackless trolleys, and streetcars approaching railroad grade crossings shall be governed by sections 4511.61 and 4511.62 of the Revised Code.

HISTORY: GC § 6307-15; 119 v 766, § 15; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75.

**§ 4511.16. Prohibition against unauthorized signs and signals.**

- (A) No person shall place, maintain, or display upon or in view of any highway any unauthorized sign, signal, marking, or device which purports to be, is an imitation of, or resembles a traffic control device or railroad sign or signal, or which attempts to direct the movement of traffic or hides from view or interferes with the effectiveness of any traffic control device or any railroad sign or signal, and no person shall place or maintain, nor shall any public authority permit, upon any highway any traffic sign or signal bearing thereon any commercial advertising. This section does not prohibit either the erection upon private property adjacent to highways of signs giving useful directional information and of a type that cannot be mistaken for traffic control devices or the erection upon private property of traffic control devices by the owner of real property in accordance with sections 4511.211 and 4511.432 of the Revised Code.

Every such prohibited sign, signal, marking, or device is a public nuisance, and the authority having jurisdiction over the highway may remove it or cause it to be removed.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-16; 119 v 766, § 16; Bureau of Code Revision, 10-1-53; 143 v H 171. Eff 5-31-90; 149 v S123, § 1, eff. 1-1-04.

**§ 4511.17. Tampering with sign, device or manhole cover; driving on freshly applied marking material.**

- (A) No person, without lawful authority, shall do any of the following:

- (1) Knowingly move, deface, damage, destroy, or otherwise improperly tamper with any traffic control device, any railroad sign or signal, or any inscription, shield, or insignia on the device, sign, or signal, or any part of the device, sign, or signal;
- (2) Knowingly drive upon or over any freshly applied pavement marking material on the surface of a roadway while the marking material is in an undried condition and is marked by flags, markers, signs, or other devices intended to protect it;
- (3) Knowingly move, damage, destroy, or otherwise improperly tamper with a manhole cover.

- (B) (1) Except as otherwise provided in this division, whoever violates division (A)(1) or (3) of this section is guilty of a misdemeanor of the third degree. If a violation of division (A)(1) or (3) of this section creates a risk of physical harm to any person, the offender is guilty of a misdemeanor of the first degree. If a violation of division (A)(1) or (3) of this section causes serious physical harm to property that is owned, leased, or controlled by a state or local authority, the offender is guilty of a felony of the fifth degree.

- (2) Except as otherwise provided in this division, whoever violates division (A)(2) of this section is guilty of a minor misdemeanor. If within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates division (A)(2) of this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates division (A)(2) of this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-17; 119 v 766, § 17; 121 v 684; Bureau of Code Revision, 10-1-53; 143 v H 162. Eff 6-28-90; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.18. Possession or sale of sign or device prohibited.**

- (A) As used in this section, "traffic control device" means any sign, traffic control signal, or other device conforming to and placed or erected in accordance with the manual adopted under section 4511.09 of the Revised Code by authority of a public body or official having jurisdiction, for the purpose of regulating, warning, or guiding traffic, including signs denoting the names of streets and highways, but does not mean any pavement marking.
- (B) No individual shall buy or otherwise possess, or sell, a traffic control device, except when one of the following applies:
- (1) In the course of the individual's employment by the state or a local authority for the express or implied purpose of manufacturing, providing, erecting, moving, or removing such a traffic control device;
  - (2) In the course of the individual's employment by any manufacturer of traffic control devices other than a state or local authority;
  - (3) For the purpose of demonstrating the design and function of a traffic control device to state or local officials;
  - (4) When the traffic control device has been purchased from the state or a local authority at a sale of property that is no longer needed or is unfit for use;
  - (5) The traffic control device has been properly purchased from a manufacturer for use on private property and the person possessing the device has a sales receipt for the device or other acknowledgment of sale issued by the manufacturer.
- (C) This section does not preclude, and shall not be construed as precluding, prosecution for theft in violation of section 2913.02 of the Revised Code or a municipal ordinance relating to theft, or for receiving stolen property in violation of section 2913.51 of the Revised Code or a municipal ordinance relating to receiving stolen property.
- (D) Whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 143 v H 162. Eff 6-28-90; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.20. Willful or wanton operation on street or highway.**

- (A) No person shall operate a vehicle, trackless trolley, or streetcar on any street or highway in willful or wanton disregard of the safety of persons or property.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-20; 119 v 766, § 20; Bureau of Code Revision, 10-1-53; 132 v S 179 (Eff 12-13-67); 139 v S 432. Eff 3-16-83; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.201. Willful or wanton operation off street or highway; competitive operation exception.**

- (A) No person shall operate a vehicle, trackless trolley, or streetcar on any public or private property other than streets or highways, in willful or wanton disregard of the safety of persons or property.

This section does not apply to the competitive operation of vehicles on public or private property when the owner of such property knowingly permits such operation thereon.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 129 v 1637 (Eff 10-2-61); 132 v S 179 (Eff 12-13-67); 139 v S 432. Eff 3-16-83; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.202. Operating vehicle without reasonable control.**

- (A) No person shall operate a motor vehicle, trackless trolley, or streetcar on any street, highway, or property open to the public for vehicular traffic without being in reasonable control of the vehicle, trolley, or streetcar.
- (B) Whoever violates this section is guilty of operating a motor vehicle without being in control of it, a minor misdemeanor.

HISTORY: 139 v S 432. Eff 3-16-83; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.21. Speed Limits.**

- (A) No person shall operate a motor vehicle, trackless trolley, or streetcar at a speed greater or less than is reasonable or proper, having due regard to the traffic, surface, and width of the street or highway and any other conditions, and no person shall drive any motor vehicle, trackless trolley, or streetcar in and upon any street or highway at a greater speed than will permit the person to bring it to a stop within the assured clear distance ahead.
- (B) It is prima-facie lawful, in the absence of a lower limit declared pursuant to this section by the director of transportation or local authorities, for the operator of a motor vehicle, trackless trolley, or streetcar to operate the same at a speed not exceeding the following:
  - (1) (a) Twenty miles per hour in school zones during school recess and while children are going to or leaving school during the opening or closing hours, and when twenty miles per hour school speed limit signs are erected; except, that, on controlled-access highways and expressways, if the right-of-way line fence has been erected without pedestrian opening, the speed shall be governed by division (B)(4) of this section and on freeways, if the right-of-way line fence has been erected without pedestrian opening, the speed shall be governed by divisions (B)(8) and (9) of this section. The end of every school zone may be marked by a sign indicating the end of the zone. Nothing in this section or in the manual and specifications for a uniform system of traffic control devices shall be construed to require school zones to be indicated by signs equipped with flashing or other lights, or giving other special notice of the hours in which the school zone speed limit is in effect.
  - (b) As used in this section and in section 4511.212 of the Revised Code, "school" means any school chartered under section 3301.16 of the Revised Code and any nonchartered school that during the preceding year filed with the department of education in compliance with rule 3301-35-08 of the Ohio Administrative Code, a copy of the school's report for the parents of the school's pupils certifying that the school meets Ohio minimum standards for non chartered, non tax-supported schools and presents evidence of this filing to the jurisdiction from which it is requesting the establishment of a school zone.
  - (c) As used in this section, "school zone" means that portion of a street or highway passing a school fronting upon the street or highway that is encompassed by projecting the school property lines to the fronting street or highway, and also includes that portion of a state highway. Upon request from local authorities for streets and highways under their jurisdiction and that portion of a state highway under the jurisdiction of the director of transportation, the director may extend the traditional school zone boundaries. The distances in divisions (B)(1)(c)(i) (ii), and (iii) of this section shall not exceed three hundred feet per approach per direction and are bounded by whichever of the following distances or combinations thereof the director approves as most appropriate:
    - (i) The distance encompassed by projecting the school building lines normal to the fronting highway and extending a distance of three hundred feet on each approach direction;
    - (ii) The distance encompassed by projecting the school property lines intersecting the fronting highway and extending a distance of three hundred feet on each approach direction;

- (iii) The distance encompassed by the special marking of the pavement for a principal school pupil crosswalk plus a distance of three hundred feet on each approach direction of the highway.

Nothing in this section shall be construed to invalidate the director's initial action on August 9, 1976, establishing all school zones at the traditional school zone boundaries defined by projecting school property lines, except when those boundaries are extended as provided in divisions (B)(1)(a) and (c) of this section.

- (d) As used in this division, "crosswalk" has the meaning given that term in division (LL)(2) of section 4511.01 of the Revised Code.

The director may, upon request by resolution of the legislative authority of a municipal corporation, the board of trustees of a township, or a county board of mental retardation and developmental disabilities created pursuant to Chapter 5126. of the Revised Code, and upon submission by the municipal corporation, township, or county board of such engineering, traffic, and other information as the director considers necessary, designate a school zone on any portion of a state route lying within the municipal corporation, lying within the unincorporated territory of the township, or lying adjacent to the property of a school that is operated by such county board, that includes a crosswalk customarily used by children going to or leaving a school during recess and opening and closing hours, whenever the distance, as measured in a straight line, from the school property line nearest the crosswalk to the nearest point of the crosswalk is no more than one thousand three hundred twenty feet. Such a school zone shall include the distance encompassed by the crosswalk and extending three hundred feet on each approach direction of the state route.

- (2) Twenty-five miles per hour in all other portions of a municipal corporation, except on state routes outside business districts, through highways outside business districts, and alleys;
- (3) Thirty-five miles per hour on all state routes or through highways within municipal corporations outside business districts, except as provided in divisions (B)(4) and (6) of this section;
- (4) Fifty miles per hour on controlled-access highways and expressways within municipal corporations;
- (5) Fifty-five miles per hour on highways outside of municipal corporations, other than freeways as provided in division (B)(12) of this section;
- (6) Fifty miles per hour on state routes within municipal corporations outside urban districts unless a lower prima-facie speed is established as further provided in this section;
- (7) Fifteen miles per hour on all alleys within the municipal corporation;
- (8) Fifty-five miles per hour at all times on freeways with paved shoulders inside municipal corporations, other than freeways as provided in division (B)(12) of this section;
- (9) Fifty-five miles per hour at all times on freeways outside municipal corporations, other than freeways as provided in division (B)(12) of this section;
- (10) Fifty-five miles per hour at all times on all portions of freeways that are part of the interstate system and on all portions of freeways not part of the interstate system, but are built to the standards and specifications that are applicable to freeways that are part of the interstate system for operators of any motor vehicle weighing in excess of eight thousand pounds empty weight and any noncommercial bus;
- (11) Fifty-five miles per hour for operators of any motor vehicle weighing eight thousand pounds or less empty weight and any commercial bus at all times on all portions of freeways that are part of the interstate system and that had such a speed limit established prior to October 1, 1995, and freeways that are not part of the interstate system, but are built to the standards and specifications that are applicable to freeways that are part of the interstate system and that had such a speed limit established prior to October 1, 1995, unless a higher speed limit is established under division (L) of this section;
- (12) Sixty-five miles per hour for operators of any motor vehicle weighing eight thousand pounds or less empty weight and any commercial bus at all times on all portions of the following:

- (a) Freeways that are part of the interstate system and that had such a speed limit established prior to October 1, 1995, and freeways that are not part of the interstate system, but are built to the standards and specifications that are applicable to freeways that are part of the interstate system and that had such a speed limit established prior to October 1, 1995;
  - (b) Freeways that are part of the interstate system and freeways that are not part of the interstate system but are built to the standards and specifications that are applicable to freeways that are part of the interstate system, and that had such a speed limit established under division (L) of this section;
  - (c) Rural, divided, multi-lane highways that are designated as part of the national highway system under the "National Highway System Designation Act of 1995," 109 Stat. 568, 23 U.S.C.A. 103, and that had such a speed limit established under division (M) of this section.
- (C) It is prima-facie unlawful for any person to exceed any of the speed limitations in divisions (B)(1)(a), (2), (3), (4), (6), and (7) of this section, or any declared pursuant to this section by the director or local authorities and it is unlawful for any person to exceed any of the speed limitations in division (D) of this section. No person shall be convicted of more than one violation of this section for the same conduct, although violations of more than one provision of this section may be charged in the alternative in a single affidavit.
- (D) No person shall operate a motor vehicle, trackless trolley, or streetcar upon a street or highway as follows:
- (1) At a speed exceeding fifty-five miles per hour, except upon a freeway as provided in division (B)(12) of this section;
  - (2) At a speed exceeding sixty-five miles per hour upon a freeway as provided in division (B)(12) of this section except as otherwise provided in division (D)(3) of this section;
  - (3) If a motor vehicle weighing in excess of eight thousand pounds empty weight or a noncommercial bus as prescribed in division (B)(10) of this section, at a speed exceeding fifty-five miles per hour upon a freeway as provided in that division;
  - (4) At a speed exceeding the posted speed limit upon a freeway for which the director has determined and declared a speed limit of not more than sixty-five miles per hour pursuant to division (L)(2) or (M) of this section;
  - (5) At a speed exceeding sixty-five miles per hour upon a freeway for which such a speed limit has been established through the operation of division (L)(3) of this section;
  - (6) At a speed exceeding the posted speed limit upon a freeway for which the director has determined and declared a speed limit pursuant to division (L)(2) of this section.
- (E) In every charge of violation of this section the affidavit and warrant shall specify the time, place, and speed at which the defendant is alleged to have driven, and in charges made in reliance upon division (C) of this section also the speed which division (B)(1)(a), (2), (3), (4), (6), or (7) of, or a limit declared pursuant to, this section declares is prima-facie lawful at the time and place of such alleged violation, except that in affidavits where a person is alleged to have driven at a greater speed than will permit the person to bring the vehicle to a stop within the assured clear distance ahead the affidavit and warrant need not specify the speed at which the defendant is alleged to have driven.
- (F) When a speed in excess of both a prima-facie limitation and a limitation in division (D)(1), (2), (3), (4), (5), or (6) of this section is alleged, the defendant shall be charged in a single affidavit, alleging a single act, with a violation indicated of both division (B)(1)(a), (2), (3), (4), (6), or (7) of this section, or of a limit declared pursuant to this section by the director or local authorities, and of the limitation in division (D)(1), (2), (3), (4), (5), or (6) of this section. If the court finds a violation of division (B)(1)(a), (2), (3), (4), (6), or (7) of, or a limit declared pursuant to, this section has occurred, it shall enter a judgment of conviction under such division and dismiss the charge under division (D)(1), (2), (3), (4), (5), or (6) of this section. If it finds no violation of division (B)(1)(a), (2), (3), (4), (6), or (7) of, or a limit declared pursuant to, this section, it shall then consider whether the evidence supports a conviction under division (D)(1), (2), (3), (4), (5), or (6) of this section.
- (G) Points shall be assessed for violation of a limitation under division (D) of this section in accordance with section 4510.036 of the Revised Code.

- (H) Whenever the director determines upon the basis of a geometric and traffic characteristic study that any speed limit set forth in divisions (B)(1)(a) to (D) of this section is greater or less than is reasonable or safe under the conditions found to exist at any portion of a street or highway under the jurisdiction of the director, the director shall determine and declare a reasonable and safe prima-facie speed limit, which shall be effective when appropriate signs giving notice of it are erected at the location.
- (I) (1) Except as provided in divisions (I)(2) and (K) of this section, whenever local authorities determine upon the basis of an engineering and traffic investigation that the speed permitted by divisions (B)(1)(a) to (D) of this section, on any part of a highway under their jurisdiction, is greater than is reasonable and safe under the conditions found to exist at such location, the local authorities may by resolution request the director to determine and declare a reasonable and safe prima-facie speed limit. Upon receipt of such request the director may determine and declare a reasonable and safe prima-facie speed limit at such location, and if the director does so, then such declared speed limit shall become effective only when appropriate signs giving notice thereof are erected at such location by the local authorities. The director may withdraw the declaration of a prima-facie speed limit whenever in the director's opinion the altered prima-facie speed becomes unreasonable. Upon such withdrawal, the declared prima-facie speed shall become ineffective and the signs relating thereto shall be immediately removed by the local authorities.
- (2) A local authority may determine on the basis of a geometric and traffic characteristic study that the speed limit of sixty-five miles per hour on a portion of a freeway under its jurisdiction that was established through the operation of division (L)(3) of this section is greater than is reasonable or safe under the conditions found to exist at that portion of the freeway. If the local authority makes such a determination, the local authority by resolution may request the director to determine and declare a reasonable and safe speed limit of not less than fifty-five miles per hour for that portion of the freeway. If the director takes such action, the declared speed limit becomes effective only when appropriate signs giving notice of it are erected at such location by the local authority.
- (J) Local authorities in their respective jurisdictions may authorize by ordinance higher prima-facie speeds than those stated in this section upon through highways, or upon highways or portions thereof where there are no intersections, or between widely spaced intersections, provided signs are erected giving notice of the authorized speed, but local authorities shall not modify or alter the basic rule set forth in division (A) of this section or in any event authorize by ordinance a speed in excess of fifty miles per hour.

Alteration of prima-facie limits on state routes by local authorities shall not be effective until the alteration has been approved by the director. The director may withdraw approval of any altered prima-facie speed limits whenever in the director's opinion any altered prima-facie speed becomes unreasonable, and upon such withdrawal, the altered prima-facie speed shall become ineffective and the signs relating thereto shall be immediately removed by the local authorities.

- (K) (1) As used in divisions (K)(1), (2), (3), and (4) of this section, "unimproved highway" means a highway consisting of any of the following:
- (a) Unimproved earth;
  - (b) Unimproved graded and drained earth;
  - (c) Gravel.
- (2) Except as otherwise provided in divisions (K)(4) and (5) of this section, whenever a board of township trustees determines upon the basis of an engineering and traffic investigation that the speed permitted by division (B)(5) of this section on any part of an unimproved highway under its jurisdiction and in the unincorporated territory of the township is greater than is reasonable or safe under the conditions found to exist at the location, the board may by resolution declare a reasonable and safe prima-facie speed limit of fifty-five but not less than twenty-five miles per hour. An altered speed limit adopted by a board of township trustees under this division becomes effective when appropriate traffic control devices, as prescribed in section 4511.11 of the Revised Code, giving notice thereof are erected at the location, which shall be no sooner than sixty days after adoption of the resolution.
- (3) (a) Whenever, in the opinion of a board of township trustees, any altered prima-facie speed limit established by the board under this division becomes unreasonable, the board may adopt a resolution withdrawing the altered prima-facie speed limit. Upon the adoption of such a resolution, the altered prima-facie speed limit becomes ineffective and the traffic control devices relating thereto shall be immediately removed.

- (b) Whenever a highway ceases to be an unimproved highway and the board has adopted an altered prima-facie speed limit pursuant to division (K)(2) of this section, the board shall, by resolution, withdraw the altered prima-facie speed limit as soon as the highway ceases to be unimproved. Upon the adoption of such a resolution, the altered prima-facie speed limit becomes ineffective and the traffic control devices relating hereto shall be immediately removed.
- (4) (a) If the boundary of two townships rests on the centerline of an unimproved highway in unincorporated territory and both townships have jurisdiction over the highway, neither of the boards of township trustees of such townships may declare an altered prima-facie speed limit pursuant to division (K)(2) of this section on the part of the highway under their joint jurisdiction unless the boards of township trustees of both of the townships determine, upon the basis of an engineering and traffic investigation, that the speed permitted by division (B)(5) of this section is greater than is reasonable or safe under the conditions found to exist at the location and both boards agree upon a reasonable and safe prima-facie speed limit of less than fifty-five but not less than twenty-five miles per hour for that location. If both boards so agree, each shall follow the procedure specified in division (K)(2) of this section for altering the prima-facie speed limit on the highway. Except as otherwise provided in division (K)(4)(b) of this section, no speed limit altered pursuant to division (K)(4)(a) of this section may be withdrawn unless the boards of township trustees of both townships determine that the altered prima-facie speed limit previously adopted becomes unreasonable and each board adopts a resolution withdrawing the altered prima-facie speed limit pursuant to the procedure specified in division (K)(3)(a) of this section.
- (b) Whenever a highway described in division (K)(4)(a) of this section ceases to be an unimproved highway and two boards of township trustees have adopted an altered prima-facie speed limit pursuant to division (K)(4)(a) of this section, both boards shall, by resolution, withdraw the altered prima-facie speed limit as soon as the highway ceases to be unimproved. Upon the adoption of the resolution, the altered prima-facie speed limit becomes ineffective and the traffic control devices relating thereto shall be immediately removed.
- (5) As used in division (K)(5) of this section:
  - (a) "Commercial subdivision" means any platted territory outside the limits of a municipal corporation and fronting a highway where, for a distance of three hundred feet or more, the frontage is improved with buildings in use for commercial purposes, or where the entire length of the highway is less than three hundred feet long and the frontage is improved with buildings in use for commercial purposes.
  - (b) "Residential subdivision" means any platted territory outside the limits of a municipal corporation and fronting a highway, where, for a distance of three hundred feet or more, the frontage is improved with residences or residences and buildings in use for business, or where the entire length of the highway is less than three hundred feet long and the frontage is improved with residences or residences and buildings in use for business.

Whenever a board of township trustees finds upon the basis of an engineering and traffic investigation that the prima-facie speed permitted by division (B)(5) of this section on any part of a highway under its jurisdiction that is located in a commercial or residential subdivision, except on highways or portions thereof at the entrances to which vehicular traffic from the majority of intersecting highways is required to yield the right-of-way to vehicles on such highways in obedience to stop or yield signs or traffic control signals, is greater than is reasonable and safe under the conditions found to exist at the location, the board may by resolution declare a reasonable and safe prima-facie speed limit of less than fifty-five but not less than twenty-five miles per hour at the location. An altered speed limit adopted by a board of township trustees under this division shall become effective when appropriate signs giving notice thereof are erected at the location by the township. Whenever, in the opinion of a board of township trustees, any altered prima-facie speed limit established by it under this division becomes unreasonable, it may adopt a resolution withdrawing the altered prima-facie speed, and upon such withdrawal, the altered prima-facie speed shall become ineffective, and the signs relating thereto shall be immediately removed by the township.

- (L) (1) Within one hundred twenty days of February 29, 1996, the director of transportation, based upon a geometric and traffic characteristic study of a freeway that is part of the interstate system or that is not part of the interstate system, but is built to the standards and specifications that are applicable to freeways that are part of the interstate system, in consultation with the director of public safety and, if

applicable, the local authority having jurisdiction over a portion of such freeway, may determine and declare that the speed limit of less than sixty-five miles per hour established on such freeway or portion of freeway either is reasonable and safe or is less than that which is reasonable and safe.

- (2) If the established speed limit for such a freeway or portion of freeway is determined to be less than that which is reasonable and safe, the director of transportation, in consultation with the director of public safety and, if applicable, the local authority having jurisdiction over the portion of freeway, shall determine and declare a reasonable and safe speed limit of not more than sixty-five miles per hour for that freeway or portion of freeway.

The director of transportation or local authority having jurisdiction over the freeway or portion of freeway shall erect appropriate signs giving notice of the speed limit at such location within one hundred fifty days of February 29, 1996. Such speed limit becomes effective only when such signs are erected at the location.

- (3) If, within one hundred twenty days of February 29, 1996, the director of transportation does not make a determination and declaration of a reasonable and safe speed limit for a freeway or portion of freeway that is part of the interstate system or that is not part of the interstate system, but is built to the standards and specifications that are applicable to freeways that are part of the interstate system and that has a speed limit of less than sixty-five miles per hour, the speed limit on that freeway or portion of a freeway shall be sixty-five miles per hour. The director of transportation or local authority having jurisdiction over the freeway or portion of the freeway shall erect appropriate signs giving notice of the speed limit of sixty-five miles per hour at such location within one hundred fifty days of February 29, 1996. Such speed limit becomes effective only when such signs are erected at the location. A speed limit established through the operation of division (L)(3) of this section is subject to reduction under division (I)(2) of this section.

- (M) Within three hundred sixty days after February 29, 1996, the director of transportation, based upon a geometric and traffic characteristic study of a rural, divided, multi-lane highway that has been designated as part of the national highway system under the "National Highway System Designation Act of 1995," 109 Stat. 568, 23 U.S.C.A. 103, in consultation with the director of public safety and, if applicable, the local authority having jurisdiction over a portion of the highway, may determine and declare that the speed limit of less than sixty-five miles per hour established on the highway or portion of highway either is reasonable and safe or is less than that which is reasonable and safe. If the established speed limit for the highway or portion of highway is determined to be less than that which is reasonable and safe, the director of transportation, in consultation with the director of public safety and, if applicable, the local authority having jurisdiction over the portion of highway, shall determine and declare a reasonable and safe speed limit of not more than sixty-five miles per hour for that highway or portion of highway. The director of transportation or local authority having jurisdiction over the highway or portion of highway shall erect appropriate signs giving notice of the speed limit at such location within three hundred ninety days after February 29, 1996. The speed limit becomes effective only when such signs are erected at the location.

- (N) (1) (a) If the boundary of two local authorities rests on the centerline of a highway and both authorities have jurisdiction over the highway, the speed limit for the part of the highway within their joint jurisdiction shall be either one of the following as agreed to by both authorities:
- (i) Either prima-facie speed limit permitted by division (B) of this section;
  - (ii) An altered speed limit determined and posted in accordance with this section.
- (b) If the local authorities are unable to reach an agreement, the speed limit shall remain as established and posted under this section.
- (2) Neither local authority may declare an altered prima-facie speed limit pursuant to this section on the part of the highway under their joint jurisdiction unless both of the local authorities determine, upon the basis of an engineering and traffic investigation, that the speed permitted by this section is greater than is reasonable or safe under the conditions found to exist at the location and both authorities agree upon a uniform reasonable and safe prima-facie speed limit of less than fifty-five but not less than twenty-five miles per hour for that location. If both authorities so agree, each shall follow the procedure specified in this section for altering the prima-facie speed limit on the highway, and the speed limit for the part of the highway within their joint jurisdiction shall be uniformly altered. No altered speed limit may be withdrawn unless both local authorities determine that the altered prima-facie

speed limit previously adopted becomes unreasonable and each adopts a resolution withdrawing the altered prima-facie speed limit pursuant to the procedure specified in this section.

(O) As used in this section:

- (1) "Interstate system" has the same meaning as in 23 U.S.C.A. 101.
- (2) "Commercial bus" means a motor vehicle designed for carrying more than nine passengers and used for the transportation of persons for compensation.
- (3) "Noncommercial bus" includes but is not limited to a school bus or a motor vehicle operated solely for the transportation of persons associated with a charitable or nonprofit organization.

(P) (1) A violation of any provision of this section is one of the following:

- (a) Except as otherwise provided in divisions (P)(1)(b), (1)(c), (2), and (3) of this section, a minor misdemeanor;
  - (b) If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to two violations of any provision of this section or of any provision of a municipal ordinance that is substantially similar to any provision of this section, a misdemeanor of the fourth degree;
  - (c) If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to three or more violations of any provision of this section or of any provision of a municipal ordinance that is substantially similar to any provision of this section, a misdemeanor of the third degree.
- (2) If the offender has not previously been convicted of or pleaded guilty to a violation of any provision of this section or of any provision of a municipal ordinance that is substantially similar to this section and operated a motor vehicle faster than thirty-five miles an hour in a business district of a municipal corporation, faster than fifty miles an hour in other portions of a municipal corporation, or faster than thirty-five miles an hour in a school zone during recess or while children are going to or leaving school during the school's opening or closing hours, a misdemeanor of the fourth degree.
  - (3) Notwithstanding division (P)(1) of this section, if the offender operated a motor vehicle in a construction zone where a sign was then posted in accordance with section 4511.98 of the Revised Code, the court, in addition to all other penalties provided by law, shall impose upon the offender a fine of two times the usual amount imposed for the violation. No court shall impose a fine of two times the usual amount imposed for the violation upon an offender if the offender alleges, in an affidavit filed with the court prior to the offender's sentencing, that the offender is indigent and is unable to pay the fine imposed pursuant to this division and if the court determines that the offender is an indigent person and unable to pay the fine.

HISTORY: GC § 6307-21; 119 v 766, § 21; 124 v 514; Bureau of Code Revision, 10-1-53; 126 v 115 (Eff 10-1-56); 127 v 931 (Eff 9-14-57); 128 v 1270 (Eff 11-4-59); 130 v 1083 (Eff 9-30-63); 130 v PtlI, H 5 (Eff 12-16-64); 131 v 1101 (Eff 11-4-65); 132 v H 1 (Eff 2-21-67); 135 v H 200 (Eff 9-28-73); 136 v H 632 (Eff 6-27-75); 136 v H 1166 (Eff 8-9-76); 137 v H 587 (Eff 11-3-77); 138 v H 20 (Eff 8-29-79); 138 v H 32 (Eff 8-29-79); 138 v S 14 (Eff 10-25-79); 140 v S 37 (Eff 9-7-83); 141 v H 795 (Eff 8-29-86); 141 v S 356 (Eff 9-24-86); 141 v H 428 (Eff 12-23-86); 141 v H 666 (Eff 3-25-87); 142 v H 43 (Eff 7-31-87); 142 v H 493 (Eff 7-15-87); 143 v H 381 (Eff 7-1-89); 144 v H 96 (Eff 6-18-91); 144 v S 201 (Eff 8-19-92); 144 v S 301 (Eff 3-15-93); 146 v H 565. Eff 2-29-96; 149 v S 123, § 1, eff. 1-1-04; 151 v H 68, § 101.01, eff. 6-29-05.

**§ 4511.211. Speed limit on private residential road or driveway.**

(A) The owner of a private road or driveway located in a private residential area containing twenty or more dwelling units may establish a speed limit on the road or driveway by complying with all of the following requirements:

- (1) The speed limit is not less than twenty-five miles per hour and is indicated by a sign that is in a proper position, is sufficiently legible to be seen by an ordinarily observant person, and meets the specifications for the basic speed limit sign included in the manual adopted by the department of transportation pursuant to section 4511.09 of the Revised Code;
- (2) The owner has posted a sign at the entrance of the private road or driveway that is in plain view and clearly informs persons entering the road or driveway that they are entering private property, a speed

limit has been established for the road or driveway, and the speed limit is enforceable by law enforcement officers under state law.

- (B) No person shall operate a vehicle upon a private road or driveway as provided in division (A) of this section at a speed exceeding any speed limit established and posted pursuant to that division.
- (C) When a speed limit is established and posted in accordance with division (A) of this section, any law enforcement officer may apprehend a person violating the speed limit of the residential area by utilizing any of the means described in section 4511.091 [4511.09.1] of the Revised Code or by any other accepted method of determining the speed of a motor vehicle and may stop and charge the person with exceeding the speed limit.
- (D) Points shall be assessed for violation of a speed limit established and posted in accordance with division (A) of this section in accordance with section 4510.036 of the Revised Code..
- (E) As used in this section:
  - (1) "Owner" includes but is not limited to a person who holds title to the real property in fee simple, a condominium owners' association, a property owners' association, the board of directors or trustees of a private community, and a nonprofit corporation governing a private community.
  - (2) "Private residential area containing twenty or more dwelling units" does not include a Chautauqua assembly as defined in section 4511.90 of the Revised Code.
- (F) A violation of division (B) of this section is one of the following:
  - (1) Except as otherwise provided in divisions (F)(2) and (3) of this section, a minor misdemeanor;
  - (2) If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to two violations of division (B) of this section or of any municipal ordinance that is substantially similar to division (B) of this section, a misdemeanor of the fourth degree;
  - (3) If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to three or more violations of division (B) of this section or of any municipal ordinance that is substantially similar to division (B) of this section, a misdemeanor of the third degree.

HISTORY: 143 v H 171. Eff 5-31-90; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.212. Complaint that local authority is not complying with school zone sign laws.**

- (A) As used in this section, "local authority" means the legislative authority of a municipal corporation, the board of trustees of a township, or the board of county commissioners of a county.
- (B) The board of education or the chief administrative officer operating or in charge of any school may submit a written complaint to the director of transportation alleging that a local authority is not complying with section 4511.11 or divisions (B)(1)(a) to (d) of section 4511.21 of the Revised Code with regard to school zones. Upon receipt of such a complaint, the director shall review or investigate the facts of the complaint and discuss the complaint with the local authority and the board of education or chief administrative officer submitting the complaint. If the director finds that the local authority is not complying with section 4511.11 or divisions (B)(1)(a) to (d) of section 4511.21 of the Revised Code with regard to school zones, the director shall issue a written order requiring the local authority to comply by a specified date and the local authority shall comply with the order. If the local authority fails to comply with the order, the director shall implement the order and charge the local authority for the cost of the implementation. Any local authority being so charged shall pay to the state the amount charged. Any amounts received under this section shall be deposited into the state treasury to the credit of the highway operating fund created by section 5735.291 of the Revised Code.

HISTORY: 144 v S 201. Eff 8-19-92.

**§ 4511.213. Duties upon approaching stationary public safety vehicle displaying emergency light.**

- (A) The driver of a motor vehicle, upon approaching a stationary public safety vehicle that is displaying a flashing red light, flashing combination red and white light, oscillating or rotating red light, oscillating or rotating combination red and white light, flashing blue light, flashing combination blue and white light, oscillating or rotating blue light, or oscillating or rotating combination blue and white light, shall do either of the following:

- (1) If the driver of the motor vehicle is traveling on a highway that consists of at least two lanes that carry traffic in the same direction of travel as that of the driver's motor vehicle, the driver shall proceed with due caution and, if possible and with due regard to the road, weather, and traffic conditions, shall change lanes into a lane that is not adjacent to that of the stationary public safety vehicle.
- (2) If the driver is not traveling on a highway of a type described in division (A)(1) of this section, or if the driver is traveling on a highway of that type but it is not possible to change lanes or if to do so would be unsafe, the driver shall proceed with due caution, reduce the speed of the motor vehicle, and maintain a safe speed for the road, weather, and traffic conditions.
- (B) This section does not relieve the driver of a public safety vehicle from the duty to drive with due regard for the safety of all persons and property upon the highway.
- (C) No person shall fail to drive a motor vehicle in compliance with division (A)(1) or (2) of this section when so required by division (A) of this section.
- (D) (1) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.
- (2) Notwithstanding section 2929.28 of the Revised Code, upon a finding that a person operated a motor vehicle in violation of division (C) of this section, the court, in addition to all other penalties provided by law, shall impose a fine of two times the usual amount imposed for the violation.
- (E) As used in this section, "public safety vehicle" has the same meaning as in section 4511.01 of the Revised Code.

HISTORY: 148 v H 86. Eff 9-28-99; 149 v S 123, § 1, eff. 1-1-04; 149 v H 490, § 1, eff. 1-1-04.

#### **§ 4511.22. Slow speed**

- (A) No person shall stop or operate a vehicle, trackless trolley, or streetcar at such slow speed as to impede or block the normal and reasonable movement of traffic, except when stopping or reduced speed is necessary for safe operation or to comply with law.
- (B) Whenever the director of transportation or local authorities determine on the basis of an engineering and traffic investigation that slow speeds on any part of a controlled-access highway, expressway, or freeway consistently impede the normal and reasonable movement of traffic, the director or such local authority may declare a minimum speed limit below which no person shall operate a motor vehicle, trackless trolley, or street car except when necessary for safe operation or in compliance with law. No minimum speed limit established hereunder shall be less than thirty miles per hour, greater than fifty miles per hour, nor effective until the provisions of section 4511.21 of the Revised Code, relating to appropriate signs, have been fulfilled and local authorities have obtained the approval of the director.
- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-22; 119 v 766, § 22; Bureau of Code Revision, 10-1-53; 127 v 51 (Eff 8-23-57); 135 v H 200 (Eff 9-28-73); 136 v H 632 (Eff 6-27-75); 144 v H 96. Eff 6-18-91; 149 v S 123, § 1, eff. 1-1-04.

#### **§ 4511.23. Speed regulations on bridges.**

- (A) No person shall operate a vehicle, trackless trolley, or streetcar over any bridge or other elevated structure constituting a part of a highway at a speed which is greater than the maximum speed that can be maintained with safety to such bridge or structure, when such structure is posted with signs as provided in this section.

The department of transportation upon request from any local authority shall, or upon its own initiative may, conduct an investigation of any bridge or other elevated structure constituting a part of a highway, and if it finds that such structure cannot with safety withstand traffic traveling at the speed otherwise permissible under sections 4511.01 to 4511.85 and 4511.98 of the Revised Code, the department shall determine and declare the maximum speed of traffic which such structure can withstand, and shall cause or permit suitable signs stating such maximum speed to be erected and maintained at a distance of at least one hundred feet before each end of such structure.

Upon the trial of any person charged with a violation of this section, proof of said determination of the maximum speed by the department and the existence of said signs shall constitute prima-facie evidence of the maximum speed which can be maintained with safety to such bridge or structure.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-23; 119 v 766, § 23; Bureau of Code Revision, 10-1-53; 135 v H 200. Eff 9-28-73; 149 v S 123, § 1, eff. 1-1-04.

#### **§ 4511.24. Emergency vehicles excepted from speed limitations.**

The prima-facie speed limitations set forth in section 4511.21 of the Revised Code do not apply to emergency vehicles or public safety vehicles when they are responding to emergency calls and are equipped with and displaying at least one flashing, rotating, or oscillating light visible under normal atmospheric conditions from a distance of five hundred feet to the front of the vehicle and when the drivers thereof sound audible signals by bell, siren, or exhaust whistle. This section does not relieve the driver of an emergency vehicle or public safety vehicle from the duty to drive with due regard for the safety of all persons using the street or highway.

HISTORY: GC § 6307-24; 119 v 766, § 24; Bureau of Code Revision, 10-1-53; 132 v H 378 (Eff 12-14-67); 135 v H 995. Eff 1-1-75.

#### **§ 4511.25. Lanes of travel upon roadways.**

- (A) Upon all roadways of sufficient width, a vehicle or trackless trolley shall be driven upon the right half of the roadway, except as follows:
- (1) When overtaking and passing another vehicle proceeding in the same direction, or when making a left turn under the rules governing such movements;
  - (2) When an obstruction exists making it necessary to drive to the left of the center of the highway; provided, any person so doing shall yield the right of way to all vehicles traveling in the proper direction upon the unobstructed portion of the highway within such distance as to constitute an immediate hazard;
  - (3) When driving upon a roadway divided into three or more marked lanes for traffic under the rules applicable thereon;
  - (4) When driving upon a roadway designated and posted with signs for one-way traffic;
  - (5) When otherwise directed by a police officer or traffic control device
- (B) Upon all roadways any vehicle or trackless trolley proceeding at less than the normal speed of traffic at the time and place and under the conditions then existing shall be driven in the righthand lane then available for traffic, or as close as practicable to the right-hand curb or edge of the roadway, except when overtaking and passing another vehicle or trackless trolley proceeding in the same direction or when preparing for a left turn.
- (C) Upon any roadway having four or more lanes for moving traffic and providing for two-way movement of traffic, no vehicle or trackless trolley shall be driven to the left of the center line of the roadway, except when authorized by official traffic control devices designating certain lanes to the left of the center of the roadway for use by traffic not otherwise permitted to use the lanes, or except as permitted under division (A)(2) of this section.

This division shall not be construed as prohibiting the crossing of the center line in making a left turn into or from an alley, private road, or driveway.

- (D) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-25; 119 v 766, § 25; Bureau of Code Revision, 10-1-53; 129 v 1032 (Eff 9-9-61); 130 v 1086 (Eff 6-10-63); 135 v H 995. Eff 1-1-75. The effective date is set by section 3 of HB 995; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.26. Vehicles traveling in opposite directions.**

- (A) Operators of vehicles and trackless trolleys proceeding in opposite directions shall pass each other to the right, and upon roadways having width for not more than one line of traffic in each direction, each operator shall give to the other one-half of the main traveled portion of the roadway or as nearly one-half as is reasonably possible.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-26; 119 v 766(778), § 26; Bureau of Code Revision. Eff 10-1-53; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.27. Rules governing overtaking and passing of vehicles.**

- (A) The following rules govern the overtaking and passing of vehicles or trackless trolleys proceeding in the same direction:
- (1) The operator of a vehicle or trackless trolley overtaking another vehicle or trackless trolley proceeding in the same direction shall, except as provided in division (A)(3) of this section, signal to the vehicle or trackless trolley to be overtaken, shall pass to the left thereof at a safe distance, and shall not again drive to the right side of the roadway until safely clear of the overtaken vehicle or trackless trolley.
  - (2) Except when overtaking and passing on the right is permitted, the operator of an overtaken vehicle shall give way to the right in favor of the overtaking vehicle at the latter's audible signal, and the operator shall not increase the speed of the operator's vehicle until completely passed by the overtaking vehicle.
  - (3) The operator of a vehicle or trackless trolley overtaking and passing another vehicle or trackless trolley proceeding in the same direction on a divided highway as defined in section 4511.35 of the Revised Code, a limited access highway as defined in section 5511.02 of the Revised Code, or a highway with four or more traffic lanes, is not required to signal audibly to the vehicle or trackless trolley being overtaken and passed.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-27; 119 v 766(778), § 27; Bureau of Code Revision, 10-1-53; 133 v S 289. Eff 11-6-69; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.28. Permission to overtake and pass on the right.**

- (A) The driver of a vehicle or trackless trolley may overtake and pass upon the right of another vehicle or trackless trolley only under the following conditions:
- (1) When the vehicle or trackless trolley overtaken is making or about to make a left turn;
  - (2) Upon a roadway with unobstructed pavement of sufficient width for two or more lines of vehicles moving lawfully in the direction being traveled by the overtaking vehicle.
- (B) The driver of a vehicle or trackless trolley may overtake and pass another vehicle or trackless trolley only under conditions permitting such movement in safety. The movement shall not be made by driving off the roadway.
- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-28; 119 v 766(778), § 28; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04..

**§ 4511.29. Driving to left of center line.**

- (A) No vehicle or trackless trolley shall be driven to the left of the center of the roadway in overtaking and passing traffic proceeding in the same direction, unless such left side is clearly visible and is free of oncoming traffic for a sufficient distance ahead to permit such overtaking and passing to be completely made, without interfering with the safe operation of any traffic approaching from the opposite direction or any traffic overtaken. In every event the overtaking vehicle or trackless trolley must return to an authorized lane of travel as soon as practicable and in the event the passing movement involves the use of a lane authorized for traffic approaching from the opposite direction, before coming within two hundred feet of any approaching vehicle.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-29; 119 v 766(778), § 29; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.30. Prohibition against driving upon left side of roadway.**

- (A) No vehicle or trackless trolley shall be driven upon the left side of the roadway under the following conditions:
- (1) When approaching the crest of a grade or upon a curve in the highway, where the operator's view is obstructed within such a distance as to create a hazard in the event traffic might approach from the opposite direction;
  - (2) When the view is obstructed upon approaching within one hundred feet of any bridge, viaduct, or tunnel;
  - (3) When approaching within one hundred feet of or traversing any intersection or railroad grade crossing.
- (B) This section does not apply to vehicles or trackless trolleys upon a one-way roadway, upon a roadway where traffic is lawfully directed to be driven to the left side, or under the conditions described in division (A)(2) of section 4511.25 of the Revised Code.

- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-30; 119 v 766(779), § 30; 120 v 221; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.31. Hazardous zones.**

- (A) The department of transportation may determine those portions of any state highway where overtaking and passing other traffic or driving to the left of the center or center line of the roadway would be especially hazardous, and may, by appropriate signs or markings on the highway, indicate the beginning and end of such zones. When such signs or markings are in place and clearly visible, every operator of a vehicle or trackless trolley shall obey the directions of the signs or markings, notwithstanding the distances set out in section 4511.30 of the Revised Code.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-31; 119 v 766(779), § 31; 124 v 514; Bureau of Code Revision, 10-1-53; 135 v H 200. Eff 9-28-73; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.32. One-way highways and rotary traffic islands.**

- (A) The department of transportation may designate any highway or any separate roadway under its jurisdiction for one-way traffic and shall erect appropriate signs giving notice thereof.

Upon a roadway designated and posted with signs for one-way traffic a vehicle shall be driven only in the direction designated.

A vehicle passing around a rotary traffic island shall be driven only to the right of the rotary traffic island.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-32; 119 v 766(779), § 32; Bureau of Code Revision, 10-1-53; 135 v H 200. Eff 9-28-73; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.33. Rules for driving in marked lanes.**

- (A) Whenever any roadway has been divided into two or more clearly marked lanes for traffic, or wherever within municipal corporations traffic is lawfully moving in two or more substantially continuous lines in the same direction, the following rules apply:

(1) A vehicle or trackless trolley shall be driven, as nearly as is practicable, entirely within a single lane or line of traffic and shall not be moved from such lane or line until the driver has first ascertained that such movement can be made with safety.

(2) Upon a roadway which is divided into three lanes and provides for two-way movement of traffic, a vehicle or trackless trolley shall not be driven in the center lane except when overtaking and passing another vehicle or trackless trolley where the roadway is clearly visible and such center lane is clear of traffic within a safe distance, or when preparing for a left turn, or where such center lane is at the

time allocated exclusively to traffic moving in the direction the vehicle or trackless trolley is proceeding and is posted with signs to give notice of such allocation.

- (3) Official signs may be erected directing specified traffic to use a designated lane or designating those lanes to be used by traffic moving in a particular direction regardless of the center of the roadway, or restricting the use of a particular lane to only buses during certain hours or during all hours, and drivers of vehicles and trackless trolleys shall obey the directions of such signs.
  - (4) Official traffic control devices may be installed prohibiting the changing of lanes on sections of roadway and drivers of vehicles shall obey the directions of every such device.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-33; 119 v 766(779), § 33; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04; 150 v H 95, § 1, eff. 9-26-03; 150 v H 95, § 3.13, eff. 1-1-04.

#### **§ 4511.34. Space between moving vehicles.**

- (A) The operator of a motor vehicle, streetcar, or trackless trolley shall not follow another vehicle, streetcar, or trackless trolley more closely than is reasonable and prudent, having due regard for the speed of such vehicle, streetcar, or trackless trolley, and the traffic upon and the condition of the highway.

The driver of any truck, or motor vehicle drawing another vehicle, when traveling upon a roadway outside a business or residence district shall maintain a sufficient space, whenever conditions permit, between such vehicle and another vehicle ahead so an overtaking motor vehicle may enter and occupy such space without danger. This paragraph does not prevent overtaking and passing nor does it apply to any lane specially designated for use by trucks.

Outside a municipal corporation, the driver of any truck, or motor vehicle when drawing another vehicle, while ascending to the crest of a grade beyond which the driver's view of the roadway is obstructed, shall not follow within three hundred feet of another truck, or motor vehicle drawing another vehicle. This paragraph shall not apply to any lane specially designated for use by trucks.

Motor vehicles being driven upon any roadway outside of a business or residence district in a caravan or motorcade, shall maintain a sufficient space between such vehicles so an overtaking vehicle may enter and occupy such space without danger. This paragraph shall not apply to funeral processions.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-34; 119 v 766(789), § 34; Bureau of Code Revision, 10-1-53; 126 v 113. Eff 9-30-55; 149 v S 123, § 1, eff. 1-1-04.

#### **§ 4511.35. Divided roadways.**

- (A) Whenever any highway has been divided into two roadways by an intervening space, or by a physical barrier, or clearly indicated dividing section so constructed as to impede vehicular traffic, every vehicle shall be driven only upon the right-hand roadway, and no vehicle shall be driven over, across, or within any such dividing space, barrier, or section, except through an opening, crossover, or intersection established by public authority. This section does not prohibit the occupancy of such dividing space, barrier, or section for the purpose of an emergency stop or in compliance with an order of a police officer.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a

misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-34a; 124 v 514; Bureau of Code Revision. Eff 10-1-53; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.36. Rules for turns at intersections.**

- (A) The driver of a vehicle intending to turn at an intersection shall be governed by the following rules:
- (1) Approach for a right turn and a right turn shall be made as close as practicable to the right-hand curb or edge of the roadway.
  - (2) At any intersection where traffic is permitted to move in both directions on each roadway entering the intersection, an approach for a left turn shall be made in that portion of the right half of the roadway nearest the center line thereof and by passing to the right of such center line where it enters the intersection and after entering the intersection the left turn shall be made so as to leave the intersection to the right of the center line of the roadway being entered. Whenever practicable the left turn shall be made in that portion of the intersection to the left of the center of the intersection.
  - (3) At any intersection where traffic is restricted to one direction on one or more of the roadways, the driver of a vehicle intending to turn left at any such intersection shall approach the intersection in the extreme left-hand lane lawfully available to traffic moving in the direction of travel of such vehicle, and after entering the intersection the left turn shall be made so as to leave the intersection, as nearly as practicable, in the left-hand lane of the roadway being entered lawfully available to traffic moving in that lane.
- (B) The operator of a trackless trolley shall comply with divisions (A)(1), (2), and (3) of this section wherever practicable.
- (C) The department of transportation and local authorities in their respective jurisdictions may cause markers, buttons, or signs to be placed within or adjacent to intersections and thereby require and direct that a different course from that specified in this section be traveled by vehicles, streetcars, or trackless trolleys, turning at an intersection, and when markers, buttons, or signs are so placed, no operator of a vehicle, streetcar, or trackless trolley shall turn such vehicle, streetcar, or trackless trolley at an intersection other than as directed and required by such markers, buttons, or signs.
- (D) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-35; 119 v 766(780), § 35; 124 v 514; Bureau of Code Revision, 10-1-53; 135 v H 200. Eff 9-28-73; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.37. Turning in roadway prohibited; exception for emergency or public safety vehicle.**

- (A) Except as provided in division (B) of this section, no vehicle shall be turned so as to proceed in the opposite direction upon any curve, or upon the approach to or near the crest of a grade, if the vehicle cannot be seen within five hundred feet by the driver of any other vehicle approaching from either direction.
- (B) The driver of an emergency vehicle or public safety vehicle, when responding to an emergency call, may turn the vehicle so as to proceed in the opposite direction. This division applies only when the emergency vehicle or public safety vehicle is responding to an emergency call, is equipped with and displaying at least one flashing, rotating, or oscillating light visible under normal atmospheric conditions from a distance of five hundred feet to the front of the vehicle, and when the driver of the vehicle is giving an audible signal by siren, exhaust whistle, or bell. This division does not relieve the driver of an emergency vehicle or public safety vehicle from the duty to drive with due regard for the safety of all persons and property upon the highway.

- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-36; 119 v 766(781), § 36; Bureau of Code Revision, 10-1-53; 145 v H 149. Eff 5-20-93; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.41. Right-of-way at intersections.**

- (A) When two vehicles, including any trackless trolley or streetcar, approach or enter an intersection from different streets or highways at approximately the same time, the driver of the vehicle on the left shall yield the right-of-way to the vehicle on the right.
- (B) The right-of-way rule declared in division (A) of this section is modified at through highways and otherwise as stated in Chapter 4511 of the Revised Code.
- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995 (Eff 1-1-75); 136 v H 1. Eff 6-13-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.42. Right of way when turning left.**

- (A) The operator of a vehicle, streetcar, or trackless trolley intending to turn to the left within an intersection or into an alley, private road, or driveway shall yield the right of way to any vehicle, streetcar, or trackless trolley approaching from the opposite direction, whenever the approaching vehicle, streetcar, or trackless trolley is within the intersection or so close to the intersection, alley, private road, or driveway as to constitute an immediate hazard.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-41; 119 v 766(782), § 41; Bureau of Code Revision, 10-1-53; 130 v 1087 (Eff 6-27-63); 135 v H 995 (Eff 1-1-75); 137 v S 62. Eff 7-8-77; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.43. Right-of-way at through highways; stop signs; yield signs.**

- (A) Except when directed to proceed by a law enforcement officer, every driver of a vehicle or trackless trolley approaching a stop sign shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or, if none, then at the point nearest the intersecting roadway where the driver has a view of approaching traffic on the intersecting roadway before entering it. After having stopped, the driver shall yield the right-of-way to any vehicle in the intersection or approaching on another roadway so closely as to constitute an immediate hazard during the time the driver is moving across or within the intersection or junction of roadways.
- (B) The driver of a vehicle or trackless trolley approaching a yield sign shall slow down to a speed reasonable for the existing conditions and, if required for safety to stop, shall stop at a clearly marked stop line, but if none, before entering the crosswalk on the near side of the intersection, or, if none, then at the point nearest the intersecting roadway where the driver has a view of approaching traffic on the intersecting roadway before entering it. After slowing or stopping, the driver shall yield the right-of-way to any vehicle or trackless trolley in the intersection or approaching on another roadway so closely as to constitute an immediate hazard during the time the driver is moving across or within the intersection or junction of

roadways. Whenever a driver is involved in a collision with a vehicle or trackless trolley in the intersection or junction of roadways, after driving past a yield sign without stopping, the collision shall be prima-facie evidence of the driver's failure to yield the right-of-way.

- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995 Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.431. Stop at sidewalk area.**

- (A) The driver of a vehicle or trackless trolley emerging from an alley, building, private road, or driveway within a business or residence district shall stop the vehicle or trackless trolley immediately prior to driving onto a sidewalk or onto the sidewalk area extending across the alley, building entrance, road, or driveway, or in the event there is no sidewalk area, shall stop at the point nearest the street to be entered where the driver has a view of approaching traffic thereon.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.432. Stop signs on private residential road or driveway.**

- (A) The owner of a private road or driveway located in a private residential area containing twenty or more dwelling units may erect stop signs at places where the road or driveway intersects with another private road or driveway in the residential area, in compliance with all of the following requirements:
- (1) The stop sign is sufficiently legible to be seen by an ordinarily observant person and meets the specifications of and is placed in accordance with the manual adopted by the department of transportation pursuant to section 4511.09 of the Revised Code;
  - (2) The owner has posted a sign at the entrance of the private road or driveway that is in plain view and clearly informs persons entering the road or driveway that they are entering private property, stop signs have been posted and must be obeyed, and the signs are enforceable by law enforcement officers under state law. The sign required by division (A)(2) of this section, where appropriate, may be incorporated with the sign required by division (A)(2) of section 4511.211 of the Revised Code.
- (B) Division (A) of section 4511.43 and section 4511.46 of the Revised Code shall be deemed to apply to the driver of a vehicle on a private road or driveway where a stop sign is placed in accordance with division (A) of this section and to a pedestrian crossing such a road or driveway at an intersection where a stop sign is in place.
- (C) When a stop sign is placed in accordance with division (A) of this section, any law enforcement officer may apprehend a person found violating the stop sign and may stop and charge the person with violating the stop sign.
- (D) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.
- (E) As used in this section, and for the purpose of applying division (A) of section 4511.43 and section 4511.46 of the Revised Code to conduct under this section:

## (1) "Intersection" means:

- (a) The area embraced within the prolongation or connection of the lateral curb lines, or, if none, then the lateral boundary lines of the roadways of two private roads or driveways which join one another at, or approximately at, right angles, or the area within which vehicles traveling upon different private roads or driveways joining at any other angle may come in conflict.
- (b) Where a private road or driveway includes two roadways thirty feet or more apart, then every crossing of two roadways of such private roads or driveways shall be regarded as a separate intersection.

## (2) "Roadway" means that portion of a private road or driveway improved, designed, or ordinarily used for vehicular travel, except the berm or shoulder. If a private road or driveway includes two or more separate roadways, the term "roadway" means any such roadway separately but not all such roadways collectively.

## (3) "Owner" and "private residential area containing twenty or more dwelling units" have the same meanings as in section 4511.211 of the Revised Code.

HISTORY: 143 v H 171. Eff 5-31-90; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.44. Right of way on public highway.**

- (A) The operator of a vehicle, streetcar, or trackless trolley about to enter or cross a highway from any place other than another roadway shall yield the right of way to all traffic approaching on the roadway to be entered or crossed.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-43; 119 v 766(782), § 43; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.46. Pedestrian on crosswalk has right-of-way.**

- (A) When traffic control signals are not in place, not in operation, or are not clearly assigning the right-of-way, the driver of a vehicle, trackless trolley, or streetcar shall yield the right-of-way, slowing down or stopping if need be to so yield or if required by section 4511.132 of the Revised Code, to a pedestrian crossing the roadway within a crosswalk when the pedestrian is upon the half of the roadway upon which the vehicle is traveling, or when the pedestrian is approaching so closely from the opposite half of the roadway as to be in danger.
- (B) No pedestrian shall suddenly leave a curb or other place of safety and walk or run into the path of a vehicle, trackless trolley, or streetcar which is so close as to constitute an immediate hazard.
- (C) Division (A) of this section does not apply under the conditions stated in division (B) of section 4511.48 of the Revised Code.
- (D) Whenever any vehicle, trackless trolley, or streetcar is stopped at a marked crosswalk or at any unmarked crosswalk at an intersection to permit a pedestrian to cross the roadway, the driver of any other vehicle, trackless trolley, or streetcar approaching from the rear shall not overtake and pass the stopped vehicle.
- (E) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995 (Eff 1-1-75); 143 v S 44. Eff 7-25-89; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.48. Right of way yielded by pedestrian.**

- (A) Every pedestrian crossing a roadway at any point other than within a marked crosswalk or within an unmarked crosswalk at an intersection shall yield the right of way to all vehicles, trackless trolleys, or streetcars upon the roadway.
- (B) Any pedestrian crossing a roadway at a point where a pedestrian tunnel or overhead pedestrian crossing has been provided shall yield the right of way to all traffic upon the roadway.
- (C) Between adjacent intersections at which traffic control signals are in operation, pedestrians shall not cross at any place except in a marked crosswalk.
- (D) No pedestrian shall cross a roadway intersection diagonally unless authorized by official traffic control devices; and, when authorized to cross diagonally, pedestrians shall cross only in accordance with the official traffic control devices pertaining to such crossing movements.
- (E) This section does not relieve the operator of a vehicle, streetcar, or trackless trolley from exercising due care to avoid colliding with any pedestrian upon any roadway.
- (F) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-46; 119 v 766(783), § 46; Bureau of Code Revision, 10-1-53; 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.481. Intoxicated or drugged pedestrian hazard on highway.**

- (A) A pedestrian who is under the influence of alcohol, any drug of abuse, or any combination of them to a degree that renders the pedestrian a hazard shall not walk or be upon a highway.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.61. Stop signs at grade crossings.**

- (A) The department of transportation and local authorities in their respective jurisdictions, with the approval of the department, may designate dangerous highway crossings over railroad tracks whether on state, county, or township highways or on streets or ways within municipal corporations, and erect stop signs thereat. When such stop signs are erected, the operator of any vehicle, streetcar, or trackless trolley shall stop within fifty, but not less than fifteen, feet from the nearest rail of the railroad tracks and shall exercise due care before proceeding across such grade crossing.
- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-59; 119 v 766(786), § 59; Bureau of Code Revision, 10-1-53; 127 v 887 (Eff 9-16-57); 135 v H 200 (Eff 9-28-73); 135 v S 171. Eff 10-31-73; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.62. Driver's duties relating to railroad grade crossings.**

- (A) (1) Whenever any person driving a vehicle or trackless trolley approaches a railroad grade crossing, the person shall stop within fifty feet, but not less than fifteen feet from the nearest rail of the railroad if any of the following circumstances exist at the crossing:
- (a) A clearly visible electric or mechanical signal device gives warning of the immediate approach of a train.
  - (b) A crossing gate is lowered.
  - (c) A flagperson gives or continues to give a signal of the approach or passage of a train.
  - (d) There is insufficient space on the other side of the railroad grade crossing to accommodate the vehicle or trackless trolley the person is operating without obstructing the passage of other vehicles, trackless trolleys, pedestrians, or railroad trains, notwithstanding any traffic control signal indication to proceed.
  - (e) An approaching train is emitting an audible signal or is plainly visible and is in hazardous proximity to the crossing.
  - (f) There is insufficient undercarriage clearance to safely negotiate the crossing.
- (2) A person who is driving a vehicle or trackless trolley and who approaches a railroad grade crossing shall not proceed as long as any of the circumstances described in divisions (A)(1)(a) to (f) of this section exist at the crossing.
- (B) No person shall drive any vehicle through, around, or under any crossing gate or barrier at a railroad crossing while the gate or barrier is closed or is being opened or closed unless the person is signaled by a law enforcement officer or flagperson that it is permissible to do so.

(C) Whoever violates this section is guilty of a misdemeanor of the fourth degree.

HISTORY: GC § 6307-60; 119 v 766(786), § 60; Bureau of Code Revision, 10-1-53; 135 v H 995 (Eff 1-1-75); 147 v S 60. Eff 10-21-97; 149 v S 123, § 1, eff. 1-1-04; 150 v H 95, § 1, eff. 9-26-03; 150 v H 95, § 3.13, eff. 1-1-04.

**§ 4511.63. Vehicles required to stop at grade crossings.**

- (A) Except as provided in division (B) of this section, the operator of any bus, any school vehicle, or any vehicle transporting a material or materials required to be placarded under 49 C.F.R. Parts 100-185, before crossing at grade any track of a railroad, shall stop the vehicle and, while so stopped, shall listen through an open door or open window and look in both directions along the track for any approaching train, and for signals indicating the approach of a train, and shall proceed only upon exercising due care after stopping, looking, and listening as required by this section. Upon proceeding, the operator of such a vehicle shall cross only in a gear that will ensure there will be no necessity for changing gears while traversing the crossing and shall not shift gears while crossing the tracks.
- (B) This section does not apply at grade crossings when the public utilities commission has authorized and approved an exempt crossing as provided in this division.
- (1) Any local authority may file an application with the commission requesting the approval of an exempt crossing. Upon receipt of such a request, the commission shall authorize a limited period for the filing of comments by any party regarding the application and then shall conduct a public hearing in the community seeking the exempt crossing designation. The commission shall provide appropriate prior public notice of the comment period and the public hearing. By registered mail, the commission shall notify each railroad operating over the crossing of the comment period.
  - (2) After considering any comments or other information received, the commission may approve or reject the application. By order, the commission may establish conditions for the exempt crossing designation, including compliance with division (b) of 49 C.F.R. Part 392.10, when applicable. An exempt crossing designation becomes effective only when appropriate signs giving notice of the exempt designation are erected at the crossing as ordered by the commission and any other conditions ordered by the commission are satisfied.

- (3) By order, the commission may rescind any exempt crossing designation made under this section if the commission finds that a condition at the exempt crossing has changed to such an extent that the continuation of the exempt crossing designation compromises public safety. The commission may conduct a public hearing to investigate and determine whether to rescind the exempt crossing designation. If the commission rescinds the designation, it shall order the removal of any exempt crossing signs and may make any other necessary order.

(C) As used in this section:

- (1) "School vehicle" means any vehicle used for the transportation of pupils to and from a school or school-related function if the vehicle is owned or operated by, or operated under contract with, a public or nonpublic school.
- (2) "Bus" means any vehicle originally designed by its manufacturer to transport sixteen or more passengers, including the driver, or carries sixteen or more passengers, including the driver.
- (3) "Exempt crossing" means a highway rail grade crossing authorized and approved by the public utilities commission under division (B) of this section at which vehicles may cross without making the stop otherwise required by this section

(E) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If the offender previously has been convicted of or pleaded guilty to one or more violations of this section or section 4511.76, 4511.761 [4511.76.1], 4511.762 [4511.76.2], 4511.764 [4511.76.4], 4511.77, or 4511.79 of the Revised Code or a municipal ordinance that is substantially similar to any of those sections, whoever violates this section is guilty of a misdemeanor of the fourth degree.

HISTORY: GC § 6307-61; 119 v 766(786), § 61; 124 v 514; Bureau of Code Revision, 10-1-53; 125 v 903(1025) (Eff 10-1-53); 145 v H 154. Eff 6-30-93; 149 v S 123, § 1, eff. 1-1-04; 150 v H 95, § 1, eff. 9-26-03; 150 v H 95, § 3.13, eff. 1-1-04; 150 v S 156, § 1, eff. 5-18-05.

**§ 4511.64. Slow-moving vehicles or equipment crossing railroad tracks.**

- (A) No person shall operate or move any crawler-type tractor, steam shovel, derrick, roller, or any equipment or structure having a normal operating speed of six or less miles per hour or a vertical body or load clearance of less than nine inches above the level surface of a roadway, upon or across any tracks at a railroad grade crossing without first complying with divisions (A)(1) and (2) of this section.
- (1) Before making any such crossing, the person operating or moving any such vehicle or equipment shall first stop the same, and while stopped the person shall listen and look in both directions along such track for any approaching train and for signals indicating the approach of a train, and shall proceed only upon exercising due care.
- (2) No such crossing shall be made when warning is given by automatic signal or crossing gates or a flagperson or otherwise of the immediate approach of a railroad train or car.
- (B) If the normal sustained speed of such vehicle, equipment, or structure is not more than three miles per hour, the person owning, operating, or moving the same shall also give notice of such intended crossing to a station agent or superintendent of the railroad, and a reasonable time shall be given to such railroad to provide proper protection for such crossing. Where such vehicles or equipment are being used in constructing or repairing a section of highway lying on both sides of a railroad grade crossing, and in such construction or repair it is necessary to repeatedly move such vehicles or equipment over such crossing, one daily notice specifying when such work will start and stating the hours during which it will be prosecuted is sufficient.
- (C) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-62; 119 v 766(786), § 62; Bureau of Code Revision. Eff 10-1-53; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.65. Through highways.**

- (A) All state routes are hereby designated as through highways, provided that stop signs, yield signs, or traffic control signals shall be erected at all intersections with such through highways by the department of transportation as to highways under its jurisdiction and by local authorities as to highways under their jurisdiction, except as otherwise provided in this section. Where two or more state routes that are through highways intersect and no traffic control signal is in operation, stop signs or yield signs shall be erected at one or more entrances thereto by the department, except as otherwise provided in this section.

Whenever the director of transportation determines on the basis of an engineering and traffic investigation that stop signs are necessary to stop traffic on a through highway for safe and efficient operation, nothing in this section shall be construed to prevent such installations. When circumstances warrant, the director also may omit stop signs on roadways intersecting through highways under his jurisdiction. Before the director either installs or removes a stop sign under this division, he shall give notice, in writing, of that proposed action to the affected local authority at least thirty days before installing or removing the stop sign.

- (B) Other streets or highways, or portions thereof, are hereby designated through highways if they are within a municipal corporation, if they have a continuous length of more than one mile between the limits of said street or highway or portion thereof, and if they have "stop" or "yield" signs or traffic control signals at the entrances of the majority of intersecting streets or highways. For purposes of this section, the limits of said street or highway or portion thereof shall be a municipal corporation line, the physical terminus of the street or highway, or any point on said street or highway at which vehicular traffic thereon is required by regulatory signs to stop or yield to traffic on the intersecting street, provided that in residence districts a municipal corporation may by ordinance designate said street or highway, or portion thereof, not to be a through highway and thereafter the affected residence district shall be indicated by official traffic control devices. Where two or more through highways designated under this division intersect and no traffic control signal is in operation, stop signs or yield signs shall be erected at one or more entrances thereto by the department or by local authorities having jurisdiction, except as otherwise provided in this section.
- (C) The department or local authorities having jurisdiction need not erect stop signs at intersections they find to be so constructed as to permit traffic to safely enter a through highway without coming to a stop. Signs shall be erected at such intersections indicating that the operator of a vehicle shall yield the right-of-way to or merge with all traffic proceeding on the through highway.
- (D) Local authorities with reference to highways under their jurisdiction may designate additional through highways and shall erect stop signs, yield signs, or traffic control signals at all streets and highways intersecting such through highways, or may designate any intersection as a stop or yield intersection and shall erect like signs at one or more entrances to such intersection.

HISTORY: GC § 6307-63; 119 v 766(787), § 63; Bureau of Code Revision, 10-1-53; 128 v 1270 (Eff 11-4-59); 131 v 1103 (Eff 10-15-65); 135 v H 200 (Eff 9-28-73); 136 v H 21 (Eff 12-30-75); 138 v H 290 (Eff 1-10-80); 143 v H 258. Eff 11-2-89.

**§ 4511.66. Prohibition against parking on highways.**

- (A) Upon any highway outside a business or residence district, no person shall stop, park, or leave standing any vehicle, whether attended or unattended, upon the paved or main traveled part of the highway if it is practicable to stop, park, or so leave such vehicle off the paved or main traveled part of said highway. In every event a clear and unobstructed portion of the highway opposite such standing vehicle shall be left for the free passage of other vehicles, and a clear view of such stopped vehicle shall be available from a distance of two hundred feet in each direction upon such highway.

This section does not apply to the driver of any vehicle which is disabled while on the paved or improved or main traveled portion of a highway in such manner and to such extent that it is impossible to avoid stopping and temporarily leaving the disabled vehicle in such position.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been

convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-64; 119 v 766(788), § 64; Bureau of Code Revision. Eff 10-1-53; 149 v S 123, § 1, eff. 1-1-04.

**[§ 4511.66.1] § 4511.661. Condition when motor vehicle left unattended.**

(A) No person driving or in charge of a motor vehicle shall permit it to stand unattended without first stopping the engine, locking the ignition, removing the key from the ignition, effectively setting the parking brake, and, when the motor vehicle is standing upon any grade, turning the front wheels to the curb or side of the highway.

The requirements of this section relating to the stopping of the engine, locking of the ignition, and removing the key from the ignition of a motor vehicle shall not apply to an emergency vehicle or a public safety vehicle.

(B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995 (Eff 1-1-75); 136 v H 763. Eff 8-6-76; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.67. Police may remove illegally parked vehicle.**

Whenever any police officer finds a vehicle standing upon a highway in violation of section 4511.66 of the Revised Code, such officer may move such vehicle, or require the driver or other person in charge of the vehicle to move the same, to a position off the paved or improved or main traveled part of such highway.

Whenever any police officer finds a vehicle unattended upon any highway, bridge, or causeway, or in any tunnel, where such vehicle constitutes an obstruction to traffic, such officer may provide for the removal of such vehicle to the nearest garage or other place of safety.

HISTORY: GC § 6307-65; 119 v 766(788), § 65; 121 v 684; Bureau of Code Revision. Eff 10-1-53.

**§ 4511.68. Parking prohibitions.**

(A) No person shall stand or park a trackless trolley or vehicle, except when necessary to avoid conflict with other traffic or to comply with sections 4511.01 to 4511.78, 4511.99, and 4513.01 to 4513.37 of the Revised Code, or while obeying the directions of a police officer or a traffic control device, in any of the following places:

- (1) On a sidewalk, except a bicycle;
- (2) In front of a public or private driveway;
- (3) Within an intersection;
- (4) Within ten feet of a fire hydrant;
- (5) On a crosswalk;
- (6) Within twenty feet of a crosswalk at an Intersection;
- (7) Within thirty feet of, and upon the approach to, any flashing beacon, stop sign, or traffic control device;
- (8) Between a safety zone and the adjacent curb or within thirty feet of points on the curb immediately opposite the ends of a safety zone, unless a different length is indicated by a traffic control device;
- (9) Within fifty feet of the nearest rail of a railroad crossing;
- (10) Within twenty feet of a driveway entrance to any fire station and, on the side of the street opposite the entrance to any fire station, within seventy-five feet of the entrance when it is properly posted with signs;

- (11) Alongside or opposite any street excavation or obstruction when such standing or parking would obstruct traffic;
- (12) Alongside any vehicle stopped or parked at the edge or curb of a street;
- (13) Upon any bridge or elevated structure upon a highway, or within a highway tunnel;
- (14) At any place where signs prohibit stopping,
- (15) Within one foot of another parked vehicle;
- (16) On the roadway portion of a freeway, expressway, or thruway.

(B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-66; 119 v 766(788), § 66; 124 v 514; Bureau of Code Revision, 10-1-53; 130 v 1087. Eff 8-5-63; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.681. Parking on private property.**

- (A) If an owner of private property posts on the property, in a conspicuous manner, a prohibition against parking on the property or conditions and regulations under which parking is permitted, no person shall do either of the following:
- (1) Park a vehicle on the property without the owner's consent;
  - (2) Park a vehicle on the property in violation of any condition or regulation posted by the owner.

(B) Whoever violates this section is guilty of a minor misdemeanor.

HISTORY: 139 v H 707 (Eff 1-1-83); 140 v H 112. Eff 10-4-84; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.69. Parking near curb, facing direction of travel; locations and privileges for walking-impaired persons.**

- (A) Every vehicle stopped or parked upon a roadway where there is an adjacent curb shall be stopped or parked with the right-hand wheels of the vehicle parallel with and not more than twelve inches from the right-hand curb, unless it is impossible to approach so close to the curb; in such case the stop shall be made as close to the curb as possible and only for the time necessary to discharge and receive passengers or to load or unload merchandise. Local authorities by ordinance may permit angle parking on any roadway under their jurisdiction, except that angle parking shall not be permitted on a state route within a municipal corporation unless an unoccupied roadway width of not less than twenty-five feet is available for free-moving traffic.
- (B) Local authorities by ordinance may permit parking of vehicles with the left-hand wheels adjacent to and within twelve inches of the left-hand curb of a one-way roadway.
- (C) No vehicle or trackless trolley shall be stopped or parked on a road or highway with the vehicle or trackless trolley facing in a direction other than the direction of travel on that side of the road or highway.
- (D) Notwithstanding any statute or any rule, resolution, or ordinance adopted by any local authority, air compressors, tractors, trucks, and other equipment, while being used in the construction, reconstruction, installation, repair, or removal of facilities near, on, over, or under a street or highway, may stop, stand, or park where necessary in order to perform such work, provided a flagperson is on duty or warning signs or lights are displayed as may be prescribed by the director of transportation.
- (E) Special parking locations and privileges for persons with disabilities that limit or impair the ability to walk, also known as handicapped parking spaces or disability parking spaces, shall be provided and designated by all political subdivisions and by the state and all agencies and instrumentalities thereof at all offices and facilities, where parking is provided, whether owned, rented, or leased, and at all publicly owned parking garages. The locations shall be designated through the posting of an elevated sign, whether permanently affixed or movable, imprinted with the international symbol of access and shall be

reasonably close to exits, entrances, elevators, and ramps. All elevated signs posted in accordance with this division and division (C) of section 3781.111 [3781.11.1] of the Revised Code shall be mounted on a fixed or movable post, and the distance from the ground to the top edge of the sign shall measure five feet. If a new sign or a replacement sign designating a special parking location is posted on or after October 14, 1999, there also shall be affixed upon the surface of that sign or affixed next to the designating sign a notice that states the fine applicable for the offense of parking a motor vehicle in the special designated parking location if the motor vehicle is not legally entitled to be parked in that location.

- (F) (1) No person shall stop, stand, or park any motor vehicle at special parking locations provided under division (E) of this section or at special clearly marked parking locations provided in or on privately owned parking lots, parking garages, or other parking areas and designated in accordance with that division, unless one of the following applies:
- (a) The motor vehicle is being operated by or for the transport of a person with a disability that limits or impairs the ability to walk and is displaying a valid removable windshield placard or special license plates;
  - (b) The motor vehicle is being operated by or for the transport of a handicapped person and is displaying a parking card or special handicapped license plates.
- (2) Any motor vehicle that is parked in a special marked parking location in violation of division (F)(1)(a) or (b) of this section may be towed or otherwise removed from the parking location by the law enforcement agency of the political subdivision in which the parking location is located. A motor vehicle that is so towed or removed shall not be released to its owner until the owner presents proof of ownership of the motor vehicle and pays all towing and storage fees normally imposed by that political subdivision for towing and storing motor vehicles. If the motor vehicle is a leased vehicle, it shall not be released to the lessee until the lessee presents proof that that person is the lessee of the motor vehicle and pays all towing and storage fees normally imposed by that political subdivision for towing and storing motor vehicles.
- (3) If a person is charged with a violation of division (F)(1)(a) or (b) of this section, it is an affirmative defense to the charge that the person suffered an injury not more than seventy-two hours prior to the time the person was issued the ticket or citation and that, because of the injury, the person meets at least one of the criteria contained in division (A)(1) of section 4503.44 of the Revised Code.
- (G) When a motor vehicle is being operated by or for the transport of a person with a disability that limits or impairs the ability to walk and is displaying a removable windshield placard or a temporary removable windshield placard or special license plates, or when a motor vehicle is being operated by or for the transport of a handicapped person and is displaying a parking card or special handicapped license plates, the motor vehicle is permitted to park for a period of two hours in excess of the legal parking period permitted by local authorities, except where local ordinances or police rules provide otherwise or where the vehicle is parked in such a manner as to be clearly a traffic hazard.
- (H) No owner of an office, facility, or parking garage where special parking locations are required to be designated in accordance with division (E) of this section shall fail to properly mark the special parking locations in accordance with that division or fail to maintain the markings of the special locations, including the erection and maintenance of the fixed or movable signs.
- (I) Nothing in this section shall be construed to require a person or organization to apply for a removable windshield placard or special license plates if the parking card or special license plates issued to the person or organization under prior law have not expired or been surrendered or revoked.
- (J) (1) Whoever violates division (A) or (C) of this section is guilty of a minor misdemeanor.
- (2) (a) Whoever violates division (F)(1)(a) or (b) of this section is guilty of a misdemeanor and shall be punished as provided in division (J)(2)(a) and (b) of this section. Except as otherwise provided in division (J)(2)(a) of this section, an offender who violates division (F)(1)(a) or (b) of this section shall be fined not less than two hundred fifty nor more than five hundred dollars. An offender who violates division (F)(1)(a) or (b) of this section shall be fined not more than one hundred dollars if the offender, prior to sentencing, proves either of the following to the satisfaction of the court:
- (i) At the time of the violation of division (F)(1)(a) of this section, the offender or the person for whose transport the motor vehicle was being operated had been issued a removable windshield placard that then was valid or special license plates that then were valid but the

offender or the person neglected to display the placard or license plates as described in division (F)(1)(a) of this section.

- (ii) At the time of the violation of division (F)(1)(b) of this section, the offender or the person for whose transport the motor vehicle was being operated had been issued a parking card that then was valid or special handicapped license plates that then were valid but the offender or the person neglected to display the card or license plates as described in division (F)(1)(b) of this section.

- (b) In no case shall an offender who violates division (F)(1)(a) or (b) of this section be sentenced to any term of imprisonment.

An arrest or conviction for a violation of division (F)(1)(a) or (b) of this section does not constitute a criminal record and need not be reported by the person so arrested or convicted in response to any inquiries contained in any application for employment, license, or other right or privilege, or made in connection with the person's appearance as a witness

The clerk of the court shall pay every fine collected under division (J)(2) of this section to the political subdivision in which the violation occurred. Except as provided in division (J)(2) of this section, the political subdivision shall use the fine moneys it receives under division (J)(2) of this section to pay the expenses it incurs in complying with the signage and notice requirements contained in division (E) of this section. The political subdivision may use up to fifty per cent of each fine it receives under division (J) (2) of this section to pay the costs of educational, advocacy, support, and assistive technology programs for persons with disabilities, and for public improvements within the political subdivision that benefit or assist persons with disabilities, if governmental agencies or nonprofit organizations offer the programs.

- (3) Whoever violates division (H) of this section shall be punished as follows:

- (a) Except as otherwise provided in division (J)(3) of this section, the offender shall be issued a warning.
- (b) If the offender previously has been convicted of or pleaded guilty to a violation of division (H) of this section or of a municipal ordinance that is substantially similar to that division, the offender shall not be issued a warning but shall be fined not more than twenty-five dollars for each parking location that is not properly marked or whose markings are not properly maintained.

- (K) As used in this section:

- (1) "Handicapped person" means any person who has lost the use of one or both legs or one or both arms, who is blind, deaf, or so severely handicapped as to be unable to move without the aid of crutches or a wheelchair, or whose mobility is restricted by a permanent cardiovascular, pulmonary, or other handicapping condition.
- (2) "Person with a disability that limits or impairs the ability to walk" has the same meaning as in section 4503.44 of the Revised Code.
- (3) "Special license plates" and "removable windshield placard" mean any license plates or removable windshield placard or temporary removable windshield placard issued under section 4503.41 or 4503.44 of the Revised Code, and also mean any substantially similar license plates or removable windshield placard or temporary removable windshield placard issued by a state, district, country, or sovereignty.

HISTORY: GC §§ 6307-67; 119 v 766(789), §§ 67; 121 v 684; 124 v 514; Bureau of Code Revision, 10-1-53; 135 v H 200 (Eff 9-28-v H 48 (Eff 1-1-83); 139 v H 116 (Eff 7-5-82); 140 v H 174 (Eff 9-30-83); 142 v H 111 (Eff 4-27-88); 144 v H 73 (Eff 9-25-91); 144 v S 98 (Eff 11-12-92); 145 v H 687 (Eff 1-1-95); 148 v H 148. Eff 10-14-99; 149 v S 123, § 1, eff. 1-1-04; 149 v H 490, § 1, eff. 1-1-04.

#### **§ 4511.712. Obstructing passage of other vehicles.**

- (A) No driver shall enter an intersection or marked crosswalk or drive onto any railroad grade crossing unless there is sufficient space on the other side of the intersection, crosswalk, or grade crossing to accommodate the vehicle, streetcar, or trackless trolley the driver is operating without obstructing the passage of other vehicles, streetcars, trackless trolleys, pedestrians, or railroad trains, notwithstanding any traffic control signal indication to proceed.

- (B) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If, within one year of the offense, the offender previously has been convicted of or pleaded guilty to one predicate motor vehicle or traffic offense, whoever violates this section is guilty of a misdemeanor of the fourth degree. If, within one year of the offense, the offender previously has been convicted of two or more predicate motor vehicle or traffic offenses, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: 135 v H 995. Eff 1-1-75; 149 v S 123, § 1, eff. 1-1-04.

**§ 4511.75. Stopping for school bus; signals.**

- (A) The driver of a vehicle, streetcar, or trackless trolley upon meeting or overtaking from either direction any school bus stopped for the purpose of receiving or discharging any school child, person attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities, or child attending a program offered by a head start agency, shall stop at least ten feet from the front or rear of the school bus and shall not proceed until such school bus resumes motion, or until signaled by the school bus driver to proceed.

It is no defense to a charge under this division that the school bus involved failed to display or be equipped with an automatically extended stop warning sign as required by division (B) of this section.

- (B) Every school bus shall be equipped with amber and red visual signals meeting the requirements of section 4511.771 of the Revised Code, and an automatically extended stop warning sign of a type approved by the state board of education, which shall be actuated by the driver of the bus whenever but only whenever the bus is stopped or stopping on the roadway for the purpose of receiving or discharging school children, persons attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities, or children attending programs offered by head start agencies. A school bus driver shall not actuate the visual signals or the stop warning sign in designated school bus loading areas where the bus is entirely off the roadway or at school buildings when children or persons attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities are loading or unloading at curbside or at buildings when children attending programs offered by head start agencies are loading or unloading at curbside. The visual signals and stop warning sign shall be synchronized or otherwise operated as required by rule of the board.
- (C) Where a highway has been divided into four or more traffic lanes, a driver of a vehicle, streetcar, or trackless trolley need not stop for a school bus approaching from the opposite direction which has stopped for the purpose of receiving or discharging any school child, persons attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities, or children attending programs offered by head start agencies. The driver of any vehicle, streetcar, or trackless trolley overtaking the school bus shall comply with division (A) of this section.
- (D) School buses operating on divided highways or on highways with four or more traffic lanes shall receive and discharge all school children, persons attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities, and children attending programs offered by head start agencies on their residence side of the highway.
- (E) No school bus driver shall start the driver's bus until after any child, person attending programs offered by community boards of mental health and county boards of mental retardation and developmental disabilities, or child attending a program offered by a head start agency who may have alighted therefrom has reached a place of safety on the child's or person's residence side of the road.
- (F) (1) Whoever violates division (A) of this section may be fined an amount not to exceed five hundred dollars. A person who is issued a citation for a violation of division (A) of this section is not permitted to enter a written plea of guilty and waive the person's right to contest the citation in a trial but instead must appear in person in the proper court to answer the charge.
- (2) In addition to and independent of any other penalty provided by law, the court or mayor may impose upon an offender who violates this section a class seven suspension of the offender's driver's license, commercial driver's license, temporary instruction permit, probationary license, or nonresident operating privilege from the range specified in division (A)(7) of section 4510.02 of the Revised Code. When a license is suspended under this section, the court or mayor shall cause the

offender to deliver the license to the court, and the court or clerk of the court immediately shall forward the license to the registrar of motor vehicles, together with notice of the court's action

(G) As used in this section:

- (1) "Head start agency" has the same meaning as in section 3301.31 of the Revised Code.
- (2) "School bus," as used in relation to children who attend a program offered by a head start agency, means a bus that is owned and operated by a head start agency, is equipped with an automatically extended stop warning sign of a type approved by the state board of education, is painted the color and displays the markings described in section 4511.77 of the Revised Code, and is equipped with amber and red visual signals meeting the requirements of section 4511.771 of the Revised Code, irrespective of whether or not the bus has fifteen or more children aboard at any time. "School bus" does not include a van owned and operated by a head start agency, irrespective of its color, lights, or markings.

HISTORY: GC § 6307-73; 119 v 766(790), § 73; 123 v 614; Bureau of Code Revision, 10-1-53; 125 v 167 (Eff 10-2-53); 135 v H 995 (Eff 1-1-75); 136 v H 369 (Eff 8-29-75); 137 v S 389 (Eff 3-15-79); 138 v S 160 (Eff 10-31-80); 140 v H 478 (Eff 3-28-85); 147 v H 618. Eff 3-22-99; 149 v S 123, § 1, eff. 1-1-04; 150 v H 95, § 3.13, eff. 7-1-04.

#### **§ 4511.76. School bus construction, design, equipment, operation and licensing rules.**

- (A) The department of public safety, by and with the advice of the superintendent of public instruction, shall adopt and enforce rules relating to the construction, design, and equipment, including lighting equipment required by section 4511.771 of the Revised Code, of all school buses both publicly and privately owned and operated in this state.
- (B) The department of education, by and with the advice of the director of public safety, shall adopt and enforce rules relating to the operation of all vehicles used for pupil transportation.
- (C) No person shall operate a vehicle used for pupil transportation within this state in violation of the rules of the department of education or the department of public safety. No person, being the owner thereof or having the supervisory responsibility therefor, shall permit the operation of a vehicle used for pupil transportation within this state in violation of the rules of the department of education or the department of public safety.
- (D) The department of public safety shall adopt and enforce rules relating to the issuance of a license under section 4511.763 of the Revised Code. The rules may relate to the moral character of the applicant; the condition of the equipment to be operated; the liability and property damage insurance carried by the applicant; the posting of satisfactory and sufficient bond; and such other rules as the director of public safety determines reasonably necessary for the safety of the pupils to be transported.
- (E) As used in this section, "vehicle used for pupil transportation" means any vehicle that is identified as such by the department of education by rule and that is subject to Chapter 3301-83 of the Administrative Code.
- (F) Except as otherwise provided in this division, whoever violates this section is guilty of a minor misdemeanor. If the offender previously has been convicted of or pleaded guilty to one or more violations of this section or section 4511.63, 4511.761, 4511.762, 4511.764, 4511.77, or 4511.79 of the Revised Code or a municipal ordinance that is substantially similar to any of those sections, whoever violates this section is guilty of a misdemeanor of the third degree.

HISTORY: GC § 6307-74; 119 v 766(790), § 74; 122 v 284; Bureau of Code Revision, 10-1-53; 126 v 392(412) (Eff 3-17-55); 129 v 1273 (Eff 10-26-61); 131 v 1105 (Eff 9-1-65); 132 v H 1 (Eff 2-21-67); 135 v H 995 (Eff 1-1-75); 144 v S 98 (Eff 11-12-92); 147 v S 60 (Eff 10-21-97); 149 v H 73. Eff 6-29-2001; 149 v S 123, § 1, eff. 1-1-04.

#### **§ 4511.98. Warning signs as to increased penalties in construction zones.**

The director of transportation, board of county commissioners, or board of township trustees shall cause signs to be erected advising motorists that increased penalties apply for certain traffic violations occurring on streets or highways in a construction zone. The increased penalties shall be effective only when signs are erected in accordance with the guidelines and design specifications established by the director under section

5501.27 of the Revised Code, and when a violation occurs during hours of actual work within the construction zone.

HISTORY: 145 v H 247. Eff 5-1-95; 150 v H 52, § 1, eff. 6-1-04.

**§ 4513.40. Warning sign before safety device at street crossing.**

When a safety device has been installed in the traveled portion of a street at a railroad grade crossing for the protection of the traveling public, the municipal corporation shall place a warning sign not less than two hundred feet from the crossing. The driver of any vehicle shall place his vehicle under control at the location of said warning signs so as to be able to bring said vehicle to a complete stop at said safety device. Colliding with such safety device at the crossing is prima-facie evidence that the driver is a reckless driver.

HISTORY: GC § 591-1; 117 v 655; Bureau of Code Revision, 10-1-53; 125 v 903(1026). Eff 10-1-53.

**§ 4519.40. Prohibitions.**

(A) The applicable provisions of Chapters 4511. and 4549. of the Revised Code shall be applied to the operation of snowmobiles, off-highway motorcycles, and all purpose vehicles, except that no snowmobile, off-highway motorcycle, or all-purpose vehicle shall be operated as follows:

- (1) On any limited access highway or freeway or the right-of-way thereof, except for emergency travel only during such time and in such manner as the director of public safety shall designate;
- (2) On any private property, or in any nursery or planting area, without the permission of the owner or other person having the right to possession of the property;
- (3) On any land or waters controlled by the state, except at those locations where a sign has been posted permitting such operation;
- (4) On the tracks or right-of-way of any operating railroad;
- (5) While transporting any firearm, bow, or other implement for hunting, that is not unloaded and securely encased;
- (6) For the purpose of chasing, pursuing, capturing, or killing any animal or wildfowl;
- (7) During the time from sunset to sunrise, unless displaying lighted lights as required by section 4519.20 of the Revised Code.

(B) Whoever violates this section shall be fined not less than fifty nor more than five hundred dollars, imprisoned not less than three nor more than thirty days, or both.

HISTORY: 134 v H 214 (Eff 3-7-72); 138 v H 450 (Eff 5-29-80); 144 v S 98 (Eff 11-12-92); 147 v H 611 (Eff 7-1-99); 148 v H 484. Eff 10-5-2000; 149 v S 123, § 1, eff. 1-1-04.

**§ 4907.47. Installation of crossing signals; apportionment of cost; additional protective devices.**

(A) If, after public hearing as to the necessity for installing protective devices at a public railroad highway grade crossing, written notice of which is published once a week for three consecutive weeks in a newspaper of general circulation in the county in which the crossing is located and is given the railroad and public authority involved at least thirty days in advance of such hearing, it is the opinion of the public utilities commission that the public safety requires a gate, automatic alarm bell, or other mechanical device to be erected and maintained at any place where a public road or street is crossed at the same level by a railroad, and the crossing has been declared by the commission to be so dangerous and hazardous as to require additional protective devices, or the public safety requires that a flagman be stationed and maintained at such crossing, the commission shall give the superintendent, manager, or other officer in charge of such railroad a written order of what is required, and shall assign the cost of installing any such device between the railroad and the public in any proportion it determines proper that is consistent with any applicable federal requirements, after giving due consideration to the factors listed in division (B) of this section.

(B) In assigning the cost of any such device the commission shall consider factors of volume of vehicular traffic, volume of train traffic, train type and speed, limitations of view and the causes thereof, savings, if any, which will inure to the railroad as the result of the installation, benefits to the public resulting from the reduction of hazard at the crossing, the probable cost of the installation, the future cost to the railroad of

maintaining any such device, and any other special factors and conditions that the commission considers relevant. The commission may accept a railroad's agreement to maintain the installation as being its share of the cost for the protection. If any part of the cost is assigned to the public, it shall be apportioned to the state agency or political subdivision having jurisdiction over such crossing, and may be paid from any funds levied and made available for highway or street purposes; provided, that funds from the grade crossing protection fund created by section 4907.472 of the Revised Code may be used to pay the public's share of the cost. After the commission has issued an appropriate order requiring that additional protective devices be installed by a specific date, which shall be a reasonable time from the date of the order, the railroad concerned shall erect or install the additional protective devices or station the flagman within the time prescribed by the order. If the additional protective devices are not erected or installed within that time, the commission may reduce or eliminate the amount of any funds in the grade crossing protection fund obligated to pay the public's share of the costs relating to the erection, installation, and maintenance of the additional protective devices and, consistent with any applicable federal requirements, may assign to the railroad concerned any amount, up to one hundred per cent, of the total amount of the costs of erecting, installing, and maintaining the additional protective devices.

Any person owning or operating a railroad and neglecting or refusing to erect or maintain such gate, automatic alarm bell, or other mechanical device, or to maintain such flagman, when required by the commission pursuant to this section or section 4907.471 of the Revised Code, and after the commission has issued an appropriate order finding that the public funds will be made available with respect to any protective device it has ordered installed, shall forfeit to the state, for every such neglect or refusal, one thousand dollars, and in addition, shall forfeit one thousand dollars for each day such neglect or refusal continues.

HISTORY: RS § 247a; 86 v 367; 91 v 353; GC §§ 588, 589; Bureau of Code Revision, 10-1-53; 129 v 313 (Eff 9-21-61); 135 v H 111 (Eff 7-26-73); 137 v S 221 (Eff 11-23-77); 141 v H 201 (Eff 7-1-85); 143 v H 111. Eff 10-29-89.

**§ 4907.471. Survey to determine crossings with highest probability of accident; additional protective devices.**

- (A) The public utilities commission shall survey all public crossings of railroads at grade, whether on state, county, or township highways or on streets or ways within municipal corporations. The commission shall devise a formula according to sound highway engineering practice for determining the probability of accident at each such crossing and may include in the formula factors representing volume of vehicular traffic, volume of train traffic, history of previous accidents, train type and speed, limitations of view, intersection angle, number of tracks, highway alignment, and such other special factors and conditions as are in its opinion relevant. The commission shall submit the formula to the director of transportation, who shall review it to ensure that it is consistent with applicable federal requirements.

The commission shall classify all such public crossings according to that formula and shall prepare a priority list for the protection of such crossings, giving highest priority to the crossings at which the commission finds the highest probability of accident, and lowest priority to the ones at which it finds the least probability of accident, provided that for the purposes of this section the commission shall place first on the list any crossing that meets all of the following criteria:

- (1) The crossing is at a section of railroad track that is being reactivated on or after May 1, 1990, and that has not been used for at least three years prior to the reactivation as determined by the commission;
- (2) The territory abutting the railroad's right-of-way for a distance of three hundred feet or more has been improved with residences during the period of time the track was not being used;
- (3) The commission has designated the crossing as dangerous and hazardous under division (A) of this section.

The priority list shall be for the use of the commission in carrying out this section and sections 4907.47, 4907.474, and 4907.475 of the Revised Code and shall not be admissible in evidence in any action to recover damages for negligence arising out of the use of such grade crossings. The list shall be made available to the department of transportation for use in carrying out sections 4511.61 and 4955.33 of the Revised Code.

The survey shall be continuous, and after the original list is prepared, the commission may change the respective priority ratings as it may from time to time determine. When new crossings at grade are opened, the commission shall survey them and place them on the priority list at such places as in its opinion the probability of accident at those crossings warrants.

The commission may, pursuant to the priority ratings established as provided in this section, designate as dangerous and hazardous any railroad highway grade crossing it determines to be in need of additional protective devices. With respect to a high priority crossing so designated, the commission may negotiate with the railroad concerned, and with the state agency or political subdivision having jurisdiction over the crossing, an agreement providing for the installation at the crossing of appropriate luminous reflecting warning signs, luminous flashing signals, crossing gates illuminated at night, or other protective devices. The number, type, and location of the signs, signals, gates, or other protective devices, which shall conform with generally recognized national standards, shall be determined by agreement among the commission, the railroad concerned, and the state agency or political subdivision. The assignment of any part or all of the cost of the installation and subsequent maintenance of such signs, signals, gates, or other protective devices to the railroad and to the state or the political subdivisions shall be by the commission in any proportion it determines proper that is consistent with any applicable federal requirements, after giving due consideration to the factors listed in division (C) of this section.

- (B) In cases where the railroad does not agree that the installation of additional protective devices is necessary, or where no agreement can be reached with the railroad as to the number, type, or location of such devices or the proportion of cost to be assigned to the railroad, the commission shall hold a public hearing as to the necessity for installing additional protective devices at the crossing at issue. Written notice of the hearing shall be given to the railroad at least thirty days in advance of the hearing, and notice of the hearing shall be published once a week for three consecutive weeks in a newspaper of general circulation in the county in which the crossing at issue is located. If, after the hearing, it is the opinion of the commission that the public safety requires additional protective devices to be erected and maintained at the crossing, the commission shall give the superintendent, manager, or other officer in charge of the railroad a written order of the protective devices required and the date by which any action shall be completed, and shall assign to the parties the cost of installing and maintaining the protective devices in any proportion it determines proper that is consistent with any applicable federal requirements, after giving due consideration to the factors listed in division (C) of this section.
- (C) In assigning the cost of additional protective devices, the commission shall consider factors of volume of vehicular traffic, volume of train traffic, train type and speed, limitations of view and the causes thereof, savings, if any, which will inure to the railroad as the result of the installation, benefits to the public resulting from the reduction of hazard at the crossing, the probable cost of the installation, the future cost to the railroad of maintaining the devices, and any other special factors and conditions that the commission considers relevant. The commission may accept a railroad's agreement to maintain the additional protective devices as being its share of the cost for the protection. If any part of the cost of installation is assigned by the commission to the state agency or political subdivision having jurisdiction over the crossing, that cost may be paid from any funds levied and made available for highway or street purposes, provided that funds from the grade crossing protection fund created by section 4907.472 of the Revised Code may be used to pay the public's share of the cost. After the commission has issued an appropriate order requiring that additional protective devices be installed by a specific date, which shall be a reasonable time from the date of the order, the railroad concerned shall erect or install the additional protective devices within the time prescribed by the order. If the additional protective devices are not erected or installed within that time, the commission may reduce or eliminate the amount of any funds in the grade crossing protection fund obligated to pay the public's share of the costs relating to the erection, installation, and maintenance of the additional protective devices and, consistent with any applicable federal requirements, may assign to the railroad concerned any amount, up to one hundred per cent, of the total amount of the costs of erecting, installing, and maintaining the additional protective devices.

HISTORY: RC § 5523.31, 129 v 582(945) (Eff 1-10-61); 135 v H 111 (Eff 7-26-73); 135 v H 200 (Eff 9-28-73); 137 v S 221 (Eff 11-23-77); 141 v H 201 (Eff 7-1-85); RC § 4907.47.1, 143 v H 111 (Eff 10-29-89); 144 v S 8 (Eff 5-21-91); 144 v H 248. Eff 11-28-91.

**§ 4907.48. Regulation of crossing signals.**

All gates, bells, or devices erected under the direction of the public utilities commission shall be built within the time, in the manner, and of materials approved by the commission. Such devices so authorized shall be located in the highway or street on one or both sides of the railroad tracks, as the commission deems the public safety requires. Such gates shall be so constructed that when closed they obstruct or prevent passage across such railroad from the side on which a gate is located. Such bell must be so constructed that it will ring before the approach of every train of cars or locomotive within three hundred feet or more of such crossing, and continue to ring until such train or locomotive has reached the crossing. A person shall be in charge of such gate who shall close it at the approach of each train or locomotive and keep it open at all other times. If an automatic bell or other mechanical device is required at such crossing, the railroad shall keep such bell or device in good working order. For every neglect of duty imposed by this section such railroad shall forfeit twenty-five dollars.

HISTORY: RS § 247b; 86 v 367; 91 v 353; GC § 590; 113 v 83; Bureau of Code Revision. Eff 10-1-53.

**§ 4907.49. Dangerous crossings.**

When two or more railroads cross a public highway or street at a dangerous crossing, the expenses incurred in the erection and maintenance of gates, bells, or other devices, and of necessary gatekeepers or flagmen, and apportioned by the public utilities commission as railroad expense, shall be shared equally by the railroads.

Chapters 4901., 4903., 4905., 4907., 4909., 4921., and 4923. of the Revised Code do not prevent the use of automatic bells or other mechanical devices by a railroad at a public crossing not declared dangerous by the public utilities commission, nor do they prevent state, county, township, or municipal officials from entering into an agreement with a railroad to pay all or part of the expense of erecting a warning device. Any funds levied and made available for highways or street purposes may be used to pay the public share of the cost under such an agreement. If a gate is erected or a flagman is stationed and maintained by a railroad, either alone or pursuant to such an agreement, the gate or flagman shall not be abandoned nor an automatic bell or other mechanical device substituted for the gate or flagman, unless the commission consents to the abandonment or substitution.

HISTORY: 145 v S 75. Eff 10-20-94.

**§ 4907.52. Safety devices at grade crossings.**

When two railroads, a railroad and an interurban railroad or electric or street railway, two interurban railroads, or a railroad or electric railway and a street or highway cross at grade, if, in the opinion of the public utilities commission, public safety requires protection, the commission, upon its own motion or upon complaint, after notice to the railroads interested and full investigation, may make an order requiring the railroads so intersecting and crossing to install such devices as in the opinion of the commission will properly protect such crossing.

The commission may make any other orders regulating the speed and running of trains or of cars and the switching of cars over such crossing or street, and it shall apportion the expense of installation or maintenance of such devices between the railroad companies whose tracks are thus protected.

HISTORY: RS § 247e; 92 v 315; 99 v 390, § 2; GC §§ 594, 595; Bureau of Code Revision. Eff 10-1-53.

**§ 4951.02. Grant of right to construct.**

The right to construct or extend a street railway within or beyond the limits of a municipal corporation may be granted only by its legislative authority by ordinance. The right to construct such street railway without the limits of a municipal corporation may be granted only by the board of county commissioners by an order entered on its journal.

The legislative authority or the board may fix the conditions upon which such street railways may be constructed, operated, extended, and consolidated.

HISTORY: RS § 3443; RS Bates § 1536-183; 66 v 140; 67 v 10; 96 v 31, § 29; GC §§ 9101, 9113; Bureau of Code Revision. Eff 10-1-53.

**§ 4951.14. Acquisition or appropriation for crossings.**

Whenever it is deemed necessary by a majority of the board of directors of a street railway company to cross the streets, avenues, alleys, ways, or any part thereof, of any municipal corporation or any public highway outside of a municipal corporation, the legislative authority of such municipal corporation, or the public officers owning or having charge of such highways outside of municipal corporations, may agree with such company as to the manner and mode of such crossing and the compensation to be paid for it. If the parties fail to agree, such company may proceed in accordance with sections 163.01 to 163.22, inclusive, of the Revised Code. In its final order the court shall fix the manner and mode of such crossing. Upon compliance with such decree, the company may construct and maintain such crossing in accordance with the order in said cause.

HISTORY: GC § 9118-1; 101 v 375; Bureau of Code Revision, 10-1-53; 131 v 1201. Eff 1-1-66.

**§ 4955.201. Abandonment of track; restoration of roadway.**

(A) If the interstate commerce commission approves the abandonment of a railroad track that crosses a road or highway at grade, the railroad that owned the track immediately after the approval of the abandonment shall remove the track at the crossing and fill the space previously occupied by the rails with the same material that comprises the road or highway at the crossing. Upon completion of the work, the surface of the crossing where the rails previously were located shall be the same height as the surface of the road or highway abutting the crossing. The restored portion of the road or highway shall meet the construction standards applicable to the road or highway of which the restored portion is a part.

(B) No railroad shall fail to remove from a crossing the rails that comprise a track whose abandonment has been approved or fail to fill the space previously occupied by the rails as required by division (A) of this section.

HISTORY: 145 v H154. Eff 6-30-93.

**§ 4955.33. Crossbuck signs; additional reflective signs; experimental signs.**

At all points where its railroad crosses a public road at a common grade, each company shall erect crossbuck signing at positions at each such crossing that are in accordance with the department of transportation manual for uniform traffic control devices, adopted under section 4511.09 of the Revised Code, to give notice of the proximity of the railroad and warn persons to be on the lookout for the locomotive. Any such signing that has been or is erected in accordance with this section may lawfully be continued in use until it is replaced. A company that neglects or refuses to comply with this section is liable in damages for all injuries that occur to persons or property from such neglect or refusal.

Each crossbuck sign also shall be accompanied by an additional sign consisting of three panels, with the middle panel bearing the word "yield" spelled vertically. The front and rear faces of the crossbuck sign and of the three panels of the additional sign shall be coated or treated with a reflective material, and if the crossbuck sign and additional sign are mounted on a vertical girder or post, the girder or post also shall be coated or treated with a reflective material. The director, after consultation with those persons knowledgeable in the area of railroad-highway grade crossing safety as he may select, shall determine specifications for the crossbuck sign, additional sign, girder, or post, and for the reflectiveness of the reflective material described in this section.

The director of transportation may erect experimental signs at certain crossings in lieu of the above required signing, for the purpose of conducting research for the development of better signing systems. The erection of such a sign by the director at a particular crossing relieves the railroad company from any liability in damages that might otherwise arise under this section at the crossing.

With the prior approval of the director, a railroad company or local authority may erect experimental signs and warning devices at a crossing in lieu of the above required signing, for the purpose of conducting research for the development of better warning signing systems and devices. Such signs and warning devices may be erected on either an interim or permanent basis, as determined by the director, and the erection in accordance with this section of such signs and warning devices at a particular crossing relieves the railroad company or local authority from any liability in damages that might otherwise arise under this section at the crossing.

HISTORY: RS § 3323; S&C 279; 50 v 274, §18; GC § 8852; 113 v 27; Bureau of Code Revision, 10-1-53; 127 v 887 (Eff 9-16-57); 135 v H 200 (Eff 9-28-73); 135 v S 567 (Eff 6-29-74); 143 v H 258 (Eff 11-2-89); 144 v H 648. Eff 1-1-95.

**§ 5501.27. Rules for warning signs in construction zones.**

- (A) The director of transportation shall adopt rules that do the following:
- (1) Rules governing the posting of signs advising motorists that increased penalties apply for certain traffic violations occurring on streets or highways in a construction zone;
  - (2) Rules governing the posting of signs to be used pursuant to section 2903.081 [2903.08.1] of the Revised Code giving notice to motorists of the prohibitions set forth in sections 2903.06 and 2903.08 of the Revised Code regarding the death of or injury to any person in a construction zone as a proximate result of a reckless operation offense or speeding offense.
- (B) The rules required under divisions (A)(1) and (2) of this section shall include guidelines to determine which areas are appropriate to the posting of such signs. The guidelines may include consideration of the following: the duration of the work on the street or highway, the proximity of workers to moving traffic, the existence of any unusual or hazardous conditions, the volume of traffic on the street or highway, and any other appropriate factors. The director shall formulate design specifications for the signs described in division (A)(1) of this section advising motorists of the increased penalties and the signs described in division (A)(2) of this section notifying motorists of the prohibitions set forth in sections 2903.06 and 2903.08 of the Revised Code regarding the death of or injury to any person in a construction zone as a proximate result of a reckless operation offense or speeding offense as described in that division. For purposes of traffic violation penalties, nothing in this section is intended to conflict with any standard set forth in the federal manual of uniform traffic control devices for streets and highways.
- (C) As used in this section and in section 4511.98 of the Revised Code, "construction zone" means that lane or portion of street or highway open to vehicular traffic and adjacent to a lane, berm, or shoulder of a street or highway within which lane, berm, or shoulder construction, reconstruction, resurfacing, or any other work of a repair or maintenance nature, including public utility work, is being conducted, commencing with the point where the first worker or piece of equipment is located and ending where the last worker or piece of equipment is located.

HISTORY: 145 v H 247. Eff 11-1-94; 150 v H 52, § 1, eff. 6-1-04.

**§ 5591.42. Carrying capacity of bridges; warning notice.**

The board of county commissioners together with the county engineer or an engineer to be selected by the board, or the director of transportation, may ascertain the safe carrying capacity of the bridges on roads or highways under their jurisdiction. Where the safe carrying capacity of any such bridge is ascertained and found to be less than the load limit prescribed by sections 5577.01 to 5577.12 of the Revised Code, warning notice shall be conspicuously posted near each end of the bridge. The notice shall caution all persons against driving on the bridge a loaded conveyance of greater weight than the bridge's carrying capacity.

HISTORY: RS § 4944; S&C 193; 66 v 90; GC § 7572; 101 v 220; 119 v 182; Bureau of Code Revision, 10-1-53; 135 v H 200 (Eff 9-28-73); 139 v S 114 (Eff 10-27-81); 143 v H 258. Eff 11-2-89.

## APPENDIX C. SIGNING INDEX

### Regulatory Signs



R1-1  
Sec. 2B.04



R1-2  
Sec. 2B.08



R1-2a  
Sec. 2B.08



R1-3  
Sec. 2B.04



R1-4  
Sec. 2B.04



R1-5  
Sec. 2B.11



R1-5a  
Sec. 2B.11



R1-6  
Sec. 2B.12



R2-1  
Sec. 2B.13




R2-2  
Sec. 2B.14



R2-H2a  
Sec. 2B.14



R2-H2b  
Sec. 2B.13



R2-H2c  
Sec. 2B.13



R2-3  
Sec. 2B.15



R2-4  
Sec. 2B.16



R2-4a  
Sec. 2B.16



R2-6  
Sec. 2B.17



R3-1  
Sec. 2B.19



R3-1a  
Sec. 8B.06  
Sec. 10C.09



R3-2  
Sec. 2B.19



R3-2a  
Sec. 8B.06  
Sec. 10C.09



R3-3  
Sec. 2B.19

### Regulatory Signs - continued



R3-4  
Sec. 2B.19



R3-5  
Sec. 2B.21



R3-5a  
Sec. 2B.21



R3-5b  
Sec. 2B.21



R3-5c  
Sec. 2B.21



R3-5d  
Sec. 2B.21



R3-5e  
Sec. 2B.21



R3-5f  
Sec.2B.21



R3-5g  
Sec. 2B.21



R3-6  
Sec.2B.22



R3-7  
Sec.2B. 21



R3-8  
Sec.2B. 23



R3-8a  
Sec. 2B. 23




R3-8b  
Sec.2B. 23



R3-9a  
Sec. 2B.24



R3-9b  
Sec. 2B.24



R3-9d  
Sec. 2B.25



R3-9f  
Sec. 2B.25




R3-9g  
Sec. 2B.25



R3-9h  
Sec. 2B.25




R3-9i  
Sec. 2B.25



R3-10  
Sec. 2B.26



R3-10a  
Sec. 2B.26



R3-10b  
Sec. 2B.26



R3-11  
Sec. 2B.26



R3-11a  
Sec. 2B.26



R3-11b  
Sec. 2B.26



R3-11c  
Sec. 2B.26

**Regulatory Signs - continued**



R3-12  
Sec. 2B.26



R3-12a  
Sec. 2B.26



R3-12b  
Sec. 2B.28



R3-13  
Sec. 2B.26



R3-13a  
Sec. 2B.26



R3-14  
Sec. 2B.26



R3-14a  
Sec. 2B.26



R3-14b  
Sec. 2B.26



R3-15  
Sec. 2B.26



R3-15a  
Sec. 2B.26



R3-17  
Sec. 9B.04



R3-17a  
Sec. 9B.04



R3-17b  
Sec. 9B.04



R3-18  
Sec. 2B.19



R4-1  
Sec. 2B.29



R4-2  
Sec. 2B.30



R4-3  
Sec. 2B.31




R4-4  
Sec. 9B.05



R4-5  
Sec. 2B.32



R4-6  
Sec. 2B.32



R4-7  
Sec. 2B.33


**Regulatory Signs - continued**



R4-7a  
Sec. 2B.33



R4-7b  
Sec. 2B.33



R4-8  
Sec. 2B.33



R4-9  
Sec. 6F.11



R4-10  
Sec. 2C.13



R4-H11  
Sec. 2B.33.1



R4-H12  
Sec. 28.33.1



R5-1  
Sec. 2B.34



R5-1a  
Sec. 2B.35



R5-1b  
Sec. 9B.06



R5-2  
Sec. 2B.36



R5-2a  
Sec. 2B.36



R5-H2b  
Sec. 2B.36



R5-H2c  
Sec. 2B.36



R5-3  
Sec. 2B.36



R5-4  
Sec. 2B.36



R5-5  
Sec. 2B.36



R5-6  
Sec. 2B.36



R5-7  
Sec. 2B.36



R5-8  
Sec. 2B.36



R5-10a  
Sec. 2B.36



R5-10b  
Sec. 2B.36



R5-10c  
Sec. 2B.36



R6-1  
Sec. 2B.37






R6-2  
Sec. 2B.37



R6-3  
Sec. 2B.38

**Regulatory Signs - continued**



**Regulatory Signs - continued**



R8-3  
Sec. 2B.39



R8-3a  
Sec. 2B.39



R8-3c  
Sec. 2B.39



R8-3d  
Sec. 2B.39



R8-4  
Sec. 2B.42



R8-5  
Sec. 2B.39



R8-6  
Sec. 2B.39



R8-7  
Sec. 2B.42



R8-8  
Sec. 8B.07  
Sec. 10C.05



R8-9  
Sec. 8B.09  
Sec. 10C.06



R8-10  
Sec. 8B.10  
Sec. 10C.08



R9-1  
Sec. 2B.43



R9-2  
Sec. 2B.44



R9-3  
Sec. 2B.44



R9-3a  
Sec. 2B.44



R9-3b  
Sec. 2B.44



R9-3c  
Sec. 9B.06



R9-4  
Sec. 2B.43



R9-4a  
Sec. 2B.43



R9-5  
Sec. 9B.10



R9-6  
Sec. 9B.10



R9-7  
Sec. 9B.11




R9-8  
Sec. 6F.12



R9-9  
Sec. 6F.13



R9-10  
Sec. 6F.13



R9-11  
Sec. 6F.13

**Regulatory Signs - continued**



R9-11a  
Sec. 6F.13




R10-1  
Sec 2B.45



R10-2  
Sec. 2B.45



R10-2a  
Sec. 2B.45



R10-3  
Sec. 2B.45




R10-3a  
Sec. 2B.45




R10-3b  
Sec. 2B.45



R10-3c  
Sec. 2B.45



R10-3d  
Sec. 2B.45



R10-3e  
Sec. 2B.45



R10-4  
Sec. 2B. 45



R10-4a  
Sec. 2B.45



R10-4b  
Sec. 2B.45




R10-5  
Sec. 2B.45



R10-6  
Sec. 2B.45




R10-6a  
Sec. 2B.45



R10-7  
Sec. 2B.45



R10-8  
Sec. 2B.45



R10-10  
Sec. 2B.45




R10-11  
Sec. 2B.45



R10-11a  
Sec.2B.45



R10-11b  
Sec. 2B.45



R10-12  
Sec. 2B.45



R10-13  
Sec. 2B.45



R10-15  
Sec. 2B.45

**Regulatory Signs - continued**



R10-16  
Sec. 2B.45



R10-18  
Sec. 2B.46




R10-19  
Sec. 2B.46



R10-20a  
Sec. 2B.45

OR



R10-21  
Sec. 2B.45



R10-22  
Sec. 9B.12




R11-1  
Sec. 2B.47




R11-2  
Sec. 2B.48



R11-3  
Sec. 2B.48



R11-3a  
Sec. 2B.48



R11-3b  
Sec. 2B.48



R11-4  
Sec. 2B.48




R11-H5a  
Sec. 6F.14.1



R12-1  
Sec. 2B.49



R12-2  
Sec. 2B.49



R12-3  
Sec. 2B.49



R12-4  
Sec. 2B.49



R12-5  
Sec. 2B.49



R12-H5  
Sec. 2B.49



R13-H1  
Sec. 2B.50



R13-H2  
Sec. 2B.50

**Regulatory Signs - continued**



R14-1  
Sec. 2B.51



R14-2  
Sec. 2B.52



R14-3  
Sec. 2B.46



R15-1  
Sec. 8B.03  
Sec. 10C.02



R15-2  
Sec. 8B.03  
Sec. 10C.02



R15-3  
Sec. 8B.05  
Sec. 10C.10



R15-4a  
Sec. 10C.13



R15-4b  
Sec. 10C.13



R15-4c  
Sec. 10C.13



R15-5  
Sec. 10C.14



R15-5a  
Sec. 10C.14



R15-6  
Sec. 10C.12



R15-6a  
Sec. 10C.12



R15-7  
Sec. 10C.11



R15-7a  
Sec. 10C.11



R15-8  
Sec. 8B.16  
Sec. 10C.17



R16-H3  
Sec. 7B.15

Intentionally blank.

### Warning Signs



W1-1  
Sec. 2C.06



W1-1a  
Sec. 2C.07



W1-2  
Sec. 2C.06



W1-2a  
Sec. 2C.07



W1-3  
Sec. 2C.06



W1-4  
Sec. 2C.06



W1-4b  
Sec. 6F.46



W1-4c  
Sec. 6F.46



W1-5  
Sec. 2C.06



W1-6  
Sec. 2C.09



W1-7  
Sec. 2C.38



W1-8  
Sec. 2C.10



W1-10  
Sec. 2C.08



W1-11  
Sec. 2C.06



W1-H11  
Sec. 6F.41.1



W1-13  
Sec. 2C.11



W1-15  
Sec. 2C.06



W2-1  
Sec. 2C.37



W2-2  
Sec. 2C.37



W2-3  
Sec. 2C.37



W2-4  
Sec. 2C.37



W2-5  
Sec. 2C.37



W2-6  
Sec. 2C.37



W3-1  
Sec. 2C.29



W3-1a  
Sec. 2C.29



W3-2  
Sec. 2C.29



W3-2a  
Sec. 2C.29



W3-3  
Sec. 2C.29



W3-3a  
Sec. 2C.29



W3-4  
Sec. 2C.29

**Warning Signs – continued**



W3-5  
Sec. 2C.30



W3-5a  
Sec. 2C.30



W3-6  
Sec. 4I.02



W3-H12  
Sec. 4B.02



W4-1  
Sec. 2C.31



W4-2  
Sec. 2C.33



W4-3  
Sec. 2C.32



W4-4p  
Sec. 2C.50



W4-5  
Sec. 2C.31



W4-6  
Sec. 2C.32



W4-7  
Sec. 6F.23



W5-1  
Sec. 2C.15



W5-2  
Sec. 2C.16



W5-3  
Sec. 2C.17



W5-4  
Sec. 6F.26



W5-4a  
Sec. 9B.18



W6-1  
Sec. 2C.18



W6-1a  
Sec. 2C.18



W6-1b  
Sec. 2C.18



W6-2  
Sec. 2C.19



W6-2a  
Sec. 2C.19



W6-2b  
Sec. 2C.19



W6-3  
Sec. 2C.19



W6-4  
Sec. 6F.70



W7-1  
Sec. 2C.12



W7-1a  
Sec. 2C.12



W7-1b  
Sec. 2C.12



W7-2  
Sec. 2C.12



W7-2b  
Sec. 2C.12



W7-3  
Sec. 2C.12

**Warning Signs – continued**



W7-3a  
Sec. 2C.12



W7-3b  
Sec. 2C.12



W7-4  
Sec. 2C.13



W7-4b  
Sec. 2C.13



W7-4c  
Sec. 2C.13



W7-4d  
Sec. 2C.13



W7-4e  
Sec. 2C.13



W7-4f  
Sec. 2C.13



W7-5  
Sec. 9B.18



W7-6  
Sec. 2C.14



W8-1  
Sec. 2C.21



W8-2  
Sec. 2C.21



W8-3  
Sec. 2C.25



W8-4  
Sec. 2C.26



W8-5  
Sec. 2C.27



W8-6  
Sec. 2C.40



W8-7  
Sec. 2C.28.1



W8-8  
Sec. 2C.28.1



W8-9  
Sec. 2C.24



W8-9a  
Sec. 2C.26



W8-10  
Sec. 9B.16



W8-10p  
Sec. 9B.16



W8-11  
Sec. 6F.43



W8-H12  
Sec. 6F.44



W8-H12a  
Sec. 6F.44



W8-13  
Sec. 2C.28



W9-1  
Sec. 2C.33



W9-2  
Sec. 2C.33



W9-3  
Sec. 6F.22

**Warning Signs - continued**



W9-3a  
Sec. 6F.22



W10-1  
Sec. 8B.04  
Sec. 10C.15



W10-1a  
Sec. 8B.05  
Sec. 10C.10



W10-2  
Sec. 8B.04  
Sec. 10C.15



W10-3  
Sec. 8B.04  
Sec. 10C.15



W10-4  
Sec. 8B.04  
Sec. 10C.15



W10-5  
Sec. 8B.17  
Sec. 10C.16



W10-7  
Sec. 10C.17




W10-8  
Sec. 8B.13



W10-9  
Sec. 8B.14



W10-10  
Sec. 8B.15



W10-11  
Sec. 8B.18  
Sec. 10C.18



W10-11a  
Sec. 8B.18  
Sec. 10C.18



W10-11b  
Sec. 8B.18  
Sec. 10C.18



W10-12  
Sec. 8B.19  
Sec. 10C.19



W10-13  
Sec. 8B.15



W10-14  
Sec. 8B.17



W10-14a  
Sec. 8B.17



W10-15  
Sec. 8B.17



W11-1  
Sec. 9B.17



W11-2  
Sec. 2C.41



W11-3  
Sec. 2C.41



W11-4  
Sec. 2C.41



W11-5  
Sec. 2C.41



W11-5a  
Sec. 2C.40



W11-6  
Sec. 2C.41



W11-7  
Sec. 2C.41



W11-8  
Sec. 2C.40



W11-9  
Sec. 2C.41



W11-10  
Sec. 2C.40



W11-11  
Sec. 2C.40

**Warning Signs - continued**

					
W11-12p Sec. 2C.40	W11-14 Sec. 2C.40	W12-1 Sec. 2C.20	W12-2 Sec. 2C.22	W12-2p Sec. 2C.22	W13-1 Sec. 2C.46
					
W13-2 Sec. 2C.36	W13-3 Sec. 2C.36	W13-4 Sec. 6F.25	W13-5 Sec. 2C.36	W14-1 Sec. 2C.21	W14-1a Sec. 2C.21
					
W14-2 Sec. 2C.21	W14-2a Sec. 2C.21	W14-3 Sec. 2C.45	W15-1 Sec. 2C.35	W16-1 Sec. 2C.51	W16-2 Sec. 2C.45
					
W16-2a Sec. 2C.45	W16-3 Sec. 2C.45	W16-3a Sec. 2C.45	W16-4 Sec. 2C.45	W16-5p Sec. 2C.47	W16-6p Sec. 2C.47
					
W16-7p Sec. 2C.47	W16-8 Sec. 2C.49	W16-8a Sec. 2C.49	W16-9p Sec. 2C.34	W16-10 Sec. 2C.53	W16-11 Sec. 2C.52

**Warning Signs - continued**



W16-12p  
Sec. 2C.37



W16-13p  
Sec. 2C.29



W17-1  
Sec. 2C.24



W18-1  
Sec. 5C.12



W20-1  
Sec. 6F.17



W20-2  
Sec. 6F.18



W20-3  
Sec. 6F.19



W20-4  
Sec. 6F.20



W20-5  
Sec. 6F.21



W20-5a  
Sec. 6F.21



W20-7  
Sec. 6F.29



W20-7a  
Sec. 6F.29



W21-1  
Sec. 6F.31



W21-1a  
Sec. 6F.31



W21-2  
Sec. 6F.32



W21-3  
Sec. 6F.33



W21-5  
Sec. 6F.35



W21-5a  
Sec. 6F.35



W21-5b  
Sec. 6F.35



W21-6  
Sec. 6F.36



W21-7  
Sec. 6F.37



W22-1  
Sec. 6F.39



W22-2  
Sec. 6F.40



W22-3  
Sec. 6F.49



W23-1  
Sec. 6F.27



W24-1  
Sec. 6F.45



W24-1a  
Sec. 6F.45



W24-1b  
Sec. 6F.45



W25-1  
Sec. 2C.39



W25-2  
Sec. 2C.39

### Guide Signs – Marker Series



M1-1  
Sec. 2D.11



M1-2  
Sec. 2D.11



M1-3  
Sec. 2D.11



M1-4  
Sec. 2D.11



M1-5  
Sec. 2D.11



M1-6  
Sec. 2D.11



M1-H6a  
Sec. 2D.11



M1-H6b  
Sec. 2D.11



M1-7  
Sec. 2D.11



M1-8  
Sec. 9B.20



M1-9  
Sec. 9B.20



M1-10  
Sec. 2E.08



M2-1  
Sec. 2D.13



M2-2  
Sec. 2D.14



M3-1  
Sec. 2D.15



M3-2  
Sec. 2D.15



M3-3  
Sec. 2D.15



M3-4  
Sec. 2D.15



M4-1  
Sec. 2D.17



M4-1a  
Sec. 2D.17



M4-2  
Sec. 2D.18



M4-3  
Sec. 2D.19



M4-4  
Sec. 2D.20



M4-5  
Sec. 2D.21



M4-6  
Sec. 2D.22



M4-7  
Sec. 2D.23



M4-7a  
Sec. 2D.23



M4-8  
Sec. 6F.53



M4-8a  
Sec. 6F.53



M4-8b  
Sec. 6F.53

### Guide Signs – Marker Series



M4-9  
Sec. 6F.53



M4-9a  
Sec. 6F.53



M4-9b  
Sec. 6F.53



M4-9c  
Sec. 6F.53



M4-10  
Sec. 6F.53



M4-11  
Sec. 9B.21



M4-12  
Sec. 9B.21



M4-13  
Sec. 9B.21



M5-1  
Sec. 2D.25



M5-2  
Sec. 2D.25



M6-1  
Sec. 2D.26



M6-2  
Sec. 2D.26



M6-3  
Sec. 2D.26



M6-4  
Sec. 2D.26



M6-5  
Sec. 2D.26



M6-6  
Sec. 2D.26



M6-7  
Sec. 2D.26



M7-1  
Sec. 9B.21



M7-2  
Sec. 9B.21



M7-3  
Sec. 9B.21



M7-4  
Sec. 9B.21



M7-5  
Sec. 9B.21



M7-6  
Sec. 9B.21



M7-7  
Sec. 9B.21





M8-H3  
Sec. 2D.53



M8-H3p  
Sec. 2D.53

### Guide Signs- Directional Series

					
D1-1b Sec. 9B.21	D1-1c Sec. 9B.21	D1-H4 Sec. 2D.34	D1-H4a Sec. 2D.34	D2-H1 Sec. 2D.36	
					
D2-H2 Sec. 2D.36	D2-H3 Sec. 2D.36	D3-1 Sec. 2D.38	D3-2 Sec. 2D.39	D3-2 Sec. 2D.39	
					
D3-2 Sec. 2D.39	D4-1 Sec. 2D.40	D4-2 Sec. 2D.41	D4-3 Sec. 9B.20	D5-1 Sec. 2D.42	D5-H1 Sec. 2E.52
					
D5-1a Sec. 2E.52	D5-1b Sec. 2E.52	D5-H1b Sec. 2D.42	D5-2 Sec. 2D.42	D5-2a Sec. 2E.52	
					
D5-H2b Sec. 2D.42	D5-3 Sec. 2D.42	D5-4 Sec. 2D.42	D5-5 Sec. 2D.42	D5-5a Sec. 2D.42	D5-5b Sec. 2D.42
					
D5-5c Sec. 2D.42	D5-5d Sec. 2D.42	D5-5e Sec. 2D.42	D5-6 Sec. 2E.52	D5-H6 Sec. 2E.52	D5-7 Sec. 2E.52

### Guide Signs- Directional Series

					
D5-H7 Sec. 2E.52	D5-7a Sec. 2E.53	D5-8 Sec. 2E.53	D5-9 Sec. 2E.53	D5-9a Sec. 2E.53	D5-10 Sec. 2E.53

						
D5-11 Sec. 2E.53	D6-1 Sec. 2D.43 Sec. 2E.52	D6-2 Sec. 2D.43 Sec. 2E.52	D6-3 Sec. 2D.43 Sec. 2E.52	D6-H3 Sec. 2D.43	D6-4 Sec. 2D.52	D6-4a Sec. 2D.52

				
D7-H4 Sec. 2H.09	D7-H4a Sec. 2H.09	D8-1 Sec. 2D.44	D8-2 Sec. 2D.44	D8-H2 Sec. 2D.44

						
D8-3 Sec. 2D.44	D9-1 Sec. 2D.45	D9-2 Sec. 2D.45	D9-3 Sec. 2D.45	D9-3a Sec. 2D.45	D9-4 Sec. 2D.45	D9-6 Sec. 2D.45

						
D9-7 Sec. 2D.45	D9-8 Sec. 2D.45	D9-9 Sec. 2D.45	D9-10 Sec. 2D.45	D9-11 Sec. 2D.45	D9-11a Sec. 2D.45	D9-11b Sec. 2D.45

					
D9-12 Sec. 2D.45	D9-13 Sec. 2D.45	D9-13a Sec. 2D.45	D9-13b Sec. 2D.45	D9-13c Sec. 2D.45	D9-14 Sec. 2D.45

### Guide Signs- Directional Series



D9-15  
Sec. 2E.51



D9-16  
Sec. 2D.45



D9-17  
Sec. 2D.45



D9-18  
Sec. 2E.51



D9-18a  
Sec. 2E.51



D9-18e  
Sec. 2E.51



D10-1  
Sec. 2D.46



D10-1a  
Sec. 2D.46



D10-2  
Sec. 2D.46



D10-2a  
Sec. 2D.46



D10-3  
Sec. 2D.46



D10-3a  
Sec. 2D.46



D10-4  
Sec. 2E.54



D10-5  
Sec. 2E.54



D10-H5a  
Sec. 2E.54



D11-1  
Sec. 9B.17



D12-1  
Sec. 2D.45



D12-2  
Sec. 2D.45



D12-3  
Sec. 2D.45



D12-4  
Sec. 2D.45



D12-5  
Sec. 2D.45



D13-1  
Sec. 2D.51



D13-2  
Sec. 2D.51

### Guide Signs- Information Series



I1-1  
Sec. 2D.47



I-2  
Sec. 2D.48



I-H2  
Sec. 2D.48



I-H2a  
Sec. 2D.48



I-H2b  
Sec. 2D.48



I-H2c  
Sec. 2D.48



I-H2d  
Sec. 2D.48



I-H2e  
Sec. 2D.48



I-H2f  
Sec. 2D.48



I-H2g  
Sec. 2D.48



I-3  
Sec. 2D.48



I-5  
Sec. 2D.48



I-6  
Sec. 2D.48



I-7  
Sec. 2D.48



I-8  
Sec. 2D.48



I-11  
Sec. 2D.48



I-12  
Sec. 10C.20



I-13  
Sec. 8B.12



I-13a  
Sec. 8B.12

### Guide Signs- Freeways, Expressways and Miscellaneous

					
E1-H1 Sec. 2E.30	E1-H1 Sec. 2E.30	E1-H1 Sec. 2E.30	E1-H1 Sec. 2E.30	E1-H3 Sec. 2E.33	
					
E1-H5 Sec. 2E.28	E2-H1 Sec. 2E.31	E2-H1a Sec. 2E.31	E2-2 Sec. 2E.51	E2-3 Sec. 2E.51	
					
E3-H1 Sec. 2E.32	E3-H2 Sec. 2H.09	E4-H1 Sec. 2E.19	E5-H1 Sec. 2E.34	E5-H1a Sec. 2E.34	
					
E5-H1b Sec. 2E.34	E5-H1c Sec. 2E.34	E5-2 Sec 6F.28	E5-2a Sec. 6F.28	E5-H2b Sec. 6F.28	E5-3 Sec. 6F.28
					
E6-H2 Sec. 2E.11	E6-H2 Sec. 2E.11	E7-H1 Sec. 2E.36	E7-H2 Sec. 2E.37		

### Guide Signs- Freeways, Expressways and Miscellaneous – continued



E7-H3  
Sec. 2E.38



E7-H4  
Sec. 2E.39



E8-H2  
Sec. 2E.55



E8-H2a  
Sec 2E.55



E8-H3  
Sec. 2E.55



E11-1  
Sec. 2E.20



E11-1a  
Sec. 2E.20



E11-1b  
Sec. 2E.20



E11-1c  
Sec. 2E.20



E13-1  
Sec. 2E.34



G20-1  
Sec. 6F.51



G20-2  
Sec. 6F.52



G20-4  
Sec. 6F.54

### Recreational and Cultural Interest Series



RG-010  
*Sec. 2H.04*



RG-020  
*Sec. 2H.04*



RG-030  
*Sec. 2H.04*



RG-040  
*Sec. 2H.04*



RG-050  
*Sec. 2H.04*



RG-060  
*Sec. 2H.04*

(This is just a representative few of the symbol signs in this series. The full series is shown in Figure 2H-5 and discussed in Section 2H.04.)

### Emergency Management Series



EM-1  
Sec. 21.03



EM-2  
Sec. 21.04



EM-3  
Sec. 21.05



EM-4  
Sec. 21.06



EM-5  
Sec. 21.07



EM-6a  
Sec. 21.08



EM-6b  
Sec. 21.08



EM-6c  
Sec. 21.08



EM-6d  
Sec. 21.08



EM-7a  
Sec. 21.09



EM-7b  
Sec. 21.09




EM-7c  
Sec. 21.09




EM-7d  
Sec. 21.09


### Object Markers and End of Roadway Markers




OM1-1  
Sec. 3C.01




OM1-2  
Sec. 3C.01



OM1-3  
Sec. 3C.01



OM2-1V  
Sec. 3C.01



OM2-1H  
Sec. 3C.01



OM2-2V  
Sec. 3C.01



OM2-2H  
Sec. 3C.01



OM-3L  
Sec. 3C.02



OM-3C  
Sec. 3C.02



OM-3R  
Sec. 3C.02




OM-H3L  
Sec. 3C.02




OM-H3C  
Sec. 3C.02




OM-H3R  
Sec. 3C.02



OM4-1  
Sec. 3C.04



OM4-2  
Sec. 3C.04



OM4-3  
Sec. 3C.04

### School Area Signs



R16-H3  
Sec. 7B.15



S1-1  
Sec. 7B.08



S3-1  
Sec. 7B.10



S3-H2  
Sec. 7B.10



S4-1  
Sec. 7B.11



S4-3  
Sec. 7B.11



S4-5  
Sec. 7B.12




S4-H5  
Sec. 7B.11



S4-5a  
Sec. 7B.12



S4-6  
Sec. 7B.11




S5-2  
Sec. 7B.13



S5-H3  
Sec. 7B.11



S5-H4  
Sec. 7B.11



S5-H5  
Sec. 7B.11

## **INDEX**

This section has been reserved for an index similar to the one currently in the national Manual on Uniform Traffic Control Devices.



## Notes

## Notes